

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|---------------|--|---------------|-------------|-----------------|-----------------------------------|
| D1A | | Boiler Gaskets Synthetic | | | | Total Amount - 10 Sq Ft |
| | 19 | BOILER ROOM (0001) | NONE DETECTED | 101508-MV-6 | | 10 Sq Ft |
| D2A | | Interior Boiler Insulation Interior Refractory | | | | Total Amount - 100 Sq Ft |
| | 20 | BOILER ROOM (0001) | ASSUMED | | | 100 Sq Ft |
| H1A | | Sprayed-On Structural Fireproofing Gray, Fluffy Cellulose | | | | Total Amount - 40000 Sq Ft |
| | 1 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-27 | ROOM 1111. | 40000 Sq Ft |
| H1B | | Sprayed-On Structural Fireproofing Green w/Blue Cellulose | | | | Total Amount - 5030 Sq Ft |
| | 37 | ROOM 2301 | NONE DETECTED | 101508MV-28 | | 30 Sq Ft |
| | 46 | THROUGHOUT 3RD FLOOR | NONE DETECTED | | | 5000 Sq Ft |
| I2A | | 2' x 2' Acoustical Ceiling Tile Light Texture w/Revealed Edge | | | | Total Amount - 15000 Sq Ft |
| | 4 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-13 | OFFICE. | 15000 Sq Ft |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|---|----------------------------------|---------------|-------------|-----------------|-----------------------------------|
| I3A | 2' x 4' Ceiling Tile Pockmarks & Pin Holes | | | | | Total Amount - 50000 Sq Ft |
| | 5 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-18 | ROOM 2314. | 50000 Sq Ft |
| I3B | 2' x 4' Ceiling Tile Vinyl-Coated Sheetrock | | | | | Total Amount - 930 Sq Ft |
| | 22 | KITCHEN (1105J) | NSM | | | 500 Sq Ft |
| | 24 | ROOM 1103 | NSM | | | 180 Sq Ft |
| | 25 | SMALL KITCHEN 1105C | NSM | | | 160 Sq Ft |
| | 43 | ROOM 2313 | NSM | | | 90 Sq Ft |
| K1A | Sheet Vinyl Flooring & Adhesive Blue Marbled | | | | | Total Amount - 1444 Sq Ft |
| | 32 | ROOM 2109 | ASSUMED | | | 784 Sq Ft |
| | 36 | ROOM 2113 | ASSUMED | | | 660 Sq Ft |
| K2A | 12" x 12" Vinyl Floor Tile & Mastic White w/Black & Gray Smudges | | | | | Total Amount - 35000 Sq Ft |
| | 6 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-23 | | 35000 Sq Ft |
| K3A | Miscellaneous Flooring Gray Stair Treads w/Raised Circles | | | | | Total Amount - 2000 Sq Ft |
| | 27 | STAIRWELL 1302 NEAR LOADING DOCK | ASSUMED | | | 2000 Sq Ft |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|---|---------------------------------------|---------------|---|---|-----------------|-----------------------------------|
| LOA Flexible Duct Connector Black Vinyl | | | | | | Total Amount - 2 Sq Ft |
| 28 | ELEVATOR EQUIPMENT ROOM 1301 | NSM | | | | 2 Sq Ft |
| MOA Plaster 1911 Original Building Columns | | | | | | Total Amount - 300 Sq Ft |
| 17 | LOWER LEVEL MECHANICAL ROOM & STORAGE | NONE DETECTED | 101508MV-1, 2, 3 | 1: ROOM 0002. 2: ROOM 0001. 3: ROOM 0001A. | | 300 Sq Ft |
| MOB Plaster 1911 Original Building Walls & Ceiling | | | | | | Total Amount - 50000 Sq Ft |
| 2 | THROUGHOUT BUILDING | NONE DETECTED | 101508-MV-5, 7, 20, 24, 25, 26; 501-V-7 | 5: ROOM 0002. 7: ROOM 1201. 20: ROOM 2323. 24: ROOM 3201. 25: STAIRS BY ROOM 2103. 26: ROOM 3400. V-7: BASEMENT RESTROOM. | | 50000 Sq Ft |
| NOA Drywall/Joint Compound 2000 Installation | | | | | | Total Amount - 50000 Sq Ft |
| 3 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-15 | HALLWAY 124. | | 50000 Sq Ft |
| POA Fire Doors Metal - 1.5 Hr Rating (Warnock Hersey) | | | | | | Total Amount - 40 Sq Ft |
| 21 | BOILER ROOM (0001) | NEW | | | | 40 Sq Ft |
| QOA Carpet Adhesive 1997 Installation | | | | | | Total Amount - 35000 Sq Ft |
| 7 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-21 | ROOM 2113. | | 35000 Sq Ft |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|---|---------------|----------------------------------|-----------------------|-----------------|------------------------|
| ROA | Baseboard/Mopboard Adhesive Silver Baseboard | | Total Amount - 5000 Sq Ft | | | |
| 8 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-8 | HALLWAY BY ROOM 1127. | 5000 Sq Ft | |
| ROB | Baseboard/Mopboard Adhesive 4" Navy Baseboard | | Total Amount - 110 Sq Ft | | | |
| 33 | ROOM 2109 | ASSUMED | | | 60 Sq Ft | |
| 35 | ROOM 2113 | ASSUMED | | | 50 Sq Ft | |
| TOA | Light Cord Insulation White Wiring for Light Fixture | | Total Amount - 200 Lin Ft | | | |
| 9 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-11 | ROOM 4311. | 200 Lin Ft | |
| TOB | Light Cord Insulation Black Light Fixture Wire | | Total Amount - 200 Lin Ft | | | |
| 10 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-22 | ROOM 2107C. | 200 Lin Ft | |
| VOA | Sink Undercoating Black | | Total Amount - 200 Sq Ft | | | |
| 11 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-12 | ROOM 1107. | 200 Sq Ft | |
| VOB | Sink Undercoating Smooth White | | Total Amount - 6 Sq Ft | | | |
| 34 | ROOM 2109 | ASSUMED | | | 6 Sq Ft | |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|---|--------------------------------|---------------|-------------|-----------------|---------------------------------|
| W1A | 1' x 1' Ceiling Tile Adhesive Dark Brown | | | | | Total Amount - 177 Sq Ft |
| | 29 | MAIN OFFICE AREA | NONE DETECTED | 101508MV-14 | | 50 Sq Ft |
| | 31 | ROOM 2109 | NONE DETECTED | | | 15 Sq Ft |
| | 45 | ROOM 2004 | NONE DETECTED | | | 2 Sq Ft |
| | 47 | ROOM 3400 & ASSOCIATED OFFICES | NONE DETECTED | 101508MV-10 | OFFICE 3406. | 100 Sq Ft |
| | 48 | ROOM 3201 | NONE DETECTED | | | 10 Sq Ft |
| W1B | 1' x 1' Ceiling Tile Adhesive Light Tan | | | | | Total Amount - 174 Sq Ft |
| | 30 | ROOM 2108 | NONE DETECTED | 101508MV-17 | | 25 Sq Ft |
| | 38 | HALLWAY OUTSIDE ROOM 2317 | NONE DETECTED | | | 30 Sq Ft |
| | 39 | ROOM 2317 | NONE DETECTED | 101508MV-19 | | 40 Sq Ft |
| | 40 | ROOM 2318 | NONE DETECTED | | | 4 Sq Ft |
| | 41 | ROOM 2315 | NONE DETECTED | | | 40 Sq Ft |
| | 42 | ROOM 2316 | NONE DETECTED | | | 25 Sq Ft |
| | 44 | ROOM 2314 | NONE DETECTED | | | 10 Sq Ft |
| XOA | Miscellaneous Material Tan Caulk | | | | | Total Amount - 10 Sq Ft |
| | 18 | LOWER LEVEL STORAGE (0001A) | 4 CH | 101508MV-4 | | 10 Sq Ft |

| Homogeneous Area ID Code (Material Type) | IEA Event No. | Location | % Asbestos | Sample No. | Sample Location | Estimated Total Amount |
|--|---|---------------|-------------|-----------------------|-----------------|-----------------------------------|
| XOB | Miscellaneous Material Tan Sheetrock Adhesive | | | | | Total Amount - 200 Sq Ft |
| 16 | THROUGHOUT LOWER LEVEL | NONE DETECTED | 101508MV-9 | HALLWAY BY ROOM 1115. | 200 Sq Ft | |
| XOC | Miscellaneous Material Red Fire Stop | | | | | Total Amount - 300 Sq Ft |
| 12 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-16 | HALLWAY 124. | 300 Sq Ft | |
| XOD | Miscellaneous Material Gray Duct Caulk | | | | | Total Amount - 200 Sq Ft |
| 13 | THROUGHOUT BUILDING | NONE DETECTED | 101508MV-29 | ROOM 0002. | 200 Sq Ft | |
| XOF | Miscellaneous Material Black Table Tops (Wood) | | | | | Total Amount - 160 Sq Ft |
| 49 | ROOM 4207 | NSM | | | 160 Sq Ft | |
| X1A | Miscellaneous Material 4" X 8" Quarry Tile System | | | | | Total Amount - 4660 Sq Ft |
| 14 | THROUGHOUT BUILDING RESTROOMS | ASSUMED | | | 4000 Sq Ft | |
| 23 | KITCHEN (1105J) | ASSUMED | | | 500 Sq Ft | |
| 26 | SMALL KITCHEN 1105C | ASSUMED | | | 160 Sq Ft | |
| X1B | Miscellaneous Material 4" X 8" Blue Ceramic Wall Tile System | | | | | Total Amount - 15000 Sq Ft |
| 15 | THROUGHOUT BUILDING RESTROOMS | ASSUMED | | | 15000 Sq Ft | |