

380 North Victoria Street, Saint Paul, MN 55104

**Chart C - All Materials List**

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2A		Mudded Pipe Joints on Millboard Insulation 1954 Original Building				<b>Total Amount - 4 Joints</b>
	151	1954 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2100	50 CH	207N-4A		4 Joints
A4A		Mudded Pipe Joints on Fiberglass Insulation Old Yellow Fiberglass				<b>Total Amount - 67 Joints</b>
	9	1954 ORIGINAL BUILDING BOILER ROOM 0201	NONE DETECTED	051717-BF-1, 3; 2001-1901-ME-2A, 3A, 5	BF-1,3: BOILER ROOM. ME-5: BOILER ROOM.	55 Joints
	36	KITCHEN 1204	NONE DETECTED			5 Joints
	47	KITCHEN MECHANICAL ROOM 1206	NONE DETECTED			7 Joints
A4B		Mudded Pipe Joints on Fiberglass Insulation Newer White Fiberglass				<b>Total Amount - 22 Joints</b>
	10	1954 ORIGINAL BUILDING BOILER ROOM 0201	NONE DETECTED	524-JJT-19	JJT-19: BOILER ROOM NORTH SIDE.	6 Joints
	46	KITCHEN MECHANICAL ROOM 1206	NONE DETECTED	524-JJT-14, 15	SOUTH END 1ST PIPE AS YOU WALK IN DOOR BY CEILING.	16 Joints
A4C		Mudded Pipe Joints on Fiberglass Insulation 1974 Addition				<b>Total Amount - 532 Joints</b>
	191	1974 ADDITION TUNNELS	NONE DETECTED	2001-1901-MEW-1A; 1A, B, C (NOVA)		395 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	199	1974 ADDITION GYMNASIUM 1307	NONE DETECTED			4 Joints
	204	GYMNASIUM STORAGE ROOM 1307B	NONE DETECTED			3 Joints
	206	UPPER GYMNASIUM MECHANICAL ROOM OFF ROOM 1307B	NONE DETECTED	2001-1901-ME-6, 7; 524-JJT-24	JJT-24: NORTHEAST END BY ENTRANCE.	90 Joints
	222	1974 ADDITION 1ST FLOOR NORTH BOYS' RESTROOM 1511B	NONE DETECTED			6 Joints
	223	1974 ADDITION NORTH CUSTODIAL ROOM 1511C	NONE DETECTED	524-JJT-27, 28	NORTHEAST ENTRANCE.	28 Joints
	224	1974 ADDITION 1ST FLOOR NORTH GIRLS' RESTROOM 1511A	NONE DETECTED	524-JJT-29, 30	JJT-39: SOUTHEAST CORNER. JJT-30: SOUTHEAST END.	6 Joints
A4D		Mudded Pipe Joints on Fiberglass Insulation				<b>Total Amount - 12 Joints</b>
	48	KITCHEN MECHANICAL ROOM 1206	50 CH	072115BV-01	BV-01: KITCHEN ROOM 1206.	12 Joints
B2A		Millboard Pipe Insulation 1954 Original Building				<b>Total Amount - 496 Lin Ft</b>
	85	ROOMS 1102-1106 & RESTROOMS	20 CH	45OU-A-4, 5, 6;	BOILER ROOM AND TUNNELS (SINCE REMOVED)	120 Lin Ft
	125	1954 ORIGINAL BUILDING NORTH HALLWAY 1600	20 CH			200 Lin Ft
	137	ROOM 1602 & RESTROOM 1602A	20 CH			50 Lin Ft
	145	ROOM 1603 & RESTROOM 1603A	20 CH			50 Lin Ft
	150	1954 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2100	20 CH			26 Lin Ft
	156	ROOMS 2101-2106 & RESTROOMS 2107 & 2109	20 CH			50 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
B3A	Pre-Formed Pipe Insulation (1954)					<b>Total Amount - 9 Lin Ft</b>
	41	KITCHEN STORAGE 1207	ASSUMED			1 Lin Ft
	126	1954 ORIGINAL BUILDING NORTH HALLWAY 1600	ASSUMED			8 Lin Ft
E1A	Stack Gasket 1954 Original Building					<b>Total Amount - 2 Sq Ft</b>
	11	1954 ORIGINAL BUILDING BOILER ROOM 0201	15 CH	030209-RV-01		2 Sq Ft
F2B	Exterior Duct Insulation 1974 Addition (Fiberglass)					<b>Total Amount - 620 Sq Ft</b>
	50	KITCHEN MECHANICAL ROOM 1206	NONE DETECTED	2001-1501-A-11, 12, 13		20 Sq Ft
	209	UPPER GYMNASIUM MECHANICAL ROOM	NONE DETECTED	2001-1501-A-18, 19, 20		600 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Fissured					<b>Total Amount - 12069 Sq Ft</b>
	21	CUSTODIAL OFFICE STORAGE 1211	NONE DETECTED	207N-12A		75 Sq Ft
	28	ROOM 1209 (LOUNGE)	NONE DETECTED			500 Sq Ft
	42	KITCHEN STORAGE 1207	NONE DETECTED	524-JJT-17	JJT-17: ABOVE DOOR AT SOUTH END STORAGE AREA.	200 Sq Ft
	52	CAFETERIA (1203)	NONE DETECTED	207N-15A		2600 Sq Ft
	60	GIRLS' RESTROOM (1202B)	NONE DETECTED			64 Sq Ft
	67	1954 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1000	NONE DETECTED	301-WC-B (NOVA)		1200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	81	1954 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1100	NONE DETECTED	301-WC-A, C (NOVA)		1600 Sq Ft
	105	ROOM 1110	NONE DETECTED	2001-1501A-4		370 Sq Ft
	128	1954 ORIGINAL BUILDING NORTH HALLWAY 1600	NONE DETECTED			800 Sq Ft
	131	ROOM 1602	NONE DETECTED			900 Sq Ft
	139	ROOM 1603	NONE DETECTED			900 Sq Ft
	147	1954 ORIGINAL BUILDING SOUTH STAIRWELL 1199A	NONE DETECTED	2001-1501-A-2		450 Sq Ft
	152	1954 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2100	NONE DETECTED			1550 Sq Ft
	160	STORAGE 2101A	NONE DETECTED			200 Sq Ft
	166	ROOM 2111	NONE DETECTED			200 Sq Ft
	170	ROOM 2110	NONE DETECTED			200 Sq Ft
	183	1954 ORIGINAL BUILDING NORTH STAIRWELL 2199B	NONE DETECTED			260 Sq Ft
<b>11C</b>		<b>1' x 1' Acoustical Ceiling Tile White Paper w/Gray Flecks (Spline)</b>				<b>Total Amount - 600 Sq Ft</b>
	37	KITCHEN 1204	NONE DETECTED	2001-1901-ME-1; 524-JJT-13	JJT-13: EAST SIDE BY KITCHEN OFFICE.	600 Sq Ft
<b>12A</b>		<b>2' x 2' Acoustical Ceiling Tile Fissures w/Pin Holes</b>				<b>Total Amount - 610 Sq Ft</b>
	210	ROOM 1401	NONE DETECTED	207N-16A; 524-JJT-25	JJT-25: NORTHWEST CORNER.	610 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2B		2' x 2' Acoustical Ceiling Tile Textured w/Pin Holes			<b>Total Amount - 1000 Sq Ft</b>	
72	MAIN OFFICE 1001-1007	NONE DETECTED	301-WP-A, B, C (NOVA)		1000 Sq Ft	
I3A		2' x 4' Ceiling Tile Textured w/Pin Holes			<b>Total Amount - 10750 Sq Ft</b>	
57	CAFETERIA STAGE (1201)	NONE DETECTED	524-JJT-12	JJT-12: CENTER OF STAGE BY VENT.	480 Sq Ft	
84	ROOMS 1102-1106	NONE DETECTED	303-WP-A, B (NOVA)		4800 Sq Ft	
90	ROOM 1112A (NURSE'S OFFICE RESTROOM)	NONE DETECTED	524-JJT-2; 303-WP-C (NOVA)	JJT-2: SOUTHEAST CORNER ABOVE DOOR.	50 Sq Ft	
155	ROOMS 2101-2106	NONE DETECTED			4920 Sq Ft	
212	ROOM 1404	NONE DETECTED			360 Sq Ft	
214	ROOM 1405	NONE DETECTED	524-JJT-26	SOUTHEAST CORNER.	140 Sq Ft	
I3B		2' x 4' Ceiling Tile Widthwise Fissures w/Pin Holes			<b>Total Amount - 792 Sq Ft</b>	
86	ROOMS 1113, 1114, 1115, & 1100B HALLWAY	NONE DETECTED	207N-13A; 303-PF-A, B, C (NOVA)		600 Sq Ft	
87	ROOM 1112 (NURSE'S OFFICE)	NONE DETECTED			192 Sq Ft	
I4B		Acoustical Ceiling Tile Tectum Panels			<b>Total Amount - 1200 Sq Ft</b>	
198	1974 ADDITION GYMNASIUM 1307	NONE DETECTED	524-JJT-23	JJT-23: NORTHEAST SIDE.	1200 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J1A	Cementitious Panels Window Panels					<b>Total Amount - 180 Sq Ft</b>
	20	CUSTODIAL OFFICE 1210	ASSUMED			12 Sq Ft
	25	CUSTODIAL OFFICE STORAGE 1211	ASSUMED			12 Sq Ft
	34	ROOM 1209 (LOUNGE)	ASSUMED			56 Sq Ft
	45	KITCHEN STORAGE 1207	ASSUMED			100 Sq Ft
J1D	Cementitious Panels Door Transom					<b>Total Amount - 12 Sq Ft</b>
	17	1ST FLOOR HALLWAY OUTSIDE ELEVATOR	ASSUMED			6 Sq Ft
	27	HALLWAY 1200 OUTSIDE CUSTODIAL OFFICE	ASSUMED			6 Sq Ft
J2A	Transite Piping/Ducting 10"-30" Ducting (1974)					<b>Total Amount - 440 Sq Ft</b>
	187	THROUGHOUT 1974 ADDITION	ASSUMED			440 Sq Ft
J3A	Miscellaneous Cementitious Material Black Masonite Panel (Johnson Controls)					<b>Total Amount - 6 Sq Ft</b>
	13	1954 ORIGINAL BUILDING BOILER ROOM 0201	NSM			6 Sq Ft
K1A	Sheet Vinyl Flooring & Adhesive Light & Dark Gray					<b>Total Amount - 850 Sq Ft</b>
	228	ROOM 1504	NONE DETECTED	2001-1501-A-21	A-21: OUTER WALL BY DOOR EXIT.	850 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2A		12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan, Pink, Gray & Brown Blotches				<b>Total Amount - 500 Sq Ft</b>
	30	ROOM 1209 (LOUNGE)	NONE DETECTED	030209-RV-21		500 Sq Ft
K2C		12" x 12" Vinyl Floor Tile & Mastic Beige w/Pink & Gray Flecks				<b>Total Amount - 64 Sq Ft</b>
	62	GIRLS' RESTROOM (1202B)	NONE DETECTED	524-JJT-4; 310-FT4-A (NOVA)	JJT-4: ROOM 1105 SOUTHEAST CORNER OF TILE AREA (SINCE REMOVED).	64 Sq Ft
K2E		12" x 12" Vinyl Floor Tile & Mastic Dark Tan Mottle				<b>Total Amount - 90 Sq Ft</b>
	80	COPY ROOM 1007	NONE DETECTED	030209-RV-16		90 Sq Ft
K2F		12" x 12" Vinyl Floor Tile & Mastic Light Tan Mottle				<b>Total Amount - 90 Sq Ft</b>
	79	COPY ROOM 1007	NONE DETECTED	030209-RV-17		90 Sq Ft
K2G		12" x 12" Vinyl Floor Tile & Mastic Blue Mottle (2009)				<b>Total Amount - 1575 Sq Ft</b>
	18	CUSTODIAL OFFICE 1210	NEW			250 Sq Ft
	23	CUSTODIAL OFFICE STORAGE 1211	NEW			75 Sq Ft
	201	1974 ADDITION GYMNASIUM 1307	NEW			800 Sq Ft
	203	GYMNASIUM STORAGE ROOM 1310A	NEW			130 Sq Ft
	205	GYMNASIUM STORAGE ROOM 1307B	NEW			320 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2H	12" x 12" Vinyl Floor Tile & Mastic White w/Confetti (2009)					<b>Total Amount - 4000 Sq Ft</b>
	200	1974 ADDITION GYMNASIUM 1307	NEW			4000 Sq Ft
K3A	Miscellaneous Flooring 2' x 2' Light Brown Tiles					<b>Total Amount - 1310 Sq Ft</b>
	54	CAFETERIA (1203)	NONE DETECTED	030209-RV-22	AT BACK DOOR	1310 Sq Ft
K3C	Miscellaneous Flooring 2' x 2' Dark Brown Tiles					<b>Total Amount - 1310 Sq Ft</b>
	55	CAFETERIA (1203)	NONE DETECTED	030209-RV-23	AT BACK DOOR	1310 Sq Ft
K3D	Miscellaneous Flooring 2' X 2' Speckled (2015)					<b>Total Amount - 330 Sq Ft</b>
	88	ROOM 1112 (NURSE'S OFFICE)	NEW			330 Sq Ft
K3F	Miscellaneous Flooring 18"x18" Gray with Blue, White, and Black Specks (2020)					<b>Total Amount - 11990 Sq Ft</b>
	44	KITCHEN STORAGE 1207	NEW			200 Sq Ft
	69	1954 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1000	NEW			630 Sq Ft
	83	1954 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1100	NEW			1600 Sq Ft
	95	ROOM 1102	NEW			230 Sq Ft
	98	ROOM 1111	NEW			30 Sq Ft



Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	102	ROOM 1103	NEW			230 Sq Ft
	110	ROOM 1104	NEW			230 Sq Ft
	116	ROOM 1105	NEW			830 Sq Ft
	121	ROOM 1106	NEW			830 Sq Ft
	136	ROOM 1602 & CLOSET 1602B	NEW			1000 Sq Ft
	143	ROOM 1603 & CLOSET 1603B	NEW			500 Sq Ft
	154	1954 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2100	NEW			1550 Sq Ft
	157	ROOM 2101	NEW			700 Sq Ft
	162	STORAGE 2101A	NEW			200 Sq Ft
	163	ROOM 2102	NEW			830 Sq Ft
	168	ROOM 2103	NEW			780 Sq Ft
	174	ROOM 2104	NEW			60 Sq Ft
	177	ROOM 2105	NEW			780 Sq Ft
	180	ROOM 2106	NEW			780 Sq Ft
LOB		Flexible Duct Connector Coarse White Fabric				<b>Total Amount - 5 Sq Ft</b>
	49	KITCHEN MECHANICAL ROOM 1206	45 CH	524-JJT-16	JJT-16: EAST SIDE OF VENT.	5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount	
LOC		Flexible Duct Connector Black Vinyl				<b>Total Amount - 30 Sq Ft</b>	
	208	UPPER GYMNASIUM MECHANICAL ROOM	NONE DETECTED	2001-1901-ME-1B	ME-1B: MECHANICAL ROOM.	30 Sq Ft	
MOA		Plaster 1954 Original Building				<b>Total Amount - 16600 Sq Ft</b>	
	8	1954 ORIGINAL BUILDING BASEMENT	NONE DETECTED	2001-01141-1; 524-JJT-20; 306-CP1-A, B, C (NOVA)	JJT-20: ABOVE ENTRANCE TO BOILER AREA ON CEILING.	1600 Sq Ft	
	15	THROUGHOUT 1954 ORIGINAL BUILDING 1ST FLOOR	NONE DETECTED	030209-RV-12; 306-CE-A, B; 306-NA-A, B (NOVA)	RV-12: HALLWAY CEILING OUTSIDE ROOM 1103.	10000 Sq Ft	
	149	THROUGHOUT 1954 ORIGINAL BUILDING 2ND FLOOR	NONE DETECTED	030209-RV-06; 2001-1501-A-3	RV-06: ROOM 2101 STORAGE CEILING. A-3: ROOM 201 WALL BY BASE OF DOOR.	5000 Sq Ft	
NOA		Drywall/Joint Compound Renovation				<b>Total Amount - 4500 Sq Ft</b>	
	16	THROUGHOUT 1954 ORIGINAL BUILDING 1ST FLOOR	NONE DETECTED	2001-1501-A-5, 6; 524-JJT-8	A-5: ROOM 101. A-6: ROOM 1103 ON RIGHT WALL AT BASE. JJT-8: MAIN OFFICE SECRETARY'S OFFICE ABOVE DOOR. (SINCE REMOVED).	4500 Sq Ft	
NOC		Drywall/Joint Compound Vinyl-Covered Sheetrock Wall Panels				<b>Total Amount - 600 Sq Ft</b>	
	109	ROOM 1104	NONE DETECTED	2001-1501-A-7	A-7: ROOM 104 RIGHT SIDE OF WALL AT BASE.	300 Sq Ft	
	115	ROOM 1105	NONE DETECTED			300 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount	
N0D		Drywall/Joint Compound Vinyl-Covered Sheetrock (1974)				<b>Total Amount - 10000 Sq Ft</b>	
	188	THROUGHOUT 1974 ADDITION	NONE DETECTED	524-JJT-21; 2001-1501-A-9	JJT-21: ROOM 1413 AT RIGHT SIDE BOTTOM OF DOOR. A-9: ROOM 1445 BY DOOR ENTRY (SINCE REMOVED).	10000 Sq Ft	
N0E		Drywall/Joint Compound 1974 Addition				<b>Total Amount - 18500 Sq Ft</b>	
	189	THROUGHOUT 1974 ADDITION	NONE DETECTED	524-JJT-32; 2001-1501A-9	JJT-32: ROOM 3 SOUTHEAST CORNER BOTTOM. A-9: COMPUTER ROOM.	18500 Sq Ft	
POA		Fire Doors Metal - Underwriter's Laboratories				<b>Total Amount - 22 Sq Ft</b>	
	14	1954 ORIGINAL BUILDING BOILER ROOM 0201	ASSUMED			22 Sq Ft	
POB		Fire Doors Wood Composite - 30 Min Rating (Weyerhaeuser)				<b>Total Amount - 60 Sq Ft</b>	
	93	ROOM 1113	ASSUMED			20 Sq Ft	
	94	ROOM 1115	ASSUMED			20 Sq Ft	
	101	ROOM 1111	ASSUMED			20 Sq Ft	
POC		Fire Doors Metal w/Fiberglass Core - 3 Hr Rating (Superior)				<b>Total Amount - 20 Sq Ft</b>	
	207	UPPER GYMNASIUM MECHANICAL ROOM	NSM			20 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0A		Carpet Adhesive Multi-Colored Berber Carpet				<b>Total Amount - 40000 Sq Ft</b>
1	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-ZZ-1C, 3C; 309-LBMC-A, B (NOVA)	LBMC-A,B: LIBRARY SERVER ROOM.	40000 Sq Ft	
Q0B		Carpet Adhesive Blue w/Tan, White & Aqua Specks				<b>Total Amount - 1500 Sq Ft</b>
73	MAIN OFFICE 1001-1006	NONE DETECTED			1000 Sq Ft	
213	ROOM 1404	NONE DETECTED	309-BLUM-A, B (NOVA)	309-BLUM-A,B (NOVA): LIBRARY 1501 (SINCE REMOVED).	360 Sq Ft	
215	ROOM 1405	NONE DETECTED			140 Sq Ft	
Q0C		Carpet Adhesive Multi-Colored Carpet Squares (20XX)				<b>Total Amount - 2250 Sq Ft</b>
227	LIBRARY 1501	NEW			2250 Sq Ft	
Q0D		Carpet Adhesive Black Striped Carpet Squares (2020)				<b>Total Amount - 280 Sq Ft</b>
70	ENTRANCE 1000A	NEW			280 Sq Ft	
Q0E		Carpet Adhesive Green with Blue Carpet Squares (2020)				<b>Total Amount - 3310 Sq Ft</b>
96	ROOM 1102	NEW			600 Sq Ft	
99	ROOM 1111	NEW			170 Sq Ft	
103	ROOM 1103	NEW			600 Sq Ft	
107	ROOM 1110	NEW			200 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	111	ROOM 1104	NEW			600 Sq Ft
	133	ROOM 1602	NEW			200 Sq Ft
	144	ROOM 1603 & CLOSET 1603B	NEW			500 Sq Ft
	165	ROOM 2111	NEW			220 Sq Ft
	172	ROOM 2110	NEW			220 Sq Ft
<b>ROA</b>	Baseboard/Mopboard Adhesive 4" Black Baseboard					<b>Total Amount - 40 Sq Ft</b>
	19	CUSTODIAL OFFICE 1210	NONE DETECTED	2001-1901-ZZ-2C		25 Sq Ft
	24	CUSTODIAL OFFICE STORAGE 1211	NONE DETECTED			15 Sq Ft
<b>ROB</b>	Baseboard/Mopboard Adhesive 4" Dark Brown Baseboard					<b>Total Amount - 1150 Sq Ft</b>
	2	THROUGHOUT BUILDING	NONE DETECTED	524-JJT-3; 2001-1901-ZZ-4B	JJT-3: HALLWAY OUTSIDE NURSE'S OFFICE. SOUTHEAST CORNER BY DOOR. JJT-33: 1974 ADDITION ROOM 4 SOUTHEAST CORNER BELOW LIGHT SWITCH.	1150 Sq Ft
<b>ROC</b>	Baseboard/Mopboard Adhesive 6" Brown Baseboard					<b>Total Amount - 25 Sq Ft</b>
	31	ROOM 1209 (LOUNGE)	NONE DETECTED			15 Sq Ft
	63	GIRLS' RESTROOM (1202B)	NONE DETECTED	072115BV-03	BV-03: GIRLS' RESTROOM 1202B.	10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROD		Baseboard/Mopboard Adhesive 4" Beige Baseboard			<b>Total Amount - 23 Sq Ft</b>	
59	CAFETERIA STAGE (1201)	NONE DETECTED	07102018-KP-01	KP-01: CAFETERIA STAGE (1201).	3 Sq Ft	
74	MAIN OFFICE 1001-1007	NONE DETECTED			20 Sq Ft	
SOA		Wood Floor Felt / Vapor Barrier 1954 Original Building (Elevated)			<b>Total Amount - 630 Sq Ft</b>	
58	CAFETERIA STAGE (1201)	NSM			630 Sq Ft	
TOA		Light Cord Insulation White Fuzzy Cords			<b>Total Amount - 24 Lin Ft</b>	
56	CAFETERIA (1203)	ASSUMED			24 Lin Ft	
VOA		Sink Undercoating Lavender			<b>Total Amount - 10 Sq Ft</b>	
159	ROOM 2101	5 CH	030209-RV-07		10 Sq Ft	
VOB		Sink Undercoating Gray w/Gooseneck Faucet			<b>Total Amount - 44 Sq Ft</b>	
76	MAIN OFFICE ROOM 1005	NONE DETECTED			8 Sq Ft	
100	ROOM 1111	NONE DETECTED			5 Sq Ft	
119	ROOM 1105	NONE DETECTED			5 Sq Ft	
124	ROOM 1106	NONE DETECTED			6 Sq Ft	
142	ROOM 1603	NONE DETECTED			5 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	164	ROOM 2102	NONE DETECTED	030209-RV-08		5 Sq Ft
	169	ROOM 2103	NONE DETECTED			5 Sq Ft
	181	ROOM 2106	NONE DETECTED			5 Sq Ft
VOC	Sink Undercoating Beige					<b>Total Amount - 5 Sq Ft</b>
	135	ROOM 1602	NONE DETECTED	030209-RV-10		5 Sq Ft
VOD	Sink Undercoating Black (1974)					<b>Total Amount - 48 Sq Ft</b>
	193	ROOM 1306	5 CH			4 Sq Ft
	195	ROOM 1305	5 CH			4 Sq Ft
	196	ROOM 1303	5 CH			4 Sq Ft
	197	ROOM 1302	5 CH			4 Sq Ft
	211	ROOM 1403	5 CH			4 Sq Ft
	216	ROOM 1406	5 CH			4 Sq Ft
	217	ROOM 1409	5 CH			4 Sq Ft
	218	ROOM 1410	5 CH			4 Sq Ft
	220	ROOM 1413	5 CH			4 Sq Ft
	225	ROOM 1509	5 CH			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	226	ROOM 1506	5 CH			4 Sq Ft
	229	ROOM 1504	5 CH	030209-RV-14		4 Sq Ft
VOE	Sink Undercoating White					<b>Total Amount - 10 Sq Ft</b>
	230	ROOM 1504	5 CH	030209-RV-15		10 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					<b>Total Amount - 2801 Sq Ft</b>
	22	CUSTODIAL OFFICE STORAGE 1211	NONE DETECTED			15 Sq Ft
	29	ROOM 1209 (LOUNGE)	NONE DETECTED			125 Sq Ft
	43	KITCHEN STORAGE 1207	NONE DETECTED			50 Sq Ft
	53	CAFETERIA (1203)	NONE DETECTED			600 Sq Ft
	61	GIRLS' RESTROOM (1202B)	NONE DETECTED			16 Sq Ft
	68	1954 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1000	NONE DETECTED			300 Sq Ft
	82	1954 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1100	NONE DETECTED	030209-RV-11		400 Sq Ft
	106	ROOM 1110	NONE DETECTED			75 Sq Ft
	129	1954 ORIGINAL BUILDING NORTH HALLWAY 1600	NONE DETECTED			200 Sq Ft
	132	ROOM 1602	NONE DETECTED			200 Sq Ft
	140	ROOM 1603	NONE DETECTED			200 Sq Ft



Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	148	1954 ORIGINAL BUILDING SOUTH STAIRWELL 1199A	NONE DETECTED			100 Sq Ft
	153	1954 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2100	NONE DETECTED			320 Sq Ft
	161	STORAGE 2101A	NONE DETECTED	030209-RV-04		50 Sq Ft
	167	ROOM 2111	NONE DETECTED			45 Sq Ft
	171	ROOM 2110	NONE DETECTED			45 Sq Ft
	184	1954 ORIGINAL BUILDING NORTH STAIRWELL 2199B	NONE DETECTED			60 Sq Ft
W1C	1' x 1' Ceiling Tile Adhesive Associated w/I1C					<b>Total Amount - 125 Sq Ft</b>
	38	KITCHEN 1204	<1 ANT	072611-JC-01		125 Sq Ft
X0A	Miscellaneous Material Pipe & Valve Flange Gaskets					<b>Total Amount - 25 Sq Ft</b>
	12	1954 ORIGINAL BUILDING BOILER ROOM 0201	ASSUMED			25 Sq Ft
X0B	Miscellaneous Material Lightweight Concrete Roof Deck					<b>Total Amount - 6000 Sq Ft</b>
	35	KITCHEN 1204	NONE DETECTED			600 Sq Ft
	66	1954 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1000	NONE DETECTED	030209-RV-02	RV-02: ABOVE ENTRY TO NORTH WING.	1400 Sq Ft
	71	MAIN OFFICE 1001-1007	NONE DETECTED			1000 Sq Ft
	127	1954 ORIGINAL BUILDING NORTH HALLWAY 1600	NONE DETECTED			800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	130	ROOMS 1602 & 1603	NONE DETECTED			2200 Sq Ft
X0D	Miscellaneous Material Tackboards					<b>Total Amount - 1200 Sq Ft</b>
	3	THROUGHOUT 1954 ORIGINAL BUILDING	NSM			1200 Sq Ft
X0E	Miscellaneous Material Tackboard Adhesive on Demountable Wall					<b>Total Amount - 2 Sq Ft</b>
	113	ROOM 1104	NONE DETECTED	072611-JC-02		2 Sq Ft
X0F	Miscellaneous Material Tackboard Adhesive (1974)					<b>Total Amount - 16 Sq Ft</b>
	194	ROOM 1305	NONE DETECTED	072611-JC-04	JC-04: ROOM 1305.	16 Sq Ft
X0G	Miscellaneous Material Wired Window Glazing					<b>Total Amount - 6 Sq Ft</b>
	7	THROUGHOUT 1954 ORIGINAL BUILDING CLASSROOMS	6 CH	072115BV-02	BV-02: ROOM 1112.	6 Sq Ft
X0GG	Miscellaneous Material Exterior Window Caulking (1954)					<b>Total Amount - 30 Sq Ft</b>
	5	THROUGHOUT 1954 ADDITION	NONE DETECTED	072115BV-05	BV-05: ROOM 1603.	30 Sq Ft
X0H	Miscellaneous Material Tan Exterior Duct Caulking					<b>Total Amount - 20 Sq Ft</b>
	192	1973 ADDITION TUNNELS	10 CH	072115BV-04	BV-04: NORTHEAST TUNNEL ENTRANCE OFF OF BOILER ROOM.	20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOHH		Miscellaneous Material Exterior Grill Caulking				<b>Total Amount - 10 Sq Ft</b>
	6	THROUGHOUT 1954 ADDITION	8 CH	072115BV-06	BV-06: ROOM 1602.	10 Sq Ft
XOI		Miscellaneous Material Exterior Window Caulking (1973)				<b>Total Amount - 50 Sq Ft</b>
	186	THROUGHOUT 1973 ADDITION	NONE DETECTED	072115BV-07	BV-07: ROOM 1505.	50 Sq Ft
X1A		Miscellaneous Material Tan & White Speckle Countertops				<b>Total Amount - 505 Sq Ft</b>
	89	ROOM 1112 (NURSE'S OFFICE)	NONE DETECTED			50 Sq Ft
	97	ROOM 1102	NONE DETECTED			60 Sq Ft
	104	ROOM 1103	NONE DETECTED			60 Sq Ft
	112	ROOM 1104	NONE DETECTED			60 Sq Ft
	118	ROOM 1105	NONE DETECTED			60 Sq Ft
	122	ROOM 1106	NONE DETECTED			60 Sq Ft
	158	ROOM 2101	NONE DETECTED	524-JJT-1	JJT-1: SOUTH END OF COUNTERTOP TO THE SOUTH OF ENTRY.	35 Sq Ft
	175	ROOM 2104	NONE DETECTED			60 Sq Ft
	178	ROOM 2105	NONE DETECTED			60 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1B	Miscellaneous Material Gray w/Dark Gray Streaked Countertops		<b>Total Amount - 130 Sq Ft</b>			
	134	ROOM 1602	NONE DETECTED			60 Sq Ft
	141	ROOM 1603	NONE DETECTED			30 Sq Ft
	182	ROOM 2106	NONE DETECTED	313-G-A (NOVA); 2001-1501-A-14	A-14: BY WINDOW ON RIGHT SIDE.	40 Sq Ft
X1C	Miscellaneous Material Brown w/Dark Brown Streaks Countertop		<b>Total Amount - 190 Sq Ft</b>			
	32	ROOM 1209 (LOUNGE)	NONE DETECTED			60 Sq Ft
	117	ROOM 1105	NONE DETECTED	2001-1501A-10		50 Sq Ft
	123	ROOM 1106	NONE DETECTED			50 Sq Ft
	219	ROOM 1413	NONE DETECTED			30 Sq Ft
X1D	Miscellaneous Material Beige Countertop		<b>Total Amount - 25 Sq Ft</b>			
	75	MAIN OFFICE 1001 & 1007	NONE DETECTED	524-JJT-7	JJT-7: EAST SIDE BOTTOM OF COUNTER.	25 Sq Ft
X1E	Miscellaneous Material Orange/Red Countertops		<b>Total Amount - 10 Sq Ft</b>			
	33	ROOM 1209 (LOUNGE)	NONE DETECTED	524-JJT-18	JJT-18: SOUTHEAST END OF CABINET ON TOP RAIL.	10 Sq Ft
X1F	Miscellaneous Material Beige Countertops		<b>Total Amount - 145 Sq Ft</b>			
	190	THROUGHOUT 1974 ADDITION	NONE DETECTED	524-JJT-31	JJT-31: ROOM 1506 WEST END OF COUNTER.	145 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1G		Miscellaneous Material 6" Red Quarry Tile				<b>Total Amount - 700 Sq Ft</b>
	4	THROUGHOUT 1954 ORIGINAL BUILDING	NONE DETECTED	052220BV-01	BV-01: HALLWAY NEAR CUSTODIAL OFFICE.	700 Sq Ft
X1I		Miscellaneous Material Multi-Sized Blue, Gray & Tan Ceramic Floor Tile System				<b>Total Amount - 443 Sq Ft</b>
	26	CUSTODIAL RESTROOM 1211A	ASSUMED			25 Sq Ft
	65	BOYS' RESTROOM (1202A)	ASSUMED			72 Sq Ft
	108	GIRLS' RESTROOM 1109	ASSUMED			150 Sq Ft
	114	CUSTODIAL CLOSET 1108	ASSUMED			3 Sq Ft
	138	RESTROOM 1602A	ASSUMED			20 Sq Ft
	146	RESTROOM 1603A	ASSUMED			20 Sq Ft
	173	GIRLS' RESTROOM 2109	ASSUMED			150 Sq Ft
	176	CUSTODIAL CLOSET 2108	ASSUMED			3 Sq Ft
X1J		Miscellaneous Material 1" White, Brown & Beige Ceramic Floor Tile System				<b>Total Amount - 465 Sq Ft</b>
	39	KITCHEN 1204	ASSUMED			465 Sq Ft
X1K		Miscellaneous Material 1" White, Brown & Tan Ceramic Floor Tile System				<b>Total Amount - 266 Sq Ft</b>
	40	KITCHEN 1204	ASSUMED			266 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1M		Miscellaneous Material 2" Gray Ceramic Floor Tile System				<b>Total Amount - 36 Sq Ft</b>
	91	ROOM 1112A (NURSE'S OFFICE RESTROOM)	ASSUMED			36 Sq Ft
X1N		Miscellaneous Material 4" White Ceramic Wall Tile System				<b>Total Amount - 50 Sq Ft</b>
	92	ROOM 1112A (NURSE'S OFFICE RESTROOM)	ASSUMED			50 Sq Ft
X1O		Miscellaneous Material Multi-Sized Blue & Pink Ceramic Floor Tile System				<b>Total Amount - 345 Sq Ft</b>
	64	GIRLS' RESTROOM (1202B)	ASSUMED			45 Sq Ft
	120	BOYS' RESTROOM 1107	ASSUMED			150 Sq Ft
	179	BOYS' RESTROOM 2107	ASSUMED			150 Sq Ft
X1P		Miscellaneous Material 1" Beige Ceramic Wall Tile System				<b>Total Amount - 170 Sq Ft</b>
	202	STORAGE 1311	ASSUMED			170 Sq Ft
X1Q		Miscellaneous Material 6" Red Quarry Tile				<b>Total Amount - 1000 Sq Ft</b>
	185	THROUGHOUT 1973 ADDITION	ASSUMED			1000 Sq Ft
X1R		Miscellaneous Material 6" Tan Quarry Tile				<b>Total Amount - 400 Sq Ft</b>
	221	1974 ADDITION RESTROOMS 1511A/B	NONE DETECTED	052220BV-03	BV-03: HALLWAY NEAR ROOM 1414.	400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1S		Miscellaneous Material 1" X 1" Beige Ceramic Floor Tile System				<b>Total Amount - 32 Sq Ft</b>
	51	KITCHEN RESTROOM 1205A	ASSUMED			32 Sq Ft
X1T		Miscellaneous Material 6" X 6" Beige Ceramic Wall Tile System (200x)				<b>Total Amount - 72 Sq Ft</b>
	77	MAIN OFFICE RESTROOM	NEW			72 Sq Ft
X1U		Miscellaneous Material 1' X 1' Beige Ceramic Floor Tile System (200x)				<b>Total Amount - 45 Sq Ft</b>
	78	MAIN OFFICE RESTROOM	NEW			45 Sq Ft