

1575 L'Orient Street, Saint Paul, MN 55117

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A1A		Mudded Pipe Joints on Air Cell Insulation 1952 Original Building				Total Amount - 3 Joints
	15	ROOM 1104A (ELECTRICAL)	ASSUMED			3 Joints
B1A		Air Cell Pipe Insulation 1952 Original Building				Total Amount - 5 Lin Ft
	14	ROOM 1104A (ELECTRICAL)	ASSUMED			5 Lin Ft
D1A		Boiler Gaskets White Shiny Gasket				Total Amount - 2 Sq Ft
	10	BOILER ROOM	NONE DETECTED	112508MV-5		2 Sq Ft
D2A		Interior Boiler Insulation Floor				Total Amount - 60 Sq Ft
	11	BOILER ROOM	ASSUMED			60 Sq Ft
H2B		Trowelled-On Structural Fireproofing Plaster on Beams (1962)				Total Amount - 1000 Sq Ft
	92	THROUGHOUT 1962 ADDITION	NONE DETECTED	527-JJT-26, 27, 37	26: IN CORNER OF HALLWAY ADJACENT TO ROOM 2222. 27: WEST SIDE OF HALLWAY ABOVE CEILING ADJACENT TO 1952 ORIGINAL BUILDING. 37: OUTSIDE ROOM 1219.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount	
H2C		Trowelled-On Structural Fireproofing Plaster on Beams (1952)				Total Amount - 1985 Sq Ft	
	18	HALLWAY 1000 BY MAIN OFFICE	NONE DETECTED	527-JJT-73	JJT-73: ABOVE HATCH IN CLOSET.	90 Sq Ft	
	21	ROOM 1003 (MAIN OFFICE)	NONE DETECTED			35 Sq Ft	
	25	ROOM 1002 (WORK ROOM)	NONE DETECTED			30 Sq Ft	
	29	ROOM 1004 (NURSE)	NONE DETECTED			35 Sq Ft	
	35	ROOM 1005 (CONFERENCE ROOM)	NONE DETECTED			30 Sq Ft	
	52	1952 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1200	NONE DETECTED	527-JJT-66, 67	66: BY HATCH OF ROOM 1216. 67: ABOVE CEILING ABOVE DOORWAY OF ROOM 1211.	925 Sq Ft	
	70	ROOM 1213 (STAFF LOUNGE)	NONE DETECTED	527-JJT-58	EAST WALL ABOVE WINDOW.	40 Sq Ft	
	176	1952 ORIGINAL BUILDING 2ND FLOOR HALLWAY OUTSIDE ROOMS 2203-2218	NONE DETECTED	527-JJT-46, 47	46: ABOVE CEILING IN HALLWAY OUTSIDE ROOM 2216. 47: ABOVE CEILING IN HALLWAY OUTSIDE ROOM 2217.	800 Sq Ft	
H2D		Trowelled-On Structural Fireproofing Plaster on Beams (1966)				Total Amount - 350 Sq Ft	
	116	1966 ADDITION 1ST FLOOR HALLWAY	NONE DETECTED	527-JJT-16, 17, 89	16: BY AIR HANDLER ABOVE CEILING TO THE RIGHT. 17: ABOVE CEILING OUTSIDE ROOM 2223. 89: BY AIR HANDLER ABOVE CEILING TO THE LEFT.	350 Sq Ft	
I1C		1' x 1' Acoustical Ceiling Tile Fissures (1952)				Total Amount - 750 Sq Ft	
	53	RESTROOM 1209A BY ROOM 1211	NONE DETECTED	527-JJT-64	INSIDE LARGER RESTROOM ABOVE DOOR.	150 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	219	1952 ORIGINAL BUILDING 2ND FLOOR GIRLS' RESTROOM 2209	NONE DETECTED			300 Sq Ft
	223	1952 ORIGINAL BUILDING 2ND FLOOR BOYS' RESTROOM 2203	NONE DETECTED			300 Sq Ft
I1D	1' x 1' Acoustical Ceiling Tile Pegboard					Total Amount - 2000 Sq Ft
	38	ROOM 1106 (GYMNASIUM)	NONE DETECTED	527-JJT-85	INSIDE 1ST SET OF DOUBLE DOORS ON CEILING.	2000 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Light Texture w/Pin Holes					Total Amount - 160 Sq Ft
	19	STORAGE CLOSETS 1010 BY MAIN OFFICE	NONE DETECTED	112508MV-22	MV-22: HALLWAY 1000 NEAR MAIN OFFICE.	160 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Lightly Textured w/Revealed Edge (2010)					Total Amount - 40000 Sq Ft
	1	THROUGHOUT BUILDING	NEW			40000 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Dents w/Pin Holes w/Revealed Edge (2011)					Total Amount - 1590 Sq Ft
	22	ROOM 1003 (MAIN OFFICE)	NEW			1000 Sq Ft
	23	ASSISTANT PRINCIPALS' OFFICE	NEW			160 Sq Ft
	24	PRINCIPALS' OFFICE	NEW			270 Sq Ft
	36	ROOM 1005 (CONFERENCE ROOM)	NEW			160 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3A	2' x 4' Ceiling Tile Bumpy Texture w/Pin Holes					Total Amount - 11665 Sq Ft
	26	ROOM 1002 (WORK ROOM)	NONE DETECTED	112508MV-23	MV-23: ROOM 1003 (MAIN OFFICE) (SINCE REMOVED).	160 Sq Ft
	30	ROOM 1004 (NURSE)	NONE DETECTED			160 Sq Ft
	119	RESTROOM BY ROOM 1223	NONE DETECTED			200 Sq Ft
	155	1966 ADDITION 2ND FLOOR STAFF RESTROOM 2224A	NONE DETECTED			50 Sq Ft
	215	STAFF RESTROOM 2210	NONE DETECTED			45 Sq Ft
	221	1952 ORIGINAL BUILDING 2ND FLOOR GIRLS' RESTROOM 2209	NONE DETECTED			50 Sq Ft
	233	ROOM 1110 (MULTI-PURPOSE)	NONE DETECTED	527-JJT-75	ABOVE NORTHWEST DOUBLE DOOR.	2500 Sq Ft
	262	THROUGHOUT 2001 ADDITION	NONE DETECTED			8500 Sq Ft
I3B	2' x 4' Ceiling Tile Vinyl-Covered Sheetrock					Total Amount - 500 Sq Ft
	237	KITCHEN 1112	NSM			500 Sq Ft
I3C	2' x 4' Ceiling Tile Pockmarks, Dents & Pin Holes					Total Amount - 12985 Sq Ft
	229	1990 ADDITION HALLWAY 1100	NONE DETECTED	527-JJT-59	JJT-59: ROOM 1213 (STAFF LOUNGE) NORTHEAST CORNER OF ROOM BY REFRIGERATOR (SINCE REMOVED).	1000 Sq Ft
	235	ROOM 1110A	NONE DETECTED			225 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	239	COMPUTER LAB/IMC (1111/1113)	NONE DETECTED			2400 Sq Ft
	242	ROOM 1111A OFFICE	NONE DETECTED	527-JJT-78	SOUTHWEST CORNER.	280 Sq Ft
	245	ROOM 1114	NONE DETECTED			80 Sq Ft
	249	THROUGHOUT 1993 ADDITION	NONE DETECTED			9000 Sq Ft
K0I	9" x 9" Vinyl Floor Tile & Mastic White w/Black Streaks					Total Amount - 750 Sq Ft
	75	ROOM 1214	10 CH (TILE ONLY)	527-JJT-53	ADJACENT TO DOOR JAMB.	750 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Tan Mottle					Total Amount - 5930 Sq Ft
	4	THROUGHOUT 1ST & 2ND FLOOR HALLWAYS	NONE DETECTED	112508MV-10	MV-10: HALLWAY BY BOILER ROOM.	5000 Sq Ft
	17	ROOM 1103 (CUSTODIAL OFFICE)	NONE DETECTED			180 Sq Ft
	95	ROOM 1219	NONE DETECTED			750 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic White, Maroon & Gray Swirls					Total Amount - 325 Sq Ft
	13	ROOM 1104 (COPY ROOM)	NONE DETECTED			130 Sq Ft
	16	ROOM 1104A (ELECTRICAL)	NONE DETECTED			80 Sq Ft
	216	STAFF RESTROOM 2210	NONE DETECTED			35 Sq Ft
	247	ROOM 1302A	NONE DETECTED	527-JJT-84	JJT-84: 1993 ADDITION ROOM 1309 SOUTH SIDE OF DOOR ENTRY (SINCE REMOVED).	80 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2C		12" x 12" Vinyl Floor Tile & Mastic White w/Beige Smudges			Total Amount - 380 Sq Ft	
	27	ROOM 1002 (WORK ROOM)	NONE DETECTED	112508MV-11		160 Sq Ft
	31	ROOM 1004 (NURSE)	NONE DETECTED			160 Sq Ft
	49	ROOM 1204/1206 (CUSTODIAL)	NONE DETECTED			60 Sq Ft
K2D		12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown & White Swirls			Total Amount - 3635 Sq Ft	
	217	STAFF RESTROOM 2210	NONE DETECTED			10 Sq Ft
	230	1990 ADDITION HALLWAY 1100	NONE DETECTED			1000 Sq Ft
	234	ROOM 1110 (MULTI-PURPOSE)	NONE DETECTED			2400 Sq Ft
	236	ROOM 1110A	NONE DETECTED	527-JJT-76	NORTH SIDE OF DOUBLE DOOR ENTRY.	225 Sq Ft
K2E		12" x 12" Vinyl Floor Tile & Mastic Light Gray Mottle			Total Amount - 2220 Sq Ft	
	40	ROOM 1106 (GYMNASIUM)	NONE DETECTED			2100 Sq Ft
	41	ROOM 1106A (GYMNASIUM OFFICE/STORAGE)	NONE DETECTED	112508MV-12		120 Sq Ft
K2F		12" x 12" Vinyl Floor Tile & Mastic Light Brown w/Brown & White Specks			Total Amount - 160 Sq Ft	
	20	STORAGE CLOSETS 1010 BY MAIN OFFICE	NONE DETECTED	112508MV-13		160 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2G	12" x 12" Vinyl Floor Tile & Mastic White w/White & Tan Swirls		Total Amount - 70 Sq Ft			
55	RESTROOM 1209A BY ROOM 1211	NONE DETECTED	527-JJT-65	INSIDE LARGER RESTROOM.	70 Sq Ft	
K2H	12" x 12" Vinyl Floor Tile & Mastic Light Blue w/Dark Blue & White Streaks		Total Amount - 3000 Sq Ft			
251	THROUGHOUT 1993 ADDITION	NONE DETECTED	527-JJT-81	JJT-81: ROOM 1310.	3000 Sq Ft	
K2I	12" x 12" Vinyl Floor Tile & Mastic White w/Tan & Brown Swirls		Total Amount - 310 Sq Ft			
136	ROOM 1232 (1985 ADDITION 1ST FLOOR ELEVATOR STORAGE)	NONE DETECTED	527-JJT-1	ADJACENT TO DOOR JAMB IN NORTHEAST CORNER.	80 Sq Ft	
137	ROOM 1229 (1985 ADDITION 1ST FLOOR ELEVATOR EQUIPMENT)	NONE DETECTED			80 Sq Ft	
139	ROOM 2229	NONE DETECTED			150 Sq Ft	
K2J	12" x 12" Vinyl Floor Tile & Mastic Multi-Shaded Gray Smudges		Total Amount - 60 Sq Ft			
72	ROOM 1213 (STAFF LOUNGE)	NONE DETECTED	112508MV-14		60 Sq Ft	
K2K	12" x 12" Vinyl Floor Tile & Mastic Beige w/Brown		Total Amount - 1680 Sq Ft			
259	1993 ADDITION HALLWAY	NONE DETECTED	112508MV-36	MV-36: BY RESTROOMS.	1400 Sq Ft	
260	1993 ADDITION ROOM 1309	NONE DETECTED			280 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2L	12" x 12" Vinyl Floor Tile & Mastic Cream w/Beige					Total Amount - 2000 Sq Ft
269	2001 ADDITION HALLWAY 1300	NONE DETECTED	112508MV-55	MV-55: HALLWAY BY ROOM 1315.	2000 Sq Ft	
K2M	12" x 12" Vinyl Floor Tile & Mastic Light Blue Mottle					Total Amount - 1500 Sq Ft
263	THROUGHOUT 2001 ADDITION	NONE DETECTED	112508MV-56	MV-56: ROOM 1314.	1500 Sq Ft	
K2N	12" x 12" Vinyl Floor Tile & Mastic Pink w/Black Specks (2010)					Total Amount - 18170 Sq Ft
58	ROOMS 1210 (STORAGE) & 1210A	NEW			400 Sq Ft	
60	ROOM 1211	NEW			800 Sq Ft	
63	ROOM 1212	NEW			750 Sq Ft	
81	ROOM 1215	NEW			750 Sq Ft	
87	ROOM 1216	NEW			750 Sq Ft	
100	ROOM 1218	NEW			375 Sq Ft	
104	ROOM 1220	NEW			500 Sq Ft	
107	ROOM 1221	NEW			750 Sq Ft	
112	ROOM 1222 & 1222A (ELECTRICAL)	NEW			375 Sq Ft	
117	ROOM 1223	NEW			250 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	125	ROOM 1225	NEW			750 Sq Ft
	130	ROOM 1230	NEW			750 Sq Ft
	140	ROOM 2228	NEW			860 Sq Ft
	145	ROOM 2225	NEW			750 Sq Ft
	150	ROOM 2223	NEW			250 Sq Ft
	158	ROOM 2222	NEW			600 Sq Ft
	161	ROOM 2221	NEW			900 Sq Ft
	166	ROOM 2220	NEW			900 Sq Ft
	171	ROOM 2219	NEW			900 Sq Ft
	177	ROOM 2218	NEW			750 Sq Ft
	182	ROOM 2217	NEW			750 Sq Ft
	187	ROOM 2216	NEW			725 Sq Ft
	191	ROOM 2215	NEW			750 Sq Ft
	196	ROOM 2214	NEW			900 Sq Ft
	201	ROOM 2213	NEW			750 Sq Ft
	206	ROOM 2212	NEW			850 Sq Ft
	212	ROOM 2211	NEW			275 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	222	ROOM 2207	NEW			60 Sq Ft
K3A	Miscellaneous Flooring Black Floor Mastic (1952)					Total Amount - 80 Sq Ft
	37	ROOM 1005 (CONFERENCE ROOM)	<1 CH	112508MV-37	MV-37: ROOM 2212 (SINCE REMOVED).	80 Sq Ft
K3B	Miscellaneous Flooring 2' X 2' Tan Rubber Flooring					Total Amount - 25 Sq Ft
	138	1985 ADDITION ELEVATOR	NEW			25 Sq Ft
LOC	Flexible Duct Connector Black Vinyl					Total Amount - 5 Sq Ft
	46	ROOM 1108 (STAGE)	NSM			1 Sq Ft
	76	ROOM 1214	NSM			1 Sq Ft
	154	ROOM 2226 (CUSTODIAN)	NSM			2 Sq Ft
	231	1990 ADDITION HALLWAY 1100	NSM			1 Sq Ft
L0D	Flexible Duct Connector Green Canvas					Total Amount - 3 Sq Ft
	45	ROOM 1108 (STAGE)	NONE DETECTED	2001-1504-GC		3 Sq Ft
M0A	Plaster Rough, Sandy Texture (1966)					Total Amount - 140 Sq Ft
	123	CUSTODIAL CLOSET 1228	NONE DETECTED	112508MV-1, 2		40 Sq Ft
	153	ROOM 2226 (CUSTODIAN)	NONE DETECTED	527-JJT-4	SOUTHEAST SIDE ABOVE DOOR.	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOB Plaster Rough Texture (1952)						Total Amount - 400 Sq Ft
	9	BOILER ROOM	NONE DETECTED	112508MV-3, 4; 527-JJT-74	3,4: SOUTHEAST CORNER OF RESTROOM.	400 Sq Ft
MOC Plaster Smooth (1966)						Total Amount - 1600 Sq Ft
	114	THROUGHOUT 1966 ADDITION	NONE DETECTED	112508MV-6, 7, 53, 54; 527-JJT-21	MV-6: HALLWAY BY ROOM 2225. MV-7: HALLWAY BY ROOM 1225. MV-53: 1ST FLOOR RESTROOM ENTRY. MV-54: HALLWAY BY ROOM 1230. JJT-21: 2ND FLOOR HALLWAY.	1600 Sq Ft
MOD Plaster Smooth (1962)						Total Amount - 600 Sq Ft
	93	THROUGHOUT 1962 ADDITION	NONE DETECTED	112508MV-62, 63; 527-JJT-28	MV-62: HALLWAY 2219. MV-63: HALLWAY 1218. JJT-28: HALLWAY BY 2221.	600 Sq Ft
MOE Plaster Smooth (1952)						Total Amount - 17000 Sq Ft
	5	THROUGHOUT 1952 ORIGINAL BUILDING	NONE DETECTED	112508-MV-8, 9, 48, 50, 51, 52 ; 527-JJT-55	MV-8: STAFF LOUNGE. MV-9: STAIRS 1299A. MV-48: 2ND FLOOR GIRLS' RESTROOM. MV-50: OUTSIDE ROOM 2218. MV-51; ROOM 2205. MV-52: ROOM 1204. JJT-55: ROOM 1216.	17000 Sq Ft
NOA Drywall/Joint Compound 1966 Addition						Total Amount - 1000 Sq Ft
	115	THROUGHOUT 1966 ADDITION	NONE DETECTED	2001-1501-MIS-03	2ND FLOOR HALLWAY.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
NOB		Drywall/Joint Compound 1952 Original Building				Total Amount - 10000 Sq Ft
	6	THROUGHOUT 1952 ORIGINAL BUILDING	NONE DETECTED	527-JJT-61, 68	JJT-61: ROOM 1211. JJT-68: STAGE.	10000 Sq Ft
N0D		Drywall/Joint Compound 1990 Addition				Total Amount - 2000 Sq Ft
	227	THROUGHOUT 1990 ADDITION	NONE DETECTED	527-JJT-79	HALLWAY.	2000 Sq Ft
N0E		Drywall/Joint Compound 1985 Addition				Total Amount - 500 Sq Ft
	135	THROUGHOUT 1985 ADDITION	NONE DETECTED	527-JJT-2	ELEVATOR EQUIPMENT ROOM.	500 Sq Ft
N0F		Drywall/Joint Compound 2001 Addition				Total Amount - 3000 Sq Ft
	261	THROUGHOUT 2001 ADDITION	NONE DETECTED	112508MV-61	MV-61: ROOM 1318.	3000 Sq Ft
P0A		Fire Doors Composite - No Rating (Weldwood)				Total Amount - 20 Sq Ft
	12	BOILER ROOM	ASSUMED			20 Sq Ft
P0B		Fire Doors Wood - 1 Hr Rating (Underwriter's Laboratories)				Total Amount - 20 Sq Ft
	246	ROOM 1114	ASSUMED			20 Sq Ft
Q0F		Carpet Adhesive Brown Berber Carpeting				Total Amount - 3160 Sq Ft
	71	ROOM 1213 (STAFF LOUNGE)	NONE DETECTED	112508MV-38	MV-38: ROOM 1211 (SINCE REMOVED).	480 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	240	COMPUTER LAB/IMC (1111/1113)	NONE DETECTED			2400 Sq Ft
	243	ROOM 1111A OFFICE	NONE DETECTED	112508MV-40		280 Sq Ft
Q0J	Carpet Adhesive Light Blue Berber Carpeting					Total Amount - 4000 Sq Ft
	250	THROUGHOUT 1993 ADDITION	NONE DETECTED	527-JJT-82	JJT-82: ROOM 1314.	4000 Sq Ft
Q0K	Carpet Adhesive Blue w/Multi-Colored Highlights					Total Amount - 4200 Sq Ft
	264	THROUGHOUT 2001 ADDITION	NONE DETECTED	112508MV-58	MV-58: ROOM 1321.	4200 Sq Ft
ROA	Baseboard/Mopboard Adhesive 4" Black Baseboard					Total Amount - 1500 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	527-JJT-3, 23, 69	JJT-3: 1985 ELEVATOR LOBBY. JJT-23: 1966 ADDITION HALLWAY. JJT-69: 1954 ADDITION.	1500 Sq Ft
ROB	Baseboard/Mopboard Adhesive 4" Brown Baseboard					Total Amount - 50 Sq Ft
	94	THROUGHOUT 1962 ADDITION	NONE DETECTED	527-JJT-32	JJT-32: ROOM 1221.	50 Sq Ft
ROF	Baseboard/Mopboard Adhesive Dark Blue Baseboard					Total Amount - 200 Sq Ft
	265	THROUGHOUT 2001 ADDITION	NONE DETECTED	112508MV-57	MV-57: ROOM 1315.	200 Sq Ft
ROI	Baseboard/Mopboard Adhesive 4" Tannish Gray Baseboard					Total Amount - 5 Sq Ft
	47	ROOM 1108 (STAGE)	NONE DETECTED	112508MV-42		5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROL		Baseboard/Mopboard Adhesive 4" Tannish Brown Baseboard				Total Amount - 300 Sq Ft
	228	THROUGHOUT 1990 ADDITION	NONE DETECTED			100 Sq Ft
	248	THROUGHOUT 1993 & 2001 ADDITIONS	NONE DETECTED	112508MV-43	MV-43: 1993 HALLWAY BY ROOM 1304.	200 Sq Ft
ROM		Baseboard/Mopboard Adhesive 4" Light Blue Baseboard				Total Amount - 100 Sq Ft
	252	THROUGHOUT 1993 ADDITION	NONE DETECTED	527-JJT-80	JJT-80: ROOM 1310.	100 Sq Ft
RON		Baseboard/Mopboard Adhesive 4" Tan Baseboard (2010)				Total Amount - 200 Sq Ft
	7	THROUGHOUT 1952 ORIGINAL BUILDING	NEW			200 Sq Ft
SOA		Wood Floor Felt / Vapor Barrier Elevated (1952)				Total Amount - 450 Sq Ft
	42	ROOM 1108 (STAGE)	ASSUMED			450 Sq Ft
SOB		Wood Floor Felt / Vapor Barrier Renovation				Total Amount - 750 Sq Ft
	80	ROOM 1214	ASSUMED			750 Sq Ft
TOA		Light Cord Insulation White				Total Amount - 48 Lin Ft
	43	ROOM 1108 (STAGE)	ASSUMED			48 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOA	Sink Undercoating Gray					Total Amount - 116 Sq Ft
	28	ROOM 1002 (WORK ROOM)	NONE DETECTED			5 Sq Ft
	32	ROOM 1004 (NURSE)	NONE DETECTED			4 Sq Ft
	69	ROOM 1212	NONE DETECTED	112508MV-44		12 Sq Ft
	74	ROOM 1213 (STAFF LOUNGE)	NONE DETECTED			5 Sq Ft
	85	ROOM 1215	NONE DETECTED			5 Sq Ft
	99	ROOM 1219	NONE DETECTED			5 Sq Ft
	103	ROOM 1218	NONE DETECTED			5 Sq Ft
	111	ROOM 1221	NONE DETECTED			5 Sq Ft
	129	ROOM 1225	NONE DETECTED			5 Sq Ft
	134	ROOM 1230	NONE DETECTED			5 Sq Ft
	141	ROOM 2228	NONE DETECTED			5 Sq Ft
	148	ROOM 2225	NONE DETECTED			5 Sq Ft
	165	ROOM 2221	NONE DETECTED			5 Sq Ft
	170	ROOM 2220	NONE DETECTED			5 Sq Ft
	175	ROOM 2219	NONE DETECTED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	181	ROOM 2218	NONE DETECTED			5 Sq Ft
	186	ROOM 2217	NONE DETECTED			5 Sq Ft
	190	ROOM 2216	NONE DETECTED			5 Sq Ft
	195	ROOM 2215	NONE DETECTED			5 Sq Ft
	200	ROOM 2214	NONE DETECTED			5 Sq Ft
	205	ROOM 2213	NONE DETECTED			5 Sq Ft
	210	ROOM 2212	NONE DETECTED			5 Sq Ft
VOB	Sink Undercoating Black					Total Amount - 5 Sq Ft
	90	ROOM 1216	NONE DETECTED	112508MV-45		5 Sq Ft
VOC	Sink Undercoating Gray (1993)					Total Amount - 29 Sq Ft
	244	ROOM 1111A OFFICE	NONE DETECTED	112508MV-40		4 Sq Ft
	254	THROUGHOUT 1993 ADDITION	NONE DETECTED	112508MV-46		25 Sq Ft
VOD	Sink Undercoating Gray (2001)					Total Amount - 40 Sq Ft
	266	THROUGHOUT 2001 ADDITION	NONE DETECTED	112508MV-60	MV-60: ROOM 1315.	40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1C	1' x 1' Ceiling Tile Adhesive Associated w/I1C		Total Amount - 170 Sq Ft			
	54	RESTROOM 1209A BY ROOM 1211	NONE DETECTED	112508MV-19	MV-19: 1952 ORIGINAL BUILDING 1ST FLOOR NORTHEAST STAIRWELL (SINCE REMOVED).	30 Sq Ft
	220	1952 ORIGINAL BUILDING 2ND FLOOR GIRLS' RESTROOM 2209	NONE DETECTED	112508MV-47		70 Sq Ft
	224	1952 ORIGINAL BUILDING 2ND FLOOR BOYS' RESTROOM 2203	NONE DETECTED			70 Sq Ft
W1D	1' x 1' Ceiling Tile Adhesive Associated w/I1D		Total Amount - 500 Sq Ft			
	39	ROOM 1106 (GYMNASIUM)	ASSUMED			500 Sq Ft
X0A	Miscellaneous Material AHU Seam Tar Gasket		Total Amount - 5 Sq Ft			
	44	ROOM 1108 (STAGE)	NONE DETECTED	112508MV-16		5 Sq Ft
X0B	Miscellaneous Material Damp Proofing		Total Amount - 1000 Sq Ft			
	232	WALL CHASE BY MULTI-PURPOSE 1110	5 CH	112508MV-17		1000 Sq Ft
X0C	Miscellaneous Material Gray Ductwork Caulk		Total Amount - 200 Sq Ft			
	3	THROUGHOUT BUILDING	NONE DETECTED	112508MV-18	MV-18: KITCHEN.	200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount	
X0D		Miscellaneous Material Wired Window Glaze				Total Amount - 6 Sq Ft	
	48	1ST FLOOR SOUTHWEST STAIRWELL 1199A	3 CH	112508MV-20		2 Sq Ft	
	113	STAIRWELL NEAR ROOM 1222	3 CH			2 Sq Ft	
	226	1952 ADDITION 2ND FLOOR SOUTHWEST STAIRWELL 2299A	3 CH			2 Sq Ft	
X0E		Miscellaneous Material Red Countertops				Total Amount - 240 Sq Ft	
	96	ROOM 1219	NONE DETECTED	527-JJT-36	NORTHEAST CORNER BY SINK.	120 Sq Ft	
	142	ROOM 2228	NONE DETECTED	527-JJT-5, 56	JJT-5: ROOM 2228 AT NORTHEAST CORNER OF ROOM. JJT-56: ROOM 1216 AT SOUTHWEST CORNER BY SINK (SINCE REMOVED).	120 Sq Ft	
X0F		Miscellaneous Material Lime Green Countertops				Total Amount - 140 Sq Ft	
	118	ROOM 1223	NONE DETECTED			10 Sq Ft	
	149	ROOM 2225	NONE DETECTED	527-JJT-6	SOUTHEAST CORNER OF ROOM.	120 Sq Ft	
	151	ROOM 2223	NONE DETECTED			10 Sq Ft	
X0G		Miscellaneous Material Yellow Countertops				Total Amount - 240 Sq Ft	
	133	ROOM 1230	NONE DETECTED	527-JJT-11	NORTHEAST CORNER OF ROOM.	120 Sq Ft	
	167	ROOM 2220	NONE DETECTED	527-JJT-24	SOUTHEAST CORNER BY SINK.	120 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOH	Miscellaneous Material Light Blue Countertops					Total Amount - 480 Sq Ft
	108	ROOM 1221	NONE DETECTED	527-JJT-34	NORTHWEST CORNER BY SINK.	120 Sq Ft
	126	ROOM 1225	NONE DETECTED	527-JJT-14	NORTHWEST CORNER BY SINK.	120 Sq Ft
	162	ROOM 2221	NONE DETECTED			120 Sq Ft
	172	ROOM 2219	NONE DETECTED			120 Sq Ft
XOJ	Miscellaneous Material Gray, White & Brown Swirled Countertops					Total Amount - 517 Sq Ft
	65	ROOM 1212	NONE DETECTED	527-JJT-51	BY UNIVENT HEATER TO LEFT.	60 Sq Ft
	77	ROOM 1214	NONE DETECTED			80 Sq Ft
	86	ROOM 1215	NONE DETECTED			7 Sq Ft
	91	ROOM 1216	NONE DETECTED			70 Sq Ft
	178	ROOM 2218	NONE DETECTED			50 Sq Ft
	183	ROOM 2217	NONE DETECTED			50 Sq Ft
	192	ROOM 2215	NONE DETECTED			50 Sq Ft
	197	ROOM 2214	NONE DETECTED			50 Sq Ft
	202	ROOM 2213	NONE DETECTED			50 Sq Ft
	207	ROOM 2212	NONE DETECTED			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOK		Miscellaneous Material White Countertops				Total Amount - 300 Sq Ft
	64	ROOM 1212	NONE DETECTED	527-JJT-50	SOUTHWEST CORNER BY SINK.	300 Sq Ft
XOL		Miscellaneous Material Dingy Yellow Countertops				Total Amount - 30 Sq Ft
	66	ROOM 1212	NONE DETECTED	527-JJT-54	NORTHWEST CORNER OF ROOM 1214 (SINCE REMOVED).	30 Sq Ft
XON		Miscellaneous Material Mirror Adhesive				Total Amount - 200 Sq Ft
	78	ROOM 1214	ASSUMED			200 Sq Ft
XOO		Miscellaneous Material White & Tan Cloud Designed Countertops				Total Amount - 60 Sq Ft
	73	ROOM 1213 (STAFF LOUNGE)	NONE DETECTED	527-JJT-60	NORTHEAST CORNER OF ROOM BY WINDOWS.	60 Sq Ft
XOQ		Miscellaneous Material Wire Window Glaze (1993)				Total Amount - 20 Sq Ft
	255	THROUGHOUT 1993 ADDITION	NONE DETECTED	112508MV-49		20 Sq Ft
XOR		Miscellaneous Material Dark Tan Countertops				Total Amount - 40 Sq Ft
	253	THROUGHOUT 1993 ADDITION	NONE DETECTED	527-JJT-83	ROOM 1313 SOUTHEAST CORNER BY SINK.	40 Sq Ft
XOS		Miscellaneous Material White w/Gray & Tan Dashes Countertops				Total Amount - 120 Sq Ft
	82	ROOM 1215	NONE DETECTED	527-JJT-57	SOUTHEAST CORNER OF ROOM.	120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOT		Miscellaneous Material Wired Window Glaze (2001)				Total Amount - 10 Sq Ft
	267	THROUGHOUT 2001 ADDITION	NONE DETECTED	112508MV-59	MV-58: ROOM 1323.	10 Sq Ft
XOU		Miscellaneous Material Kiln Gloves				Total Amount - 2 Sq Ft
	59	ROOMS 1210 (STORAGE) & 1210A	ASSUMED			2 Sq Ft
X1A		Miscellaneous Material Chalkboard Adhesive (1966)				Total Amount - 160 Sq Ft
	127	ROOM 1225	ASSUMED			40 Sq Ft
	131	ROOM 1230	ASSUMED			40 Sq Ft
	143	ROOM 2228	ASSUMED			40 Sq Ft
	146	ROOM 2225	ASSUMED			40 Sq Ft
X1B		Miscellaneous Material Metal Frame Chalkboard Adhesive (1962)				Total Amount - 240 Sq Ft
	97	ROOM 1219	ASSUMED			40 Sq Ft
	102	ROOM 1218	ASSUMED			20 Sq Ft
	105	ROOM 1220	ASSUMED			20 Sq Ft
	109	ROOM 1221	ASSUMED			40 Sq Ft
	163	ROOM 2221	ASSUMED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	168	ROOM 2220	ASSUMED			40 Sq Ft
	173	ROOM 2219	ASSUMED			40 Sq Ft
X1C	Miscellaneous Material Wood Frame Chalkboard Adhesive (1962)					Total Amount - 40 Sq Ft
	159	ROOM 2222	ASSUMED			40 Sq Ft
X1D	Miscellaneous Material Wood Frame Chalkboard Adhesive (1952)					Total Amount - 340 Sq Ft
	67	ROOM 1212	<1 CH			40 Sq Ft
	88	ROOM 1216	<1 CH			40 Sq Ft
	179	ROOM 2218	<1 CH			40 Sq Ft
	184	ROOM 2217	<1 CH	112508MV-21		40 Sq Ft
	188	ROOM 2216	<1 CH			40 Sq Ft
	193	ROOM 2215	<1 CH			40 Sq Ft
	198	ROOM 2214	<1 CH			40 Sq Ft
	203	ROOM 2213	<1 CH			40 Sq Ft
	208	ROOM 2212	<1 CH			20 Sq Ft
X1E	Miscellaneous Material Metal Frame Chalkboard Adhesive (1952)					Total Amount - 100 Sq Ft
	61	ROOM 1211	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	83	ROOM 1215	ASSUMED			20 Sq Ft
	211	ROOM 2212	ASSUMED			20 Sq Ft
	213	ROOM 2211	ASSUMED			40 Sq Ft
X1F	Miscellaneous Material Metal Frame Corkboard Adhesive (1952)					Total Amount - 290 Sq Ft
	62	ROOM 1211	ASSUMED			100 Sq Ft
	84	ROOM 1215	ASSUMED			150 Sq Ft
	214	ROOM 2211	ASSUMED			40 Sq Ft
X1G	Miscellaneous Material Wood Frame Corkboard Adhesive (1952)					Total Amount - 646 Sq Ft
	68	ROOM 1212	ASSUMED			10 Sq Ft
	79	ROOM 1214	ASSUMED			16 Sq Ft
	89	ROOM 1216	ASSUMED			100 Sq Ft
	180	ROOM 2218	ASSUMED			80 Sq Ft
	185	ROOM 2217	ASSUMED			80 Sq Ft
	189	ROOM 2216	ASSUMED			80 Sq Ft
	194	ROOM 2215	ASSUMED			80 Sq Ft
	199	ROOM 2214	ASSUMED			80 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	204	ROOM 2213	ASSUMED			80 Sq Ft
	209	ROOM 2212	ASSUMED			40 Sq Ft
X1H	Miscellaneous Material Metal Frame Corkboard Adhesive (1962)					Total Amount - 700 Sq Ft
	98	ROOM 1219	ASSUMED			100 Sq Ft
	101	ROOM 1218	ASSUMED			100 Sq Ft
	106	ROOM 1220	ASSUMED			100 Sq Ft
	110	ROOM 1221	ASSUMED			100 Sq Ft
	164	ROOM 2221	ASSUMED			100 Sq Ft
	169	ROOM 2220	ASSUMED			100 Sq Ft
	174	ROOM 2219	ASSUMED			100 Sq Ft
X1I	Miscellaneous Material Metal Frame Corkboard Adhesive (1966)					Total Amount - 430 Sq Ft
	128	ROOM 1225	ASSUMED			100 Sq Ft
	132	ROOM 1230	ASSUMED			100 Sq Ft
	144	ROOM 2228	ASSUMED			100 Sq Ft
	147	ROOM 2225	ASSUMED			100 Sq Ft
	152	ROOM 2223	ASSUMED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1J		Miscellaneous Material Wood Frame Corkboard Adhesive (1962)				Total Amount - 80 Sq Ft
	160	ROOM 2222	ASSUMED			80 Sq Ft
X1K		Miscellaneous Material Metal Frame Chalkboard Adhesive (1990)				Total Amount - 10 Sq Ft
	241	COMPUTER LAB/IMC (1111/1113)	NEW			10 Sq Ft
X1L		Miscellaneous Material Metal Frame Chalkboard Adhesive (1993)				Total Amount - 50 Sq Ft
	256	THROUGHOUT 1993 ADDITION	NEW			50 Sq Ft
X1M		Miscellaneous Material Metal Frame Corkboard Adhesive (1993)				Total Amount - 100 Sq Ft
	257	THROUGHOUT 1993 ADDITION	NEW			100 Sq Ft
X1N		Miscellaneous Material Multi-Size Ceramic Floor Tile System				Total Amount - 200 Sq Ft
	120	RESTROOM BY ROOM 1223	ASSUMED			200 Sq Ft
X1O		Miscellaneous Material 1" X 1" Blue Ceramic Wall Tile System				Total Amount - 10 Sq Ft
	121	RESTROOM BY ROOM 1223	ASSUMED			10 Sq Ft
X1P		Miscellaneous Material 1" X 1" Brown Ceramic Floor Tile System				Total Amount - 2400 Sq Ft
	8	THROUGHOUT 1952 ORIGINAL BUILDING RESTROOMS	ASSUMED			2400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1Q		Miscellaneous Material Multi Sized Blue Ceramic Floor Tile System				Total Amount - 250 Sq Ft
	156	1966 ADDITION 2ND FLOOR STAFF RESTROOM 2224A	ASSUMED			250 Sq Ft
X1R		Miscellaneous Material Multi Sized Beige Ceramic Wall Tile System				Total Amount - 750 Sq Ft
	157	1966 ADDITION 2ND FLOOR STAFF RESTROOM 2224A	ASSUMED			750 Sq Ft
X1S		Miscellaneous Material 2" X 2" Gray Ceramic Floor Tile System				Total Amount - 175 Sq Ft
	33	ROOM 1004B (NURSE RESTROOM)	NEW			75 Sq Ft
	268	THROUGHOUT 2001 ADDITION RESTROOMS	NEW			100 Sq Ft
X1T		Miscellaneous Material 4" X 4" Beige Ceramic Wall Tile System				Total Amount - 150 Sq Ft
	34	ROOM 1004B (NURSE RESTROOM)	ASSUMED			150 Sq Ft
X1U		Miscellaneous Material 4" X 4" White Ceramic Wall Tile System				Total Amount - 185 Sq Ft
	51	DRINKING FOUNTAINS ACCROSS FROM BOYS' RESTROOM 1208	ASSUMED			40 Sq Ft
	56	RESTROOM 1209A BY ROOM 1211	ASSUMED			100 Sq Ft
	218	STAFF RESTROOM 2210	ASSUMED			45 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1V		Miscellaneous Material 4" X 4" Blue Ceramic Wall Tile System				Total Amount - 525 Sq Ft
	50	BOYS' RESTROOM 1208	ASSUMED			70 Sq Ft
	57	RESTROOM 1209B BY ROOM 1211	ASSUMED			70 Sq Ft
	122	RESTROOM BY ROOM 1223	ASSUMED			160 Sq Ft
	225	1952 ORIGINAL BUILDING 2ND FLOOR BOYS' RESTROOM 2203	ASSUMED			225 Sq Ft
X1W		Miscellaneous Material 1" X 1" Salmon Ceramic Wall Tile System				Total Amount - 35 Sq Ft
	124	CUSTODIAL CLOSET 1228	ASSUMED			35 Sq Ft
X1X		Miscellaneous Material 6" X 6" Red Quarry Floor Tile System				Total Amount - 500 Sq Ft
	238	KITCHEN 1112	NEW			500 Sq Ft
X1Y		Miscellaneous Material 2" X 2" Light Brown Ceramic Floor Tile System				Total Amount - 500 Sq Ft
	258	THROUGHOUT 1993 ADDITION RESTROOMS	NEW			500 Sq Ft