

985 Ruth Street North, Saint Paul, MN 55119

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2A		Mudded Pipe Joints on Millboard Insulation 1958 Original Building				Total Amount - 12 Joints
	29	ROOM 1407	ASSUMED			2 Joints
	33	ROOM 1406	ASSUMED			2 Joints
	37	ROOM 1405	ASSUMED			2 Joints
	41	ROOM 1404	ASSUMED			2 Joints
	45	ROOM 1403	ASSUMED			2 Joints
	50	ROOM 1402	ASSUMED			2 Joints
A3A		Mudded Pipe Joints on Pre-formed Insulation 1958 Original Building				Total Amount - 2 Joints
	57	BOYS' RESTROOM 1402B	70 AM	328A2A		2 Joints
A4A		Mudded Pipe Joints on Fiberglass Insulation 1958 Original Building				Total Amount - 2 Joints
	64	RESTROOM 1307B	NONE DETECTED	121709ML-17		2 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
B2A	Millboard Pipe Insulation 1958 Original Building		Total Amount - 106 Lin Ft			
	28	ROOM 1407	5 CH, 10 AM, 10 CR	2001-01146-3	BOILER ROOM (WHITE OUTER LAYER)	16 Lin Ft
	32	ROOM 1406	5 CH, 10 AM, 10 CR			16 Lin Ft
	36	ROOM 1405	5 CH, 10 AM, 10 CR			16 Lin Ft
	40	ROOM 1404	5 CH, 10 AM, 10 CR			16 Lin Ft
	44	ROOM 1403	5 CH, 10 AM, 10 CR			16 Lin Ft
	49	ROOM 1402	5 CH, 10 AM, 10 CR			16 Lin Ft
	59	GIRLS' RESTROOM 1402A	5 CH, 10 AM, 10 CR			10 Lin Ft
B3A	Pre-Formed Pipe Insulation 1958 Original Building		Total Amount - 15 Lin Ft			
	48	ROOM 1402	20 CH, 30 AM			8 Lin Ft
	53	HALLWAY OUTSIDE ROOM 1402	20 CH, 30 AM	328A7A		1 Lin Ft
	56	BOYS' RESTROOM 1402B	20 CH, 30 AM			6 Lin Ft
D1A	Boiler Gaskets Burner Gasket (1992)		Total Amount - 2 Sq Ft			
	77	BOILER ROOM 2201	NONE DETECTED	121709ML-11		2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D2A	Interior Boiler Insulation Interior Refractory (1992)					Total Amount - 30 Sq Ft
78	BOILER ROOM 2201	ASSUMED				30 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Scattered Small Holes					Total Amount - 20000 Sq Ft
2	THROUGHOUT BUILDING	NONE DETECTED	2001-1501-NOK-5	NOK-5: END OF HALLWAY.		20000 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Chicken Scratch					Total Amount - 7500 Sq Ft
27	ROOMS 1305, 1307 & 1401-1407	NONE DETECTED	121709ML-09	ML-09: ROOM 1407.		7500 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Fissures w/Revealed Edge					Total Amount - 1200 Sq Ft
26	1958 ORIGINAL BUILDING HALLWAY 1400 FROM ROOMS 1401-1407	NONE DETECTED	121709ML-08	ML-08: OUTSIDE ROOM 1405.		1200 Sq Ft
I2E	2' x 2' Acoustical Ceiling Tile Small Pock Marks & Pin Holes (2011)					Total Amount - 270 Sq Ft
19	OFFICE RECEPTION	NEW				270 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Vinyl-Coated Gypsum (2015)					Total Amount - 700 Sq Ft
14	KITCHEN AREAS 1101-1104	NEW				700 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic White w/Multi-Colored Smudges (1992)					Total Amount - 5155 Sq Ft
18	CAFETERIA/GYMNASIUM 1111/1113	NONE DETECTED	121709ML-02	ML-02: STORAGE ROOM 1114.		4800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	22	ROOM 1006 WORK ROOM	NONE DETECTED			160 Sq Ft
	24	ROOM 1008 LOUNGE	NONE DETECTED			170 Sq Ft
	72	STORAGE ROOM 1305B	NONE DETECTED			25 Sq Ft
K3A	Miscellaneous Flooring 2' x 2' Multi-Colored Floor Tile (201X)					Total Amount - 20000 Sq Ft
	3	THROUGHOUT BUILDING	NEW			20000 Sq Ft
M0A	Plaster 1958 Original Building					Total Amount - 800 Sq Ft
	54	RESTROOMS 1402A & 1402B	NONE DETECTED			200 Sq Ft
	61	ROOM 1307	NONE DETECTED	121709ML-15, 16		300 Sq Ft
	67	ROOM 1305	NONE DETECTED	121709ML-14		300 Sq Ft
N0A	Drywall/Joint Compound					Total Amount - 10000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	511-H3		10000 Sq Ft
P0A	Fire Doors Wood - 1 Hr Rating (Warnock Hersey)					Total Amount - 200 Sq Ft
	10	THROUGHOUT BUILDING	NEW			200 Sq Ft
Q0B	Carpet Adhesive Multi-Colored Berber Carpet					Total Amount - 5000 Sq Ft
	12	THROUGHOUT 1958 ORIGINAL BUILDING	NONE DETECTED	121709ML-06	ML-06: MAIN OFFICE.	5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0C	Carpet Adhesive Carpet Squares (2012)					Total Amount - 10000 Sq Ft
	4	THROUGHOUT BUILDING	NEW			10000 Sq Ft
ROA	Baseboard/Mopboard Adhesive Blue Baseboard					Total Amount - 100 Sq Ft
	13	THROUGHOUT 1958 ORIGINAL BUILDING	NONE DETECTED	2001-1901-XX-11B	XX-11B: GYMNASIUM.	100 Sq Ft
ROB	Baseboard/Mopboard Adhesive 4" Dark Gray Baseboard (2012)					Total Amount - 500 Sq Ft
	5	THROUGHOUT BUILDING	NEW			500 Sq Ft
ROC	Baseboard/Mopboard Adhesive 4" Dark Brown Baseboard					Total Amount - 500 Sq Ft
	6	THROUGHOUT BUILDING	NEW			500 Sq Ft
VOA	Sink Undercoating Gray					Total Amount - 40 Sq Ft
	11	THROUGHOUT BUILDING	NONE DETECTED	121709ML-07	ML-07: TEACHERS' LOUNGE.	30 Sq Ft
	20	NURSE'S OFFICE	NONE DETECTED			5 Sq Ft
	25	ROOM 1008 LOUNGE	NONE DETECTED			5 Sq Ft
X0A	Miscellaneous Material Red Fire Stop					Total Amount - 200 Sq Ft
	7	THROUGHOUT BUILDING	NONE DETECTED	121709ML-03	ML-03: BOILER ROOM.	200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOB	Miscellaneous Material Wired Window Glaze (1992)		Total Amount - 100 Sq Ft			
8	THROUGHOUT BUILDING	NONE DETECTED	121709ML-05	ML-05: ROOM 1407.	100 Sq Ft	
XOC	Miscellaneous Material Wood Frame Chalkboard Adhesive		Total Amount - 140 Sq Ft			
30	ROOM 1407	ASSUMED			20 Sq Ft	
34	ROOM 1406	ASSUMED			20 Sq Ft	
38	ROOM 1405	ASSUMED			20 Sq Ft	
42	ROOM 1404	ASSUMED			20 Sq Ft	
46	ROOM 1403	ASSUMED			20 Sq Ft	
51	ROOM 1402	ASSUMED			20 Sq Ft	
62	ROOM 1307	ASSUMED			10 Sq Ft	
68	ROOM 1305	ASSUMED			10 Sq Ft	
XOD	Miscellaneous Material Wood Frame Corkboard Adhesive		Total Amount - 1040 Sq Ft			
31	ROOM 1407	ASSUMED			130 Sq Ft	
35	ROOM 1406	ASSUMED			130 Sq Ft	
39	ROOM 1405	ASSUMED			130 Sq Ft	
43	ROOM 1404	ASSUMED			130 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	47	ROOM 1403	ASSUMED			130 Sq Ft
	52	ROOM 1402	ASSUMED			130 Sq Ft
	63	ROOM 1307	ASSUMED			130 Sq Ft
	69	ROOM 1305	ASSUMED			130 Sq Ft
X0E	Miscellaneous Material Tectum					Total Amount - 1600 Sq Ft
	17	CAFETERIA/GYMNASIUM 1111/1113	NONE DETECTED	121709ML-10	ML-10: GYMNASIUM.	1600 Sq Ft
X0F	Miscellaneous Material Gray Duct Seam Cement					Total Amount - 5 Sq Ft
	79	BOILER ROOM 2201	NONE DETECTED	121709ML-01	ML-01: BOILER ROOM.	5 Sq Ft
X0G	Miscellaneous Material Milkboard Adhesive					Total Amount - 300 Sq Ft
	15	KITCHEN AREAS 1101-1104	NONE DETECTED	121709ML-12	ML-12: KITCHEN.	300 Sq Ft
X0H	Miscellaneous Material Tan Fire Stop					Total Amount - 30 Sq Ft
	9	THROUGHOUT BUILDING	NONE DETECTED	121709ML-13	ML-13: ROOM 1305.	30 Sq Ft
X1A	Miscellaneous Material 6" X 6" Quarry Tile System (200x)					Total Amount - 925 Sq Ft
	16	KITCHEN AREAS 1101-1104	NEW			700 Sq Ft
	73	STORAGE ROOM 1302	NEW			225 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1B		Miscellaneous Material 1" X 1" Green Ceramic Floor Tile System				Total Amount - 120 Sq Ft
	58	BOYS' RESTROOM 1402B	ASSUMED			120 Sq Ft
X1C		Miscellaneous Material 4" X 4" Green/Yellow Ceramic Wall Tile System				Total Amount - 480 Sq Ft
	55	RESTROOMS 1402A & 1402B	ASSUMED			400 Sq Ft
	65	RESTROOM 1307B	ASSUMED			40 Sq Ft
	70	RESTROOM 1305A	ASSUMED			40 Sq Ft
X1D		Miscellaneous Material Multi-Sized Ceramic Floor Tile System				Total Amount - 200 Sq Ft
	60	GIRLS' RESTROOM 1402A	ASSUMED			120 Sq Ft
	66	RESTROOM 1307B	ASSUMED			40 Sq Ft
	71	RESTROOM 1305A	ASSUMED			40 Sq Ft
X1E		Miscellaneous Material 2" X 2" Gray Ceramic Floor Tile System				Total Amount - 1020 Sq Ft
	21	NURSE'S OFFICE RESTROOM	NEW			50 Sq Ft
	23	ROOM 1006 WORK ROOM RESTROOM	NEW			75 Sq Ft
	74	RESTROOM 1208	NEW			45 Sq Ft
	75	RESTROOMS 1202A AND 1202B	NEW			400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	80	RESTROOMS 2202A AND 2202B	NEW			400 Sq Ft
	82	RESTROOM 2208A	NEW			50 Sq Ft
X1F	Miscellaneous Material 4" X 4" White Ceramic Wall Tile System					Total Amount - 800 Sq Ft
	76	RESTROOMS 1202A AND 1202B	NEW			600 Sq Ft
	81	RESTROOMS 2202A AND 2202B	NEW			200 Sq Ft