

707 Holly Avenue, Saint Paul, MN 55104

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A1B	Mudded Pipe Joints on Air Cell Insulation 1926 Addition					Total Amount - 21 Joints
	350	1926 ADDITION 2ND FLOOR HALLWAY 2200	ASSUMED			20 Joints
	395	1926 ADDITION 2ND FLOOR CUSTODIAL CLOSET 2203A	ASSUMED			1 Joints
A2A	Mudded Pipe Joints on Millboard Insulation 1925 Original Building					Total Amount - 2 Joints
	74	ROOM 1314	ASSUMED			2 Joints
A2B	Mudded Pipe Joints on Millboard Insulation 1926 Addition					Total Amount - 11 Joints
	334	1926 ADDITION 1ST FLOOR NORTH HALLWAY 1200B	35-40 CH	2001-1901-WMW-2A, 3A, 4A		11 Joints
A4D	Mudded Pipe Joints on Fiberglass Insulation 1975 Addition					Total Amount - 183 Joints
	146	1975 ADDITION HALLWAY 1300D	NONE DETECTED			20 Joints
	150	1975 ADDITION HALLWAY 1100	NONE DETECTED			75 Joints
	153	CUSTODIAL OFFICE 1115	NONE DETECTED			8 Joints
	154	CUSTODIAL STORAGE 1115A	NONE DETECTED			37 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	155	CUSTODIAL RESTROOM 1115B	NONE DETECTED			4 Joints
	156	ROOM 1116	NONE DETECTED			1 Joints
	162	ROOM 1117	NONE DETECTED			9 Joints
	182	MEDIA CENTER ROOM 1111	NONE DETECTED			2 Joints
	186	MEDIA CENTER ROOM 1110A (SERVER)	NONE DETECTED			1 Joints
	195	ROOM 1120	NONE DETECTED			1 Joints
	201	ROOM 1121	NONE DETECTED			14 Joints
	209	MAIN OFFICE 1002	NONE DETECTED	073108-MV-1, 2, 3	MV-1,2,3: ROOM 1001.	10 Joints
	224	CAFETERIA STORAGE 1107A	NONE DETECTED			1 Joints
B1A	Air Cell Pipe Insulation 1925 Original Building					Total Amount - 168 Lin Ft
	8	ROOM 1301	ASSUMED			8 Lin Ft
	14	ROOM 1302	ASSUMED			8 Lin Ft
	24	ROOM 1303	ASSUMED			8 Lin Ft
	30	ROOM 1306 & ASSOCIATED ROOMS	ASSUMED			4 Lin Ft
	36	ROOM 1307	ASSUMED			12 Lin Ft
	51	ROOM 1308	ASSUMED			12 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	56	CLOSET 1308A	ASSUMED			2 Lin Ft
	57	ROOM 1309	ASSUMED			10 Lin Ft
	69	ROOM 1312	ASSUMED			8 Lin Ft
	71	STORAGE 1312A	ASSUMED			4 Lin Ft
	72	ROOM 1312B	ASSUMED			4 Lin Ft
	84	ROOM 2301	ASSUMED			8 Lin Ft
	86	ROOM 2302	ASSUMED			8 Lin Ft
	89	ROOM 2303	ASSUMED			8 Lin Ft
	93	ROOM 2305 & CLOSET 2305A	ASSUMED			8 Lin Ft
	97	ROOM 2307	ASSUMED			8 Lin Ft
	100	ROOM 2308	ASSUMED			8 Lin Ft
	102	ROOM 2309	ASSUMED			8 Lin Ft
	104	ROOM 2310	ASSUMED			4 Lin Ft
	109	ROOM 2311	ASSUMED			8 Lin Ft
	112	ROOM 2312	ASSUMED			8 Lin Ft
	117	ROOM 2313	ASSUMED			8 Lin Ft
	121	ROOM 2314	ASSUMED			4 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
B1B	Air Cell Pipe Insulation 1926 Addition					Total Amount - 386 Lin Ft
	244	THROUGHOUT 1926 ADDITION 1ST & 2ND FLOOR ROOMS	20 CH	207H-8A		200 Lin Ft
	292	CUSTODIAL CLOSET 1207A	20 CH			15 Lin Ft
	349	1926 ADDITION 2ND FLOOR HALLWAY 2200	20 CH			150 Lin Ft
	394	1926 ADDITION 2ND FLOOR CUSTODIAL CLOSET 2203A	20 CH			16 Lin Ft
	402	1926 ADDITION 3RD FLOOR CUSTODIAL CLOSET 3203A	20 CH			5 Lin Ft
B2A	Millboard Pipe Insulation 1925 Original Building					Total Amount - 4 Lin Ft
	73	ROOM 1314	ASSUMED			4 Lin Ft
B2B	Millboard Pipe Insulation 1926 Addition					Total Amount - 92 Lin Ft
	293	CUSTODIAL CLOSET 1207A	NONE DETECTED	2001-1501-E2, E3	E-2,3: TUNNELS (SINCE REMOVED).	15 Lin Ft
	333	1926 ADDITION 1ST FLOOR NORTH HALLWAY 1200B	NONE DETECTED	033009ML-62		60 Lin Ft
	396	1926 ADDITION 2ND FLOOR CUSTODIAL CLOSET 2203A	NONE DETECTED			12 Lin Ft
	403	1926 ADDITION 3RD FLOOR CUSTODIAL CLOSET 3203A	NONE DETECTED			5 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
H1A	Sprayed-On Structural Fireproofing Gray (2002)		Total Amount - 2000 Sq Ft			
	230	THROUGHOUT 2002 ADDITION	NONE DETECTED	033009ML-44, 45, 46, 47, 48	ML-44: HALLWAY 1100A. ML-45: LOUNGE 1103A. ML-46: ROOM 1102. ML-47: ROOM 1103. ML-48: ROOM 1101.	2000 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Pegboard (1925)		Total Amount - 9410 Sq Ft			
	9	ROOM 1301	NONE DETECTED			660 Sq Ft
	15	ROOM 1302	NONE DETECTED			660 Sq Ft
	31	ROOM 1306 & ASSOCIATED ROOMS	NONE DETECTED			250 Sq Ft
	37	ROOM 1307	NONE DETECTED			900 Sq Ft
	45	1925 ORIGINAL BUILDING GYMNASIUM 1317	NONE DETECTED			2400 Sq Ft
	52	ROOM 1308	NONE DETECTED			900 Sq Ft
	58	ROOM 1309	NONE DETECTED			1000 Sq Ft
	90	ROOM 2303	NONE DETECTED	207H-15A		660 Sq Ft
	107	ROOM 2311	NONE DETECTED			660 Sq Ft
	113	ROOM 2312	NONE DETECTED			660 Sq Ft
	118	ROOM 2313	NONE DETECTED			660 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I1B	1' x 1' Acoustical Ceiling Tile Craters & Small Holes					Total Amount - 9300 Sq Ft
	157	ROOM 1116	NONE DETECTED			800 Sq Ft
	163	ROOM 1117	NONE DETECTED			120 Sq Ft
	167	ROOM 1114	NONE DETECTED			120 Sq Ft
	172	ROOM 1110 (MEDIA CENTER)	NONE DETECTED			1500 Sq Ft
	176	MEDIA CENTER ROOM 1113	NONE DETECTED			120 Sq Ft
	180	MEDIA CENTER ROOM 1112	NONE DETECTED			120 Sq Ft
	183	MEDIA CENTER ROOM 1111	NONE DETECTED			120 Sq Ft
	187	ROOM 1118	NONE DETECTED			300 Sq Ft
	191	ROOM 1119	NONE DETECTED			300 Sq Ft
	196	ROOM 1120	NONE DETECTED			800 Sq Ft
	202	ROOM 1121	NONE DETECTED			120 Sq Ft
	207	MAIN ENTRANCE 1000	NONE DETECTED			280 Sq Ft
	211	MAIN OFFICE 1002	NONE DETECTED	052008-BF-2		1500 Sq Ft
	221	CAFETERIA 1107 & STORAGE 1107A	NONE DETECTED			2500 Sq Ft
	226	KITCHEN 1104	NONE DETECTED	207H-13A		600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I1C	1' x 1' Acoustical Ceiling Tile Fissures w/Pin Holes					Total Amount - 3420 Sq Ft
	249	ROOM 1202	NONE DETECTED			140 Sq Ft
	317	ROOM 1221 (AUDITORIUM)	NONE DETECTED			320 Sq Ft
	341	ROOM 1220/1220A	NONE DETECTED	033009ML-67		1260 Sq Ft
	344	ROOM 2224	NONE DETECTED	2001-1901-WM1		1000 Sq Ft
	352	ROOM 2223	NONE DETECTED			300 Sq Ft
	355	BAND PRACTICE ROOMS 2226-2230	NONE DETECTED			150 Sq Ft
	357	ROOM 2222	NONE DETECTED			250 Sq Ft
I1D	1' x 1' Acoustical Ceiling Tile Pegboard (1926)					Total Amount - 3010 Sq Ft
	255	1926 ADDITION BASEMENT HALLWAY 0200/0200A	NONE DETECTED			400 Sq Ft
	264	ROOM 0217	NONE DETECTED			230 Sq Ft
	267	ROOM 0218	NONE DETECTED	207H-11A		1100 Sq Ft
	269	ROOM 0218A (KILN ROOM)	NONE DETECTED			100 Sq Ft
	278	CUSTODIAL STORAGE 0218B	NONE DETECTED			140 Sq Ft
	282	ELECTRICAL ROOM 0211	NONE DETECTED			120 Sq Ft
	365	ROOM 2216	NONE DETECTED			220 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	375	ROOM 2209	NONE DETECTED	510Y5		700 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Dents & Pin Holes w/Revealed Edge					Total Amount - 480 Sq Ft
	81	1975 ADDITION 2ND FLOOR EAST ELEVATOR LOBBY 2317	NONE DETECTED	207H-12A	12A: SMALL ROOM OFF MEDIA CENTER (SINCE REMOVED).	120 Sq Ft
	123	1975 ADDITION 3RD FLOOR EAST ELEVATOR LOBBY 3316	NONE DETECTED			120 Sq Ft
	397	1975 ADDITION 2ND FLOOR WEST ELEVATOR LOBBY 2202	NONE DETECTED			120 Sq Ft
	398	1975 ADDITION 3RD FLOOR WEST ELEVATOR LOBBY 3202	NONE DETECTED			120 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Small Gouges & Pin Holes					Total Amount - 6060 Sq Ft
	174	ROOM 1110 (MEDIA CENTER) & OFFICES	NONE DETECTED	033009ML-36	ML-36: NEAR ENTRY DOOR FROM HALLWAY.	1480 Sq Ft
	229	KITCHEN OFFICE 1106	NONE DETECTED			80 Sq Ft
	231	THROUGHOUT 2002 ADDITION	NONE DETECTED			2000 Sq Ft
	316	ROOM 1221 (AUDITORIUM)	NONE DETECTED			2500 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Rough Texture w/Revealed Edge (2008)					Total Amount - 3000 Sq Ft
	210	MAIN OFFICE 1002	NONE DETECTED	040209ML-83		3000 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Bumpy w/Small Holes					Total Amount - 5850 Sq Ft
	238	1975 ADDITION HALLWAY OUTSIDE ROOM 1101	NONE DETECTED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	254	1926 ADDITION BASEMENT HALLWAY 0200/0200A	NONE DETECTED	033009ML-50		2000 Sq Ft
	262	ROOM 0214	NONE DETECTED			700 Sq Ft
	273	ROOM 0213	NONE DETECTED	302-PHTA-2		810 Sq Ft
	275	ROOM 0212	NONE DETECTED	302-PHTB-5		910 Sq Ft
	303	HALLWAY 1200D	NONE DETECTED			280 Sq Ft
	306	ROOM 1226	NONE DETECTED			160 Sq Ft
	309	ROOM 1225	NONE DETECTED			120 Sq Ft
	313	ROOM 1224	NONE DETECTED	2001-1901-WMW-1A		150 Sq Ft
	374	ROOM 2209	NONE DETECTED			700 Sq Ft
I2E	2' x 2' Acoustical Ceiling Tile Gouges & Pin Holes in Concentric Pattern					Total Amount - 710 Sq Ft
	297	ROOMS 1210, 1211 & 1212	NONE DETECTED			350 Sq Ft
	299	ROOM 1213	NONE DETECTED	033009ML-59		120 Sq Ft
	301	ROOM 1214	NONE DETECTED			240 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Light Texture w/Revealed Edge (2010)					Total Amount - 3400 Sq Ft
	147	1975 ADDITION HALLWAY 1300D	NEW			770 Sq Ft
	151	1975 ADDITION HALLWAY 1100	NEW			2350 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	206	MAIN ENTRANCE 1000	NEW			280 Sq Ft
I3A	2' x 4' Ceiling Tile Dents & Pin Holes in Concentric Pattern					Total Amount - 860 Sq Ft
	75	ROOM 1314	NONE DETECTED	033009ML-18		160 Sq Ft
	77	ROOM 1313	NONE DETECTED			700 Sq Ft
I3B	2' x 4' Ceiling Tile Vinyl-Coated Gypsum					Total Amount - 1390 Sq Ft
	225	KITCHEN 1104	NSM			1100 Sq Ft
	236	ROOM 1103	NSM			290 Sq Ft
J3A	Miscellaneous Cementitious Material Black Lab Table Tops					Total Amount - 104 Sq Ft
	161	ROOM 1116	NONE DETECTED	033009ML-32		48 Sq Ft
	200	ROOM 1120	NONE DETECTED	399-BLKA-46; 399-BLKA-50		56 Sq Ft
J3B	Miscellaneous Cementitious Material Black Window Sills (2002)					Total Amount - 12 Sq Ft
	235	ROOM 1103A (LOUNGE)	NONE DETECTED	033009ML-42		12 Sq Ft
J3C	Miscellaneous Cementitious Material Black Slate Electrical Panel					Total Amount - 4 Sq Ft
	424	1926 ADDITION NORTH PENTHOUSE	NSM			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
KOA		9" x 9" Vinyl Floor Tile & Mastic Tan w/Brown & Beige Streaks				Total Amount - 2750 Sq Ft
	28	1925 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1300	7 CH (TILE), NONE DETECTED (MASTIC)	033009ML-08		800 Sq Ft
	34	ROOM 1306 & ASSOCIATED ROOMS	7 CH (TILE), NONE DETECTED (MASTIC)			350 Sq Ft
	82	1925 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2300	7 CH (TILE), NONE DETECTED (MASTIC)			800 Sq Ft
	127	1925 ORIGINAL BUILDING 3RD FLOOR HALLWAY 3300	7 CH (TILE), NONE DETECTED (MASTIC)			800 Sq Ft
KOB		9" x 9" Vinyl Floor Tile & Mastic Gray w/Pink & White Streaks				Total Amount - 900 Sq Ft
	39	ROOM 1307	5 CH (TILE & MASTIC)	033009ML-11		900 Sq Ft
KOC		9" x 9" Vinyl Floor Tile & Mastic Black w/White Streaks				Total Amount - 4 Sq Ft
	404	1926 ADDITION 3RD FLOOR CUSTODIAL CLOSET 3203A	3-6 CH (TILE)	040209ML-78; 033009ML-14	ML-78: CUSTODIAL CLOSET 1316 (SINCE REMOVED).	4 Sq Ft
KOD		9" x 9" Vinyl Floor Tile & Mastic Beige w/Tan Flecks				Total Amount - 50 Sq Ft
	79	ROOM 1313B	5 CH (TILE), 10 CH (MASTIC)	033009ML-21		50 Sq Ft
KOF		9" x 9" Vinyl Floor Tile & Mastic Brown w/Black & Beige Streaks				Total Amount - 490 Sq Ft
	266	ROOM 0217	5 CH (TILE)	033009ML-55	ML-55: ROOM 0218 (SINCE REMOVED).	230 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	280	CUSTODIAL STORAGE 0218B	5 CH (TILE)			140 Sq Ft
	284	ELECTRICAL ROOM 0211	5 CH (TILE)			120 Sq Ft
K0G	9" x 9" Vinyl Floor Tile & Mastic Tan w/Red & Butterscotch Streaks					Total Amount - 20 Sq Ft
	371	ROOM 2211A	7 CH (TILE)	033009ML-71	ML-71: ROOM 1217A (SINCE REMOVED).	20 Sq Ft
K0H	9" x 9" Vinyl Floor Tile & Mastic Tan w/Beige Marbling					Total Amount - 480 Sq Ft
	288	ROOM 0208	2 CH (TILE), 10 CH (MASTIC)	033009ML-57		450 Sq Ft
	289	STAFF RESTROOM 0207	2 CH (TILE), 10 CH (MASTIC)			30 Sq Ft
K0I	9" x 9" Vinyl Floor Tile & Mastic Dark Maroon					Total Amount - 8 Sq Ft
	320	ROOM 1221 (AUDITORIUM)	NONE DETECTED	033009ML-69; 399-CPA-75		8 Sq Ft
K0J	9" x 9" Vinyl Floor Tile & Mastic Gray					Total Amount - 4500 Sq Ft
	332	1926 ADDITION 1ST FLOOR HALLWAY 1200	15 CH (TILE)			1500 Sq Ft
	351	1926 ADDITION 2ND FLOOR HALLWAY 2200	15 CH (TILE)	040209ML-73	ML-73: OUTSIDE ROOM 2208.	1500 Sq Ft
	399	1926 ADDITION 3RD FLOOR HALLWAY 3200	15 CH (TILE)			1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
KOK		9" x 9" Vinyl Floor Tile & Mastic Light Brown w/Brown & Beige Streaks				Total Amount - 1200 Sq Ft
	390	ROOM 2204	2 CH (TILE), 8 CH (MASTIC)	040209ML-76		600 Sq Ft
	393	ROOM 2203	2 CH (TILE), 8 CH (MASTIC)			600 Sq Ft
KOM		9" x 9" Vinyl Floor Tile & Mastic Dark Green				Total Amount - 8 Sq Ft
	319	ROOM 1221 (AUDITORIUM)	NONE DETECTED	033009ML-68; 399-CPA-76		8 Sq Ft
KOQ		9" x 9" Vinyl Floor Tile & Mastic White with Gray Streaks and Flecks				Total Amount - 35 Sq Ft
	106	ROOM 2310 RESTROOM	ASSUMED			35 Sq Ft
K1A		Sheet Vinyl Flooring & Adhesive Gray Pebble Look				Total Amount - 397 Sq Ft
	11	ROOM 1301	NONE DETECTED			50 Sq Ft
	18	ROOM 1302	NONE DETECTED			30 Sq Ft
	26	ROOM 1303	NONE DETECTED	033009ML-09		30 Sq Ft
	29	1925 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1300	NONE DETECTED			20 Sq Ft
	41	ROOM 1307	NONE DETECTED			12 Sq Ft
	55	ROOM 1308	NONE DETECTED			50 Sq Ft
	61	ROOM 1309	NONE DETECTED			60 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	83	1925 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2300	NONE DETECTED			20 Sq Ft
	99	ROOM 2307	NONE DETECTED			20 Sq Ft
	111	ROOM 2311	NONE DETECTED			35 Sq Ft
	128	1925 ORIGINAL BUILDING 3RD FLOOR HALLWAY 3300	NONE DETECTED			20 Sq Ft
	132	ROOM 3304	NONE DETECTED			25 Sq Ft
	137	ROOM 3308	NONE DETECTED			25 Sq Ft
K1B	Sheet Vinyl Flooring & Adhesive Brown Pebble Pattern					Total Amount - 110 Sq Ft
	294	1926 ADDITION 1ST FLOOR HALLWAY 1200A	NONE DETECTED			10 Sq Ft
	335	1926 ADDITION 1ST FLOOR NORTH HALLWAY 1200B	NONE DETECTED			10 Sq Ft
	381	1926 ADDITION 2ND FLOOR HALLWAY 2200A	NONE DETECTED	040209ML-74		10 Sq Ft
	386	ROOM 2205	NONE DETECTED			12 Sq Ft
	400	1926 ADDITION 3RD FLOOR HALLWAY 3200A	NONE DETECTED			12 Sq Ft
	407	ROOM 3205	NONE DETECTED			10 Sq Ft
	417	ROOM 3209	NONE DETECTED			12 Sq Ft
	420	ROOM 3210	NONE DETECTED			12 Sq Ft
	426	ROOM 3213	NONE DETECTED			12 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	428	1926 ADDITION 3RD FLOOR HALLWAY 3200B	NONE DETECTED			10 Sq Ft
K2A		12" x 12" Vinyl Floor Tile & Mastic Beige w/Gray Flecks				Total Amount - 25 Sq Ft
	35	ROOM 1306 RESTROOM	NONE DETECTED	033009ML-30		25 Sq Ft
K2B		12" x 12" Vinyl Floor Tile & Mastic Tan Mottle				Total Amount - 1850 Sq Ft
	22	1925 ORIGINAL BUILDING SOUTH STAIRWELL	NONE DETECTED	033009ML-29	ML-29: BETWEEN 2ND & 3RD FLOORS.	330 Sq Ft
	251	ROOM 1202	NONE DETECTED			320 Sq Ft
	336	ROOM 1219	NONE DETECTED			1200 Sq Ft
K2C		12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown & White Streaks				Total Amount - 650 Sq Ft
	62	1925 ORIGINAL BUILDING NORTH STAIRWELL 1399B	3 CH (TILE), 5 CH (MASTIC)	033009ML-15		340 Sq Ft
	67	1925 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1300B	3 CH (TILE), 5 CH (MASTIC)			150 Sq Ft
	76	ROOM 1314	3 CH (TILE), 5 CH (MASTIC)			160 Sq Ft
K2D		12" x 12" Vinyl Floor Tile & Mastic Beige & Tan Mottle				Total Amount - 5985 Sq Ft
	68	ROOM 1311	NONE DETECTED	033009ML-16		200 Sq Ft
	148	1975 ADDITION HALLWAY 1300D	NONE DETECTED			770 Sq Ft
	152	1975 ADDITION HALLWAY 1100	NONE DETECTED			2350 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	159	ROOM 1116	NONE DETECTED			1000 Sq Ft
	189	ROOM 1118	NONE DETECTED			340 Sq Ft
	198	ROOM 1120	NONE DETECTED			1000 Sq Ft
	252	1926 ADDITION SOUTH STAIRWELL	NONE DETECTED			325 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic White w/Black Flecks					Total Amount - 50 Sq Ft
	95	RESTROOM 2304	NONE DETECTED	033009ML-24		50 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Beige w/Brown Streaks					Total Amount - 7388 Sq Ft
	149	1975 ADDITION HALLWAY 1300D	3-5 CH (TILE), 10 CH (MASTIC)			40 Sq Ft
	165	ROOM 1117	3-5 CH (TILE), 10 CH (MASTIC)	033009ML-33		180 Sq Ft
	185	MEDIA CENTER ROOM 1110A (SERVER)	3-5 CH (TILE), 10 CH (MASTIC)			160 Sq Ft
	204	ROOM 1121	3-5 CH (TILE), 10 CH (MASTIC)			180 Sq Ft
	239	1975 ADDITION HALLWAY OUTSIDE ROOM 1101	3-5 CH (TILE), 10 CH (MASTIC)			22 Sq Ft
	257	1926 ADDITION BASEMENT HALLWAY 0200/0200A	3-5 CH (TILE), 10 CH (MASTIC)			2360 Sq Ft
	263	ROOM 0214	3-5 CH (TILE), 10 CH (MASTIC)			700 Sq Ft
	274	ROOM 0213	3-5 CH (TILE), 10 CH (MASTIC)			810 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	276	ROOM 0212	3-5 CH (TILE), 10 CH (MASTIC)	033009ML-54	ML-54: BACK CORNER BY PIPE CHASE.	910 Sq Ft
	285	BASEMENT STAIRWELL 0299E (DEAD END)	3-5 CH (TILE), 10 CH (MASTIC)	033009ML-55		16 Sq Ft
	291	ROOM 0201 (ELEVATOR LOBBY)	3-5 CH (TILE), 10 CH (MASTIC)			110 Sq Ft
	296	ROOM 1209	3-5 CH (TILE), 10 CH (MASTIC)			600 Sq Ft
	298	ROOMS 1210, 1211 & 1212	3-5 CH (TILE), 10 CH (MASTIC)			350 Sq Ft
	302	ROOM 1214	3-5 CH (TILE), 10 CH (MASTIC)			240 Sq Ft
	304	HALLWAY 1200D	3-5 CH (TILE), 10 CH (MASTIC)			280 Sq Ft
	307	ROOM 1226	3-5 CH (TILE), 10 CH (MASTIC)			160 Sq Ft
	310	ROOM 1225	3-5 CH (TILE), 10 CH (MASTIC)			120 Sq Ft
	314	ROOM 1224	3-5 CH (TILE), 10 CH (MASTIC)			150 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Green Mottle (2002)					Total Amount - 599 Sq Ft
	178	MEDIA CENTER ROOM 1113	NONE DETECTED	040209ML-85		9 Sq Ft
	234	ROOM 1103A (LOUNGE)	NONE DETECTED			590 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Brown w/Multi-Colored Spots (2008)					Total Amount - 860 Sq Ft
	214	MAIN OFFICE 1018	NONE DETECTED	033009ML-40		430 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	216	MAIN OFFICE 1017	NONE DETECTED			430 Sq Ft
K2I	12" x 12" Vinyl Floor Tile & Mastic White w/Multi-Colored Flecks					Total Amount - 4520 Sq Ft
	223	CAFETERIA 1107 & STORAGE 1107A	NONE DETECTED	033009ML-41		3900 Sq Ft
	233	2002 ADDITION HALLWAY 1100A	NONE DETECTED			330 Sq Ft
	237	ROOM 1103	NONE DETECTED			290 Sq Ft
K2J	12" x 12" Vinyl Floor Tile & Mastic Beige w/Multi-Colored Flecks					Total Amount - 3750 Sq Ft
	245	1926 ADDITION WEST GYMNASIUM 1201	NONE DETECTED	040209ML-84		3750 Sq Ft
K2K	12" x 12" Vinyl Floor Tile & Mastic Tan w/Thin Brown & Beige Streaks					Total Amount - 50 Sq Ft
	326	ROOM 1215A - SERVER ROOM	2 CH (TILE), 10 CH (MASTIC)	033009ML-61		50 Sq Ft
K2L	12" x 12" Vinyl Floor Tile & Mastic Beige w/Brown Streaks					Total Amount - 1258 Sq Ft
	387	ROOM 2205	8 CH (MASTIC)			12 Sq Ft
	389	ROOM 2204	8 CH (MASTIC)	040209ML-75		600 Sq Ft
	392	ROOM 2203	8 CH (MASTIC)			600 Sq Ft
	408	ROOM 3205	8 CH (MASTIC)			10 Sq Ft
	418	ROOM 3209	8 CH (MASTIC)			12 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	421	ROOM 3210	8 CH (MASTIC)			12 Sq Ft
	427	ROOM 3213	8 CH (MASTIC)			12 Sq Ft
K2M	12" x 12" Vinyl Floor Tile & Mastic Light Brown w/Tan & Beige Mottle					Total Amount - 25 Sq Ft
	432	RESTROOM 3217	3 CH (MASTIC)	040209ML-82		25 Sq Ft
K2N	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (2009)					Total Amount - 200 Sq Ft
	122	ROOM 2314	NEW			140 Sq Ft
	142	ROOM 3313	NEW			60 Sq Ft
K2O	12" x 12" Vinyl Floor Tile & Mastic White w/Tan Flecks (2009)					Total Amount - 360 Sq Ft
	253	1926 ADDITION SOUTH STAIRWELL	NEW			360 Sq Ft
K2P	12" x 12" Vinyl Floor Tile & Mastic White with Brown Flecks (2020)					Total Amount - 34 Sq Ft
	258	1926 ADDITION BASEMENT HALLWAY 0200/0200A	NEW			34 Sq Ft
K3C	Miscellaneous Flooring Tan Border Tiles					Total Amount - 10 Sq Ft
	321	ROOM 1221 (AUDITORIUM)	NONE DETECTED	033009ML-70; 399-CPA-31		10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3D		Miscellaneous Flooring Dark Gray w/Raised Circles (2009)				Total Amount - 560 Sq Ft
	21	1925 ORIGINAL BUILDING SOUTH STAIRWELL	NEW			280 Sq Ft
	63	1925 ORIGINAL BUILDING NORTH STAIRWELL 1399B	NEW			280 Sq Ft
K3E		Miscellaneous Flooring Black Floor Tile Mastic (K0F)				Total Amount - 30 Sq Ft
	271	ROOM 0218A (KILN ROOM)	NONE DETECTED	033009-ML-54		30 Sq Ft
K3F		Miscellaneous Flooring Gray Vinyl Sheets (2020)				Total Amount - 300 Sq Ft
	217	NURSE'S OFFICE 1015	NEW			300 Sq Ft
L0A		Flexible Duct Connector Beige (1925)				Total Amount - 20 Sq Ft
	42	1925 ORIGINAL BUILDING BASEMENT FAN ROOM 0301	NONE DETECTED	2001-1504-X1		20 Sq Ft
L0B		Flexible Duct Connector Beige (1926)				Total Amount - 60 Sq Ft
	260	1926 ADDITION FAN ROOM 0216C	NONE DETECTED			15 Sq Ft
	261	1926 ADDITION FAN ROOM 0215	NONE DETECTED			10 Sq Ft
	290	1926 ADDITION BASEMENT FAN ROOM 0202	NONE DETECTED	033009ML-51		35 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOA		Plaster 1925 Original Building			Total Amount - 70000 Sq Ft	
	4	THROUGHOUT 1925 ORIGINAL BUILDING (EAST)	NONE DETECTED	033009-ML-01, 06, 17, 28; 2001-1501-E7; 578-8, 11	ML-01: OLD GIRLS' LOCKER ROOM 2316 WALL. ML-06: ROOM 1302 CEILING. ML-17: ROOM 1300B CEILING. ML-28: 3RD FLOOR SOUTH STAIRWELL WALL. E7: CUSTODIAL CLOSET BY ROOM 1308. 578-8: BASEMENT FAN ROOM STAIRWELL WALL. 578-11: ROOM 1309 CEILING.	70000 Sq Ft
MOB		Plaster 1926 Addition			Total Amount - 70000 Sq Ft	
	240	THROUGHOUT 1926 ADDITION (WEST)	NONE DETECTED	033009ML-49, 53, 58, 60; 040209ML-80, 81; 2001-1501-E15, E16; 578-4	ML-49: BASEMENT HALLWAY BY SOUTH STAIRWELL (CEILING). ML-53: ROOM 1W (CEILING). ML-58: ROOM 1213 WALL. ML-60: OLD STAGE CEILING ABOVE ROOM 1226. ML-80; 3RD FLOOR HALLWAY CEILING OUTSIDE ROOM 3213. ML-81: 2ND FLOOR CUSTODIAL CLOSET SOUTH. E15: CUSTODIAL CLOSET BY ROOM 1200D. E16: GYMNASIUM WALL. 578-4: CEILING ABOVE BOILER ROOM DOOR.	70000 Sq Ft
MOC		Plaster 1966 Addition			Total Amount - 225 Sq Ft	
	80	ROOM 1313A	NONE DETECTED	033009ML-20		225 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOD		Plaster 1975 Addition			Total Amount - 200 Sq Ft	
	232	2002 ADDITION HALLWAY 1100A	NONE DETECTED	033009ML-43		200 Sq Ft
NOA		Drywall/Joint Compound Renovation			Total Amount - 13000 Sq Ft	
	5	THROUGHOUT 1925 ORIGINAL BUILDING (EAST)	NONE DETECTED	2001-1501-E5; 578-2, 9, 10	2ND FLOOR ELEVATOR BY PIPE. 578-2: WOOD SHOP STORAGE. 578-9: OFFICE B. 578-10: GYMNASIUM STORAGE.	5000 Sq Ft
	241	THROUGHOUT 1926 ADDITION (WEST)	NONE DETECTED	2001-1501-E16	ENTRANCE BY GYMNASIUM	8000 Sq Ft
NOD		Drywall/Joint Compound 1975 Addition			Total Amount - 4000 Sq Ft	
	143	THROUGHOUT 1975 ADDITION	NONE DETECTED	2001-1501-E18; 578-1, 7	E18: KITCHEN RESTROOM BY HEATER. 578-1: CUSTODIAL CLOSET DECK. 578-7: MAIN OFFICE RESTROOM.	4000 Sq Ft
POA		Fire Doors Pieced Metal			Total Amount - 120 Sq Ft	
	259	1926 ADDITION BOILER ROOM 0216	NSM			100 Sq Ft
	286	BASEMENT STAIRWELL 0299E (DEAD END)	NSM			20 Sq Ft
QOA		Carpet Adhesive Green with White and Pink Berber Carpet (Yellow Adhesive)			Total Amount - 20000 Sq Ft	
	6	THROUGHOUT 1925 ORIGINAL BUILDING (EAST)	ASSUMED			20000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0B Carpet Adhesive Brown with Red Accents Berber Carpet (Yellow Adhesive)						Total Amount - 450 Sq Ft
169	ROOM 1114		ASSUMED			450 Sq Ft
Q0C Carpet Adhesive Multi Colored Striped Carpet Squares (20xx)						Total Amount - 1480 Sq Ft
175	ROOM 1110 (MEDIA CENTER) & OFFICES		NEW			1480 Sq Ft
Q0D Carpet Adhesive Blue with Red Accents Berber Carpet						Total Amount - 220 Sq Ft
193	ROOM 1119		ASSUMED			220 Sq Ft
R0A Baseboard/Mopboard Adhesive Various						Total Amount - 1000 Sq Ft
1	THROUGHOUT BUILDING		NONE DETECTED	2001-1901-XX-38B; 308-BR4A-65; 308-BR4B-66; 308-BRC-64; 308-BRNB-61; 308-BRA-62; 308-BLKA-56; 308-BLKB-57; 308-BLKA-60; 308-GRYA-67; 308-GRB-68; 308-BRB-63; 308-BLUB-59; 308-BLUA-58	308-BR4A-65: HALL 1200C. 308-BR4B-66: MUSIC. 308-BRC-64: WOOD SHOP. 308-BRNB-61: IMC. 308-BRB-63: THERAPY STORAGE. 308-GRB-68: WEST BUILDING NORTHEAST STORAGE.	1000 Sq Ft
R0B Baseboard/Mopboard Adhesive 4" Brown						Total Amount - 230 Sq Ft
160	ROOM 1116		ASSUMED			100 Sq Ft
190	ROOM 1118		ASSUMED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	199	ROOM 1120	ASSUMED			100 Sq Ft
ROC	Baseboard/Mopboard Adhesive 4" Black					Total Amount - 90 Sq Ft
	166	ROOM 1117	ASSUMED			20 Sq Ft
	170	ROOM 1114	ASSUMED			50 Sq Ft
	205	ROOM 1121	ASSUMED			20 Sq Ft
ROD	Baseboard/Mopboard Adhesive 4" Blue					Total Amount - 20 Sq Ft
	194	ROOM 1119	ASSUMED			20 Sq Ft
SOA	Wood Floor Felt / Vapor Barrier 1925 Original Building					Total Amount - 19420 Sq Ft
	12	ROOM 1301	ASSUMED			660 Sq Ft
	17	ROOM 1302	ASSUMED			660 Sq Ft
	25	ROOM 1303	ASSUMED			660 Sq Ft
	33	ROOM 1306 & ASSOCIATED ROOMS	ASSUMED			350 Sq Ft
	40	ROOM 1307	ASSUMED			900 Sq Ft
	48	1925 ORIGINAL BUILDING GYMNASIUM STORAGE 1317A	ASSUMED			70 Sq Ft
	50	CUSTODIAL CLOSET 1317B OFF GYMNASIUM 1317	ASSUMED			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	54	ROOM 1308	ASSUMED			900 Sq Ft
	60	ROOM 1309	ASSUMED			1000 Sq Ft
	66	1925 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1300B	ASSUMED			150 Sq Ft
	70	ROOM 1312	ASSUMED			900 Sq Ft
	85	ROOM 2301	ASSUMED			660 Sq Ft
	87	ROOM 2302	ASSUMED			660 Sq Ft
	92	ROOM 2303	ASSUMED			660 Sq Ft
	94	ROOM 2305 & CLOSET 2305A	ASSUMED			260 Sq Ft
	98	ROOM 2307	ASSUMED			660 Sq Ft
	101	ROOM 2308	ASSUMED			660 Sq Ft
	103	ROOM 2309	ASSUMED			660 Sq Ft
	105	ROOM 2310	ASSUMED			280 Sq Ft
	110	ROOM 2311	ASSUMED			660 Sq Ft
	115	ROOM 2312	ASSUMED			660 Sq Ft
	120	ROOM 2313	ASSUMED			660 Sq Ft
	124	ROOM 3301	ASSUMED			660 Sq Ft
	125	ROOM 3302	ASSUMED			660 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	130	ROOM 3303	ASSUMED			660 Sq Ft
	131	ROOM 3304	ASSUMED			350 Sq Ft
	133	ROOM 3305	ASSUMED			660 Sq Ft
	134	ROOM 3306	ASSUMED			660 Sq Ft
	135	ROOM 3307	ASSUMED			660 Sq Ft
	136	ROOM 3308	ASSUMED			350 Sq Ft
	138	ROOM 3309	ASSUMED			660 Sq Ft
	139	ROOM 3311	ASSUMED			660 Sq Ft
	141	ROOM 3312	ASSUMED			660 Sq Ft
SOAA	Wood Floor Felt / Vapor Barrier Renovation #1					Total Amount - 2400 Sq Ft
	47	1925 ORIGINAL BUILDING GYMNASIUM 1317	ASSUMED			2400 Sq Ft
SOB	Wood Floor Felt / Vapor Barrier 1926 Addition					Total Amount - 18840 Sq Ft
	246	PHY ED OFFICE 1206	NONE DETECTED			180 Sq Ft
	247	GYMNASIUM STORAGE 1205	NONE DETECTED	403-BLK-A	BLK-A: WEST GYMNASIUM (SINCE REMOVED).	180 Sq Ft
	248	GYMNASIUM STORAGE 1204	NONE DETECTED			330 Sq Ft
	300	ROOM 1213	NONE DETECTED			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	305	HALLWAY 1200D	NONE DETECTED			280 Sq Ft
	308	ROOM 1226	NONE DETECTED			160 Sq Ft
	311	ROOM 1225	NONE DETECTED			120 Sq Ft
	315	ROOM 1224	NONE DETECTED			150 Sq Ft
	327	ROOM 1215	NONE DETECTED			380 Sq Ft
	328	ROOM 1216	NONE DETECTED			380 Sq Ft
	329	ROOM 1217	NONE DETECTED			380 Sq Ft
	337	ROOM 1219	NONE DETECTED			1200 Sq Ft
	343	ROOM 1220/1220A	NONE DETECTED	033009ML-66	ML-66: CLOSET.	1260 Sq Ft
	354	ROOM 2223	NONE DETECTED			300 Sq Ft
	359	ROOM 2222	NONE DETECTED			250 Sq Ft
	360	ROOM 2221	NONE DETECTED			300 Sq Ft
	361	ROOM 2220	NONE DETECTED			250 Sq Ft
	362	ROOM 2219	NONE DETECTED			300 Sq Ft
	363	ROOM 2218	NONE DETECTED			250 Sq Ft
	364	ROOM 2217	NONE DETECTED			500 Sq Ft
	367	ROOM 2216	NONE DETECTED			220 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	369	ROOM 2210	NONE DETECTED			90 Sq Ft
	370	ROOM 2211	NONE DETECTED			105 Sq Ft
	373	ROOM 2212	NONE DETECTED			105 Sq Ft
	377	ROOM 2209	NONE DETECTED			700 Sq Ft
	382	ROOM 2208	NONE DETECTED			600 Sq Ft
	383	ROOM 2207	NONE DETECTED			600 Sq Ft
	385	ROOM 2205	NONE DETECTED			750 Sq Ft
	388	ROOM 2204	NONE DETECTED			600 Sq Ft
	391	ROOM 2203	NONE DETECTED			600 Sq Ft
	401	ROOM 3203	NONE DETECTED			600 Sq Ft
	405	ROOM 3204	NONE DETECTED			600 Sq Ft
	406	ROOM 3205	NONE DETECTED			750 Sq Ft
	411	ROOM 3207	NONE DETECTED			600 Sq Ft
	412	ROOM 3208	NONE DETECTED			900 Sq Ft
	416	ROOM 3209	NONE DETECTED			600 Sq Ft
	419	ROOM 3210	NONE DETECTED			600 Sq Ft
	425	ROOM 3213	NONE DETECTED			750 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	429	ROOM 3214	NONE DETECTED			600 Sq Ft
	430	ROOM 3215	NONE DETECTED			600 Sq Ft
	431	ROOM 3216	NONE DETECTED			600 Sq Ft
SOBB	Wood Floor Felt / Vapor Barrier Renovation #2					Total Amount - 3000 Sq Ft
	322	ROOM 1221 (AUDITORIUM)	ASSUMED			3000 Sq Ft
UOA	Light Pad Insulation Round Light Pads					Total Amount - 3 Sq Ft
	277	BASEMENT STAIRWELL WEST	65 CH	033009ML-56	ML-56: BASEMENT STAIRWELL 0299F (DEAD END) (SINCE REMOVED).	1 Sq Ft
	330	ROOM 1217A	65 CH			1 Sq Ft
	372	ROOM 2211A	65 CH			1 Sq Ft
UOB	Light Pad Insulation Suspended Light					Total Amount - 2 Sq Ft
	287	BASEMENT STAIRWELL 0299E	ASSUMED			2 Sq Ft
VOA	Sink Undercoating Off-White					Total Amount - 6 Sq Ft
	13	ROOM 1301	NONE DETECTED	033009ML-04		6 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOB		Sink Undercoating Gray w/Gooseneck Faucet				Total Amount - 6 Sq Ft
	19	ROOM 1302	NONE DETECTED	033009ML-07		6 Sq Ft
VOC		Sink Undercoating Black				Total Amount - 6 Sq Ft
	27	ROOM 1303	3 CH	033009ML-10		6 Sq Ft
VOD		Sink Undercoating Black w/Horizontal Faucet				Total Amount - 5 Sq Ft
	171	ROOM 1114	4 CH	033009ML-35		5 Sq Ft
VOE		Sink Undercoating Off-White w/Gooseneck Faucet				Total Amount - 3 Sq Ft
	179	MEDIA CENTER ROOM 1113	NONE DETECTED	033009ML-37		3 Sq Ft
VOF		Sink Undercoating Smooth Light Gray				Total Amount - 3 Sq Ft
	213	MAIN OFFICE 1002	NONE DETECTED	033009ML-38		3 Sq Ft
VOG		Sink Undercoating Rough Gray w/Gooseneck				Total Amount - 4 Sq Ft
	218	NURSE'S OFFICE 1015	NONE DETECTED	033009ML-39		4 Sq Ft
VOH		Sink Undercoating Gray w/Ball Faucet				Total Amount - 48 Sq Ft
	340	ROOM 1219	NONE DETECTED	033009ML-65		48 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1A	1' x 1' Ceiling Tile Adhesive Associated w/11A					Total Amount - 2200 Sq Ft
	10	ROOM 1301	NONE DETECTED			150 Sq Ft
	16	ROOM 1302	NONE DETECTED	033009ML-05		150 Sq Ft
	32	ROOM 1306 & ASSOCIATED ROOMS	NONE DETECTED			50 Sq Ft
	38	ROOM 1307	NONE DETECTED			200 Sq Ft
	46	1925 ORIGINAL BUILDING GYMNASIUM 1317	NONE DETECTED			600 Sq Ft
	53	ROOM 1308	NONE DETECTED			200 Sq Ft
	59	ROOM 1309	NONE DETECTED			250 Sq Ft
	91	ROOM 2303	NONE DETECTED			150 Sq Ft
	108	ROOM 2311	NONE DETECTED			150 Sq Ft
	114	ROOM 2312	NONE DETECTED			150 Sq Ft
	119	ROOM 2313	NONE DETECTED	033009ML-25		150 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/11B					Total Amount - 2230 Sq Ft
	158	ROOM 1116	NONE DETECTED			200 Sq Ft
	164	ROOM 1117	NONE DETECTED			30 Sq Ft
	168	ROOM 1114	NONE DETECTED	033009ML-34		30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	173	ROOM 1110 (MEDIA CENTER)	NONE DETECTED			350 Sq Ft
	177	MEDIA CENTER ROOM 1113	NONE DETECTED			30 Sq Ft
	181	MEDIA CENTER ROOM 1112	NONE DETECTED			30 Sq Ft
	184	MEDIA CENTER ROOM 1111	NONE DETECTED			30 Sq Ft
	188	ROOM 1118	NONE DETECTED			70 Sq Ft
	192	ROOM 1119	NONE DETECTED			70 Sq Ft
	197	ROOM 1120	NONE DETECTED			200 Sq Ft
	203	ROOM 1121	NONE DETECTED			30 Sq Ft
	208	MAIN ENTRANCE 1000	NONE DETECTED			60 Sq Ft
	212	MAIN OFFICE 1002	NONE DETECTED	052008-BF-2		350 Sq Ft
	222	CAFETERIA 1107 & STORAGE 1107A	NONE DETECTED			600 Sq Ft
	227	KITCHEN 1104	NONE DETECTED			150 Sq Ft
W1C	1' x 1' Ceiling Tile Adhesive Associated w/I1C					Total Amount - 765 Sq Ft
	250	ROOM 1202	NONE DETECTED			30 Sq Ft
	318	ROOM 1221 (AUDITORIUM)	NONE DETECTED			75 Sq Ft
	342	ROOM 1220/1220A	NONE DETECTED	033009ML-67		300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	345	ROOM 2224	NONE DETECTED			200 Sq Ft
	353	ROOM 2223	NONE DETECTED			75 Sq Ft
	356	BAND PRACTICE ROOMS 2226-2230	NONE DETECTED			35 Sq Ft
	358	ROOM 2222	NONE DETECTED			50 Sq Ft
W1D	1' x 1' Ceiling Tile Adhesive Associated w/I1D					Total Amount - 700 Sq Ft
	256	1926 ADDITION BASEMENT HALLWAY 0200/0200A	NONE DETECTED	033009ML-52		100 Sq Ft
	265	ROOM 0217	NONE DETECTED			50 Sq Ft
	268	ROOM 0218	NONE DETECTED			250 Sq Ft
	270	ROOM 0218A (KILN ROOM)	NONE DETECTED			20 Sq Ft
	279	CUSTODIAL STORAGE 0218B	NONE DETECTED			30 Sq Ft
	283	ELECTRICAL ROOM 0211	NONE DETECTED			30 Sq Ft
	366	ROOM 2216	NONE DETECTED			50 Sq Ft
	376	ROOM 2209	NONE DETECTED			170 Sq Ft
X0A	Miscellaneous Material White Mastic					Total Amount - 4 Sq Ft
	43	1925 ORIGINAL BUILDING BASEMENT FAN ROOM 0301	NONE DETECTED	033009ML-03		4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOB	Miscellaneous Material Pipe/Valve Flange Gaskets		Total Amount - 24 Sq Ft			
	44	1926 ADDITION TUNNEL LINK 0300	ASSUMED			24 Sq Ft
XOC	Miscellaneous Material White Marble Adhesive (1925)		Total Amount - 90 Sq Ft			
	20	1925 ORIGINAL BUILDING 1ST FLOOR GIRLS' RESTROOM 1319	NONE DETECTED			10 Sq Ft
	49	OLD LOCKER ROOMS 1318 & 1317C OFF GYMNASIUM 1317	NONE DETECTED	033009ML-02		20 Sq Ft
	65	1925 ORIGINAL BUILDING 1ST FLOOR BOYS' RESTROOM 1315	NONE DETECTED			10 Sq Ft
	88	1925 ORIGINAL BUILDING 2ND FLOOR GIRLS' RESTROOM 2316	NONE DETECTED			10 Sq Ft
	96	RESTROOM 2304	NONE DETECTED			10 Sq Ft
	116	1925 ORIGINAL BUILDING 2ND FLOOR BOYS' RESTROOM 2315	NONE DETECTED			10 Sq Ft
	126	1925 ORIGINAL BUILDING 3RD FLOOR GIRLS' RESTROOM 3315	NONE DETECTED			10 Sq Ft
	140	1925 ORIGINAL BUILDING 3RD FLOOR BOYS' RESTROOM 3314	NONE DETECTED			10 Sq Ft
XOD	Miscellaneous Material Slate Chalkboard Adhesive (1925)		Total Amount - 250 Sq Ft			
	2	THROUGHOUT 1925 ORIGINAL BUILDING	NONE DETECTED	033009ML-27	ML-27: ROOM 3202.	250 Sq Ft
XOE	Miscellaneous Material Dark Brown Tackboard Adhesive		Total Amount - 1000 Sq Ft			
	3	THROUGHOUT 1925 ORIGINAL BUILDING	NONE DETECTED	033009ML-22	ML-22: LOOSE PANEL IN ROOM 1314.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0F	Miscellaneous Material Trowelled Brown Adhesive on Brown Chalkboard (1975)					Total Amount - 200 Sq Ft
	145	THROUGHOUT 1975 ADDITION	NONE DETECTED	033009ML-19	ML-19: OFFICE CHALKBOARD REMOVED & STORED IN ROOM 1314.	200 Sq Ft
X0G	Miscellaneous Material Vermiculite Fill					Total Amount - 7000 Sq Ft
	144	THROUGHOUT 1975 ADDITION	<1 ACT	082715JP-01, 02, 03; 033009ML-23	JP-01: ROOM 1115B (CUSTODIAL RESTROOM). JP-02: 2ND FLOOR ELEVATOR LOBBY 2317. JP-03: 3RD FLOOR ELEVATOR LOBBY. ML-23: 2ND FLOOR ELEVATOR LOBBY 2317.	7000 Sq Ft
X0H	Miscellaneous Material Gray Window Glazing					Total Amount - 4 Sq Ft
	129	1925 ORIGINAL BUILDING PENTHOUSE (3302A)	NONE DETECTED	033009ML-26		4 Sq Ft
X0I	Miscellaneous Material Coarse White Asbestos Gloves					Total Amount - 6 Sq Ft
	272	ROOM 0218A (KILN ROOM)	ASSUMED			6 Sq Ft
X0J	Miscellaneous Material White Marble Adhesive (1926)					Total Amount - 85 Sq Ft
	295	BOYS' RESTROOM 1208	NONE DETECTED			10 Sq Ft
	331	1926 ADDITION 1ST FLOOR GIRLS' RESTROOM 1218	NONE DETECTED			15 Sq Ft
	368	1926 ADDITION 2ND FLOOR GIRLS' RESTROOM 2215	NONE DETECTED	040209ML-72		15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	384	1926 ADDITION 2ND FLOOR BOYS' RESTROOM 2206	NONE DETECTED			15 Sq Ft
	409	1926 ADDITION 3RD FLOOR BOYS' RESTROOM 3206	NONE DETECTED			15 Sq Ft
	422	1926 ADDITION 3RD FLOOR GIRLS' RESTROOM 3212	NONE DETECTED			15 Sq Ft
XOK		Miscellaneous Material Olive w/Brown & Beige Marbling Countertops				Total Amount - 130 Sq Ft
	338	ROOM 1219	NONE DETECTED	033009ML-64		130 Sq Ft
XOL		Miscellaneous Material Tan Terrazzo-Look Countertops				Total Amount - 60 Sq Ft
	339	ROOM 1219	35 CH	033009ML-63		60 Sq Ft
XOM		Miscellaneous Material Slate Chalkboard Adhesive (1926)				Total Amount - 300 Sq Ft
	242	THROUGHOUT 1926 ADDITION (WEST)	NONE DETECTED	040209ML-79	ML-79: LOOSE CHALKBOARD IN SOUTH PENTHOUSE.	300 Sq Ft
XON		Miscellaneous Material Tackboard Adhesive (1926)				Total Amount - 1200 Sq Ft
	243	THROUGHOUT 1926 ADDITION (WEST)	ASSUMED			1200 Sq Ft
XOO		Miscellaneous Material Red Window Glaze (1926)				Total Amount - 4 Sq Ft
	410	1926 ADDITION SOUTH PENTHOUSE	NONE DETECTED	040209ML-77		2 Sq Ft
	423	1926 ADDITION NORTH PENTHOUSE	NONE DETECTED			2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOP	Miscellaneous Material Exterior Door & Transom Caulk (1925)					Total Amount - 16 Sq Ft
7	1925 ORIGINAL BUILDING 1ST FLOOR ENTRANCES	3 CH	051712-MV-01	MV-01: ROOM 1303 DOOR TRANSOM.	16 Sq Ft	
XOQ	Miscellaneous Material Gray Interior Wood Window Glaze (1926)					Total Amount - 36 Sq Ft
323	ROOM 1221 (AUDITORIUM)	<1 CH	051712-MV-02, 04	MV-02: ROOM 2224. MN-04: ROOM 3208.	24 Sq Ft	
346	ROOM 2224	<1 CH			6 Sq Ft	
378	WEST STAIRWELL LANDING	<1 CH			3 Sq Ft	
413	ROOM 3208	<1 CH			3 Sq Ft	
XOR	Miscellaneous Material Brown Interior Wood Window Glaze (1926)					Total Amount - 36 Sq Ft
324	ROOM 1221 (AUDITORIUM)	NONE DETECTED	051712-MV-05	MV-05: ROOM 3208.	24 Sq Ft	
347	ROOM 2224	NONE DETECTED			6 Sq Ft	
379	WEST STAIRWELL LANDING	NONE DETECTED			3 Sq Ft	
414	ROOM 3208	NONE DETECTED			3 Sq Ft	
XOS	Miscellaneous Material Brown Interior Wood Window Caulk (1926)					Total Amount - 36 Sq Ft
325	ROOM 1221 (AUDITORIUM)	NONE DETECTED	051712-MV-03	MV-03: ROOM 2224.	24 Sq Ft	
348	ROOM 2224	NONE DETECTED			6 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	380	WEST STAIRWELL LANDING	NONE DETECTED			3 Sq Ft
	415	ROOM 3208	NONE DETECTED			3 Sq Ft
X1A	Miscellaneous Material 6" X 6" Quarry Floor Tile System					Total Amount - 1100 Sq Ft
	228	KITCHEN 1104	ASSUMED			1100 Sq Ft
X1B	Miscellaneous Material 1" X 1" Tan/Brown Ceramic Floor Tile System					Total Amount - 170 Sq Ft
	215	MAIN OFFICE RESTROOMS	ASSUMED			60 Sq Ft
	219	NURSE'S OFFICE 1011 RESTROOM	ASSUMED			60 Sq Ft
	312	ROOM 1225 RESTROOM	ASSUMED			50 Sq Ft
X1C	Miscellaneous Material 6" X 6" Red Quarry Tile System					Total Amount - 260 Sq Ft
	23	1925 ORIGINAL BUILDING SOUTH STAIRWELL	ASSUMED			130 Sq Ft
	64	1925 ORIGINAL BUILDING NORTH STAIRWELL 1399B	ASSUMED			130 Sq Ft
X1D	Miscellaneous Material Brown 6" X 6" 1966 Quarry Tile System					Total Amount - 700 Sq Ft
	78	ROOM 1313	ASSUMED			700 Sq Ft
X1F	Miscellaneous Material 2" X 2" Gray with White Specks					Total Amount - 45 Sq Ft
	220	NURSE'S OFFICE 1012 RESTROOM	ASSUMED			45 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1G	Miscellaneous Material 2' X 2' Tan Ceramic Floor Tile System	CUSTODIAL STORAGE 0210	ASSUMED			Total Amount - 130 Sq Ft
281						