

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2B		Mudded Pipe Joints on Millboard Insulation 1964 Addition				Total Amount - 6 Joints
	163	1964 ADDITION 1ST FLOOR HALLWAY 1300	ASSUMED			2 Joints
	194	1964 ADDITION 2ND FLOOR HALLWAY 2300	ASSUMED			1 Joints
	206	ROOM 2302A	ASSUMED			3 Joints
A3B		Mudded Pipe Joints on Pre-formed Insulation 1964 Addition				Total Amount - 22 Joints
	161	1964 ADDITION 1ST FLOOR HALLWAY 1300A	ASSUMED			22 Joints
B2A		Millboard Pipe Insulation 1926 Original Building				Total Amount - 1 Lin Ft
	9	ENTRY TO FAN ROOM 0202	5 CH	2001-01152-2		1 Lin Ft
B2B		Millboard Pipe Insulation 1964 Addition				Total Amount - 249 Lin Ft
	162	1964 ADDITION 1ST FLOOR HALLWAY 1300	40 CH	041609ML-36		50 Lin Ft
	164	AUDITORIUM/CAFETERIA 1302	40 CH			30 Lin Ft
	169	1964 ADDITION GYMNASIUM 1306	40 CH			40 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	178	BOYS' LOCKER ROOM	40 CH			1 Lin Ft
	193	1964 ADDITION 2ND FLOOR HALLWAY 2300	40 CH			38 Lin Ft
	198	ROOM 2302	40 CH			40 Lin Ft
	205	ROOM 2302A	40 CH			50 Lin Ft
B3B	Pre-Formed Pipe Insulation 1964 Addition					Total Amount - 150 Lin Ft
	160	1964 ADDITION 1ST FLOOR HALLWAY 1300A	20 AM	ACB450X-A8	A8: ROOM 2302A.	150 Lin Ft
F2A	Exterior Duct Insulation Thick Black Tar Layer					Total Amount - 140 Sq Ft
	12	FAN ROOM 0104 OFF BOILER ROOM	NONE DETECTED	041409ML-03		140 Sq Ft
F2B	Exterior Duct Insulation Thin Black Tar Layer					Total Amount - 100 Sq Ft
	13	FAN ROOM 0104 OFF BOILER ROOM	NONE DETECTED	041409ML-04		100 Sq Ft
F2C	Exterior Duct Insulation Soft Plaster w/Vermiculite					Total Amount - 20 Sq Ft
	207	ROOM 2302A	30 CH	041609ML-38; 2001-1501-K-5, 6, 7		20 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Glacial					Total Amount - 4850 Sq Ft
	10	ENTRY TO FAN ROOM 0202	NONE DETECTED	041409ML-05		40 Sq Ft
	22	1926 ORIGINAL BUILDING BASEMENT HALLWAY	NONE DETECTED			1200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	25	ROOM 0204	NONE DETECTED			1900 Sq Ft
	28	ROOM 0206 (STORAGE)	NONE DETECTED			200 Sq Ft
	31	ROOM 0207	NONE DETECTED			600 Sq Ft
	58	ROOM 0210 (STORAGE)	NONE DETECTED	041409ML-11		90 Sq Ft
	61	ROOM 0208	NONE DETECTED			260 Sq Ft
	64	ROOM 0209 (STORAGE)	NONE DETECTED			120 Sq Ft
	69	MUSIC PRACTICE ROOMS & OFFICES 1207-1210	NONE DETECTED	345-18		440 Sq Ft
11B	1' x 1' Acoustical Ceiling Tile Flat Glacial					Total Amount - 16725 Sq Ft
	149	1991 ADDITION MEDIA CENTER 1213	NONE DETECTED	041409ML-08	ML-08: STAIRWELL 0099B (SINCE REMOVED).	625 Sq Ft
	157	1964 ADDITION 1ST FLOOR HALLWAYS 1300 & 1300A	NONE DETECTED			1200 Sq Ft
	165	AUDITORIUM/CAFETERIA 1302	NONE DETECTED	ACB450X-A1		4700 Sq Ft
	170	1964 ADDITION GYMNASIUM 1306	NONE DETECTED	345-19		6000 Sq Ft
	190	1964 ADDITION 2ND FLOOR HALLWAY 2200	NONE DETECTED			800 Sq Ft
	195	1964 ADDITION 2ND FLOOR HALLWAY 2300	NONE DETECTED			300 Sq Ft
	199	ROOM 2302	NONE DETECTED			900 Sq Ft
	208	ROOM 2303	NONE DETECTED			800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	212	ROOM 2304	NONE DETECTED			300 Sq Ft
	216	ROOM 2305	NONE DETECTED			1100 Sq Ft
I1D	1' x 1' Acoustical Ceiling Tile Pegboard (1926)					Total Amount - 1125 Sq Ft
	91	ROOM 1106	NONE DETECTED	041409ML-17		1000 Sq Ft
	167	AUDITORIUM/CAFETERIA SOUTHWEST STORAGE 1302A	NONE DETECTED			125 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Glacial w/Revealed Edge					Total Amount - 5050 Sq Ft
	102	ROOM 2111	NONE DETECTED			660 Sq Ft
	117	ROOM 2109	NONE DETECTED			660 Sq Ft
	120	ROOM 2108	NONE DETECTED	041409ML-24		660 Sq Ft
	123	ROOM 2105	NONE DETECTED			660 Sq Ft
	133	ROOM 3107	NONE DETECTED			1080 Sq Ft
	135	ROOM 3109	NONE DETECTED			150 Sq Ft
	137	ROOM 3108	NONE DETECTED			100 Sq Ft
	140	ROOM 3110	NONE DETECTED			1080 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3A	2' x 4' Ceiling Tile Craters & Pin Holes (1991)					Total Amount - 10590 Sq Ft
	68	1926 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1200	NONE DETECTED			500 Sq Ft
	72	ROOM 1205 (CHOIR)	NONE DETECTED			1300 Sq Ft
	77	ROOM 1212 (BAND)	NONE DETECTED			1400 Sq Ft
	90	ROOM 1106	NONE DETECTED			1000 Sq Ft
	93	ROOM 1107	NONE DETECTED			350 Sq Ft
	95	ROOM 1108	NONE DETECTED			320 Sq Ft
	96	HALLWAY H2 OUTSIDE ROOMS 1107-1108	NONE DETECTED			270 Sq Ft
	108	STAFF LOUNGE 2110	NONE DETECTED			400 Sq Ft
	111	STAFF WORK ROOM 2107	NONE DETECTED	345-16		600 Sq Ft
	148	1991 ADDITION MEDIA CENTER 1213	NONE DETECTED			2000 Sq Ft
	187	HALLWAY OUTSIDE 1977 GYMNASIUM	NONE DETECTED			200 Sq Ft
	188	1991 ADDITION 2ND FLOOR ROOMS 2201-2204 & FOYER 2200	NONE DETECTED			2000 Sq Ft
	221	1991 ADDITION STAIRWELL BY ROOM 2305	NONE DETECTED			250 Sq Ft
I3B	2' x 4' Ceiling Tile Widthwise Fissures & Pin Holes (1991)					Total Amount - 7510 Sq Ft
	19	BASEMENT HALLWAY 0201A OUTSIDE ELEVATOR	NONE DETECTED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	30	ROOM 0207	NONE DETECTED			200 Sq Ft
	37	ROOM 0105	NONE DETECTED			1260 Sq Ft
	39	ROOM 0106	NONE DETECTED			160 Sq Ft
	43	ROOM 0107	NONE DETECTED			720 Sq Ft
	47	ROOM 0108	NONE DETECTED	2001-1504-HH8		720 Sq Ft
	51	ROOM 0109	NONE DETECTED			875 Sq Ft
	55	ROOM 0109A	NONE DETECTED			30 Sq Ft
	60	ROOM 0208	NONE DETECTED			260 Sq Ft
	66	1ST FLOOR STAFF RESTROOMS BY CUSTODIAL OFFICE	NONE DETECTED			85 Sq Ft
	85	ADMINISTRATION OFFICES ROOM 1004	NONE DETECTED			3000 Sq Ft
	106	ROOM 2119	NONE DETECTED			160 Sq Ft
I3C	2' x 4' Ceiling Tile Pin Holes					Total Amount - 6700 Sq Ft
	83	ROOM 1102	NONE DETECTED			660 Sq Ft
	84	ROOM 1101	NONE DETECTED			660 Sq Ft
	98	ROOM 2114	NONE DETECTED			660 Sq Ft
	99	ROOM 2116	NONE DETECTED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	101	ROOM 2112	NONE DETECTED			660 Sq Ft
	126	ROOM 2103	NONE DETECTED	041409ML-25		660 Sq Ft
	127	ROOM 2101	NONE DETECTED			660 Sq Ft
	129	ROOM 3101	NONE DETECTED			660 Sq Ft
	130	ROOM 3103	NONE DETECTED			660 Sq Ft
	142	ROOM 3114	NONE DETECTED			660 Sq Ft
	145	ROOM 3116	NONE DETECTED			660 Sq Ft
J3A	Miscellaneous Cementitious Material Slate Window Sills					Total Amount - 31 Sq Ft
	94	ROOM 1106	NONE DETECTED	041409ML-18		20 Sq Ft
	219	ROOM 2305	NONE DETECTED	345-1		9 Sq Ft
	222	1991 ADDITION STAIRWELL BY ROOM 2305	NONE DETECTED			2 Sq Ft
J3B	Miscellaneous Cementitious Material Black Lab Tabletop w/o Drip Edge					Total Amount - 50 Sq Ft
	131	ROOM 3103	NONE DETECTED	041409ML-26		50 Sq Ft
J3C	Miscellaneous Cementitious Material Old Black Sink					Total Amount - 6 Sq Ft
	143	ROOM 3114	NONE DETECTED	041409ML-29		6 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K0A	9" x 9" Vinyl Floor Tile & Mastic Tan w/White Streaks		Total Amount - 1800 Sq Ft			
	73	ROOM 1205 (CHOIR)	10 CH (TILE & MASTIC)	041409ML-15		800 Sq Ft
	78	ROOM 1212 (BAND)	10 CH (TILE & MASTIC)			1000 Sq Ft
K0B	9" x 9" Vinyl Floor Tile & Mastic Tan w/Dark Brown & Beige Streaks		Total Amount - 120 Sq Ft			
	210	ROOM 2303	1-3 CH (TILE), 5 CH (MASTIC)	041609ML-39; 2001-1901-RJH-3	ML-39: UNDER SINK. SAMPLE 39 ANALYZED AT 5 CH (MASTIC ONLY). RJH-3: ROOM 2305 (SINCE REMOVED).	120 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic White w/Thin Brown Streaks		Total Amount - 160 Sq Ft			
	105	ROOM 2119	3 CH (TILE)	041409ML-07	ML-07: ELEVATOR (SINCE REMOVED).	160 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic Beige w/Black Specks		Total Amount - 2592 Sq Ft			
	100	ROOM 2116	NONE DETECTED			42 Sq Ft
	134	ROOM 3107	NONE DETECTED	041409ML-27	ML-27: ROOM 3107 UNDER CENTRAL ISLAND.	1150 Sq Ft
	136	ROOM 3109	NONE DETECTED			150 Sq Ft
	138	ROOM 3108	NONE DETECTED			100 Sq Ft
	141	ROOM 3110	NONE DETECTED			1150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2C	12" x 12" Vinyl Floor Tile & Mastic Tan w/Beige Mottle (1995)					Total Amount - 5860 Sq Ft
	109	STAFF LOUNGE 2110	NONE DETECTED	345-17		70 Sq Ft
	112	STAFF WORK ROOM 2107	NONE DETECTED			600 Sq Ft
	159	1964 ADDITION 1ST FLOOR HALLWAYS 1300 & 1300A	NONE DETECTED			1300 Sq Ft
	197	1964 ADDITION 2ND FLOOR HALLWAY 2300	NONE DETECTED			450 Sq Ft
	201	ROOM 2302	NONE DETECTED			980 Sq Ft
	211	ROOM 2303	NONE DETECTED			800 Sq Ft
	214	ROOM 2304	NONE DETECTED			420 Sq Ft
	215	STAIR LANDING OUTSIDE ROOM 2304	NONE DETECTED			20 Sq Ft
	218	ROOM 2305	NONE DETECTED			1100 Sq Ft
	220	ROOM 2305A	NONE DETECTED			120 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic Gray w/Dark Gray & White Streaks					Total Amount - 4600 Sq Ft
	172	1964 ADDITION GYMNASIUM 1306	NONE DETECTED	041409ML-30	ML-30: AUDITORIUM/CAFETERIA 1302 AT EAST RADIATOR (SINCE REMOVED).	4600 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (1991)					Total Amount - 1320 Sq Ft
	147	1964 ADDITION HALLWAY 1299E	NONE DETECTED	041609ML-44	ML-44: UNDER STAIRS.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	189	1991 ADDITION 2ND FLOOR FOYER 2200	NONE DETECTED			120 Sq Ft
	192	1964 ADDITION 2ND FLOOR HALLWAY 2100B	NONE DETECTED			200 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (1991)					Total Amount - 150 Sq Ft
	152	1991 ADDITION SERVER ROOM 1214	NONE DETECTED	041609ML-43		150 Sq Ft
K3A	Miscellaneous Flooring 2' x 2' Gray Floor Tile					Total Amount - 6020 Sq Ft
	24	1926 ORIGINAL BUILDING BASEMENT HALLWAY	NONE DETECTED	041609ML-42	ML-42: AT DOOR TO ROOM 0204.	1200 Sq Ft
	33	ROOM 0207	NONE DETECTED			875 Sq Ft
	36	STAIRWELL 0099B	NONE DETECTED			50 Sq Ft
	38	ROOM 0105	NONE DETECTED			1260 Sq Ft
	44	ROOM 0107	NONE DETECTED			720 Sq Ft
	48	ROOM 0108	NONE DETECTED			720 Sq Ft
	52	ROOM 0109	NONE DETECTED			875 Sq Ft
	57	STAIRWELL 0099A	NONE DETECTED			60 Sq Ft
	63	ROOM 0208	NONE DETECTED			260 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3B		Miscellaneous Flooring 20" x 20" Tan Marble Look Tiles (1995)				Total Amount - 3600 Sq Ft
	82	1926 ORIGINAL BUILDING 1ST FLOOR MAIN HALLWAY 1000	NONE DETECTED	041409ML-21		1200 Sq Ft
	97	1926 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2100	NONE DETECTED			1200 Sq Ft
	128	1926 ORIGINAL BUILDING 3RD FLOOR HALLWAY 3100	NONE DETECTED			1200 Sq Ft
K3C		Miscellaneous Flooring 2' x 2' Dark Gray				Total Amount - 1765 Sq Ft
	173	1964 ADDITION GYMNASIUM 1306	NONE DETECTED	041409ML-31	ML-31: AT STORAGE 1306A.	1400 Sq Ft
	174	1964 ADDITION GYMNASIUM;STORAGE 1306A	NONE DETECTED			85 Sq Ft
	175	1964 ADDITION GYMNASIUM STORAGE 1306B	NONE DETECTED			110 Sq Ft
	176	ENTRY (G8) TO GIRLS' LOCKER ROOM FROM GYMNASIUM	NONE DETECTED			85 Sq Ft
	177	ENTRY TO BOYS' LOCKER ROOM	NONE DETECTED			85 Sq Ft
K3D		Miscellaneous Flooring Rubberized Tan Flooring & Adhesive				Total Amount - 6500 Sq Ft
	186	1977 ADDITION GYMNASIUM 1305	NONE DETECTED	041609ML-32		6500 Sq Ft
K3E		Miscellaneous Flooring 2' x 2' Tan Terrazzo-Look				Total Amount - 35 Sq Ft
	20	ELEVATOR	NEW			35 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
LOA Flexible Duct Connector Coarse Tan						Total Amount - 17 Sq Ft
	14	FAN ROOM 0104 OFF BOILER ROOM	NONE DETECTED	2001-1504-HH3	3: FAN ROOM OFF BOILER ROOM.	17 Sq Ft
MOA Plaster 1926 Original Building						Total Amount - 120000 Sq Ft
	4	THROUGHOUT 1926 ORIGINAL BUILDING	NONE DETECTED	041409ML-06, 10, 12, 14, 23; 2001-1501-K-4; 510Q-3P	ML-06: FAN ROOM ENTRY CEILING. ML-10: ROOM 1337 CEILING. ML-12: 1ST FLOOR WOMEN'S STAFF RESTROOM WALL. ML-14: ROOM 1210 CEILING. ML-23: ROOM 2108 SOFFIT. K-4: 2ND FLOOR STAFF LOUNGE. Q-3P: 3RD FLOOR SOCIAL WORKER'S OFFICE.	120000 Sq Ft
MOB Plaster 1964 Addition						Total Amount - 25000 Sq Ft
	146	THROUGHOUT 1964 ADDITION	<1 CH	041609ML-33, 34, 37; 2001-1501-K4; 2001-1901-RJHW-1A; 345-11, 12, 13	ML-33: GIRLS' LOCKER ROOM. ML-34: 1964 ADDITION HALLWAY CEILING OUTSIDE GYMNASIUM. ML-37: ROOM 2302A CEILING. K4: BY FORMER LIBRARY BREAK ROOM. RJHW-1A: CUSTODIAL CLOSET. 345-11,12,13: ABOVE KITCHEN COOLER.	25000 Sq Ft
NOA Drywall/Joint Compound Various (199X)						Total Amount - 10000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	2001-1501-K2; 2001-1504-HH7; 345-10, 14	K2: 1926 PENTHOUSE. HH7: BASEMENT. 345-10: CUSTODIAL CLOSET BY ROOM 2112. 345-14: ROOM 2111.	10000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
POA	Fire Doors Metal w/Solid Wood Core					Total Amount - 100 Sq Ft
	15	BOILER ROOM 0103	NSM			60 Sq Ft
	42	ROOM 0101	NSM			20 Sq Ft
	56	BASEMENT TUNNEL (NORTH)	NSM			20 Sq Ft
QOA	Carpet Adhesive Various Berber Carpet					Total Amount - 50000 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	345-9	345-9: ROOM 2111.	50000 Sq Ft
ROA	Baseboard/Mopboard Adhesive 8" Black Baseboard (1991)					Total Amount - 300 Sq Ft
	21	THROUGHOUT 1926 ORIGINAL BUILDING BASEMENT	NONE DETECTED	041409ML-19		300 Sq Ft
ROB	Baseboard/Mopboard Adhesive 4" Black Baseboard					Total Amount - 230 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED	041409ML-20	ML-20: ROOM 1212.	200 Sq Ft
	74	ROOM 1205 (CHOIR)	NONE DETECTED			15 Sq Ft
	79	ROOM 1212 (BAND)	NONE DETECTED			15 Sq Ft
ROC	Baseboard/Mopboard Adhesive 4" Brown					Total Amount - 20 Sq Ft
	113	STAFF WORK ROOM 2107	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROD Baseboard/Mopboard Adhesive 4" Cream						Total Amount - 10 Sq Ft
139	ROOM 3108	NEW				10 Sq Ft
SOA Wood Floor Felt / Vapor Barrier 1926 Original Building						Total Amount - 40000 Sq Ft
5	THROUGHOUT 1926 ORIGINAL BUILDING	NSM				40000 Sq Ft
SOB Wood Floor Felt / Vapor Barrier 1964 Addition (Elevated)						Total Amount - 800 Sq Ft
153	STAGE 1301	NSM				800 Sq Ft
TOA Light Cord Insulation Black Fuzzy						Total Amount - 48 Lin Ft
155	STAGE 1301	ASSUMED				48 Lin Ft
VOA Sink Undercoating Coarse Black						Total Amount - 30 Sq Ft
41	ROOM 0101	5 CH		041409ML-09		30 Sq Ft
VOB Sink Undercoating Black w/Gooseneck Faucet						Total Amount - 10 Sq Ft
71	ROOM 1209	5 CH		041409ML-13		5 Sq Ft
86	MAIN OFFICE ROOM 1007 (WORK ROOM)	5 CH				5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOC	Sink Undercoating Pink w/Gooseneck Faucet					Total Amount - 20 Sq Ft
	88	NURSE'S OFFICE 1015	10 CH	041409ML-16		5 Sq Ft
	107	ROOM 2119	10 CH			5 Sq Ft
	202	ROOM 2302	10 CH			10 Sq Ft
VOD	Sink Undercoating Gray					Total Amount - 15 Sq Ft
	110	STAFF LOUNGE 2110	NONE DETECTED	041409ML-22		5 Sq Ft
	114	STAFF WORK ROOM 2107	NONE DETECTED			5 Sq Ft
	151	1991 ADDITION MEDIA CENTER OFFICE 1215	NONE DETECTED			5 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					Total Amount - 1110 Sq Ft
	11	ENTRY TO FAN ROOM 0202	NONE DETECTED	041409ML-05		10 Sq Ft
	23	1926 ORIGINAL BUILDING BASEMENT HALLWAY	NONE DETECTED			300 Sq Ft
	26	ROOM 0204	NONE DETECTED			400 Sq Ft
	29	ROOM 0206 (STORAGE)	NONE DETECTED			40 Sq Ft
	32	ROOM 0207	NONE DETECTED			150 Sq Ft
	59	ROOM 0210 (STORAGE)	NONE DETECTED	041409ML-11		20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	62	ROOM 0208	NONE DETECTED			60 Sq Ft
	65	ROOM 0209 (STORAGE)	NONE DETECTED			30 Sq Ft
	70	MUSIC PRACTICE ROOMS & OFFICES 1207-1210	NONE DETECTED			100 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B					Total Amount - 3950 Sq Ft
	150	1991 ADDITION MEDIA CENTER 1213	NONE DETECTED			150 Sq Ft
	158	1964 ADDITION 1ST FLOOR HALLWAYS 1300 & 1300A	NONE DETECTED	041609ML-35		300 Sq Ft
	166	AUDITORIUM/CAFETERIA 1302	NONE DETECTED			1000 Sq Ft
	171	1964 ADDITION GYMNASIUM 1306	NONE DETECTED			1500 Sq Ft
	191	1964 ADDITION 2ND FLOOR HALLWAY 2200	NONE DETECTED			200 Sq Ft
	196	1964 ADDITION 2ND FLOOR HALLWAY 2300	NONE DETECTED			75 Sq Ft
	200	ROOM 2302	NONE DETECTED			200 Sq Ft
	209	ROOM 2303	NONE DETECTED			200 Sq Ft
	213	ROOM 2304	NONE DETECTED			75 Sq Ft
	217	ROOM 2305	NONE DETECTED			250 Sq Ft
W1D	1' x 1' Ceiling Tile Adhesive Associated w/I1D					Total Amount - 280 Sq Ft
	92	ROOM 1106	NONE DETECTED	041409ML-17		250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	168	AUDITORIUM/CAFETERIA SOUTHWEST STORAGE 1302A	NONE DETECTED			30 Sq Ft
X0A	Miscellaneous Material Pipe & Valve Flange Gaskets					Total Amount - 35 Sq Ft
	17	BOILER ROOM 0103	25 CH			30 Sq Ft
	18	ROOM 0103C OFF BOILER ROOM	25 CH	041409ML-01		5 Sq Ft
X0B	Miscellaneous Material Interior Window Glazing					Total Amount - 4 Sq Ft
	16	BOILER ROOM 0103	NONE DETECTED	041409ML-02		4 Sq Ft
X0C	Miscellaneous Material Black Chalkboards w/Dark Brown Trim - Adhesive					Total Amount - 96 Sq Ft
	34	ROOM 0207	ASSUMED			8 Sq Ft
	45	ROOM 0107	ASSUMED			16 Sq Ft
	49	ROOM 0108	ASSUMED			16 Sq Ft
	53	ROOM 0109	ASSUMED			16 Sq Ft
	103	ROOM 2111	ASSUMED			10 Sq Ft
	118	ROOM 2109	ASSUMED			10 Sq Ft
	121	ROOM 2108	ASSUMED			10 Sq Ft
	124	ROOM 2105	ASSUMED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0D	Miscellaneous Material Tackboard w/Dark Brown Trim -Adhesive					Total Amount - 334 Sq Ft
	27	ROOM 0204	ASSUMED			30 Sq Ft
	35	ROOM 0207	ASSUMED			80 Sq Ft
	46	ROOM 0107	ASSUMED			36 Sq Ft
	50	ROOM 0108	ASSUMED			36 Sq Ft
	54	ROOM 0109	ASSUMED			24 Sq Ft
	104	ROOM 2111	ASSUMED			32 Sq Ft
	119	ROOM 2109	ASSUMED			32 Sq Ft
	122	ROOM 2108	ASSUMED			32 Sq Ft
	125	ROOM 2105	ASSUMED			32 Sq Ft
X0E	Miscellaneous Material Vermiculite					Total Amount - 1 Sq Ft
	40	ROOM 0101	ASSUMED			1 Sq Ft
X0F	Miscellaneous Material Slate Chalkboard Adhesive (1964)					Total Amount - 10 Sq Ft
	75	ROOM 1205 (CHOIR)	ASSUMED			5 Sq Ft
	80	ROOM 1212 (BAND)	ASSUMED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOG	Miscellaneous Material Tackboard Adhesive (1964)					Total Amount - 50 Sq Ft
	76	ROOM 1205 (CHOIR)	ASSUMED			25 Sq Ft
	81	ROOM 1212 (BAND)	ASSUMED			25 Sq Ft
XOH	Miscellaneous Material Slate Chalkboard Adhesive (1926)					Total Amount - 400 Sq Ft
	6	THROUGHOUT 1926 ORIGINAL BUILDING	ASSUMED			400 Sq Ft
XOI	Miscellaneous Material Tackboard Adhesive (1926)					Total Amount - 1000 Sq Ft
	7	THROUGHOUT 1926 ORIGINAL BUILDING	ASSUMED			1000 Sq Ft
XOJ	Miscellaneous Material Marble Adhesive					Total Amount - 60 Sq Ft
	8	THROUGHOUT 1926 ORIGINAL BUILDING RESTROOMS	ASSUMED			60 Sq Ft
XOK	Miscellaneous Material Fume Hood Tar Paper					Total Amount - 20 Sq Ft
	144	ROOM 3114	20 CH	041409ML-28		20 Sq Ft
XOL	Miscellaneous Material Coarse White Proscenium Curtain					Total Amount - 600 Sq Ft
	154	STAGE 1301	ASSUMED			600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOM	Miscellaneous Material Vermiculite Fill		Total Amount - 10000 Sq Ft			
185	1977 ADDITION GYMNASIUM 1305	ASSUMED	10000 Sq Ft			
XON	Miscellaneous Material Black Chalkboard w/Wood Frame Adhesive		Total Amount - 6 Sq Ft			
203	ROOM 2302	ASSUMED	6 Sq Ft			
XOO	Miscellaneous Material Tackboard w/Silver Frame Adhesive		Total Amount - 80 Sq Ft			
204	ROOM 2302	ASSUMED	80 Sq Ft			
XOP	Miscellaneous Material White Coarse Weave Fire Curtain		Total Amount - 200 Sq Ft			
156	STAGE 1301	ASSUMED	200 Sq Ft			
XOQ	Miscellaneous Material Shiny Metal Frame Corkboard		Total Amount - 40 Sq Ft			
132	ROOM 3103	ASSUMED	40 Sq Ft			
X1A	Miscellaneous Material 1" X 1" Tan and Gray with White Flecks Ceramic Floor Tile System		Total Amount - 204 Sq Ft			
67	1ST FLOOR STAFF RESTROOMS BY CUSTODIAL OFFICE	ASSUMED	142 Sq Ft			
87	MAIN OFFICE RESTROOM	ASSUMED	32 Sq Ft			
89	NURSE'S OFFICE RESTROOM	ASSUMED	30 Sq Ft			

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1B		Miscellaneous Material 4" X 4" Mauve Ceramic Wall Tile System				Total Amount - 220 Sq Ft
	115	STAFF WORK RESTROOM 2107	ASSUMED			220 Sq Ft
X1C		Miscellaneous Material 2" X 2" Gray with Black Specks Ceramic Floor Tile System				Total Amount - 56 Sq Ft
	116	STAFF WORK RESTROOM 2107	ASSUMED			56 Sq Ft
X1D		Miscellaneous Material 1" X 1" Taupe and Brown with White Flecks Ceramic Floor Tile System				Total Amount - 510 Sq Ft
	179	BOYS' LOCKER ROOM SHOWER	ASSUMED			255 Sq Ft
	182	GIRLS' LOCKER ROOM RESTROOM	ASSUMED			255 Sq Ft
X1E		Miscellaneous Material 1" X 1" Brown with White Flecks Ceramic Floor Tile System				Total Amount - 232 Sq Ft
	180	BOYS' LOCKER ROOM RESTROOMS	ASSUMED			81 Sq Ft
	181	BOYS' LOCKER ROOM COACHES' RESTROOM	ASSUMED			35 Sq Ft
	183	GIRLS' LOCKER ROOM RESTROOM	ASSUMED			81 Sq Ft
	184	GIRLS' LOCKER ROOM COACHES' RESTROOM	ASSUMED			35 Sq Ft