

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D1A Boiler Gaskets Access Gaskets (Boilers #1 & #2)						Total Amount - 10 Sq Ft
	12	BOILER ROOM (TB1)	NONE DETECTED	031809-MV-01		10 Sq Ft
D1B Boiler Gaskets Front Access Gasket (Old Boiler)						Total Amount - 1 Sq Ft
	13	BOILER ROOM (TB1)	NONE DETECTED	031809-MV-02		1 Sq Ft
D1C Boiler Gaskets Burner Gasket (Boiler #1 & #2)						Total Amount - 2 Sq Ft
	15	BOILER ROOM (TB1)	NONE DETECTED	032015MV-01	MV-01: BURNER GASKET.	2 Sq Ft
D2A Interior Boiler Insulation Boilers #1 & #2 at Burner						Total Amount - 6 Sq Ft
	14	BOILER ROOM (TB1)	NONE DETECTED	032015MV-10	MV-10: BURNER REFRACTORY.	6 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D2B		Interior Boiler Insulation Old Boiler			Total Amount - 200 Sq Ft	
	16	BOILER ROOM (TB1)	NONE DETECTED	032015-MV-02, 03, 04, 05, 06, 07, 08, 09, 11, 12, 13, 14, 15	MV-02: OLD EXTERIOR BRICK. MV-03: OLD EXTERIOR BRICK MORTAR. MV-04: NEW EXTERIOR BRICK. MV-05: NEW EXTERIOR BRICK MORTAR. MV-06: SIDEWALL BRICK & MORTAR (INTERIOR). MV-07: UPPER SIDEWALL REFRACTORY. MV-08: LOWER SIDEWALL REFRACTORY. MV-09: SIDEWALL INSULATION. MV-11: FLOOR REFRACTORY (TOP). MV-12: FLOOR REFRACTORY (MIDDLE). MV-13: LIGHTWEIGHT FLOOR BETWEEN MIDDLE & SAND. MV-14: SAND LAYER. MV-15: HARD LAYER BELOW SAND LAYER.	200 Sq Ft
I1A		1' x 1' Acoustical Ceiling Tile Pegboard (1915)			Total Amount - 1300 Sq Ft	
	89	ROOM 2202	NONE DETECTED			100 Sq Ft
	96	ROOM 2005	NONE DETECTED			600 Sq Ft
	112	CAFETERIA (2100)	NONE DETECTED	510R1		600 Sq Ft
I1B		1' x 1' Acoustical Ceiling Tile Pegboard (1923)			Total Amount - 600 Sq Ft	
	162	ROOM 2407	NONE DETECTED	031809-MV-38		600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2A	2' x 2' Acoustical Ceiling Tile Pockmarks & Pin Holes					Total Amount - 6950 Sq Ft
	21	ELEVATOR LOBBY	NONE DETECTED			50 Sq Ft
	24	ROOM 1405	NONE DETECTED			600 Sq Ft
	29	ROOM 1407	NONE DETECTED			600 Sq Ft
	33	ROOM 1409	NONE DETECTED			600 Sq Ft
	39	ROOM 1411	NONE DETECTED			600 Sq Ft
	44	ROOM 1415	NONE DETECTED			600 Sq Ft
	54	ROOM 1204	NONE DETECTED			750 Sq Ft
	58	ROOM 2210	NONE DETECTED	031809-MV-13		700 Sq Ft
	152	ELEVATOR LOBBY NEAR ROOM 2230	NONE DETECTED			50 Sq Ft
	164	ROOM 2407	NONE DETECTED			600 Sq Ft
	167	ROOM 2409	NONE DETECTED			600 Sq Ft
	172	ROOM 2411	NONE DETECTED			600 Sq Ft
	175	ROOM 2415	NONE DETECTED			600 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Pin Holes					Total Amount - 850 Sq Ft
	69	ROOM 2207 ENTRY	NONE DETECTED	031809-MV-24		60 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	135	HALLWAY 2220	NONE DETECTED			330 Sq Ft
	139	BOYS' & GIRLS' RESTROOMS (2222 & 2224)	NONE DETECTED			400 Sq Ft
	145	ENTRY TO ROOM 2230	NONE DETECTED			60 Sq Ft
I3A	2' x 4' Ceiling Tile 1' x 1'-Look Grubs w/Pin Holes w/Revealed Edge					Total Amount - 6320 Sq Ft
	61	ROOM 2211	NONE DETECTED			1000 Sq Ft
	72	ROOM 2207	NONE DETECTED			180 Sq Ft
	77	ROOM 2205	NONE DETECTED			560 Sq Ft
	79	ROOM 2206	NONE DETECTED			900 Sq Ft
	84	ROOM 2204	NONE DETECTED			900 Sq Ft
	91	ROOM 2202	NONE DETECTED	2001-1501-L4		900 Sq Ft
	118	ROOM 2001 (LIBRARY)	NONE DETECTED			600 Sq Ft
	149	ROOM 2230	NONE DETECTED			280 Sq Ft
	155	ROOM 2402	NONE DETECTED			1000 Sq Ft
I3B	2' x 4' Ceiling Tile Widthwise Fissures w/Pin Holes					Total Amount - 2310 Sq Ft
	119	ROOM 2001 (LIBRARY)	NONE DETECTED	2001-1501-L5		200 Sq Ft
	121	ROOM 2312	NONE DETECTED			600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	127	ROOM 2313	NONE DETECTED			600 Sq Ft
	130	ROOM 2315	NONE DETECTED			560 Sq Ft
	133	HALLWAY 2310	NONE DETECTED			350 Sq Ft
I3D	2' x 4' Ceiling Tile Vinyl-Covered Sheetrock					Total Amount - 670 Sq Ft
	142	KITCHEN (2221)	NSM			670 Sq Ft
I3E	2' x 4' Ceiling Tile Foam Panels w/Egg Carton Pattern					Total Amount - 860 Sq Ft
	114	CAFETERIA (2100)	NSM			860 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Beige Mottle					Total Amount - 90 Sq Ft
	143	ROOM 2270 KITCHEN STORAGE	NONE DETECTED	031809-MV-07		90 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown & White Smears					Total Amount - 95 Sq Ft
	70	ROOM 2207 ENTRY	NONE DETECTED	031809-MV-25		25 Sq Ft
	136	HALLWAY 2220	NONE DETECTED			60 Sq Ft
	146	ENTRY TO ROOM 2230	NONE DETECTED			10 Sq Ft
K2C	12" x 12" Vinyl Floor Tile & Mastic White w/Multi-Colored Smears					Total Amount - 425 Sq Ft
	71	ROOM 2207 ENTRY	NONE DETECTED			35 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	137	HALLWAY 2220	NONE DETECTED			270 Sq Ft
	144	ROOM 2228	NONE DETECTED	031809-MV-31		70 Sq Ft
	147	ENTRY TO ROOM 2230	NONE DETECTED			50 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic Gray w/White & Dark Gray Smears					Total Amount - 180 Sq Ft
	122	ROOM 2312	NONE DETECTED	031809-MV-28		180 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Light Tan Mottle w/Beige Streaks					Total Amount - 950 Sq Ft
	52	SOUTHEAST STAIRWELL	NONE DETECTED	031809-MV-39		200 Sq Ft
	159	1923 ADDITION HALLWAY (2400)	NONE DETECTED			750 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Blue w/Blue Flecks					Total Amount - 600 Sq Ft
	45	ROOM 1415	NONE DETECTED	031809-MV-40		600 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Tan Mottle					Total Amount - 750 Sq Ft
	49	1923 ADDITION HALLWAY (1400)	NEW			750 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown & White Streaks					Total Amount - 400 Sq Ft
	40	ROOM 1411	NONE DETECTED	2001-01153-3		400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2I	12" x 12" Vinyl Floor Tile & Mastic Mustard Yellow		Total Amount - 200 Sq Ft			
41	ROOM 1411	NONE DETECTED	2001-1501-L2		200 Sq Ft	
K2J	12" x 12" Vinyl Floor Tile & Mastic Brown, Tan & White Checkerboard Pattern		Total Amount - 1200 Sq Ft			
26	ROOM 1405	NONE DETECTED			600 Sq Ft	
34	ROOM 1409	NONE DETECTED	031809-MV-41		600 Sq Ft	
K2K	12" x 12" Vinyl Floor Tile & Mastic Dark Green Border w/Checkered Light Green & White		Total Amount - 600 Sq Ft			
30	ROOM 1407	NONE DETECTED	031809-MV-42		600 Sq Ft	
K3A	Miscellaneous Flooring 2' x 2' Gray w/White Flecks		Total Amount - 100 Sq Ft			
22	ELEVATOR LOBBY	NEW			50 Sq Ft	
153	ELEVATOR LOBBY NEAR ROOM 2230	NEW			50 Sq Ft	
K3B	Miscellaneous Flooring 2' x 2' Light Green w/White Flecks		Total Amount - 200 Sq Ft			
57	RAMP TO GYMNASIUM	NEW			100 Sq Ft	
107	ROOM 2004A	NEW			100 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
LOA		Flexible Duct Connector Tan Canvas				Total Amount - 2 Sq Ft
	19	MECHANICAL ROOM 1304	NONE DETECTED	031809-MV-03		2 Sq Ft
LOB		Flexible Duct Connector Black Vinyl				Total Amount - 4 Sq Ft
	20	MECHANICAL ROOM 1304	NSM			4 Sq Ft
L0C		Flexible Duct Connector Green Canvas				Total Amount - 16 Sq Ft
	17	CRAWL SPACE/MECHANICAL 1201	NONE DETECTED			8 Sq Ft
	48	ROOM 1410 (CUSTODIAL OFFICE)	NONE DETECTED	031809-MV-06	MV-6: MECHANICAL ROOM 1304.	8 Sq Ft
L0D		Flexible Duct Connector White Woven				Total Amount - 6 Sq Ft
	18	CRAWL SPACE/MECHANICAL 1201	60 CH	545-3		6 Sq Ft
M0A		Plaster 1915 Original Building				Total Amount - 50000 Sq Ft
	5	THROUGHOUT 1915 ORIGINAL BUILDING	NONE DETECTED	031809-MV-14, 15, 16, 17, 18, 19; 510R2		50000 Sq Ft
M0B		Plaster 1920 Addition				Total Amount - 5000 Sq Ft
	7	THROUGHOUT 1920 ADDITION	NONE DETECTED	031809-MV-20, 21, 22, 23 ; 2001-1501-L13		5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOC	Plaster 1923 Addition					Total Amount - 20000 Sq Ft
	10	THROUGHOUT 1923 ADDITION	NONE DETECTED	031809-MV-32, 33, 34, 35, 36, 37; 2001-1501- L14		20000 Sq Ft
NOA	Drywall/Joint Compound					Total Amount - 5000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	200-1501-L12	L12: ECFE AREA.	5000 Sq Ft
Q0A	Carpet Adhesive Gray/Blue Berber Carpet					Total Amount - 2980 Sq Ft
	78	ROOM 2205	NONE DETECTED			560 Sq Ft
	116	MAIN OFFICE AREA	NONE DETECTED	031809-MV-08		500 Sq Ft
	120	ROOM 2001 (LIBRARY)	NONE DETECTED			1500 Sq Ft
	123	ROOM 2312	NONE DETECTED			420 Sq Ft
Q0B	Carpet Adhesive Red Berber Carpet					Total Amount - 150 Sq Ft
	106	ROOM 2004	NONE DETECTED	031809-MV-09		150 Sq Ft
Q0C	Carpet Adhesive Green Berber Carpet					Total Amount - 540 Sq Ft
	66	ROOM 2208	NONE DETECTED			80 Sq Ft
	73	ROOM 2207	NONE DETECTED	031809-MV-11		180 Sq Ft
	150	ROOM 2230	NONE DETECTED			280 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0E		Carpet Adhesive Tan Striped Carpet Squares			Total Amount - 750 Sq Ft	
	25	ROOM 1405	NEW			600 Sq Ft
	105	ROOM 2004B	NEW			150 Sq Ft
R0A		Baseboard/Mopboard Adhesive 4" Tan Baseboard			Total Amount - 35 Sq Ft	
	23	ELEVATOR LOBBY	NONE DETECTED			5 Sq Ft
	74	ROOM 2207	NONE DETECTED	031809-MV-12		10 Sq Ft
	148	ENTRY TO ROOM 2230	NONE DETECTED			5 Sq Ft
	151	ROOM 2230	NONE DETECTED			10 Sq Ft
	154	ELEVATOR LOBBY NEAR ROOM 2230	NONE DETECTED			5 Sq Ft
R0B		Baseboard/Mopboard Adhesive 4" Dark Brown Baseboard			Total Amount - 10 Sq Ft	
	138	HALLWAY 2220	NONE DETECTED	031809-MV-27		10 Sq Ft
R0C		Baseboard/Mopboard Adhesive 4" Blue Baseboard			Total Amount - 20 Sq Ft	
	124	ROOM 2312	NONE DETECTED			10 Sq Ft
	134	HALLWAY 2310	NONE DETECTED	031809-MV-30		10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
SOA		Wood Floor Felt / Vapor Barrier 1915 Original Building			Total Amount - 20000 Sq Ft	
6	THROUGHOUT 1915 ORIGINAL BUILDING	ASSUMED			20000 Sq Ft	
SOB		Wood Floor Felt / Vapor Barrier 1920 Addition (Elevated)			Total Amount - 3000 Sq Ft	
8	THROUGHOUT 1920 ADDITION	ASSUMED			3000 Sq Ft	
SOC		Wood Floor Felt / Vapor Barrier 1923 Addition			Total Amount - 6000 Sq Ft	
11	THROUGHOUT 1923 ADDITION	ASSUMED			6000 Sq Ft	
SOD		Wood Floor Felt / Vapor Barrier 1920 Addition (On-Grade)			Total Amount - 3000 Sq Ft	
53	GYMNASIUM (1203)	ASSUMED			3000 Sq Ft	
VOA		Sink Undercoating Gray Double Sink			Total Amount - 44 Sq Ft	
55	ROOM 1204	NONE DETECTED			4 Sq Ft	
100	ROOM 2005	NONE DETECTED			10 Sq Ft	
108	ROOM 2004A	NONE DETECTED			10 Sq Ft	
125	ROOM 2312	NONE DETECTED			10 Sq Ft	
128	ROOM 2313	NONE DETECTED		031809-MV-29	10 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOB	Sink Undercoating Gray					Total Amount - 30 Sq Ft
	65	ROOM 2212	NEW			6 Sq Ft
	83	ROOM 2206	NEW			6 Sq Ft
	88	ROOM 2204	NEW			6 Sq Ft
	95	ROOM 2202	NEW			6 Sq Ft
	102	ROOM 2005	NEW			6 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/11A					Total Amount - 325 Sq Ft
	90	ROOM 2202	NONE DETECTED			25 Sq Ft
	97	ROOM 2005	NONE DETECTED	031809-MV-10		150 Sq Ft
	113	CAFETERIA (2100)	NONE DETECTED			150 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/11B					Total Amount - 150 Sq Ft
	163	ROOM 2407	NONE DETECTED	031809-MV-38		150 Sq Ft
W3E	2' x 4' Ceiling Tile Adhesive Associated w/13E					Total Amount - 200 Sq Ft
	115	CAFETERIA (2100)	NONE DETECTED	081512ML-06	ML-06: CAFETERIA.	200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOA	Miscellaneous Material Gray Duct Caulk		Total Amount - 150 Sq Ft			
2	THROUGHOUT BUILDING	NONE DETECTED	031809-MV-04	MV-4: MECHANICAL ROOM 1304.	150 Sq Ft	
XOB	Miscellaneous Material Red Fire Stop		Total Amount - 50 Sq Ft			
3	THROUGHOUT BUILDING	NONE DETECTED	031809-MV-05	MV-5: MECHANICAL ROOM 1304.	50 Sq Ft	
XOC	Miscellaneous Material Chalkboard Adhesive (1915)		Total Amount - 185 Sq Ft			
80	ROOM 2206	ASSUMED			40 Sq Ft	
85	ROOM 2204	ASSUMED			40 Sq Ft	
92	ROOM 2202	ASSUMED			40 Sq Ft	
98	ROOM 2005	ASSUMED			5 Sq Ft	
111	ROOM 3100	ASSUMED			20 Sq Ft	
131	ROOM 2315	ASSUMED			40 Sq Ft	
XOD	Miscellaneous Material Chalkboard Adhesive (1920)		Total Amount - 115 Sq Ft			
27	ROOM 1405	ASSUMED			10 Sq Ft	
59	ROOM 2210	ASSUMED			40 Sq Ft	
62	ROOM 2211	ASSUMED			40 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	67	ROOM 2208	ASSUMED			5 Sq Ft
	156	ROOM 2402	ASSUMED			20 Sq Ft
XOE	Miscellaneous Material Gray Fire Stop					Total Amount - 50 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	031809-MV-26	MV-26: HALLWAY 2200 BY KITCHEN.	50 Sq Ft
XOF	Miscellaneous Material Chalkboard Adhesive (1923)					Total Amount - 314 Sq Ft
	31	ROOM 1407	ASSUMED			40 Sq Ft
	35	ROOM 1409	ASSUMED			40 Sq Ft
	42	ROOM 1411	ASSUMED			40 Sq Ft
	46	ROOM 1415	ASSUMED			30 Sq Ft
	50	1923 ADDITION HALLWAY (1400)	ASSUMED			2 Sq Ft
	160	1923 ADDITION HALLWAY (2400)	ASSUMED			2 Sq Ft
	165	ROOM 2407	ASSUMED			40 Sq Ft
	168	ROOM 2409	ASSUMED			40 Sq Ft
	173	ROOM 2411	ASSUMED			40 Sq Ft
	176	ROOM 2415	ASSUMED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0G	Miscellaneous Material Orange/Brown Granite-Look Countertop					Total Amount - 40 Sq Ft
	117	MAIN OFFICE AREA	NONE DETECTED	033109-MA-01		40 Sq Ft
X0H	Miscellaneous Material Beige w/White Streaks Countertop					Total Amount - 40 Sq Ft
	158	ROOM 2405	NONE DETECTED	033109-ML-02		40 Sq Ft
X0I	Miscellaneous Material Blown-In Cellulose Insulation					Total Amount - 25000 Sq Ft
	178	THROUGHOUT ATTIC SPACES	NONE DETECTED	545-5		25000 Sq Ft
X0J	Miscellaneous Material Corkboard Adhesive (1920)					Total Amount - 50 Sq Ft
	28	ROOM 1405	ASSUMED			10 Sq Ft
	157	ROOM 2402	ASSUMED			40 Sq Ft
X0K	Miscellaneous Material Corkboard Adhesive (1923)					Total Amount - 1002 Sq Ft
	32	ROOM 1407	ASSUMED			130 Sq Ft
	36	ROOM 1409	ASSUMED			130 Sq Ft
	43	ROOM 1411	ASSUMED			130 Sq Ft
	47	ROOM 1415	ASSUMED			130 Sq Ft
	51	1923 ADDITION HALLWAY (1400)	ASSUMED			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	60	ROOM 2210	ASSUMED			50 Sq Ft
	63	ROOM 2211	ASSUMED			24 Sq Ft
	161	1923 ADDITION HALLWAY (2400)	ASSUMED			4 Sq Ft
	166	ROOM 2407	ASSUMED			100 Sq Ft
	169	ROOM 2409	ASSUMED			100 Sq Ft
	174	ROOM 2411	ASSUMED			100 Sq Ft
	177	ROOM 2415	ASSUMED			100 Sq Ft
X0L	Miscellaneous Material Black Cabinet Inserts					Total Amount - 20 Sq Ft
	56	ROOM 1204	NONE DETECTED	081512ML-05	ML-05: ROOM 1204.	20 Sq Ft
X0M	Miscellaneous Material Thin Metal Frame Corkboard Adhesive					Total Amount - 226 Sq Ft
	64	ROOM 2211	ASSUMED			24 Sq Ft
	68	ROOM 2208	ASSUMED			24 Sq Ft
	76	ROOM 2207	ASSUMED			30 Sq Ft
	82	ROOM 2206	ASSUMED			40 Sq Ft
	87	ROOM 2204	ASSUMED			40 Sq Ft
	94	ROOM 2202	ASSUMED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	101	ROOM 2005	ASSUMED			8 Sq Ft
	129	ROOM 2313	ASSUMED			20 Sq Ft
X0N	Miscellaneous Material Metal Frame Chalkboard Adhesive					Total Amount - 5 Sq Ft
	75	ROOM 2207	ASSUMED			5 Sq Ft
X0O	Miscellaneous Material Corkboard Adhesive (1915)					Total Amount - 200 Sq Ft
	81	ROOM 2206	ASSUMED			40 Sq Ft
	86	ROOM 2204	ASSUMED			40 Sq Ft
	93	ROOM 2202	ASSUMED			40 Sq Ft
	99	ROOM 2005	ASSUMED			40 Sq Ft
	126	ROOM 2312	ASSUMED			20 Sq Ft
	132	ROOM 2315	ASSUMED			20 Sq Ft
X0P	Miscellaneous Material Black Vapor Barrier on Exterior Walls					Total Amount - 1000 Sq Ft
	9	THROUGHOUT 1920 ADDITION	NONE DETECTED	062613BF-1	BF-1: ROOM 2403.	1000 Sq Ft
X1A	Miscellaneous Material 4" X 4" White with Green or Beige Accents Ceramic Wall Tile System					Total Amount - 1650 Sq Ft
	37	BOYS' AND GIRLS' RESTROOM ACROSS FROM ROOM 1409	ASSUMED			420 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	140	BOYS' & GIRLS' RESTROOMS (2222 & 2224)	ASSUMED			810 Sq Ft
	170	RESTROOMS ACROSS FROM ROOM 2409	ASSUMED			420 Sq Ft
X1B	Miscellaneous Material 2" X 2" Gray with White Specks Ceramic Floor Tile System					Total Amount - 840 Sq Ft
	38	BOYS' AND GIRLS' RESTROOM ACROSS FROM ROOM 1409	ASSUMED			160 Sq Ft
	103	ROOM 2006 RESTROOM	ASSUMED			80 Sq Ft
	110	ROOM 2004A RESTROOM	ASSUMED			40 Sq Ft
	141	BOYS' & GIRLS' RESTROOMS (2222 & 2224)	ASSUMED			400 Sq Ft
	171	RESTROOMS ACROSS FROM ROOM 2409	ASSUMED			160 Sq Ft
X1C	Miscellaneous Material 6" X 6" White with Light Green Accents Ceramic Wall Tile System					Total Amount - 290 Sq Ft
	104	ROOM 2006 RESTROOM	ASSUMED			190 Sq Ft
	109	ROOM 2004A RESTROOM	ASSUMED			100 Sq Ft