

2102 University Avenue West, Saint Paul, MN 55114

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4B		Mudded Pipe Joints on Fiberglass Insulation				Total Amount - 4 Joints
	44	ROOM 218	NONE DETECTED	111810-ML-01	ML-01: ROOM 218.	3 Joints
	48	ROOM 216	NONE DETECTED			1 Joints
D1B		Boiler Gaskets 197X Installation				Total Amount - 4 Sq Ft
	4	BOILER ROOM (104)	95 CH	111810-ML-02	ML-02: BOILER ROOM.	4 Sq Ft
G1A		Sprayed-On Acoustical Finish White Texture				Total Amount - 3120 Sq Ft
	55	1936 ORIGINAL BUILDING 2ND FLOOR HALLWAY (205) & ENTRY (202)	NONE DETECTED	111810-ML-05	ML-05: STAIRWELL LANDING.	400 Sq Ft
	57	ROOM 206	NONE DETECTED	111810-ML-04	ML-04: ROOM 206.	320 Sq Ft
	58	ROOM 201 & COPY ROOM (200)	NONE DETECTED	111810-ML-03	ML-03: ROOM 201.	720 Sq Ft
	60	1936 ORIGINAL BUILDING 3RD FLOOR HALLWAY (300) & STAIRS (300A)	NONE DETECTED			200 Sq Ft
	61	ROOM 301 & OFFICE	NONE DETECTED	111810-ML-06	ML-06: ROOM 301.	720 Sq Ft
	65	ROOM 302	NONE DETECTED			280 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	66	ROOM 306	NONE DETECTED			120 Sq Ft
	68	ROOM 305	NONE DETECTED			180 Sq Ft
	70	ROOM 303	NONE DETECTED	111810-ML-07	ML-07: ROOM 303.	180 Sq Ft
G1B	Sprayed-On Acoustical Finish Thick, White Texture (1978)					Total Amount - 1330 Sq Ft
	18	ROOM 122 & HALLWAY	NONE DETECTED	111810-ML-12	ML-12: ROOM 122 ENTRY.	500 Sq Ft
	19	ROOM 118	NONE DETECTED	111810-ML-08	ML-08: ROOM 118.	100 Sq Ft
	20	ROOM 119	NONE DETECTED			100 Sq Ft
	21	ROOM 120	NONE DETECTED	111810-ML-09	ML-09: ROOM 120.	140 Sq Ft
	23	ROOM 121	NONE DETECTED			250 Sq Ft
	25	ROOM 123	NONE DETECTED	111810-ML-10	ML-10: ROOM 123.	120 Sq Ft
	26	ROOM 124	NONE DETECTED	111810-ML-11	ML-11: ROOM 124.	120 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Rough w/Holes					Total Amount - 150 Sq Ft
	50	AREA 215 (LOBBY)	NONE DETECTED	111810-ML-13	ML-13: ROOM 215 (RECEPTIONIST).	150 Sq Ft
I3A	2' x 4' Ceiling Tile Widthwise Fissures & Pin Holes					Total Amount - 5160 Sq Ft
	14	ROOM 106 (ELEVATOR LOBBY)	NONE DETECTED			215 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	28	ROOM 234	NONE DETECTED			870 Sq Ft
	29	ROOM 229	NONE DETECTED			180 Sq Ft
	30	ROOM 230	NONE DETECTED			180 Sq Ft
	31	1978 ADDITION 2ND FLOOR HALLWAY (231)	NONE DETECTED			180 Sq Ft
	32	ROOM 232	NONE DETECTED			180 Sq Ft
	33	ROOM 233	NONE DETECTED			170 Sq Ft
	34	1975 ADDITION ENTRY (228)	NONE DETECTED			120 Sq Ft
	36	1975 ADDITION 2ND FLOOR HALLWAY (225)	NONE DETECTED			400 Sq Ft
	39	ROOM 223	NONE DETECTED			120 Sq Ft
	40	ROOM 222	NONE DETECTED			120 Sq Ft
	41	ROOM 221	NONE DETECTED			120 Sq Ft
	42	ROOM 220	NONE DETECTED			120 Sq Ft
	43	ROOM 219	NONE DETECTED			140 Sq Ft
	45	ROOM 218	NONE DETECTED			140 Sq Ft
	46	RESTROOM 219A	NONE DETECTED			55 Sq Ft
	47	ROOM 217	NONE DETECTED			130 Sq Ft
	49	ROOM 213/216 (LOBBY/COMMONS)	NONE DETECTED			1200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	52	MAIN ENTRY (214)	NONE DETECTED			80 Sq Ft
	53	ROOM 211	NONE DETECTED			160 Sq Ft
	63	ROOM 307 (HALLWAY)	NONE DETECTED	111810-ML-14	ML-14: ROOM 307.	60 Sq Ft
	64	ROOM 308 (ELEVATOR LOBBY)	NONE DETECTED			220 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan & Brown Flecks					Total Amount - 1000 Sq Ft
	6	ROOM 101	NONE DETECTED			300 Sq Ft
	7	ROOM 101A	NONE DETECTED			115 Sq Ft
	8	ROOM 101B	NONE DETECTED			100 Sq Ft
	9	ROOM 103	NONE DETECTED			320 Sq Ft
	11	ROOM 105	NONE DETECTED			65 Sq Ft
	12	ROOM 108B	NONE DETECTED			30 Sq Ft
	59	ROOM 208	NONE DETECTED	111810-ML-15	ML-15: ROOM 208.	70 Sq Ft
K3A	Miscellaneous Flooring Tan Stair Treads					Total Amount - 600 Sq Ft
	27	EAST STAIRWELL (235)	NEW			200 Sq Ft
	35	1975 ADDITION ENTRY (228)	NEW			100 Sq Ft
	54	SOUTHWEST STAIRWELL (212)	NEW			300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
LOA Flexible Duct Connector Black Vinyl Total Amount - 3 Sq Ft						
	10	ROOM 103	NSM			3 Sq Ft
M0A Plaster 1936 Original Building Total Amount - 10000 Sq Ft						
	2	THROUGHOUT 1936 ORIGINAL BUILDING	NONE DETECTED	111810-ML-16, 17, 18, 19, 20, 21, 22	ML-16: BOILER ROOM CEILING. ML-17: ROOM 201 WALL. ML-18: ROOM 204 WALL. ML-19: ROOM 206 CLOSET WALL. ML-20: ROOM 303 CLOSET CEILING. ML-21: ROOF ACCESS ROOM CEILING. ML-22: BOILER ROOM WALL.	10000 Sq Ft
NOB Drywall/Joint Compound 1975 Addition Total Amount - 3000 Sq Ft						
	13	THROUGHOUT 1975 ADDITION	NONE DETECTED	111810-ML-23	ML-23: HALLWAY OUTSIDE ROOM 223 ABOVE CEILING.	3000 Sq Ft
NOC Drywall/Joint Compound 1978 Addition Total Amount - 2000 Sq Ft						
	17	THROUGHOUT 1978 ADDITION	NONE DETECTED	111810-ML-24	ML-24: HALLWAY OUTSIDE ROOM 232 ABOVE CEILING.	2000 Sq Ft
P0A Fire Doors Metal -1 Hr (Curries) Total Amount - 20 Sq Ft						
	5	BOILER ROOM (104)	ASSUMED			20 Sq Ft
POB Fire Doors Metal -1.5 Hr Rating (Warnock Hersey) Total Amount - 80 Sq Ft						
	15	HALLWAY OUTSIDE ROOM 112	ASSUMED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	37	1975 ADDITION 2ND FLOOR HALLWAY (225)	ASSUMED			20 Sq Ft
	56	1936 ORIGINAL BUILDING 2ND FLOOR HALLWAY (205) & ENTRY (202)	ASSUMED			20 Sq Ft
POC	Fire Doors Wood -1 Hr Rating (Warnock Hersey)					Total Amount - 40 Sq Ft
	38	1975 ADDITION 2ND FLOOR HALLWAY (225)	ASSUMED			40 Sq Ft
Q0A	Carpet Adhesive Multi-Colored Berber Carpet					Total Amount - 10000 Sq Ft
	1	THROUGHOUT BUILDING	NEW			10000 Sq Ft
SOA	Wood Floor Felt / Vapor Barrier 1936 Original Building					Total Amount - 480 Sq Ft
	67	ROOM 306	ASSUMED			120 Sq Ft
	69	ROOM 305	ASSUMED			180 Sq Ft
	71	ROOM 303	ASSUMED			180 Sq Ft
VOA	Sink Undercoating Gray					Total Amount - 14 Sq Ft
	16	ROOM 112	NONE DETECTED	111810-ML-25	ML-25: ROOM 112.	6 Sq Ft
	22	ROOM 120	NONE DETECTED			4 Sq Ft
	24	ROOM 121	NONE DETECTED			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1A	1' x 1' Ceiling Tile Adhesive Associated w/11A		Total Amount - 35 Sq Ft			
	51	AREA 215 (LOBBY)	NONE DETECTED	111810-ML-13	ML-13: ROOM 215 (RECEPTIONIST).	35 Sq Ft
X0A	Miscellaneous Material Pipe/Valve Flange Gaskets		Total Amount - 11 Sq Ft			
	3	BOILER ROOM (104)	ASSUMED			11 Sq Ft
X0B	Miscellaneous Material Loose Fiberglass		Total Amount - 2000 Sq Ft			
	62	1936 ORIGINAL BUILDING ATTIC	NONE DETECTED	111810-ML-26	ML-26: ATTIC.	2000 Sq Ft