

Radiofrequency Monitoring Report

Location: Ella Baker

Performed By: Andrew Tinklenberg, EH&S Safety Specialist

Date Performed: 6/30/23

Introduction/Background:

Testing was conducted to review the radiofrequency (RF) levels present in and around select areas of the school building to verify that the levels are below Federal Communications Commission (FCC) limits for the general population/uncontrolled exposure (see the below table for the FCC limits). Wireless communication equipment is present at this site and is located on the northeast, northwest and west central rooftop areas of the building. Testing was performed using a Trifield $^{\circ}$ Model TF2 meter capable of measuring RF levels in the 20 MHz - 6 GHz range with a range of 0.001 - 19.999 milliwatts per square meter (mW/m²).

Frequency Range (MHz)	Power Density/RF Levels (mW/m²)
30-300	2,000 *

^{* -} Limit for maximum permissible exposure for the general/uncontrolled population expressed in mW/m². Information taken from FCC Resolution 19-126.

Results/Findings:

The results of the testing found that the FCC radiofrequency limit was not exceeded at any point and levels were well below the standards set for the general population. (See Table #1 on the following page for the results of the testing.)

Remarks:

It should be noted that RF levels are known to fluctuate due to a number of factors (RF generating sources present, distance from a source, objects creating interference, etc.). For this reason, the measurements in this report represent the average range of RF levels that were found to be present in the listed area at the time/date of the testing.

If you have any questions regarding this information, please feel free to contact me. Thank you,

Andrew Tinklenberg
Safety Specialist, Environmental Health & Safety
Minneapolis Public Schools
andrew.tinklenberg@mpls.k12.mn.us
612-668-0306 Phone
612-668-0310 EH & S General Office









<u>Table #1 – Ella Baker Radiofrequency Testing Results</u>

Area/Location	RF Levels (mW/m²) *	Notes/Comments
Exterior North Side of Building	<10.0	**
Exterior East Side of Building	<5.0	** Pole-mounted city transmitter
Exterior South Side of Building	<1.0	
Exterior West Side of Building	<10.0	**
Ground Floor	<0.01	
First Floor	<0.01	
Second Floor	<0.1	
Second Floor – Gym	<1.0	**
Third Floor – Room 314	<5.0	**
Third Floor – Room 316	<5.0	**
Third Floor – Room 320	<1.0	**
Third Floor – Room 322	<5.0	**
Third Floor – Room 332	<0.5	**
Third Floor – Room 334	<2.0	**
Third Floor – Room 334A	<0.5	**
Third Floor – Room 304	<0.1	

^{* -} Average RF levels did not exceed the level shown.

^{** -} Cell tower/transmitter equipment is in relative proximity to this area.