



Radiofrequency Monitoring Report

Location: Northeast Middle School
Performed By: Andrew Tinklenberg, EH&S Safety Specialist
Date Performed: 6/26/23

Introduction/Background:

Testing was conducted to review the radiofrequency (RF) levels present in and around select areas of the school building to verify that the levels are below Federal Communications Commission (FCC) limits for the general population/uncontrolled exposure (see the below table for the FCC limits). Wireless communication equipment is present at this site and is located on the northwest and north central rooftop areas. Testing was performed using a Trifield® Model TF2 meter capable of measuring RF levels in the 20 MHz – 6 GHz range with a range of 0.001 – 19.999 milliwatts per square meter (mW/m²).

Frequency Range (MHz)	Power Density/RF Levels (mW/m ²)
30-300	2,000 *

* - Limit for maximum permissible exposure for the general/uncontrolled population expressed in mW/m². Information taken from [FCC Resolution 19-126](#).

Results/Findings:

The results of the testing found that the FCC radiofrequency limit was not exceeded at any point and levels were well below the standards set for the general population. (See Table #1 on the following page for the results of the testing.)

Remarks:

It should be noted that RF levels are known to fluctuate due to a number of factors (RF generating sources present, distance from a source, objects creating interference, etc.). For this reason, the measurements in this report represent the average range of RF levels that were found to be present in the listed area at the time/date of the testing.

If you have any questions regarding this information, please feel free to contact me. Thank you,

Andrew Tinklenberg
Safety Specialist, Environmental Health & Safety
Minneapolis Public Schools
andrew.tinklenberg@mpls.k12.mn.us
612-668-0306 Phone
612-668-0310 EH & S General Office





Table #1 – Northeast Middle Radiofrequency Testing Results

Area/Location	RF Levels (mW/m ²) *	Notes/Comments
Exterior South Side of Building	<0.5	
Exterior East Side of Building	<5.0	
Exterior North Side of Building	<5.0	**
Exterior West Side of Building	<5.0	
First Floor – South Wing	<0.1	
Ground Floor – North Wing	<0.01	
First Floor – North Wing	<0.01	
Second Floor – North Wing	<0.1	
Third Floor – Room 306	<0.5	**
Third Floor – Room 304	<0.5	**
Third Floor – Room 303	<0.1	**
Third Floor – Room 301	<0.5	**
Third Floor – Room 300	<0.5	**
Third Floor – Restroom 353	<5.0	**
Third Floor – NW Stairwell	<5.0	**
Second Floor South Wing – Gym	<1.0	
Second Floor South Wing – Auditorium	<1.0	

* - Average RF levels did not exceed the level shown.

** - Cell tower/transmitter equipment is in relative proximity to this area.