

## TENDER NOTICE – CIVIL WORKS

**Tender Number: KIS.M.010.2023**

**Tender Name: SOLVIC DORM PASSAGE SLABS**

**Tender Opening Date: 24<sup>th</sup> November 2023 at 10:00 hrs**

**Tender Opening Location: Office of the Executive Administrative Manager, KIS**

We seek your valuable quotations for the undermentioned Civil Work to be carried out at the Kodaikanal International School property.



Contractors to quote only if capable of completing within 20 days of receiving Work Order from KIS. Only contractors capable of coordinating all scope of work as mentioned below are to bid for this tender. Penalties would be deducted in case of delay beyond 7 days from the completion date.

The details of our requirements are as follows: -

- Civil Works – Works including Civil, Concrete Slab Works
- Location – Highclerc Compound
- Type of Building – Concrete Slabs
- Name of Building – Dormitory
- GPS Coordinates: –

### SOLVIC DORM PASSAGE SLABS

S.No	Detail of works	unit	qty	Unit Price	Total
<b>Roof work</b>					
<b>1</b>	<b>Earthwork excavation</b>				
	Earthwork excavation in ordinary soil and dispose the excavated soil as directed by the site in charge.	CFT	150		
<b>2</b>	<b>Concrete</b>				
	4" P.C.C. 1:2:4 using 20mm HBGS jelly including cost and conveyance of all materials and labour charges etc. complete.	CFT	50		
<b>3</b>	<b>Brick work 9"</b>				
	Brick work in cm 1: 4, 9"tk using chamber burned bricks including curing, pointing to receive plaster etc. Complete.	CFT	110		

<b>4</b>	<b>RCC to Cover the Drain</b>				
	Providing reinforce cement concrete 1:2:4 for the Plinth with crushed stone aggregate of 20mm and down gauge laid consolidated, 12mm are the main rod, 8mm for the Rings, Shuttering, and cured etc. Including side form works as completed. Cost including labour and materials etc.... (Shuttering shall be done using seasoned wooden boards of thickness not less than 30mm. Surface contact with concrete shall be free from adhering grout, nails, splits and other defects. All the joints are perfectly closed and lined up. The shuttering and framing is sufficiently braced.)	CFT	140		
<b>5</b>	<b>Top Plastering</b>				
	Plastering one coat with cm 1:5 13mm thick and also make a grew to rest the Mangalore tiles etc.... complete	Sq.ft	350		
<b>TOTAL</b>					



The quotation should include the following: -

- GST at applicable rate
- Transportation and Loading / Unloading at site
- Installation at site
- Validity of Quote - minimum 21 days
- Details of date of dispatch of material and commencement of work on receipt of Purchase Order

**Please Note:** -

Your quotation should be dropped in the Tender Box at the Main Gate of the Highclerc campus on or before the specified Tender Opening Date. The quotations should **mention the Tender Number and Tender Name** as the subject of the envelope on the cover of the sealed envelope.

**Location of Tender Box**

Main Gate, Highclerc Campus,  
Kodaikanal International School,  
Seven Roads Junction, Kodaikanal - 624101

**Terms of Payment by KIS for this Tender:**

- Two or Three maximum Part Payment of 70% can be made upon submitting the running bill once the works proceed.
- 10% amount will be held as a 'Retention Amount' which will be released after 6 months of satisfactory completion of the product.
- As a KIS Policy, advances exceeding Rs. 5 lakhs will only be made against a bank guarantee from the supplier.



**Cdr AJL Fernandes (Retd.)**  
Executive Administrative Manager  
execmgr@kis.in

