



# Park Hill School District

Building Successful Futures • Each Student • Every Day

## **ADDENDUM No. 3 Park Hill School District 2024 Sidewalk Projects January 25, 2024**

You are instructed to read and note the following described changes, correction, clarifications, omissions, deletions, additions, approvals and statements pertinent to the Construction Documents.

Addendum No. 3 is a part of the Project Requirements and Package 3 - Union Chapel and shall govern in the performance of the Work.

### Concrete Sidewalk

~~Concrete sidewalk to be a minimum of 4 inches thick and reinforced with light welded wire mesh.~~ Follow Kaw Valley drawings for specifications. Place 1/2-inch fiber expansion joints where new concrete abuts existing. Expansion joints shall be placed at sidewalk intersections, at backside of curbing and not exceed every 50 LF of sidewalk run. Minimum 1-inch-deep tool joints to be placed on center and not to exceed the width of the sidewalk. Sidewalks wider than 8'-0" to have longitudinal tool joint at mid-point in width. ~~Concrete to be minimum 3,500 psi.~~ Back-fill topsoil behind new sidewalk and tamp.

### Package 3

#### Union Chapel

- Install new 4' ADA sidewalk approximately 125 linear ft. from asphalt down to playground per confluence's design.
- Install a curb approximately 18 linear from stairs to start of the sidewalk.
- Follow Kaw Valley concrete specs.

# Acknowledgment Form

## ACKNOWLEDGEMENT OF ADDENDA

The undersigned Bidder acknowledges receipt of and use of the following Addenda in the preparation of this Bid:

Addendum No. 3, dated January 25, 2024

COMPANY \_\_\_\_\_

ADDRESS \_\_\_\_\_

PHONE \_\_\_\_\_ FAX \_\_\_\_\_

EMAIL \_\_\_\_\_

PRINT NAME \_\_\_\_\_

SIGNATURE \_\_\_\_\_ Date: \_\_\_\_\_