

January 15, 2024

Lelisa Rozendal Beaverton School District 2180 SW 170th Avenue Beaverton, OR 97003

Via email: lelisa_rozendal@beaverton.k12.or.us

Regarding: Radon Testing

Scholls Heights Elementary School

16400 SW Loon Drive Beaverton, Oregon 97007

PBS Project 27121.028, Phase 0001

Dear Ms. Rozendal:

From December 12 to December 15, 2024, PBS Engineering and Environmental Inc. (PBS) performed short-term radon testing at Scholls Heights Elementary School, located at 16400 SW Loon Drive in Beaverton, Oregon.

The Environmental Protection Agency (EPA) recommends, and the Oregon Health Authority (OHA) requires, that school buildings be tested for radon, and that any radon concentrations be maintained below 4.0 picocuries per liter (pCi/L) of air. PBS used Radonova brand single-use, short-term radon test kits to measure radon levels in frequently occupied rooms that are in contact with the ground or above unoccupied basements or crawlspaces.

Laboratory results indicate that all short-term radon test results at Scholls Heights were below 4.0 pCi/L.

See the attached laboratory analysis report for more details.

In addition to the EPA recommendation that radon concentrations not exceed 4.0 pCi/L, OHA recommends that the following steps be conducted based on the results of a room's initial short-term test:

- **If the result is less than 2.0 pCi/L,** school districts are required to test again every 10 years, per Oregon Revised Statute 332.166-167.
- If the result is between 2.0 pCi/L and 4.0 pCi/L, consider fixing (i.e., lowering) the radon in that room.
- If the result is from 4.0 pCi/L to 8.0 pCi/L, perform a follow-up measurement of that room using a long-term test. This test should be conducted over as much of a nine-month school year as possible, when the room is likely to be occupied. If that result is equal to or greater than 4.0 pCi/L, the radon in the room should be fixed (i.e., lowered).
- If the initial short-term test result is equal to or greater than 8.0 pCi/L, conduct a second short-term test and average its result with the initial short-term test result. If the average of the two is equal to or greater than 4.0 pCi/L, radon in the room should be fixed (i.e., lowered).

Beaverton School District Radon Testing Report, Scholls Heights Elementary School January 2024 Page 2 of 2

Note: A great difference in the results of the short-term tests may indicate a flaw in the testing process. Investigate and consider retesting. For situations in which one of the test results is equal to or greater than 4.0 pCi/L, if the higher result is two or more times the lower result, repeat the test.

LIMITATIONS OF SCOPE

This study was limited to the tests and locations as previously indicated. The site as a whole may have other environmental concerns that will not be characterized by this study. The findings and conclusions of this work are not scientific certainties, but probabilities based on professional judgment concerning the significance of the data gathered during the course of this investigation. PBS is not able to represent conditions on the site or adjoining sites beyond those detected or observed by PBS.

Please feel free to contact me at 503.209.1500 or rich@pbsusa.com with any questions or comments.

Sincerely,

Rich Dufrense Senior Project Manager

Attachment: Radonova Laboratory Analysis Report



REPORT NUMBER REPORT DATE 6751635:1 12/21/2023

REPORT PAGE PRINT DATE 1 of 7 12/21/2023

> **OWN ID** N/A

> > BY

PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com PBS Engineering & Environmental **PBS** Engineering **PBS** Engineering

RADON MONITORING REPORT

Description of the measurement

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. 12/20/2023. They were measured 12/20/2023.

Test data have been given by PBS Engineering

Property data and address

MEASURE SITE ADDRESS Scholls Heights Elementary School

16400 SW Loon Drive Beaverton OR 97007

> **BUILDING ID** 27121.028

Test results

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK129943 [QuickScreen]	12/12/2023 03:28 PM – 12/15/2023 03:23 PM	"Main building, floor 2, office 1", Standard		< 0.6 pCi/L
RK129900 [QuickScreen]	12/12/2023 03:30 PM - 12/15/2023 03:23 PM	"Main building, floor 2, health roo, Standard		< 0.7 pCi/L
RK129905 [QuickScreen]	12/12/2023 03:32 PM – 12/15/2023 03:30 PM	"Main building, floor 2, principal, Standard		< 0.9 pCi/L
RK129926 [QuickScreen]	12/12/2023 03:34 PM – 12/15/2023 03:26 PM	"Main building, floor 2, assistant, Standard		< 0.7 pCi/L
RK129942 [QuickScreen]	12/12/2023 03:36 PM – 12/15/2023 03:25 PM	"Main building, floor 2, work room", Standard		< 0.8 pCi/L
RK129930 [QuickScreen]	12/12/2023 03:38 PM – 12/15/2023 03:28 PM	"Main building, floor 2, staff room, Standard		< 0.5 pCi/L
RK129945 [QuickScreen]	12/12/2023 03:46 PM – 12/15/2023 03:32 PM	"Main building, floor 2, room 201", Standard		< 0.8 pCi/L

Comment to the results

Severe Under Exposure for detector RK129920. Tests exposed for less than 46 hours are always invalid.

Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

Radonova Inc. makes no warranty of any kind, express or implied, as regard to the use, operation or analysis of any Radonova Inc. monitor. Radonova Inc. specifically disclaims implied warranties of merchantability and fitness for a particular purpose. Radonova Inc. is not responsible for any damage,

including consequential damages, to persons or property resulting from the use of the monitor or the resulting data.

RADONOVA INC. 1 EAST 22nd STREET, SUITE 200



 REPORT NUMBER
 REPORT DATE

 6751635:1
 12/21/2023

 REPORT PAGE
 PRINT DATE

 2 of 7
 12/21/2023

OWN ID N/A

BY PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com
PBS Engineering & Environmental
PBS Engineering
PBS Engineering

RADON MONITORING REPORT

Description of the measurement

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/20/2023**. They were measured **12/20/2023**.

Test data have been given by PBS Engineering

Property data and address

MEASURE SITE ADDRESS Scholls Heights Elementary School 16400 SW Loon Drive Beaverton OR 97007

BUILDING ID

27121.028

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK129939 [QuickScreen]	12/12/2023 03:48 PM – 12/15/2023 03:33 PM	"Main building, floor 2, room 202", Standard		< 0.7 pCi/L
RK129946 [QuickScreen]	12/12/2023 03:52 PM – 12/15/2023 03:37 PM	"Main building, floor 1, library", Standard		< 1.0 pCi/L
RK129947 [QuickScreen]	12/12/2023 03:52 PM - 12/15/2023 03:37 PM	"Main building, floor 1, library", Duplicate		< 0.9 pCi/L
RK130200 [QuickScreen]	12/12/2023 03:55 PM – 12/15/2023 03:36 PM	"Main building, floor 1, library", Standard		< 0.6 pCi/L
RK129909 [QuickScreen]	12/12/2023 03:57 PM - 12/15/2023 03:38 PM	"Main building, floor 1, room 120", Standard		< 0.6 pCi/L
RK129940 [QuickScreen]	12/12/2023 04:01 PM – 12/15/2023 03:44 PM	"Main building, floor 1, AV studio", Standard		< 0.4 pCi/L
RK130215 [QuickScreen]	12/12/2023 04:01 PM - 12/15/2023 03:44 PM	"Main building, floor 1, AV studio", Duplicate		< 0.6 pCi/L
RK129937 [QuickScreen]	12/12/2023 04:03 PM – 12/15/2023 03:43 PM	"Main building, floor 1, lib workrm, Standard		< 0.7 pCi/L
RK130673 [QuickScreen]	12/12/2023 04:05 PM – 12/15/2023 03:46 PM	"Main building, floor 1, conf rm 11, Standard		< 0.8 pCi/L

Comment to the results

Severe Under Exposure for detector RK129920. Tests exposed for less than 46 hours are always invalid.

Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED

Radonova Inc. makes no warranty of any kind, express or implied, as regard to the use, operation or analysis of any Radonova Inc. monitor. Radonova Inc. specifically disclaims implied warranties of merchantability and fitness for a particular purpose. Radonova Inc. is not responsible for any damage, including consequential damages, to persons or property resulting from the use of the monitor or the resulting data.

RADONOVA INC.



 REPORT NUMBER
 REPORT DATE

 6751635:1
 12/21/2023

 REPORT PAGE
 PRINT DATE

PORT PAGE PRINT DATE 3 of 7 12/21/2023

OWN ID N/A

BY PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com
PBS Engineering & Environmental
PBS Engineering
PBS Engineering

RADON MONITORING REPORT

Description of the measurement

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/20/2023**. They were measured **12/20/2023**.

Test data have been given by PBS Engineering

Property data and address

MEASURE SITE ADDRESS Scholls Heights Elementary School

16400 SW Loon Drive Beaverton OR 97007

> BUILDING ID 27121.028

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK130666 [QuickScreen]	12/12/2023 04:08 PM – 12/15/2023 03:47 PM	"Main building, floor 1, commons 4", Standard		< 0.8 pCi/L
RK129913 [QuickScreen]	12/12/2023 04:09 PM – 12/15/2023 03:50 PM	"Main building, floor 1, classrm 11, Standard		< 0.7 pCi/L
RK130225 [QuickScreen]	12/12/2023 04:11 PM – 12/15/2023 03:50 PM	"Main building, floor 1, classrm 11, Standard		< 0.6 pCi/L
RK130217 [QuickScreen]	12/12/2023 04:12 PM – 12/15/2023 03:51 PM	"Main building, floor 1, classrm 11, Standard		1.3 ± 0.6 pCi/L
RK130226 [QuickScreen]	12/12/2023 04:14 PM – 12/15/2023 03:52 PM	"Main building, floor 1, commons 5", Standard		< 0.8 pCi/L
RK130202 [QuickScreen]	12/12/2023 04:16 PM – 12/15/2023 03:54 PM	"Main building, floor 1, classrm 11, Standard		< 0.7 pCi/L
RK130233 [QuickScreen]	12/12/2023 04:21 PM – 12/15/2023 03:54 PM	"Main building, floor 1, classrm 11, Standard		0.9 ± 0.5 pCi/L
RK130218 [QuickScreen]	12/12/2023 04:24 PM – 12/15/2023 03:55 PM	"Main building, floor 1, classrm 11, Standard		< 0.8 pCi/L
RK130210 [QuickScreen]	12/12/2023 04:26 PM – 12/15/2023 03:56 PM	"Main building, floor 1, classrm 11, Standard		< 0.7 pCi/L

Comment to the results

Severe Under Exposure for detector RK129920. Tests exposed for less than 46 hours are always invalid.

Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED

Radonova Inc. makes no warranty of any kind, express or implied, as regard to the use, operation or analysis of any Radonova Inc. monitor. Radonova Inc. specifically disclaims implied warranties of merchantability and fitness for a particular purpose. Radonova Inc. is not responsible for any damage, including consequential damages, to persons or property resulting from the use of the monitor or the resulting data.



 REPORT NUMBER
 REPORT DATE

 6751635:1
 12/21/2023

 REPORT PAGE
 PRINT DATE

 4 of 7
 12/21/2023

OWN ID N/A

BY PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com
PBS Engineering & Environmental
PBS Engineering
PBS Engineering

RADON MONITORING REPORT

Description of the measurement

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/20/2023**. They were measured **12/20/2023**.

Test data have been given by PBS Engineering

Property data and address

MEASURE SITE ADDRESS Scholls Heights Elementary School 16400 SW Loon Drive Beaverton OR 97007

BUILDING ID

27121.028

RK130234 [QuickScreen] 12/12/2023 04:29 PM – 12/15/2023 03:58 PM "Main building, floor 1, commons 6", Duplicate < 0.6 pCi/RK129932 [QuickScreen] 12/12/2023 04:32 PM – 12/15/2023 03:59 PM "Main bldg, floor 1, class 108/107", Standard < 0.8 pCi/RK129931 [QuickScreen] 12/12/2023 04:35 PM – 12/15/2023 04:00 PM "Main bldg, floor 1, classrm 107/10, Standard < 0.4 pCi/RK129924 [QuickScreen] 12/12/2023 04:36 PM – 12/15/2023 04:02 PM "Main bldg, floor 1, classrm 106/10, Standard 0.6 ± 0.5 pCi/RK129923 [QuickScreen] 12/12/2023 04:42 PM – 12/15/2023 04:03 PM "Main building, floor 1, room 104", Standard < 0.5 pCi/RK129935 [QuickScreen] 12/12/2023 04:45 PM – 12/15/2023 04:05 PM "Main building, floor 1, gym", Standard < 0.4 pCi/RK129934 [QuickScreen] 12/12/2023 04:45 PM – 12/15/2023 04:05 PM "Main building, floor 1, gym", Standard < 0.6 pCi/RK129934 [QuickScreen]	DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK129932 [QuickScreen] 12/12/2023 04:32 PM - 12/15/2023 03:59 PM "Main bldg, floor 1, class 108/107", Standard < 0.8 pCi/RK129931 [QuickScreen]	RK130241 [QuickScreen]	12/12/2023 04:29 PM – 12/15/2023 03:57 PM	"Main building, floor 1, commons 6", Standard		< 0.8 pCi/L
RK129931 [QuickScreen] 12/12/2023 04:35 PM – 12/15/2023 04:00 PM "Main bldg, floor 1, classrm 107/10, Standard < 0.4 pCip	RK130234 [QuickScreen]	12/12/2023 04:29 PM – 12/15/2023 03:58 PM	"Main building, floor 1, commons 6", Duplicate		< 0.6 pCi/L
$RK129924 [QuickScreen]$ $12/12/2023 \ 04:36 \ PM - 12/15/2023 \ 04:02 \ PM$ "Main bldg, floor 1, classrm $106/10$, Standard $0.6 \pm 0.5 \ pCi/2023 \ 04:02 \ PM$ "Main building, floor 1, room 104 ", Standard $0.6 \pm 0.5 \ pCi/2023 \ 04:02 \ PM$ "Main building, floor 1, room 104 ", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, room 104 ", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard $0.6 \pm 0.5 \ pCi/2023 \ PM$ "Main building, floor 1, gym", Standard	RK129932 [QuickScreen]	12/12/2023 04:32 PM – 12/15/2023 03:59 PM	"Main bldg, floor 1, class 108/107", Standard		< 0.8 pCi/L
RK129923 [QuickScreen] 12/12/2023 04:42 PM – 12/15/2023 04:03 PM "Main building, floor 1, room 104", Standard < 0.5 pCi/l	RK129931 [QuickScreen]	12/12/2023 04:35 PM – 12/15/2023 04:00 PM	"Main bldg, floor 1, classrm 107/10, Standard		< 0.4 pCi/L
RK129935 [QuickScreen] 12/12/2023 04:45 PM – 12/15/2023 04:05 PM "Main building, floor 1, gym", Standard < 0.4 pCi/	RK129924 [QuickScreen]	12/12/2023 04:36 PM – 12/15/2023 04:02 PM	"Main bldg, floor 1, classrm 106/10, Standard		0.6 ± 0.5 pCi/L
RK129934 [QuickScreen] 12/12/2023 04:45 PM – 12/15/2023 04:05 PM "Main building, floor 1, gym", Standard < 0.6 pCi	RK129923 [QuickScreen]	12/12/2023 04:42 PM – 12/15/2023 04:03 PM	"Main building, floor 1, room 104", Standard		< 0.5 pCi/L
	RK129935 [QuickScreen]	12/12/2023 04:45 PM – 12/15/2023 04:05 PM	"Main building, floor 1, gym", Standard		< 0.4 pCi/L
	RK129934 [QuickScreen]	12/12/2023 04:45 PM – 12/15/2023 04:05 PM	"Main building, floor 1, gym", Standard		< 0.6 pCi/L
RK129919 [QuickScreen] 12/12/2023 04:47 PM – 12/15/2023 04:08 PM "Main building, floor 1, office 3", Standard < 0.4 pCi/	RK129919 [QuickScreen]	12/12/2023 04:47 PM – 12/15/2023 04:08 PM	"Main building, floor 1, office 3", Standard		< 0.4 pCi/L

Comment to the results

Severe Under Exposure for detector RK129920. Tests exposed for less than 46 hours are always invalid.

Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCI AIMED

Radonova Inc. makes no warranty of any kind, express or implied, as regard to the use, operation or analysis of any Radonova Inc. monitor. Radonova Inc. specifically disclaims implied warranties of merchantability and fitness for a particular purpose. Radonova Inc. is not responsible for any damage, including consequential damages, to persons or property resulting from the use of the monitor or the resulting data.



 REPORT NUMBER
 REPORT DATE

 6751635:1
 12/21/2023

REPORT PAGE5 of 7 **PRINT DATE**12/21/2023

OWN ID N/A

BY PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com
PBS Engineering & Environmental
PBS Engineering
PBS Engineering

RADON MONITORING REPORT

Description of the measurement

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/20/2023**. They were measured **12/20/2023**.

Test data have been given by PBS Engineering

Property data and address

MEASURE SITE ADDRESS Scholls Heights Elementary School 16400 SW Loon Drive

Beaverton OR 97007

BUILDING ID 27121.028

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK130681 [QuickScreen]	12/12/2023 04:50 PM – 12/15/2023 04:08 PM	"Main bldg, floor 1, custodial off", Standard		< 0.7 pCi/L
RK130656 [QuickScreen]	12/12/2023 04:50 PM - 12/15/2023 04:08 PM	"Main bldg, floor 1, custodial off", Duplicate		< 0.9 pCi/L
RK129898 [QuickScreen]	12/12/2023 04:52 PM - 12/15/2023 04:10 PM	"Main building, floor 1, café", Standard		< 0.9 pCi/L
RK130679 [QuickScreen]	12/12/2023 04:52 PM - 12/15/2023 04:11 PM	"Main building, floor 1, café", Standard		< 0.7 pCi/L
RK130619 [QuickScreen]	12/12/2023 04:57 PM - 12/15/2023 04:12 PM	"Main building, floor 1, stage", Standard		< 0.7 pCi/L
RK130249 [QuickScreen]	12/12/2023 05:00 PM - 12/15/2023 04:13 PM	"Main building, floor 1, kitchen", Standard		< 0.8 pCi/L
RK129938 [QuickScreen]	12/12/2023 05:04 PM - 12/15/2023 03:27 PM	"Main building, floor 2, conf room, Standard		< 0.5 pCi/L
RK129896 [QuickScreen]	12/12/2023 03:07 PM - 12/15/2023 03:34 PM	"Main building, floor 2, room 203", Standard		< 0.8 pCi/L
RK129920 [QuickScreen]	12/18/2023 11:01 AM – 12/18/2023 11:01 AM	BLANK, BLANK		ERR

Comment to the results

Severe Under Exposure for detector RK129920. Tests exposed for less than 46 hours are always invalid.

Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED

Radonova Inc. makes no warranty of any kind, express or implied, as regard to the use, operation or analysis of any Radonova Inc. monitor. Radonova Inc. specifically disclaims implied warranties of merchantability and fitness for a particular purpose. Radonova Inc. is not responsible for any damage,

including consequential damages, to persons or property resulting from the use of the monitor or the resulting data.

RADONOVA INC.



 REPORT NUMBER
 REPORT DATE

 6751635:1
 12/21/2023

REPORT PAGE6 of 7 **PRINT DATE**12/21/2023

OWN ID N/A

BY

PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com
PBS Engineering & Environmental
PBS Engineering
PBS Engineering

RADON MONITORING REPORT

Description of the measurement

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/20/2023**. They were measured **12/20/2023**.

Test data have been given by PBS Engineering

Property data and address

MEASURE SITE ADDRESS Scholls Heights Elementary School 16400 SW Loon Drive Beaverton OR 97007

BUILDING ID

27121.028

DETECTOR MEASUREMENT PERIOD DESCRIPTION / LOCATION FLOOR RADON RESULT RK130455 [QuickScreen] 12/12/2023 05:13 PM - 12/15/2023 04:21 PM Portable 1, Standard < 0.7 pCi/L RK130456 [QuickScreen] 12/12/2023 05:13 PM - 12/15/2023 04:21 PM Portable 1, Duplicate < 0.9 pCi/L RK130464 [QuickScreen] 12/12/2023 05:16 PM - 12/15/2023 04:22 PM Portable 2, Standard < 0.6 pCi/L RK130448 [QuickScreen] 12/12/2023 05:19 PM - 12/15/2023 04:23 PM Portable 3, Standard < 0.9 pCi/L RK130447 [QuickScreen] 12/12/2023 05:19 PM - 12/15/2023 04:24 PM Portable 3, Duplicate < 0.7 pCi/L 12/12/2023 05:21 PM - 12/15/2023 04:25 PM RK130440 [QuickScreen] Portable 4, Standard < 0.8 pCi/L RK110728 [QuickScreen] 12/15/2023 04:24 PM - 12/18/2023 11:00 AM BLANK, BLANK < 0.7 pCi/L

Comment to the results

Severe Under Exposure for detector RK129920. Tests exposed for less than 46 hours are always invalid.

Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED

Radonova Inc. makes no warranty of any kind, express or implied, as regard to the use, operation or analysis of any Radonova Inc. monitor. Radonova Inc. specifically disclaims implied warranties of merchantability and fitness for a particular purpose. Radonova Inc. is not responsible for any damage,

including consequential damages, to persons or property resulting from the use of the monitor or the resulting data.

RADONOVA INC.



REPORT NUMBER 6751635:1

REPORT DATE 12/21/2023

REPORT PAGE

7 of 7

PRINT DATE 12/21/2023

OWN ID

Measurement method: Activated Charcoal Adsorption

For this method using the QuickScreen detector, the airtight container with activated charcoal is opened in the area to be sampled and radon in the air adsorbs onto the charcoal granules. At the end of the sampling period, the container is sealed and may be sent to a laboratory for analysis. The gamma decay from the radon adsorbed to the charcoal is counted on a scintillation detector and a calculation based on calibration information is used to calculate the radon concentration at the sample site.

Measured radon concentrations

For each detector, the measured value of the radon concentration is provided. For each value an uncertainty associated with the measurement to a 95% confidence level is also provided. For example a measurement result of 4.0 ± 0.5 pCi/L means that the radon concentration is most likely contained in the range 3.5 - 4.5 pCi/L. If the start or end date of the measurement has not been provided, the radon concentration cannot be calculated. In such cases, the total exposure in pCi*days/L will be reported. The reported measured values are related to the detectors as received by Radonova Laboratories. Detector deployment is not performed by Radonova Laboratories. Measurement information such as monitoring period (dates) and placement location is provided to Radonova Laboratories by the end user. The presented results apply only to the samples tested.

Codes on non-reportable detectors

DNR Not Reported – Detector Not Returned ERR Not Reported – See comment

Measurement method versions used when the report was created

ANSI/AARST MAH-2023, Protocol for Conducting Measurements of Radon and Radon Decay Products in Homes ANSI/AARST MA-MFLB-2023, Protocol for Measurements of Radon in Multifamily, School, Commercial and Mixed-Use Buildings

Radon measurements in Multifamily Buildings, Schools and Large Buildings

The United States Environmental Protection Agency (EPA) recommends remediation if the results of one long-term test or the average of two short-term tests conducted in an occupied room are 4.0 pCi/L or higher. The average yearly residential indoor radon level in the US is estimated to be around 1.3 pCi/L. Long-term tests are conducted for more than 90 days. Short-term tests are conducted between 2 and 90 days and should be performed under closed building conditions.

If an initial short-term test result is less than 4 pCi/L, a follow-up measurement is probably not needed.

If an initial short-term test result is between 4 pCi/L and 8 pCi/L, a long-term or a short-term follow-up measurement is recommended.

If an initial short-term test result is greater than 8 pCi/L, a short term follow-up measurement is recommended in order to get a fast result.

More information about radon measurements and mitigation can be found in the ANSI/AARST publications:

- ANSI/AARST Protocol for Conducting Measurements of Radon and Radon-Decay Products in Schools and Large Buildings.
- ANSI/AARST Protocol for Conducting Radon and Radon Decay Product Measurements in Multifamily Buildings.
- ANSI/AARST Radon Mitigation Standards for Schools and Large Buildings.
- ANSI/AARST Radon Mitigation Standards for Multifamily Buildings.

For more information about the interpretation of your test results or about other radon related issues we suggest contacting your state radon office.

Signature on the report

With the signature on the report, the Measurement specialist at Radonova Laboratories certifies that the quality control procedures follows the guidance in accordance with the AARST/ANSI Measurement Protocols. Measurement information displayed in italics on report has been provided by the customer.

Certification no:

101132-AL, 107830-RT, NY ELAP ID: 11430