

January 15, 2024

Lelisa Rozendal Beaverton School District 2180 SW 170th Avenue Beaverton, OR 97003

Via email: lelisa\_rozendal@beaverton.k12.or.us

Regarding: Radon Testing

Whitford Middle School 7935 SW Scholls Ferry Road Beaverton, Oregon 97008

PBS Project 27121.028, Phase 0001

Dear Ms. Rozendal:

From December 18 to December 21, 2023, PBS Engineering and Environmental Inc. (PBS) performed short-term radon testing at Whitford Middle School, located at 7935 SW Scholls Ferry Road in Beaverton, Oregon.

The Environmental Protection Agency (EPA) recommends, and the Oregon Health Authority (OHA) requires, that school buildings be tested for radon, and that any radon concentrations be maintained below 4.0 picocuries per liter (pCi/L) of air. PBS used Radonova brand single-use, short-term radon test kits to measure radon levels in frequently occupied rooms that are in contact with the ground or above unoccupied basements or crawlspaces.

Laboratory results indicate that all short-term radon test results at Whitford Middle School were below 4.0 pCi/L.

See the attached laboratory analysis report for more details.

In addition to the EPA recommendation that radon concentrations not exceed 4.0 pCi/L, OHA recommends that the following steps be conducted based on the results of a room's initial short-term test:

- **If the result is less than 2.0 pCi/L,** school districts are required to test again every 10 years, per Oregon Revised Statute 332.166-167.
- If the result is between 2.0 pCi/L and 4.0 pCi/L, consider fixing (i.e., lowering) the radon in that room.
- If the result is from 4.0 pCi/L to 8.0 pCi/L, perform a follow-up measurement of that room using a long-term test. This test should be conducted over as much of a nine-month school year as possible, when the room is likely to be occupied. If that result is equal to or greater than 4.0 pCi/L, the radon in the room should be fixed (i.e., lowered).
- If the initial short-term test result is equal to or greater than 8.0 pCi/L, conduct a second short-term test and average its result with the initial short-term test result. If the average of the two is equal to or greater than 4.0 pCi/L, radon in the room should be fixed (i.e., lowered).

Beaverton School District Radon Testing Report, Whitford Middle School January 2024 Page 2 of 2

Note: A great difference in the results of the short-term tests may indicate a flaw in the testing process. Investigate and consider retesting. For situations in which one of the test results is equal to or greater than 4.0 pCi/L, if the higher result is two or more times the lower result, repeat the test.

### **LIMITATIONS OF SCOPE**

This study was limited to the tests and locations as previously indicated. The site as a whole may have other environmental concerns that will not be characterized by this study. The findings and conclusions of this work are not scientific certainties, but probabilities based on professional judgment concerning the significance of the data gathered during the course of this investigation. PBS is not able to represent conditions on the site or adjoining sites beyond those detected or observed by PBS.

Please feel free to contact me at 503.209.1500 or rich@pbsusa.com with any questions or comments.

Sincerely,

Rich Dufrense Senior Project Manager

Attachment: Radonova Laboratory Analysis Report



 REPORT NUMBER
 REPORT DATE

 6751632:2
 01/03/2024

 REPORT PAGE
 PRINT DATE

1 of 10 01/03/2024

OWN ID N/A

BY PBS Engineering & Environmental

REPORT RECEIVER(S) john.yuly@pbsusa.com PBS Engineering & Environmental

# RADON MONITORING REPORT

### **Description of the measurement**

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/22/2023**. They were measured **12/22/2023**.

Test data have been given by PBS Engineering

## **Property data and address**

MEASURE SITE ADDRESS Whitford Middle School 7935 SW Scholls Ferry Rd

BUILDING ID 27121.028

#### **Test results**

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK128677 [QuickScreen]	12/18/2023 11:35 AM – 12/21/2023 10:30 AM	"Main building, C-8", Duplicate		< 0.8 pCi/L
RK129381 [QuickScreen]	12/18/2023 11:36 AM – 12/21/2023 10:30 AM	"Main building, C-7", Standard		0.6 pCi/L
RK129318 [QuickScreen]	12/18/2023 11:36 AM – 12/21/2023 10:30 AM	"Main building, C-7", Duplicate		0.8 pCi/L
RK129291 [QuickScreen]	12/18/2023 11:39 AM – 12/21/2023 10:30 AM	"Main building, C-6", Standard		0.6 pCi/L
RK128686 [QuickScreen]	12/18/2023 11:39 AM – 12/21/2023 10:30 AM	"Main building, C-6", Duplicate		< 0.8 pCi/L
RK129379 [QuickScreen]	12/18/2023 11:40 AM – 12/21/2023 10:30 AM	"Main building, C-5", Standard		< 0.7 pCi/L
RK129322 [QuickScreen]	12/18/2023 11:41 AM – 12/21/2023 10:30 AM	"Main building, C-4", Standard		0.6 pCi/L

### Comment to the results

#### Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

#### DISCLAIMER



 REPORT NUMBER
 REPORT DATE

 6751632:2
 01/03/2024

 REPORT PAGE
 PRINT DATE

2 of 10 01/03/2024

OWN ID N/A

BY PBS Engineering & Environmental

**REPORT RECEIVER(S)** john.yuly@pbsusa.com PBS Engineering & Environmental

# RADON MONITORING REPORT

### **Description of the measurement**

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/22/2023**. They were measured **12/22/2023**.

Test data have been given by PBS Engineering

### **Property data and address**

MEASURE SITE ADDRESS Whitford Middle School 7935 SW Scholls Ferry Rd

**BUILDING ID** 27121.028

RK129343 [QuickScreen]       12/18/2023 11:41 AM – 12/21/2023 10:30 AM "Main building, C-3", Standard       0.7 pCi/L         RK129351 [QuickScreen]       12/18/2023 11:41 AM – 12/21/2023 10:30 AM "Main building, CO2", Standard       0.6 pCi/L         RK129346 [QuickScreen]       12/18/2023 11:42 AM – 12/21/2023 10:30 AM "Main building, C-1", Standard       0.6 pCi/L         RK129286 [QuickScreen]       12/18/2023 11:42 AM – 12/21/2023 10:30 AM "Main building, CL 4, corr. 2", Standard       0.6 pCi/L         RK129319 [QuickScreen]       12/18/2023 11:42 AM – 12/21/2023 10:30 AM "Main building, CL RM 3 WKRM 1", Standard       0.6 pCi/L         RK129293 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.4 pCi/L         RK129365 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       0.7 pCi/L         RK128727 [QuickScreen]       12/18/2023 11:48 AM – 12/21/2023 10:50 AM "Main building, B-9", Standard       0.7 pCi/L         RK128682 [QuickScreen]       12/18/2023 11:49 AM – 12/21/2023 10:50 AM "Main building, B-8", Standard       < 0.7 pCi/L	DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK129346 [QuickScreen]       12/18/2023 11:42 AM – 12/21/2023 10:30 AM "Main building, C-1", Standard       0.6 pCi/L         RK129286 [QuickScreen]       12/18/2023 11:42 AM – 12/21/2023 10:30 AM "Main building, CL 4, corr. 2", Standard       0.6 pCi/L         RK129319 [QuickScreen]       12/18/2023 11:42 AM – 12/21/2023 10:30 AM "Main building, CL RM 3 WKRM 1", Standard       0.6 pCi/L         RK129293 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.4 pCi/L         RK129365 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.1 pCi/L         RK128727 [QuickScreen]       12/18/2023 11:48 AM – 12/21/2023 10:50 AM "Main building, B-9", Standard       0.7 pCi/L	RK129343 [QuickScreen]	12/18/2023 11:41 AM – 12/21/2023 10:30 AM	"Main building, C-3", Standard		0.7 pCi/L
RK129286 [QuickScreen]       12/18/2023 11:42 AM – 12/21/2023 10:30 AM "Main building, CL 4, corr. 2", Standard       0.6 pCi/L         RK129319 [QuickScreen]       12/18/2023 11:42 AM – 12/21/2023 10:30 AM "Main building, CL RM 3 WKRM 1", Standard       0.6 pCi/L         RK129293 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.4 pCi/L         RK129365 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.1 pCi/L         RK128727 [QuickScreen]       12/18/2023 11:48 AM – 12/21/2023 10:50 AM "Main building, B-9", Standard       0.7 pCi/L	RK129351 [QuickScreen]	12/18/2023 11:41 AM – 12/21/2023 10:30 AM	"Main building, C02", Standard		0.6 pCi/L
RK129319 [QuickScreen]       12/18/2023 11:42 AM – 12/21/2023 10:30 AM "Main building, CL RM 3 WKRM 1", Standard       0.6 pCi/L         RK129293 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.4 pCi/L         RK129365 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.1 pCi/L         RK128727 [QuickScreen]       12/18/2023 11:48 AM – 12/21/2023 10:50 AM "Main building, B-9", Standard       0.7 pCi/L	RK129346 [QuickScreen]	12/18/2023 11:42 AM – 12/21/2023 10:30 AM	"Main building, C-1", Standard		0.6 pCi/L
RK129293 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.4 pCi/L         RK129365 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.1 pCi/L         RK128727 [QuickScreen]       12/18/2023 11:48 AM – 12/21/2023 10:50 AM "Main building, B-9", Standard       0.7 pCi/L	RK129286 [QuickScreen]	12/18/2023 11:42 AM – 12/21/2023 10:30 AM	"Main building, CL 4, corr. 2", Standard		0.6 pCi/L
RK129365 [QuickScreen]       12/18/2023 11:46 AM – 12/21/2023 10:30 AM "Main building, library", Standard       1.1 pCi/L         RK128727 [QuickScreen]       12/18/2023 11:48 AM – 12/21/2023 10:50 AM "Main building, B-9", Standard       0.7 pCi/L	RK129319 [QuickScreen]	12/18/2023 11:42 AM – 12/21/2023 10:30 AM	"Main building, CL RM 3 WKRM 1", Standard		0.6 pCi/L
RK128727 [QuickScreen] 12/18/2023 11:48 AM – 12/21/2023 10:50 AM "Main building, B-9", Standard 0.7 pCi/L	RK129293 [QuickScreen]	12/18/2023 11:46 AM – 12/21/2023 10:30 AM	"Main building, library", Standard		1.4 pCi/L
	RK129365 [QuickScreen]	12/18/2023 11:46 AM – 12/21/2023 10:30 AM	"Main building, library", Standard		1.1 pCi/L
RK128682 [QuickScreen] 12/18/2023 11:49 AM – 12/21/2023 10:50 AM "Main building, B-8", Standard < 0.7 pCi/L	RK128727 [QuickScreen]	12/18/2023 11:48 AM – 12/21/2023 10:50 AM	"Main building, B-9", Standard		0.7 pCi/L
	RK128682 [QuickScreen]	12/18/2023 11:49 AM – 12/21/2023 10:50 AM	"Main building, B-8", Standard		< 0.7 pCi/L

### Comment to the results

#### Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED



 REPORT NUMBER
 REPORT DATE

 6751632:2
 01/03/2024

 REPORT PAGE
 PRINT DATE

3 of 10

OWN ID N/A

01/03/2024

BY PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com PBS Engineering & Environmental

# RADON MONITORING REPORT

### **Description of the measurement**

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/22/2023**. They were measured **12/22/2023**.

Test data have been given by PBS Engineering

## **Property data and address**

MEASURE SITE ADDRESS Whitford Middle School 7935 SW Scholls Ferry Rd

BUILDING ID 27121.028

RK128718 [QuickScreen]       12/18/2023 11:50 AM - 12/21/2023 10:50 AM "Main building, B-7", Standard       0.8 pCi/L         RK128684 [QuickScreen]       12/18/2023 11:54 AM - 12/21/2023 10:50 AM "Main building, B-6", Standard       0.9 pCi/L         RK128744 [QuickScreen]       12/18/2023 11:54 AM - 12/21/2023 10:50 AM "Main building, B-5", Standard       < 0.6 pCi/L         RK128689 [QuickScreen]       12/18/2023 11:56 AM - 12/21/2023 10:50 AM "Main building, B-4", Standard       < 0.7 pCi/L         RK128750 [QuickScreen]       12/18/2023 11:57 AM - 12/21/2023 10:50 AM "Main building, B-3", Standard       < 0.7 pCi/L         RK128759 [QuickScreen]       12/18/2023 11:58 AM - 12/21/2023 10:50 AM "Main building, B-1", Standard       < 0.7 pCi/L	DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK128684 [QuickScreen]       12/18/2023 11:54 AM – 12/21/2023 10:50 AM "Main building, B-6", Standard       0.9 pCi/L         RK128744 [QuickScreen]       12/18/2023 11:54 AM – 12/21/2023 10:50 AM "Main building, B-5", Standard       < 0.6 pCi/L	RK128720 [QuickScreen]	12/18/2023 11:49 AM – 12/21/2023 10:50 AM	"Main building, B-8", Duplicate		< 0.6 pCi/L
RK128744 [QuickScreen]       12/18/2023 11:54 AM - 12/21/2023 10:50 AM "Main building, B-5", Standard       < 0.6 pCi/L	RK128718 [QuickScreen]	12/18/2023 11:50 AM – 12/21/2023 10:50 AM	"Main building, B-7", Standard		0.8 pCi/L
RK128689 [QuickScreen]       12/18/2023 11:56 AM – 12/21/2023 10:50 AM "Main building, B-4", Standard       < 0.7 pCi/L	RK128684 [QuickScreen]	12/18/2023 11:54 AM - 12/21/2023 10:50 AM	"Main building, B-6", Standard		0.9 pCi/L
RK128690 [QuickScreen]       12/18/2023 11:56 AM - 12/21/2023 10:50 AM "Main building, B-3", Standard       0.8 pCi/L         RK128750 [QuickScreen]       12/18/2023 11:57 AM - 12/21/2023 10:50 AM "Main building, B-2", Standard       < 0.7 pCi/L	RK128744 [QuickScreen]	12/18/2023 11:54 AM – 12/21/2023 10:50 AM	"Main building, B-5", Standard		< 0.6 pCi/L
RK128750 [QuickScreen]       12/18/2023 11:57 AM – 12/21/2023 10:50 AM "Main building, B-2", Standard       < 0.7 pCi/L	RK128689 [QuickScreen]	12/18/2023 11:56 AM – 12/21/2023 10:50 AM	"Main building, B-4", Standard		< 0.7 pCi/L
RK128759 [QuickScreen] 12/18/2023 11:58 AM – 12/21/2023 10:50 AM "Main building, B-1", Standard < 0.7 pCi/L	RK128690 [QuickScreen]	12/18/2023 11:56 AM – 12/21/2023 10:50 AM	"Main building, B-3", Standard		0.8 pCi/L
	RK128750 [QuickScreen]	12/18/2023 11:57 AM - 12/21/2023 10:50 AM	"Main building, B-2", Standard		< 0.7 pCi/L
RK128710 [QuickScreen] 12/18/2023 11:58 AM = 12/21/2023 10:50 AM "Main huilding C-2 Ms Thrower" Standard 0.7 nCi/L	RK128759 [QuickScreen]	12/18/2023 11:58 AM – 12/21/2023 10:50 AM	"Main building, B-1", Standard		< 0.7 pCi/L
12,10,2025 11:307W 12,21,2025 10:307W Wall balland, C 2, W.S. Mower, Standard	RK128710 [QuickScreen]	12/18/2023 11:58 AM – 12/21/2023 10:50 AM	"Main building, C-2, Ms. Thrower", Standard		0.7 pCi/L

### Comment to the results

#### Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED



 REPORT NUMBER
 REPORT DATE

 6751632:2
 01/03/2024

 REPORT PAGE
 PRINT DATE

4 of 10

OWN ID N/A

01/03/2024

BY PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com PBS Engineering & Environmental

# RADON MONITORING REPORT

### **Description of the measurement**

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/22/2023**. They were measured **12/22/2023**.

Test data have been given by PBS Engineering

## **Property data and address**

MEASURE SITE ADDRESS Whitford Middle School 7935 SW Scholls Ferry Rd

BUILDING ID 27121.028

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK128681 [QuickScreen] 12/18/2023	12:04 PM – 12/21/2023 10:50 AM	"Main building, C-1, Ms. Duplessie", Standard		< 0.6 pCi/L
RK129297 [QuickScreen] 12/18/2023	12:05 PM – 12/21/2023 10:50 AM	"Main building, A-9", Standard		0.8 pCi/L
RK129375 [QuickScreen] 12/18/2023	12:06 PM – 12/21/2023 10:50 AM	"Main building, A-8", Standard		0.7 pCi/L
RK129354 [QuickScreen] 12/18/2023	12:06 PM – 12/21/2023 10:50 AM	"Main building, A-7", Standard		0.8 pCi/L
RK129321 [QuickScreen] 12/18/2023	12:07 PM – 12/21/2023 10:50 AM	"Main building, A-7", Duplicate		0.6 pCi/L
RK129359 [QuickScreen] 12/18/2023	12:07 PM – 12/21/2023 10:50 AM	"Main building, A-6", Standard		0.8 pCi/L
RK129305 [QuickScreen] 12/18/2023	12:08 PM – 12/21/2023 10:50 AM	"Main building, A-5", Standard		0.8 pCi/L
RK129336 [QuickScreen] 12/18/2023	12:09 PM – 12/21/2023 10:50 AM	"Main building, A-4", Standard		0.6 pCi/L
RK129294 [QuickScreen] 12/18/2023	12:10 PM - 12/21/2023 10:50 AM	"Main building, A-2", Standard		1.2 pCi/L

### Comment to the results

#### Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED

Radonova Inc. makes no warranty of any kind, express or implied, as regard to the use, operation or analysis of any Radonova Inc. monitor. Radonova Inc. specifically disclaims implied warranties of merchantability and fitness for a particular purpose. Radonova Inc. is not responsible for any damage, including consequential damages, to persons or property resulting from the use of the monitor or the resulting data.

RADONOVA INC.



 REPORT NUMBER
 REPORT DATE

 6751632:2
 01/03/2024

 REPORT PAGE
 PRINT DATE

5 of 10 01/03/2024

OWN ID N/A

BY PBS Engineering & Environmental

REPORT RECEIVER(S)
john.yuly@pbsusa.com
PBS Engineering & Environmental

# RADON MONITORING REPORT

### **Description of the measurement**

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/22/2023**. They were measured **12/22/2023**.

Test data have been given by PBS Engineering

## **Property data and address**

MEASURE SITE ADDRESS Whitford Middle School 7935 SW Scholls Ferry Rd

> BUILDING ID 27121.028

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK129330 [QuickScreen]	12/18/2023 12:11 PM – 12/21/2023 10:50 AM	"Main building, A-1", Standard		1.5 pCi/L
RK129292 [QuickScreen]	12/18/2023 12:12 PM – 12/21/2023 10:50 AM	"Main building, B-10", Standard		< 0.5 pCi/L
RK129307 [QuickScreen]	12/18/2023 12:13 PM – 12/21/2023 10:50 AM	"Main building, B-12", Standard		0.5 pCi/L
RK129378 [QuickScreen]	12/18/2023 12:14 PM – 12/21/2023 10:50 AM	"Main building, B-14", Standard		0.5 pCi/L
RK129315 [QuickScreen]	12/18/2023 12:14 PM – 12/21/2023 10:50 AM	"Main building, A-15", Standard		< 0.5 pCi/L
RK129290 [QuickScreen]	12/18/2023 12:15 PM – 12/21/2023 10:50 AM	"Main building, A-12", Standard		< 0.5 pCi/L
RK129283 [QuickScreen]	12/18/2023 11:14 AM – 12/21/2023 10:50 AM	"Main building, A-11", Standard		< 0.5 pCi/L
RK128713 [QuickScreen]	12/18/2023 11:14 AM – 12/21/2023 10:50 AM	"Main building, cafeteria", Standard		1.5 pCi/L
RK128777 [QuickScreen]	12/18/2023 11:15 AM – 12/21/2023 10:50 AM	"Main building, cafeteria", Standard		1.5 pCi/L

### Comment to the results

#### Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.



 REPORT NUMBER
 REPORT DATE

 6751632:2
 01/03/2024

 REPORT PAGE
 PRINT DATE

6 of 10

OWN ID N/A

01/03/2024

BY PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com PBS Engineering & Environmental

# RADON MONITORING REPORT

### **Description of the measurement**

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/22/2023**. They were measured **12/22/2023**.

Test data have been given by PBS Engineering

## **Property data and address**

MEASURE SITE ADDRESS Whitford Middle School 7935 SW Scholls Ferry Rd

> BUILDING ID 27121.028

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK128699 [QuickScreen]	12/18/2023 11:15 AM – 12/21/2023 10:50 AM	"Main building, kitchen", Standard		1.4 pCi/L
RK128737 [QuickScreen]	12/18/2023 11:16 AM – 12/21/2023 10:50 AM	"Main building, staff rm", Standard		< 0.7 pCi/L
RK128733 [QuickScreen]	12/18/2023 11:18 AM – 12/21/2023 10:50 AM	"Main building, cust. office", Standard		0.9 pCi/L
RK128715 [QuickScreen]	12/18/2023 11:23 AM – 12/21/2023 10:50 AM	"Main building, practice rm", Standard		< 0.8 pCi/L
RK128741 [QuickScreen]	12/18/2023 11:25 AM – 12/21/2023 10:50 AM	"Main building, music", Standard		0.8 pCi/L
RK128700 [QuickScreen]	12/18/2023 11:25 AM – 12/21/2023 10:50 AM	"Main building, gym", Standard		0.7 pCi/L
RK128745 [QuickScreen]	12/18/2023 11:27 AM – 12/21/2023 10:50 AM	"Main building, gym", Standard		0.7 pCi/L
RK129298 [QuickScreen]	12/18/2023 11:28 AM – 12/21/2023 10:50 AM	"Main building, fitness gym", Standard		2.4 pCi/L
RK129353 [QuickScreen]	12/18/2023 11:29 AM – 12/21/2023 10:50 AM	"Main building, C-17A", Standard		1.9 pCi/L
		·		

### Comment to the results

#### Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED



 REPORT NUMBER
 REPORT DATE

 6751632:2
 01/03/2024

 REPORT PAGE
 PRINT DATE

7 of 10 01/03/2024

OWN ID N/A

BY PBS Engineering & Environmental

REPORT RECEIVER(S)
john.yuly@pbsusa.com
PBS Engineering & Environmental

# RADON MONITORING REPORT

### **Description of the measurement**

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/22/2023**. They were measured **12/22/2023**.

Test data have been given by PBS Engineering

## **Property data and address**

MEASURE SITE ADDRESS Whitford Middle School 7935 SW Scholls Ferry Rd

**BUILDING ID** 27121.028

RK129323 [QuickScreen]       12/18/2023 11:30 AM – 12/21/2023 10:50 AM       "Main building, C-17 office", Standard       2.8 pC         RK129377 [QuickScreen]       12/18/2023 11:31 AM – 12/21/2023 10:50 AM       "Main building, C-17", Standard       1.9 pC         RK129338 [QuickScreen]       12/18/2023 11:31 AM – 12/21/2023 10:50 AM       "Main building, C-12", Standard       0.5 pC         RK129335 [QuickScreen]       12/18/2023 11:32 AM – 12/21/2023 10:50 AM       "Main building, C-13", Standard       0.7 pC         RK129383 [QuickScreen]       12/18/2023 11:33 AM – 12/21/2023 10:50 AM       "Main building, C-10", Standard       < 0.4 pC	DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK129377 [QuickScreen]       12/18/2023 11:31 AM – 12/21/2023 10:50 AM       "Main building, C-17", Standard       1.9 pC         RK129338 [QuickScreen]       12/18/2023 11:31 AM – 12/21/2023 10:50 AM       "Main building, C-12", Standard       0.5 pC         RK129335 [QuickScreen]       12/18/2023 11:32 AM – 12/21/2023 10:50 AM       "Main building, C-13", Standard       0.7 pC         RK129383 [QuickScreen]       12/18/2023 11:33 AM – 12/21/2023 10:50 AM       "Main building, C-10", Standard       < 0.4 pC	RK129362 [QuickScreen]	12/18/2023 11:29 AM – 12/21/2023 10:50 AM	"Main building, C-17B", Standard		1.9 pCi/L
RK129338 [QuickScreen]       12/18/2023 11:31 AM – 12/21/2023 10:50 AM       "Main building, C-12", Standard       0.5 pC         RK129335 [QuickScreen]       12/18/2023 11:32 AM – 12/21/2023 10:50 AM       "Main building, C-13", Standard       0.7 pC         RK129383 [QuickScreen]       12/18/2023 11:33 AM – 12/21/2023 10:50 AM       "Main building, C-10", Standard       < 0.4 pC	RK129323 [QuickScreen]	12/18/2023 11:30 AM – 12/21/2023 10:50 AM	"Main building, C-17 office", Standard		2.8 pCi/L
RK129335 [QuickScreen]       12/18/2023 11:32 AM – 12/21/2023 10:50 AM       "Main building, C-13", Standard       0.7 pC         RK129383 [QuickScreen]       12/18/2023 11:33 AM – 12/21/2023 10:50 AM       "Main building, C-10", Standard       < 0.4 pC	RK129377 [QuickScreen]	12/18/2023 11:31 AM – 12/21/2023 10:50 AM	"Main building, C-17", Standard		1.9 pCi/L
RK129383 [QuickScreen] 12/18/2023 11:33 AM – 12/21/2023 10:50 AM "Main building, C-10", Standard < 0.4 pC	RK129338 [QuickScreen]	12/18/2023 11:31 AM – 12/21/2023 10:50 AM	"Main building, C-12", Standard		0.5 pCi/L
	RK129335 [QuickScreen]	12/18/2023 11:32 AM – 12/21/2023 10:50 AM	"Main building, C-13", Standard		0.7 pCi/L
RK129382 [QuickScreen] 12/18/2023 11:34 AM – 12/21/2023 10:50 AM "Main building, C-11", Standard 0.5 pC	RK129383 [QuickScreen]	12/18/2023 11:33 AM – 12/21/2023 10:50 AM	"Main building, C-10", Standard		< 0.4 pCi/L
	RK129382 [QuickScreen]	12/18/2023 11:34 AM – 12/21/2023 10:50 AM	"Main building, C-11", Standard		0.5 pCi/L
RK129352 [QuickScreen] 12/18/2023 11:34 AM – 12/21/2023 10:50 AM "Main building, C-9", Standard < 0.3 pC	RK129352 [QuickScreen]	12/18/2023 11:34 AM – 12/21/2023 10:50 AM	"Main building, C-9", Standard		< 0.3 pCi/L
RK129373 [QuickScreen] 12/18/2023 11:35 AM – 12/21/2023 10:50 AM "Main building, C-9B", Standard < 0.5 pC	RK129373 [QuickScreen]	12/18/2023 11:35 AM – 12/21/2023 10:50 AM	"Main building, C-9B", Standard		< 0.5 pCi/L

### Comment to the results

#### Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED



 REPORT NUMBER
 REPORT DATE

 6751632:2
 01/03/2024

 REPORT PAGE
 PRINT DATE

8 of 10 01/03/2024

OWN ID N/A

BY PBS Engineering & Environmental

REPORT RECEIVER(S)
hn.yuly@pbsusa.com

john.yuly@pbsusa.com PBS Engineering & Environmental

# RADON MONITORING REPORT

### **Description of the measurement**

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/22/2023**. They were measured **12/22/2023**.

Test data have been given by PBS Engineering

## **Property data and address**

MEASURE SITE ADDRESS Whitford Middle School 7935 SW Scholls Ferry Rd

BUILDING ID 27121.028

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK129356 [QuickScreen]	12/18/2023 11:35 AM – 12/21/2023 10:50 AM	"Main building, C-9A", Standard		0.3 pCi/L
RK129349 [QuickScreen]	12/18/2023 12:16 PM - 12/21/2023 10:50 AM	"Main building, C-8", Standard		< 0.4 pCi/L
RK128702 [QuickScreen]	12/18/2023 12:19 PM – 12/21/2023 10:50 AM	"Main building, A-10", Standard		0.6 pCi/L
RK129341 [QuickScreen]	12/18/2023 12:19 PM – 12/21/2023 10:50 AM	Main office, Standard		0.5 pCi/L
RK129314 [QuickScreen]	12/18/2023 12:20 PM - 12/21/2023 10:50 AM	Main office, Duplicate		0.5 pCi/L
RK129295 [QuickScreen]	12/18/2023 12:20 PM - 12/21/2023 10:50 AM	Main office, Standard		< 0.6 pCi/L
RK129376 [QuickScreen]	12/18/2023 12:21 PM - 12/21/2023 10:50 AM	Main office, Standard		1.0 pCi/L
RK129306 [QuickScreen]	12/18/2023 12:21 PM - 12/21/2023 10:50 AM	Main office, Standard		1.0 pCi/L
RK129316 [QuickScreen]	12/18/2023 12:22 PM – 12/21/2023 10:50 AM	Main office, Standard		0.6 pCi/L

### Comment to the results

#### Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED

Radonova Inc. makes no warranty of any kind, express or implied, as regard to the use, operation or analysis of any Radonova Inc. monitor. Radonova Inc. specifically disclaims implied warranties of merchantability and fitness for a particular purpose. Radonova Inc. is not responsible for any damage, including consequential damages, to persons or property resulting from the use of the monitor or the resulting data.

RADONOVA INC.



 REPORT NUMBER
 REPORT DATE

 6751632:2
 01/03/2024

 REPORT PAGE
 PRINT DATE

9 of 10 01/03/2024

OWN ID N/A

BY PBS Engineering & Environmental

REPORT RECEIVER(S)

john.yuly@pbsusa.com PBS Engineering & Environmental

# RADON MONITORING REPORT

### **Description of the measurement**

The measurement was performed with Activated Charcoal Adsorption by Alpha Energy Laboratories (NRPP ID: 101132 AL).

The detector(s) arrived to Alpha Energy Laboratories, Inc. **12/22/2023**. They were measured **12/22/2023**.

Test data have been given by PBS Engineering

## **Property data and address**

MEASURE SITE ADDRESS Whitford Middle School 7935 SW Scholls Ferry Rd

BUILDING ID 27121.028

DETECTOR	MEASUREMENT PERIOD	DESCRIPTION / LOCATION	FLOOR	RADON RESULT
RK129327 [QuickScreen]	12/18/2023 12:23 PM – 12/21/2023 10:50 AM	Main office, Standard		0.7 pCi/L
RK128719 [QuickScreen]	12/18/2023 12:24 PM – 12/21/2023 10:50 AM	Main office, Standard		1.1 pCi/L
RK128716 [QuickScreen]	12/18/2023 12:24 PM – 12/21/2023 10:50 AM	Main office, Standard		0.9 pCi/L
RK128735 [QuickScreen]	12/18/2023 12:24 PM – 12/21/2023 10:50 AM	Main office, Standard		1.2 pCi/L

### Comment to the results

#### Tryggve Rönnqvist (Electronically signed)

Signature Radonova Laboratories Laboratory Measurement Specialist

This report may only be reproduced in full, unless issuing laboratory has given prior written approval.

DISCLAIMED

Radonova Inc. makes no warranty of any kind, express or implied, as regard to the use, operation or analysis of any Radonova Inc. monitor. Radonova Inc. specifically disclaims implied warranties of merchantability and fitness for a particular purpose. Radonova Inc. is not responsible for any damage, including consequential damages, to persons or property resulting from the use of the monitor or the resulting data.

RADONOVA INC.



REPORT NUMBER

REPORT DATE 6751632:2 01/03/2024

REPORT PAGE 10 of 10

PRINT DATE 01/03/2024

OWN ID

### Measurement method: Activated Charcoal Adsorption

For this method using the QuickScreen detector, the airtight container with activated charcoal is opened in the area to be sampled and radon in the air adsorbs onto the charcoal granules. At the end of the sampling period, the container is sealed and may be sent to a laboratory for analysis. The gamma decay from the radon adsorbed to the charcoal is counted on a scintillation detector and a calculation based on calibration information is used to calculate the radon concentration at the sample site.

#### Measured radon concentrations

For each detector, the measured value of the radon concentration is provided. For each value an uncertainty associated with the measurement to a 95% confidence level is also provided. For example a measurement result of 4.0 ± 0.5 pCi/L means that the radon concentration is most likely contained in the range 3.5 - 4.5 pCi/L. If the start or end date of the measurement has not been provided, the radon concentration cannot be calculated. In such cases, the total exposure in pCi\*days/L will be reported. The reported measured values are related to the detectors as received by Radonova Laboratories. Detector deployment is not performed by Radonova Laboratories. Measurement information such as monitoring period (dates) and placement location is provided to Radonova Laboratories by the end user. The presented results apply only to the samples tested.

#### Codes on non-reportable detectors

Not Reported - Detector Not Returned FRR Not Reported – See comment

### Measurement method versions used when the report was created

ANSI/AARST MAH-2023, Protocol for Conducting Measurements of Radon and Radon Decay Products in Homes ANSI/AARST MA-MFLB-2023, Protocol for Measurements of Radon in Multifamily, School, Commercial and Mixed-Use Buildings

### Radon measurements in Multifamily Buildings, Schools and Large Buildings

The United States Environmental Protection Agency (EPA) recommends remediation if the results of one long-term test or the average of two short-term tests conducted in an occupied room are 4.0 pCi/L or higher. The average yearly residential indoor radon level in the US is estimated to be around 1.3 pCi/L. Long-term tests are conducted for more than 90 days. Short-term tests are conducted between 2 and 90 days and should be performed under closed building conditions.

If an initial short-term test result is less than 4 pCi/L, a follow-up measurement is probably not needed.

If an initial short-term test result is between 4 pCi/L and 8 pCi/L, a long-term or a short-term follow-up measurement is recommended.

If an initial short-term test result is greater than 8 pCi/L, a short term follow-up measurement is recommended in order to get a fast result.

#### More information about radon measurements and mitigation can be found in the ANSI/AARST publications:

- ANSI/AARST Protocol for Conducting Measurements of Radon and Radon-Decay Products in Schools and Large Buildings.
- ANSI/AARST Protocol for Conducting Radon and Radon Decay Product Measurements in Multifamily Buildings.
- ANSI/AARST Radon Mitigation Standards for Schools and Large Buildings.
- ANSI/AARST Radon Mitigation Standards for Multifamily Buildings.

For more information about the interpretation of your test results or about other radon related issues we suggest contacting your state radon office.

#### Signature on the report

With the signature on the report, the Measurement specialist at Radonova Laboratories certifies that the quality control procedures follows the guidance in accordance with the AARST/ANSI Measurement Protocols. Measurement information displayed in italics on report has been provided by the customer.

#### Certification no:

101132-AL, 107830-RT, NY ELAP ID: 11430