



**OFFICE OF ENVIRONMENTAL  
MANAGEMENT AND SERVICES**

440 North Broad Street, Suite 373  
Philadelphia, PA 19130  
Telephone (215) 400-4750  
Fax (215) 400-4751

**To:** Principal of The Philadelphia Charter School for the Arts and Sciences at H.R. Edmunds

**From:** Office of Environmental Management and Services

**Date:** October 10, 2023

**Subject:** AHERA Three (3) Year Re-Inspection Report

---

Please find the enclosed Three-Year Re-Inspection Report for The Philadelphia Charter School for the Arts and Sciences at H. R. Edmunds, prepared by Tetra Tech, Inc., to comply with the provisions of the Asbestos Hazard Emergency Response Act (AHERA).

The law requires that this report be kept in the Main, or Principal's, office. It should not be removed from this location. If the school (program) is relocated to a different building, this AHERA Re-Inspection Report and supporting Management Plan documents should remain on the premises and be provided to the next school or building occupants.

All asbestos reports must be available to the public upon request.

Please feel free to contact the School District of Philadelphia's Office of Environmental Management and Services for assistance with any comments, questions, or concerns regarding this report or any environmental related topic. Office of Environmental Management and Services staff can be reached at (215) 400-4750 or via e-mail at [environmental@philasd.org](mailto:environmental@philasd.org).

Additional information can be found on our website.

<https://www.philasd.org/capitalprograms/programsservices/environmental/>



THE SCHOOL DISTRICT OF  
PHILADELPHIA

Asbestos Hazard Emergency Response Act  
"AHERA"

ASBESTOS MANAGEMENT PLAN  
**THREE-YEAR RE-INSPECTION REPORT**

For

**THE PHILADELPHIA CHARTER SCHOOL FOR THE  
ARTS AND SCIENCES AT H.R. EDMUNDS**

**ULCS # 3422/7250  
1197 Haworth Street  
Philadelphia, Pennsylvania 19124  
Year Built: 1924**

October 2023

***Conducted by:***

Inspectors: Teagan Fortna, Julie Wankmiller, and Christian Rodebaugh

Company: Criterion Laboratories, Inc.

***Management Plan Program Prepared by:***

School District of Philadelphia and Tetra Tech, Inc.

**As mandated by the U.S. EPA AHERA regulations, this report must remain in the Main, or Principal's, office.**



# AHERA THREE-YEAR RE-INSPECTION REPORT

## Table of Contents

<b>1.0</b>	<b>Executive Summary.....</b>	<b>1</b>
<b>2.0</b>	<b>Report of the Three-Year Re-Inspection.....</b>	<b>3</b>
A.	Introduction.....	3
B.	Re-Inspection Key Definitions .....	4
C.	Room-by-Room Log Narrative.....	6
	<i>C.1 Sampling and Analysis from the Current Three-Year Re-Inspection.....</i>	<i>6</i>
	<i>C.2 Damaged Materials from the Current Three-Year Re-Inspection and Auxiliary Inspections .....</i>	<i>18</i>
D.	Designated Person Accreditation.....	19
E.	Attic and Crawl Space Summary.....	20
	<i>E.1 Attic and Crawl Space Summary .....</i>	<i>20</i>
<b>3.0</b>	<b>Historical AHERA Management Data.....</b>	<b>21</b>
A.	Introduction.....	21
B.	Historical Data Following 2018 Re-inspection Report.....	22
	<i>B.1 Historical Sampling and Analysis from the Previous Three Years.....</i>	<i>22</i>
	<i>B.2 Periodic Surveillance of Damaged Materials from the Previous Three Years.....</i>	<i>22</i>
	<i>B.3 Abatement Activity from the Previous Three Years.....</i>	<i>23</i>

## List of Appendices

APPENDIX A	Room-by-Room Log
APPENDIX B	Lab Results
APPENDIX C	Figures
APPENDIX D	2022/2023 Annual Notification
APPENDIX E	Certificates
APPENDIX F	Philadelphia School District Asbestos Management Program



# 1.0 Executive Summary

This Asbestos Hazard Emergency Response Act (AHERA) Three-Year Re-inspection Report at The Philadelphia Charter School for the Arts and Sciences at H.R. Edmunds, 1197 Haworth Street, Philadelphia, PA 19124 has been completed and submitted to the School District of Philadelphia Office of Environmental Management and Services (OEMS).

- Inspectors: Teagan Fortna, Julie Wankmiller, and Christian Rodebaugh
- Company: Criterion Laboratories, Inc.
- Completed: March 3, 2023, to March 9, 2023

The AHERA report must be reviewed prior to any renovation, demolition, or maintenance activities to avoid the unknowing disturbance of asbestos-containing building materials (ACBMs) identified within this location.

Building materials, including any assumed or known ACBMs, are listed in Appendix A, the Room-By-Room Log. This log is organized by floor, space identification (ID), and name. During the review of this log, it is critical that prior to any disturbance activities the appropriate space and component (building material) is identified. To assist with the identification of materials and their locations, lab results from any testing performed are provided in Appendix B. Drawings depicting the school facility, floors, and space IDs are included in Appendix C, Figures.

If there is any confusion about the asbestos content of a material, or planned maintenance and construction activities that will impact a known or assumed ACBM, prior to the commencement of repairs, or planned maintenance, the Building Engineer or Facility Area Manager for the school must contact OEMS to have an Environmental Impact Evaluation conducted.

The information contained in this report was obtained from the original Asbestos Management Plan for the school and from updated reports on changes and activities since the completion of the first Management Plan.

This Three-Year Re-Inspection Report is to be incorporated into the school's larger Management Plan, which includes the original Management Plan and the series of re-inspections and periodic surveillance events that have occurred since. The most recent Three-Year Re-Inspection Report or Six-Month Periodic Surveillance should be referenced for all maintenance and construction activities. Updates to the amount of material, or potential removal of materials, may have been made.

Pursuant to U.S. Environmental Protection Agency (EPA) regulations, codified at 40 Code of Federal Regulations 763.84, the district is required to provide notification of public access to environmental records. Members of the school staff, parents, guardians, temporary workers, and contractors must be informed each



year of their access rights. A copy of the annual notification provided in 2022 and 2023 is attached as Appendix D.

This report does not cover, or comment on, structural areas not assessed visibly or by sample collection. Because of limitations on destructive sampling methods, additional suspect materials may be present within walls, voids, mechanical equipment, or other concealed or confined spaces. Prior to the renovation of a school district-owned building, further survey work may be needed to comply with all local, state, and federal requirements regulating ACBM.

The School District, as the Local Education Agency, maintains AHERA reports for public inspection in the Office of the Principal or Building Administrator, and in the Administrative Offices at 440 North Broad Street.

If you have any questions, feel free to contact OEMS at (215) 400-4750.

## 2.0 Report of the Three-Year Re-Inspection

### A. Introduction

The Three-Year Re-inspection was performed to fulfill the requirements of 40 Code of Federal Regulations Part 763 - the Asbestos Hazard Emergency Response Act (AHERA). As required by AHERA, each Local Education Agency (LEA) must re-inspect all known confirmed, or assumed, asbestos-containing building material (ACBM) located in the LEA's facilities. This re-inspection is intended to update the original Asbestos Management Plan for the LEA's facilities.

As mandated by the U.S. Environmental Protection Agency (EPA) AHERA regulations, Six-Month Periodic Inspections and Three-Year Re-inspections of this location will be performed. Updated room-by-room logs will be provided following any re-inspection or periodic surveillance event. Supporting documentation regarding response actions that were performed since the last inspection or periodic surveillance event may also be provided to maintain an updated management plan. All documentation for the AHERA management plan will be housed in the AHERA Library at 440 North Broad Street, Philadelphia, PA.

This re-inspection process included a comprehensive room-by-room inventory of all thermal (T), surfacing (S) and, miscellaneous (M) materials specific to each room of this facility. Each room's thermal, ceilings, walls, floors, and miscellaneous building materials are categorized on the room-by-room log for this location (Appendix A). Additionally, an estimation of some non-asbestos-containing materials have been included on the room-by-room log.

- To comply with AHERA regulations, only damage associated with confirmed or assumed ACBM is recorded.
- The inspection was completed by Inspectors: Teagan Fortna, Julie Wankmiller, and Christian Rodebaugh  
Company: Criterion Laboratories, Inc.
- The inspection was completed between: March 3, 2023, and March 9, 2023
- This Re-Inspection Report was reviewed by Management Planners: Ian Forster, Barbara Gancarz, and Isa Haj
- The Designated Persons for the Philadelphia School District are Monique Causley and Megan Vala
- Certificates of the inspection and management planner representatives listed above are included in Appendix E

During the re-inspection of each School District of Philadelphia facility, prior Management Plan documentation for the facility was reviewed. Information on activities, such as abatements, cleanings, samplings, and inspections, that have taken place since the completion of the original Management Plan was reviewed during the re-inspection. Information from the prior Three-Year Re-Inspection Report, including samplings, damaged materials, and response actions, is included in Section 3.0 of this report.

As mandated by the U.S. EPA AHERA regulations, all future Six-Month Periodic Inspections and Three-Year Re-Inspections of this location will be performed and the inspection data in this report will be updated accordingly.



## B. Re-Inspection Key Definitions

ITEM	DEFINITION
<b>ULCS#</b>	Individual identification number assigned to each school within the School District of Philadelphia (Universal Location Code System).
<b>COMPONENT TYPE DEFINITIONS</b>	<p><b>Thermal System:</b> Material in a school building applied to pipes, fitting, boilers, breeching, tanks, ducts, or other interior structural components to prevent heat loss or gain, or water condensation, or for other purposes.</p> <p><b>Surfacing System:</b> Material in a school building that is sprayed-on, troweled-on, or otherwise applied to surfaces, such as acoustical plaster on ceilings and fireproofing material on structural members, or other materials on surfaces for acoustical, fireproofing, or other purposes.</p> <p><b>Miscellaneous:</b> Interior building material on structural components, structural members, or fixtures, such as floor and ceiling tiles. Does not include surfacing or thermal system insulation.</p>
<b>HOMOGENEOUS AREA</b>	An area of surfacing material, thermal system insulation material, or miscellaneous material that is uniform in color and texture.
<b>AMOUNT OF MATERIAL/UNIT</b>	Quantity of material and measuring unit. Units include: Square Feet (SF), Each (EA), Linear Feet (LF), and Cubic Feet (CF).
<b>DAMAGE AMOUNT</b>	Quantity of damaged material observed during the inspection. The quantity is shown in the same format as the amount of material/unit section.
<b>DATA DESIGN COLLECTION (DDC)</b>	Damage notes and pictures to provide detailed information regarding observed damage, and potential for damage, as attached in Appendix C and E.
<b>SUSPECTED FIBER RELEASE EPISODE (SFRE)</b>	Any uncontrolled or unintentional disturbance of Asbestos Containing Building Material (ACBM) resulting in visible emission during a 3-Year Inspection or 6-Month Surveillance.
<b>RESPONSE ACTION</b>	Response Actions conducted by the Philadelphia School District include: <ol style="list-style-type: none"> <li>1. Repair</li> <li>2. Enclosure</li> <li>3. Removal</li> <li>4. Encapsulation</li> </ol>
<b>ACM STATUS</b>	Asbestos Containing Material (ACM) Status denotes if the material is considered Assumed, Confirmed, No Asbestos Detected (NAD), or Non-Suspect.
<b>ASSUMED ASBESTOS</b>	A material that was not sampled and is assumed to contain asbestos for the purposes of maintenance and management.
<b>ASBESTOS CONTAINING MATERIAL</b>	A material that was sampled with lab results confirming the presence of greater than 1% asbestos by volume.
<b>NO ASBESTOS DETECTED (NAD)</b>	Any material or component that was sampled with lab results confirming the presence of less than or equal to 1% asbestos by volume.





ITEM	DEFINITION
<b>NON-SUSPECT</b>	Not known or believed to contain asbestos i.e., glass, wood, steel, aluminum, metal, etc.
<b>THREE-YEAR RE-INSPECTION</b>	This section contains the information obtained from the Three-Year Re-Inspection as required by AHERA.
<b>SIX-MONTH PERIODIC SURVEILLANCE</b>	As required by AHERA, each school is reevaluated every six months to note conditions of known asbestos materials within the structure.
<b>RESPONSE ACTION (RA)</b>	Response Actions conducted by the Philadelphia School District include: <ol style="list-style-type: none"><li>1. Repair</li><li>2. Enclosure</li><li>3. Removal</li><li>4. Encapsulation</li></ol>
<b>ROOM-BY-ROOM LOCATION LOG REPORT</b>	This section gives information, including damage amount and location, for a specific homogeneous material on a room-by-room basis and follows the re-inspection form.

*NOTE: The disparate nature of the above sources of information prohibits the verification of much information within the scope of the AHERA Three-Year Re-Inspection. Discrepancies and omissions may exist in this information, and, therefore, it is included on an "as is" basis. The inspectors for the Three-Year Re-Inspection evaluated homogeneous areas based on the current condition and location of the materials, as evidenced during the inspector's site visit.*



## C. Room-by-Room Log Narrative

The room-by-room log is included in Appendix A of this report. This log lists all components that are confirmed, or assumed, to be asbestos-containing materials (ACM). Please refer to this log before any renovation, maintenance, or repair activity within the school or facility to prevent the unintentional disturbance of ACM. Lab results from any testing performed are provided in Appendix B.

**NOTE: Contact the OEMS prior to the disturbance of any of the materials that are listed as confirmed and/or assumed, during all operations, maintenance, renovation, and/or demolition activities at this location.**

*The quantities listed for non-asbestos-containing materials and/or non-suspect-materials (NAD) are estimated. For this report, the quantities were not measured. Field verification of quantities would be necessary for renovation.*

### C.1 Sampling and Analysis from the Current Three-Year Re-Inspection

**Table Generated:** September 13, 2023

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/09/2023	1	1	111	Classroom 111	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	111	Classroom 111	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	111	Classroom 111	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	111	Classroom 111	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	111B	Classroom 111 Coat Room	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	111B	Classroom 111 Coat Room	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	111B	Classroom 111 Coat Room	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	111B	Classroom 111 Coat Room	Mastic	Floor Tile	Yellow	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/09/2023	1	1	108A	Classroom 108 Coat Room	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	108A	Classroom 108 Coat Room	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	108A	Classroom 108 Coat Room	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	108A	Classroom 108 Coat Room	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	105	Classroom 105	Floor Tile VAT 12" x 12"	N/A	Tan	NAD
3/09/2023	1	1	105	Classroom 105	Floor Tile VAT 12" x 12"	N/A	Tan	NAD
3/09/2023	1	1	105	Classroom 105	Mastic	Floor Tile	N/A	NAD
3/09/2023	1	1	105	Classroom 105	Mastic	Floor Tile	N/A	NAD
3/09/2023	1	1	105	Classroom 105	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/09/2023	1	1	G01B	Center Gymnasium Office	Floor Tile VAT 12" x 12"	N/A	Tan	NAD
3/09/2023	1	1	G01B	Center Gymnasium Office	Floor Tile VAT 12" x 12"	N/A	Tan	NAD
3/09/2023	1	1	G01B	Center Gymnasium Office	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	G01B	Center Gymnasium Office	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	G01B	Center Gymnasium Office	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/09/2023	1	1	104	Classroom 104	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	104	Classroom 104	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	104	Classroom 104	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	104	Classroom 104	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	H15	Hallway from Classroom 101 to Classroom 106	Floor Tile VAT 12" x 12"	N/A	White	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/09/2023	1	1	H15	Hallway from Classroom 101 to Classroom 106	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/09/2023	1	1	H15	Hallway from Classroom 101 to Classroom 106	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	H15	Hallway from Classroom 101 to Classroom 106	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	121B	Nurse's Office #3	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	121B	Nurse's Office #3	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	1	121B	Nurse's Office #3	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	121B	Nurse's Office #3	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	1	121B	Nurse's Office #3	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/09/2023	1	1	121B	Nurse's Office #3	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	1	121B	Nurse's Office #3	Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	1	121	Nurse's Office	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	1	121	Nurse's Office	Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	1	121A	Nurse's Office #2	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	1	121A	Nurse's Office #2	Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	1	AUD	Auditorium	Auditorium Plaster Walls	N/A	N/A	NAD
3/09/2023	1	1	AUD	Auditorium	Auditorium Plaster Walls	N/A	N/A	NAD
3/09/2023	1	1	AUD	Auditorium	Auditorium Plaster Walls	N/A	N/A	NAD
3/09/2023	1	1	AUD	Auditorium	Auditorium Plaster Walls	N/A	N/A	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/09/2023	1	1	AUD	Auditorium	Auditorium Plaster Walls	N/A	N/A	NAD
3/09/2023	1	1	AUD	Auditorium	Auditorium Plaster Walls	N/A	N/A	NAD
3/09/2023	1	1	AUD	Auditorium	Auditorium Plaster Walls	N/A	N/A	NAD
3/09/2023	1	1	120G	Staff Office Adjacent to Kitchenette	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	1	120G	Staff Office Adjacent to Kitchenette	Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	B	8	Boiler Room	Boiler Breeching	N/A	N/A	NAD
3/09/2023	1	B	8	Boiler Room	Boiler Breeching	N/A	N/A	NAD
3/09/2023	1	B	G3	Classroom G3	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	B	G3	Classroom G3	Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	B	G3	Classroom G3	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	B	G3	Classroom G3	Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	B	G3	Classroom G3	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	B	G3	Classroom G3	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	B	G3	Classroom G3	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	B	G3	Classroom G3	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	B	HB2	Hallway from Classrooms G-4 to G-5	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/09/2023	1	B	HB2	Hallway from Classrooms G-4 to G-5	Mastic	Floor Tile	Yellow	NAD



Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/09/2023	1	B	HB2	Hallway from Classrooms G-4 to G-5	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	B	HB2	Hallway from Classrooms G-4 to G-5	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/09/2023	1	B	G2	Classroom G2	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	B	G2	Classroom G2	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	B	G2	Classroom G2	Mastic	Floor Tile	Black	NAD
3/09/2023	1	B	G2	Classroom G2	Mastic	Floor Tile	Black	NAD
3/09/2023	1	B	G2	Classroom G2	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	B	G2	Classroom G2	Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	B	G4	Classroom G4	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	B	G4	Classroom G4	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	B	G4	Classroom G4	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	B	G4	Classroom G4	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	B	G4	Classroom G4	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/09/2023	1	B	G-6A	G6 Restroom	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/09/2023	1	B	G8	Classroom G8	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	B	G8	Classroom G8	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	B	G8	Classroom G8	Mastic	Floor Tile	Black	NAD
3/09/2023	1	B	G8	Classroom G8	Mastic	Floor Tile	Black	NAD
3/09/2023	1	B	G10A	G10A Office	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/09/2023	1	B	G10A	G10A Office	Floor Tile VAT 12" x 12"	N/A	Multi	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/09/2023	1	B	G10A	G10A Office	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	B	G10A	G10A Office	Mastic	Floor Tile	Yellow	NAD
3/09/2023	1	B	G10B	G10B Office	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/09/2023	1	B	G10D	G10D Office	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	B	G10D	G10D Office	Joint Compound Wall	N/A	N/A	NAD
3/09/2023	1	B	G12	Ballet Room G12	Linoleum	N/A	Blue	NAD
3/09/2023	1	B	G12	Ballet Room G12	Linoleum	N/A	Blue	NAD
3/09/2023	1	1	H14	Hallway from Classroom 111 to Classroom 107	Leveling Compound	Floor Tile	Grey	NAD
6/21/2023	1	2	202	Classroom 202	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	2	202	Classroom 202	Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	2	204	Classroom 204	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	2	204	Classroom 204	Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	1	120	Main Office Reception Area	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	1	120	Main Office Reception Area	Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	1	120E	Storage Closet Adjacent to Staff Office	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	1	120E	Storage Closet Adjacent to Staff Office	Joint Compound Wall	N/A	N/A	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
6/21/2023	1	1	120J	Storage Room Adjacent to Restrooms	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	1	120J	Storage Room Adjacent to Restrooms	Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	B	G1AB	G1 Main Windowed Office	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	B	G1AB	G1 Main Windowed Office	Joint Compound Wall	N/A	N/A	NAD
6/21/2023	1	B	8	Boiler Room	Boiler Breeching	N/A	N/A	NAD
8/07/2023	1	3	S34	Haworth Stairwell B Adjacent to Classroom 305	Fireproofing	N/A	N/A	NAD
8/07/2023	1	3	H10	Hallway from Classrooms 305 A to 308	Fireproofing	N/A	N/A	NAD
8/07/2023	1	3	302A	Special Education Classroom Across from Classroom 306	Paint	Ceiling, Concrete	N/A	NAD
8/07/2023	1	3	302A	Special Education Classroom Across from Classroom 306	Paint	Ceiling, Concrete	N/A	NAD
8/07/2023	1	3	303B	Office 303A	Paint	Ceiling, Concrete	N/A	NAD
8/07/2023	1	3	300	Elevator Lobby Adjacent to Dyre Stairwell B	Fireproofing	N/A	N/A	NAD
8/07/2023	1	2	H27	Hallway from Classroom 207 to Classroom 212	Fireproofing	N/A	N/A	NAD
8/07/2023	1	2	H27	Hallway from Classroom 207 to Classroom 212	Fireproofing	N/A	N/A	NAD
8/07/2023	1	2	206	Office 206	Fireproofing	N/A	N/A	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
8/07/2023	1	2	202A	Autistic Support Office 202A	Paint	Ceiling, Concrete	N/A	NAD
8/07/2023	1	2	202A	Autistic Support Office 202A	Paint	Ceiling, Concrete	N/A	NAD
8/07/2023	1	2	210D	Special Education Classroom Across from Classroom 210	Paint	Ceiling, Concrete	N/A	NAD
8/07/2023	1	1	15A	Staff Restroom Adjacent to Classroom 105	Fireproofing	N/A	N/A	NAD
8/07/2023	1	1	15A	Staff Restroom Adjacent to Classroom 105	Fireproofing	N/A	N/A	NAD
8/07/2023	1	1	G01A	Gymnasium Office Adjacent to Exit	Fireproofing	N/A	N/A	NAD
8/07/2023	1	B	Women's	Women's Restroom	Fireproofing	N/A	N/A	NAD
8/07/2023	1	B	Cafeteria	Cafeteria	Fireproofing	N/A	N/A	NAD
8/07/2023	1	B	Kitchen	Kitchen	Fireproofing	N/A	N/A	NAD
3/08/2023	1	1	G01G	Gymnasium Storage Room	Fireproofing	Support Post, Metal	Grey	NAD
3/08/2023	1	1	G01G	Gymnasium Storage Room	Fireproofing	Support Post, Metal	Grey	NAD
3/08/2023	1	1	G01G	Gymnasium Storage Room	Fireproofing	Support Post, Metal	Grey	NAD
3/08/2023	1	3	307	Classroom 307	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	3	307	Classroom 307	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	3	307	Classroom 307	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	3	307	Classroom 307	Mastic	Floor Tile	Yellow	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/08/2023	1	3	308	Classroom 308	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	3	308	Classroom 308	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	3	308	Classroom 308	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	3	308	Classroom 308	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	3	311	Classroom 311	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	3	311	Classroom 311	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	3	311	Classroom 311	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	3	301	Classroom 301	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	3	301	Classroom 301	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	3	301	Classroom 301	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	3	301	Classroom 301	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	3	305A	Classroom 305 A	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/08/2023	1	3	305A	Classroom 305 A	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/08/2023	1	3	305A	Classroom 305 A	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	3	305A	Classroom 305 A	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	3	305A	Classroom 305 A	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	3	305A	Classroom 305 A	Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	3	305	Classroom 305	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	3	305	Classroom 305	Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	3	307	Classroom 307	Sheetrock/Joint Compound Wall	N/A	N/A	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/08/2023	1	3	307	Classroom 307	Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	3	303B	Office 303A	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	3	303B	Office 303A	Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	3	302A	Special Education Classroom across from Classroom 306	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	3	302A	Special Education Classroom across from Classroom 306	Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	3	305A	Classroom 305 A	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/08/2023	1	3	303B	Office 303A	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/08/2023	1	3	302A	Special Education Classroom across from Classroom 306	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/08/2023	1	3	310	Classroom 310	Pipe Insulation 2-6 Inch	N/A	N/A	Confirmed
3/08/2023	1	3	310	Classroom 310	Pipe Insulation 2-6 Inch	N/A	N/A	Positive Stop
3/08/2023	1	3	310	Classroom 310	Pipe Insulation 2-6 Inch	N/A	N/A	Positive Stop
3/08/2023	1	2	208	Science Lab Classroom 208	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/08/2023	1	2	208	Science Lab Classroom 208	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/08/2023	1	2	208	Science Lab Classroom 208	Mastic	Floor Tile	N/A	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/08/2023	1	2	208	Science Lab Classroom 208	Mastic	Floor Tile	N/A	NAD
3/08/2023	1	2	208	Science Lab Classroom 208	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/08/2023	1	2	207	Classroom 207	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/08/2023	1	2	H27	Hallway from Classroom 207 to Classroom 212	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/08/2023	1	2	H27	Hallway from Classroom 207 to Classroom 212	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	2	201	Classroom 201	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	2	201	Classroom 201	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	2	201	Classroom 201	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	2	203	Classroom 203	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	2	203	Classroom 203	Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	2	203	Classroom 203	Ceiling Tile 2' x 4'	N/A	N/A	NAD
3/08/2023	1	2	H29A	Hallway at Classroom 204	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/08/2023	1	2	H29A	Hallway at Classroom 204	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	2	210C	Teacher's Lounge	Sheetrock/Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	2	210C	Teacher's Lounge	Joint Compound Wall	N/A	N/A	NAD
3/08/2023	1	2	203C	Classroom 204A	Floor Tile VAT 12" x 12"	N/A	Tan	NAD
3/08/2023	1	2	203C	Classroom 204A	Floor Tile VAT 12" x 12"	N/A	Tan	NAD
3/08/2023	1	2	203C	Classroom 204A	Mastic	Floor Tile	Black	NAD

Date	Element	Floor	Space ID	Location	Material	Material Associated With	Color	Results
3/08/2023	1	2	203C	Classroom 204A	Mastic	Floor Tile	Black	NAD
3/08/2023	1	1	G01A	Gymnasium Office Adjacent to Exit	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	1	G01A	Gymnasium Office Adjacent to Exit	Floor Tile VAT 12" x 12"	N/A	Multi	NAD
3/08/2023	1	1	G01A	Gymnasium Office Adjacent to Exit	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	1	G01A	Gymnasium Office Adjacent to Exit	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	1	H14	Hallway from Classroom 111 to Classroom 107	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/08/2023	1	1	H14	Hallway from Classroom 111 to Classroom 107	Floor Tile VAT 12" x 12"	N/A	White	NAD
3/08/2023	1	1	H14	Hallway from Classroom 111 to Classroom 107	Mastic	Floor Tile	Yellow	NAD
3/08/2023	1	1	H14	Hallway from Classroom 111 to Classroom 107	Mastic	Floor Tile	Yellow	NAD

Legend								
<b>ACM:</b> Asbestos-Containing Material	<b>CMU:</b> Concrete Masonry Unit	<b>EA:</b> Each	<b>LF:</b> Linear Feet	<b>MAG:</b> Magnesia Asbestos Pipe Wrap	<b>N/A:</b> Not Available	<b>NAD:</b> No Asbestos Detected	<b>SF:</b> Square Feet	<b>VAT:</b> Vinyl Asbestos Tile



## C.2 Damaged Materials from the Current Three-Year Re-Inspection and Auxiliary Inspections

**Table Generated:** September 13, 2023

Date	Floor	Space ID	On-Site Room Name	Material	Material Associated With	Amount of Material	Amount of Damage	ACM Status	Inspection
3/06/2023	1	111B	Classroom 111 Coat Room	Pipe Insulation 2-6 Inch	N/A	12 LF	1 LF	Confirmed	AHERA Inspection (3-Year)
3/03/2023	2	211	Classroom 211	Pipe Insulation 2-6 Inch	N/A	15 LF	1 LF	Confirmed	AHERA Inspection (3-Year)
3/03/2023	2	211A	Classroom 211 Coat Room	Pipe Insulation 2-6 Inch	N/A	14 LF	1 LF	Confirmed	AHERA Inspection (3-Year)
3/03/2023	2	212A	Classroom 212 Closet	Pipe Insulation 2-6 Inch	N/A	20 LF	1 LF	Confirmed	AHERA Inspection (3-Year)
Legend									
<b>ACM:</b> Asbestos-Containing Material		<b>CMU:</b> Concrete Masonry Unit		<b>EA:</b> Each	<b>LF:</b> Linear Feet	<b>MAG:</b> Magnesia Asbestos Pipe Wrap		<b>NAD:</b> No Asbestos Detected	<b>SF:</b> Square Feet
									<b>VAT:</b> Vinyl Asbestos Tile



## D. Designated Person Accreditation

### ASBESTOS DESIGNATED PERSON(S)

Monique Causley  
AHERA Manager  
Office of Environmental Management and Services  
440 N Broad Street, 3<sup>rd</sup> Floor  
Philadelphia, PA 19130  
Telephone: (215) 400-6635

Megan Vala  
AHERA Manager  
Office of Environmental Management and Services  
440 N Broad Street, 3<sup>rd</sup> Floor  
Philadelphia, PA 19130  
Telephone: (215) 400-6516

### Accreditation Information Statement

All persons who inspect for asbestos-containing building materials (ACBM) and who will design or carry out response actions with respect to assumed and confirmed ACBM will be accredited by a U.S. EPA approved course and a State Contractors Accreditation Program under Sections 206 (b) and 206 (c) of Title II of the act.

Monique Causley and Megan Vala  
Asbestos Designated Persons  
AHERA Managers  
Office of Environmental Management and Services



## E. Attic and Crawl Space Summary

These charts are to be used for a quick reference regarding the attic and crawl space inspection data within this facility. Prior to entering any attic or crawl space within this facility, contact OEMS and refer to the below chart and legend for determination of Category Rank. The data relative to these spaces are updated as conditions change regarding abatement or renovation activity on a case-by-case basis for each specific location and facility. In general, crawl spaces are below the basement, or first floor, and attics are above the floor space.

### Category Rank Legend

"A" - No ACM - Sample results indicate NO ACM on pipes, fittings, elbows, or equipment located within this functional space, and NO VISIBLE DEBRIS or DAMAGE was observed at the time of this inspection.

"B" – ACM Present - Sample results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, HOWEVER, NO VISIBLE DEBRIS or DAMAGE was observed at the time of this inspection.

"C" – ACM Present - Sample results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, and LOCALIZED VISIBLE DEBRIS or DAMAGE was observed at the time of this inspection.

"D" – ACM Present - Sample results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space and DISTRIBUTED VISIBLE DEBRIS or SIGNIFICANT DAMAGE was observed at the time of this inspection.

"E" - No Bulk Sample Results Available, SUSPECT ACM OBSERVED. Contact OEMS immediately for additional instructions.

### E.1 Attic and Crawl Space Summary

Attic/Crawl Space	Element	Access Area	Floor Surface	Category Rank	Comments
Attic	X	X	X	X	No Attic
Crawl Space	X	X	X	X	No Crawl Space
Legend					
<b>ACM:</b> Asbestos-Containing Material	<b>EA:</b> Each	<b>LF:</b> Linear Feet	<b>N/A:</b> Not Available	<b>SF:</b> Square Feet	<b>UOM:</b> Unit of Measurement
					<b>X:</b> Not Applicable

## 3.0 Historical AHERA Management Data

### A. Introduction

Each homogeneous area of ACBM listed in the original Management Plan, or in the prior Three-Year Re-inspection Reports, was reviewed and the data are summarized in tables B-1, B-2, and B-3.

Any changes to a homogeneous area listed in the Management Plans have been verified. Any area of suspected ACBM found during the re-inspections after 2018 that was not listed in the Management Plan, or updates, was either assumed to contain asbestos, or sampled and analyzed to determine asbestos content. Any such new areas either assumed to contain asbestos, or determined through analysis to contain asbestos, are summarized below, and have been incorporated into the more recent Three-Year Re-Inspection room-by-room log.

The data summarized below in Section B were gathered from the updated 2018 Three-Year Re-Inspection Report held by the School District of Philadelphia. This report is assumed to be comprehensive and up to date from the prior inspection reports.

## B. Historical Data Following 2018 Re-inspection Report

Information on activities affecting ACBMs at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following: sampling and analysis, new tile installation, abatement activity, and Six-Month Periodic Surveillance Data.

### B.1 Historical Sampling and Analysis from the Previous Three Years

Date	Floor	Location	Material	Color	Results
------	-------	----------	----------	-------	---------

No sampling or analysis were performed over the previous three years.

Legend							
<b>ACM:</b> Asbestos-Containing Material	<b>CMU:</b> Concrete Masonry Unit	<b>EA:</b> Each	<b>LF:</b> Linear Feet	<b>MAG:</b> Magnesia Asbestos Pipe Wrap	<b>NAD:</b> No Asbestos Detected	<b>SF:</b> Square Feet	<b>VAT:</b> Vinyl Asbestos Tile

Information on the AHERA inspection that noted damage to various building materials at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Work orders are created for corrective action responses and tracked for completion. Updates to the Management Plan include the following:

### B.2 Periodic Surveillance of Damaged Materials from the Previous Three Years

Date	Element	Floor	On Site Room Name	Material	Amount of Material	Amount of Damage
------	---------	-------	-------------------	----------	--------------------	------------------

No damaged materials surveilled over the previous three years.

Legend							
<b>ACM:</b> Asbestos-Containing Material	<b>CMU:</b> Concrete Masonry Unit	<b>EA:</b> Each	<b>LF:</b> Linear Feet	<b>MAG:</b> Magnesia Asbestos Pipe Wrap	<b>NAD:</b> No Asbestos Detected	<b>SF:</b> Square Feet	<b>VAT:</b> Vinyl Asbestos Tile

Information on the asbestos abatement and renovation activities affecting ACBMs at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

### B.3 Abatement Activity from the Previous Three Years

Date	Floor	Location	Material	Color	Removed or Encapsulated	Quantity
------	-------	----------	----------	-------	-------------------------	----------

No abatement activity performed over the previous three years.

Legend							
<b>ACM:</b> Asbestos-Containing Material	<b>CMU:</b> Concrete Masonry Unit	<b>EA:</b> Each	<b>LF:</b> Linear Feet	<b>MAG:</b> Magnesia Asbestos Pipe Wrap	<b>NAD:</b> No Asbestos Detected	<b>SF:</b> Square Feet	<b>VAT:</b> Vinyl Asbestos Tile



## APPENDIX A

---

### ROOM-BY-ROOM LOG



Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	1	101	Classroom 101	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	1	101	Classroom 101	Plaster Wall	NAD	1200	SF	N/A	SF		
1	1	101	Classroom 101	Plaster Ceiling	NAD	680	SF	N/A	SF		
1	1	101	Classroom 101	Floor Tile VAT 12" x 12"	Assumed	680	SF	0	SF	Multi	
1	1	101A	Classroom 101 Coat Room	Pipe Fitting Insulation	Confirmed	6	EA	0	EA		
1	1	101A	Classroom 101 Coat Room	Pipe Insulation 2-6 inch	Confirmed	24	LF	0	LF		
1	1	101A	Classroom 101 Coat Room	Plaster Wall	NAD	400	SF	N/A	SF		
1	1	101A	Classroom 101 Coat Room	Plaster Ceiling	NAD	60	SF	N/A	SF		
1	1	101A	Classroom 101 Coat Room	Floor Tile VAT 12" x 12"	Assumed	60	SF	0	SF	Multi	
1	1	101B	Classroom 101 Restroom	Ceramic Tile Wall	Non Suspect ACM	90	SF	N/A	SF		
1	1	101B	Classroom 101 Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	12	LF	N/A	LF		
1	1	101B	Classroom 101 Restroom	Plaster Wall	NAD	200	SF	N/A	SF		
1	1	101B	Classroom 101 Restroom	Plaster Ceiling	NAD	32	SF	N/A	SF		
1	1	101B	Classroom 101 Restroom	Floor Tile VAT 12" x 12"	Assumed	32	SF	0	SF	White	
1	1	101C	Classroom 101 Closet	Plaster Wall	NAD	100	SF	N/A	SF		
1	1	101C	Classroom 101 Closet	Plaster Ceiling	NAD	18	SF	N/A	SF		
1	1	101C	Classroom 101 Closet	Floor Tile VAT 12" x 12"	Assumed	18	SF	0	SF	Multi	
1	1	102	Classroom 102	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	1	102	Classroom 102	Plaster Wall	NAD	985	SF	N/A	SF		
1	1	102	Classroom 102	Plaster Ceiling	NAD	680	SF	N/A	SF		
1	1	102	Classroom 102	Floor Tile VAT 12" x 12"	Assumed	680	SF	0	SF	Multi	
1	1	102A	Counselors Office 104A across from Classroom 102	Brick Wall	Non Suspect ACM	228	SF	N/A	SF		
1	1	102A	Counselors Office 104A across from Classroom 102	Metal Ceiling	Non Suspect ACM	130	SF	N/A	SF		
1	1	102A	Counselors Office 104A across from Classroom 102	Concrete Ceiling	Non Suspect ACM	130	SF	N/A	SF		
1	1	102A	Counselors Office 104A across from Classroom 102	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		
1	1	102A	Counselors Office 104A across from Classroom 102	Sheetrock/Joint Compound Wall	NAD	600	SF	N/A	SF		
1	1	102A	Counselors Office 104A across from Classroom 102	Ceiling Tile 2' x 4'	NAD	260	SF	N/A	SF		
1	1	102A	Counselors Office 104A across from Classroom 102	Carpet	Non Suspect ACM	260	SF	N/A	SF		
1	1	102B	Classroom 102 Coat Room	Fiberglass Pipe Insulation	Non Suspect ACM	12	LF	N/A	LF		
1	1	102B	Classroom 102 Coat Room	Plaster Wall	NAD	650	SF	N/A	SF		
1	1	102B	Classroom 102 Coat Room	Plaster Ceiling	NAD	150	SF	N/A	SF		
1	1	102B	Classroom 102 Coat Room	Floor Tile VAT 12" x 12"	Assumed	150	SF	0	SF	Multi	
1	1	103	Classroom 103	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	2	EA	N/A	EA		
1	1	103	Classroom 103	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	1	103	Classroom 103	Plaster Wall	NAD	720	SF	N/A	SF		
1	1	103	Classroom 103	Plaster Ceiling	NAD	680	SF	N/A	SF		
1	1	103	Classroom 103	Floor Tile VAT 12" x 12"	Assumed	680	SF	0	SF	Multi	
1	1	103B	Wash Room	Pipe Insulation >6 inches	Confirmed	12	LF	0	LF		
1	1	103B	Wash Room	Plaster Wall	NAD	250	SF	N/A	SF		
1	1	103B	Wash Room	Plaster Ceiling	NAD	45	SF	N/A	SF		
1	1	103B	Wash Room	Paint associated with Floor, Concrete	Assumed	45	SF	0	SF		
1	1	103B	Wash Room	Concrete Floor	Non Suspect ACM	45	SF	N/A	SF		
1	1	104	Classroom 104	Mastic associated with Floor Tile	NAD	680	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	104	Classroom 104	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	4	EA	N/A	EA		
1	1	104	Classroom 104	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	1	104	Classroom 104	Plaster Wall	NAD	985	SF	N/A	SF		
1	1	104	Classroom 104	Plaster Ceiling	NAD	680	SF	N/A	SF		
1	1	104	Classroom 104	Floor Tile VAT 12" x 12"	NAD	680	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	104A	Classroom 104 Coat Room	Paint associated with Wall, CMU	NAD	100	SF	N/A	SF		
1	1	104A	Classroom 104 Coat Room	CMU Block Wall	Non Suspect ACM	100	SF	N/A	SF		
1	1	104A	Classroom 104 Coat Room	Plaster Wall	NAD	520	SF	N/A	SF		
1	1	104A	Classroom 104 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	1	104A	Classroom 104 Coat Room	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	1	104E	Stage Hallway	Plaster Wall	NAD	350	SF	N/A	SF		
1	1	104E	Stage Hallway	Plaster Ceiling	NAD	108	SF	N/A	SF		
1	1	104E	Stage Hallway	Wood Floor	Non Suspect ACM	108	SF	N/A	SF		
1	1	104F	Music Storage	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	4	EA	N/A	EA		
1	1	104F	Music Storage	Fiberglass Pipe Insulation	Non Suspect ACM	75	LF	N/A	LF		
1	1	104F	Music Storage	Plaster Wall	NAD	420	SF	N/A	SF		
1	1	104F	Music Storage	Plaster Ceiling	NAD	175	SF	N/A	SF		
1	1	104F	Music Storage	Wood Floor	Non Suspect ACM	175	SF	N/A	SF		
1	1	105	Classroom 105	Fiberglass Pipe Insulation	Non Suspect ACM	40	LF	N/A	LF		
1	1	105	Classroom 105	Concrete Ceiling	Non Suspect ACM	768	SF	N/A	SF		
1	1	105	Classroom 105	CMU Block Wall	Non Suspect ACM	320	SF	N/A	SF		
1	1	105	Classroom 105	Fiberglass Duct Insulation	Non Suspect ACM	200	SF	N/A	SF		
1	1	105	Classroom 105	Paint associated with Wall, CMU	NAD	1350	SF	N/A	SF		
1	1	105	Classroom 105	Expansion Seam Caulking	Assumed	90	LF	0	LF		
1	1	105	Classroom 105	CMU Block Wall	Non Suspect ACM	1350	SF	N/A	SF		
1	1	105	Classroom 105	Ceiling Tile 2' x 4'	NAD	768	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	1	105	Classroom 105	Floor Tile VAT 12" x 12"	NAD	768	SF	N/A	SF	Tan	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	105A	Classroom 105 Closet adjacent to Entrance	Duct Work	Non Suspect ACM	5	LF	N/A	LF		
1	1	105A	Classroom 105 Closet adjacent to Entrance	Fiberglass Duct Insulation	Non Suspect ACM	50	SF	N/A	SF		
1	1	105A	Classroom 105 Closet adjacent to Entrance	Expansion Seam Caulking	Assumed	180	LF	0	LF		
1	1	105A	Classroom 105 Closet adjacent to Entrance	CMU Block Wall	Non Suspect ACM	350	SF	N/A	SF		



Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	1	105A	Classroom 105 Closet adjacent to Entrance	Concrete Ceiling	Non Suspect ACM	45	SF	N/A	SF		
1	1	105A	Classroom 105 Closet adjacent to Entrance	Concrete Floor	Non Suspect ACM	45	SF	N/A	SF		
1	1	105B	Classroom 105 Closet adjacent to Windows	Paint associated with Wall, CMU	NAD	100	SF	N/A	SF		
1	1	105B	Classroom 105 Closet adjacent to Windows	Expansion Seam Caulking	Assumed	120	LF	0	LF		
1	1	105B	Classroom 105 Closet adjacent to Windows	CMU Block Wall	Non Suspect ACM	100	SF	N/A	SF		
1	1	105B	Classroom 105 Closet adjacent to Windows	Concrete Ceiling	Non Suspect ACM	10	SF	N/A	SF		
1	1	105B	Classroom 105 Closet adjacent to Windows	Concrete Floor	Non Suspect ACM	10	SF	N/A	SF		
1	1	106	Classroom 106	CMU Block Wall	Non Suspect ACM	320	SF	N/A	SF		
1	1	106	Classroom 106	Fiberglass Duct Insulation	Non Suspect ACM	200	SF	N/A	SF		
1	1	106	Classroom 106	Fiberglass Pipe Insulation	Non Suspect ACM	30	LF	N/A	LF		
1	1	106	Classroom 106	Concrete Ceiling	Non Suspect ACM	768	SF	N/A	SF		
1	1	106	Classroom 106	Paint associated with Wall, CMU	NAD	900	SF	N/A	SF		
1	1	106	Classroom 106	Expansion Seam Caulking	Assumed	90	LF	0	LF		
1	1	106	Classroom 106	CMU Block Wall	Non Suspect ACM	900	SF	N/A	SF		
1	1	106	Classroom 106	Ceiling Tile 2' x 4'	NAD	768	SF	N/A	SF		
1	1	106	Classroom 106	Floor Tile VAT 12" x 12"	Assumed	768	SF	0	SF	Tan	
1	1	106A	Classroom 106 Closet adjacent to Entrance	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		
1	1	106A	Classroom 106 Closet adjacent to Entrance	Expansion Seam Caulking	Assumed	180	LF	0	LF		
1	1	106A	Classroom 106 Closet adjacent to Entrance	CMU Block Wall	Non Suspect ACM	360	SF	N/A	SF		
1	1	106A	Classroom 106 Closet adjacent to Entrance	Concrete Ceiling	Non Suspect ACM	50	SF	N/A	SF		
1	1	106A	Classroom 106 Closet adjacent to Entrance	Concrete Floor	Non Suspect ACM	50	SF	N/A	SF		
1	1	106B	Classroom 106 Closet adjacent to Windows	Expansion Seam Caulking	Assumed	120	LF	0	LF		
1	1	106B	Classroom 106 Closet adjacent to Windows	CMU Block Wall	Non Suspect ACM	240	SF	N/A	SF		
1	1	106B	Classroom 106 Closet adjacent to Windows	Concrete Ceiling	Non Suspect ACM	10	SF	N/A	SF		
1	1	106B	Classroom 106 Closet adjacent to Windows	Concrete Floor	Non Suspect ACM	10	SF	N/A	SF		
1	1	106C	Custodial Closet adjacent to Classroom 110	Plaster Wall	NAD	240	SF	N/A	SF		
1	1	106C	Custodial Closet adjacent to Classroom 110	Plaster Ceiling	NAD	45	SF	N/A	SF		
1	1	106C	Custodial Closet adjacent to Classroom 110	Concrete Floor	Non Suspect ACM	45	SF	N/A	SF		
1	1	107	Classroom 107	CMU Block Wall	Non Suspect ACM	360	SF	N/A	SF		
1	1	107	Classroom 107	Concrete Ceiling	Non Suspect ACM	950	SF	N/A	SF		
1	1	107	Classroom 107	Fiberglass Pipe Insulation	Non Suspect ACM	120	LF	N/A	LF		
1	1	107	Classroom 107	Fiberglass Duct Insulation	Non Suspect ACM	480	SF	N/A	SF		
1	1	107	Classroom 107	Carpet	Non Suspect ACM	950	SF	N/A	SF		
1	1	107	Classroom 107	Paint associated with Wall, CMU	NAD	1200	SF	N/A	SF		
1	1	107	Classroom 107	Expansion Seam Caulking	Assumed	179	LF	0	LF		
1	1	107	Classroom 107	CMU Block Wall	Non Suspect ACM	1200	SF	N/A	SF		
1	1	107	Classroom 107	Ceiling Tile 2' x 4'	NAD	950	SF	N/A	SF		
1	1	107	Classroom 107	Paint associated with Floor, Concrete	Assumed	950	SF	0	SF		
1	1	107	Classroom 107	Concrete Floor	Non Suspect ACM	950	SF	N/A	SF		
1	1	107B	Music Practice Room in Classroom 107	Concrete Ceiling	Non Suspect ACM	300	SF	N/A	SF		
1	1	107B	Music Practice Room in Classroom 107	Fiberglass Duct Insulation	Non Suspect ACM	250	SF	N/A	SF		
1	1	107B	Music Practice Room in Classroom 107	CMU Block Wall	Non Suspect ACM	270	SF	N/A	SF		
1	1	107B	Music Practice Room in Classroom 107	Fiberglass Pipe Insulation	Non Suspect ACM	40	LF	N/A	LF		
1	1	107B	Music Practice Room in Classroom 107	Paint associated with Wall, CMU	NAD	650	SF	N/A	SF		
1	1	107B	Music Practice Room in Classroom 107	Expansion Seam Caulking	Assumed	360	LF	0	LF		
1	1	107B	Music Practice Room in Classroom 107	CMU Block Wall	Non Suspect ACM	650	SF	N/A	SF		
1	1	107B	Music Practice Room in Classroom 107	Ceiling Tile 2' x 4'	NAD	300	SF	N/A	SF		
1	1	108	Classroom 108	Fiberglass Pipe Insulation	Non Suspect ACM	24	LF	N/A	LF		
1	1	108	Classroom 108	Plaster Wall	NAD	1100	SF	N/A	SF		
1	1	108	Classroom 108	Plaster Ceiling	NAD	650	SF	N/A	SF		
1	1	108	Classroom 108	Floor Tile VAT 12" x 12"	Assumed	650	SF	0	SF	Multi	
1	1	108A	Classroom 108 Coat Room	CMU Block Wall	Non Suspect ACM	50	SF	N/A	SF		
1	1	108A	Classroom 108 Coat Room	Mastic associated with Floor Tile	NAD	100	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	108A	Classroom 108 Coat Room	Paint associated with Wall, CMU	NAD	50	SF	N/A	SF		
1	1	108A	Classroom 108 Coat Room	Plaster Wall	NAD	500	SF	N/A	SF		
1	1	108A	Classroom 108 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	1	108A	Classroom 108 Coat Room	Floor Tile VAT 12" x 12"	NAD	100	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	109	Classroom 109	Pipe Fitting Insulation	Confirmed	5	EA	0	EA		
1	1	109	Classroom 109	Pipe Insulation 2-6 inch	Confirmed	30	LF	0	LF		
1	1	109	Classroom 109	Plaster Wall	NAD	700	SF	N/A	SF		
1	1	109	Classroom 109	Plaster Ceiling	NAD	650	SF	N/A	SF		
1	1	109	Classroom 109	Floor Tile VAT 12" x 12"	Assumed	650	SF	0	SF	Multi	
1	1	110	Classroom 110	Fiberglass Pipe Insulation	Non Suspect ACM	24	LF	N/A	LF		
1	1	110	Classroom 110	Plaster Wall	NAD	1000	SF	N/A	SF		
1	1	110	Classroom 110	Plaster Ceiling	NAD	655	SF	N/A	SF		
1	1	110	Classroom 110	Floor Tile VAT 12" x 12"	Assumed	655	SF	0	SF	Multi	
1	1	110A	Classroom 110 Coat Room	Plaster Wall	NAD	700	SF	N/A	SF		
1	1	110A	Classroom 110 Coat Room	Plaster Ceiling	NAD	145	SF	N/A	SF		
1	1	110A	Classroom 110 Coat Room	Floor Tile VAT 12" x 12"	Assumed	145	SF	0	SF	Multi	
1	1	110B	Storage Room adjacent to Auditorium	Plaster Wall	NAD	400	SF	N/A	SF		
1	1	110B	Storage Room adjacent to Auditorium	Plaster Ceiling	NAD	55	SF	N/A	SF		
1	1	110B	Storage Room adjacent to Auditorium	Paint associated with Floor, Concrete	Assumed	55	SF	0	SF		
1	1	110B	Storage Room adjacent to Auditorium	Concrete Floor	Non Suspect ACM	55	SF	N/A	SF		
1	1	111	Classroom 111	Mastic associated with Floor Tile	NAD	680	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	1	111	Classroom 111	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	1	111	Classroom 111	Plaster Wall	NAD	985	SF	N/A	SF		
1	1	111	Classroom 111	Plaster Ceiling	NAD	680	SF	N/A	SF		
1	1	111	Classroom 111	Floor Tile VAT 12" x 12"	NAD	680	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	111A	Classroom 111 Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		
1	1	111A	Classroom 111 Restroom	Plaster Wall	NAD	300	SF	N/A	SF		
1	1	111A	Classroom 111 Restroom	Plaster Ceiling	NAD	32	SF	N/A	SF		
1	1	111A	Classroom 111 Restroom	Ceramic Tile Floor	Non Suspect ACM	32	SF	N/A	SF		
1	1	111B	Classroom 111 Coat Room	Mastic associated with Floor Tile	NAD	56	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	111B	Classroom 111 Coat Room	Pipe Fitting Insulation	Confirmed	4	EA	0	EA		
1	1	111B	Classroom 111 Coat Room	Pipe Insulation 2-6 inch	Confirmed	12	LF	1	LF		
1	1	111B	Classroom 111 Coat Room	Plaster Wall	NAD	350	SF	N/A	SF		
1	1	111B	Classroom 111 Coat Room	Plaster Ceiling	NAD	56	SF	N/A	SF		
1	1	111B	Classroom 111 Coat Room	Floor Tile VAT 12" x 12"	NAD	56	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	114	Nurse's Restroom	Sheetrock/Joint Compound Wall	NAD	90	SF	N/A	SF		
1	1	114	Nurse's Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		
1	1	114	Nurse's Restroom	Plaster Ceiling	NAD	46	SF	N/A	SF		
1	1	114	Nurse's Restroom	Fiberglass Duct Insulation	Non Suspect ACM	40	SF	N/A	SF		
1	1	114	Nurse's Restroom	Floor Tile VAT 12" x 12"	Assumed	23	SF	0	SF	Blue	
1	1	114	Nurse's Restroom	Sheetrock/Joint Compound Wall	NAD	200	SF	N/A	SF		
1	1	114	Nurse's Restroom	Ceiling Tile 2' x 4'	NAD	46	SF	N/A	SF		
1	1	114	Nurse's Restroom	Floor Tile VAT 12" x 12"	Assumed	23	SF	0	SF	Yellow	
1	1	120	Main Office Reception Area	Metal Ceiling	Non Suspect ACM	530	SF	N/A	SF		
1	1	120	Main Office Reception Area	Fiberglass Duct Insulation	Non Suspect ACM	250	SF	N/A	SF		
1	1	120	Main Office Reception Area	Sheetrock/Joint Compound Wall	NAD	115	SF	N/A	SF		
1	1	120	Main Office Reception Area	Sheetrock/Joint Compound Wall	NAD	1530	SF	N/A	SF		1 sample sheetrock & 1 sample joint compound NAD 06/21/2023 TF/CRI
1	1	120	Main Office Reception Area	Ceiling Tile 2' x 4'	NAD	530	SF	N/A	SF		
1	1	120	Main Office Reception Area	Laminate Floor	Non Suspect ACM	700	SF	N/A	SF		
1	1	120A	Vice Principal's Office	Fiberglass Duct Insulation	Non Suspect ACM	40	SF	N/A	SF		
1	1	120A	Vice Principal's Office	Metal Ceiling	Non Suspect ACM	192	SF	N/A	SF		
1	1	120A	Vice Principal's Office	Sheetrock/Joint Compound Wall	NAD	560	SF	N/A	SF		
1	1	120A	Vice Principal's Office	Ceiling Tile 2' x 4'	NAD	192	SF	N/A	SF		
1	1	120A	Vice Principal's Office	Laminate Floor	Non Suspect ACM	192	SF	N/A	SF		
1	1	120B	Conference Room in between Vice Principals & CEOs Office	Fiberglass Duct Insulation	Non Suspect ACM	160	SF	N/A	SF		
1	1	120B	Conference Room in between Vice Principals & CEOs Office	Brick Wall	Non Suspect ACM	42	SF	N/A	SF		
1	1	120B	Conference Room in between Vice Principals & CEOs Office	Metal Ceiling	Non Suspect ACM	210	SF	N/A	SF		
1	1	120B	Conference Room in between Vice Principals & CEOs Office	Sheetrock/Joint Compound Wall	NAD	450	SF	N/A	SF		
1	1	120B	Conference Room in between Vice Principals & CEOs Office	Ceiling Tile 2' x 4'	NAD	210	SF	N/A	SF		
1	1	120B	Conference Room in between Vice Principals & CEOs Office	Laminate Floor	Non Suspect ACM	210	SF	N/A	SF		
1	1	120C	CEO's Office	Concrete Ceiling	Non Suspect ACM	315	SF	N/A	SF		
1	1	120C	CEO's Office	Brick Wall	Non Suspect ACM	228	SF	N/A	SF		
1	1	120C	CEO's Office	Fiberglass Duct Insulation	Non Suspect ACM	90	SF	N/A	SF		
1	1	120C	CEO's Office	Sheetrock/Joint Compound Wall	NAD	600	SF	N/A	SF		
1	1	120C	CEO's Office	Ceiling Tile 2' x 4'	NAD	315	SF	N/A	SF		
1	1	120C	CEO's Office	Laminate Floor	Non Suspect ACM	315	SF	N/A	SF		
1	1	120D	Principal's Office adjacent to Conference Room	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	1	120D	Principal's Office adjacent to Conference Room	Metal Ceiling	Non Suspect ACM	250	SF	N/A	SF		
1	1	120D	Principal's Office adjacent to Conference Room	Fiberglass Duct Insulation	Non Suspect ACM	80	SF	N/A	SF		
1	1	120D	Principal's Office adjacent to Conference Room	CMU Block Wall	Non Suspect ACM	54	SF	N/A	SF		
1	1	120D	Principal's Office adjacent to Conference Room	Sheetrock/Joint Compound Wall	NAD	500	SF	N/A	SF		
1	1	120D	Principal's Office adjacent to Conference Room	Ceiling Tile 2' x 4'	NAD	250	SF	N/A	SF		
1	1	120D	Principal's Office adjacent to Conference Room	Laminate Floor	Non Suspect ACM	500	SF	N/A	SF		
1	1	120DA	Restroom in Principal's Office adjacent to Conference Room	CMU Block Wall	Non Suspect ACM	18	SF	N/A	SF		
1	1	120DA	Restroom in Principal's Office adjacent to Conference Room	Metal Ceiling	Non Suspect ACM	36	SF	N/A	SF		
1	1	120DA	Restroom in Principal's Office adjacent to Conference Room	Fiberglass Pipe Insulation	Non Suspect ACM	15	LF	N/A	LF		
1	1	120DA	Restroom in Principal's Office adjacent to Conference Room	Sheetrock/Joint Compound Wall	NAD	25	SF	N/A	SF		
1	1	120DA	Restroom in Principal's Office adjacent to Conference Room	Ceramic Tile Wall	Non Suspect ACM	200	SF	N/A	SF		
1	1	120DA	Restroom in Principal's Office adjacent to Conference Room	Floor Tile VAT 12" x 12"	Assumed	36	SF	0	SF	White	
1	1	120DA	Restroom in Principal's Office adjacent to Conference Room	Ceiling Tile 2' x 4'	NAD	36	SF	N/A	SF		
1	1	120E	Storage Closet adjacent to Staff Office	Laminate Floor	Non Suspect ACM	25	SF	N/A	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	1	120E	Storage Closet adjacent to Staff Office	Sheetrock/Joint Compound Wall	NAD	120	SF	N/A	SF		1 sample sheetrock & 1 sample joint compound NAD 06/21/2023 TF/CRI
1	1	120E	Storage Closet adjacent to Staff Office	Ceiling Tile 2' x 4'	NAD	25	SF	N/A	SF		
1	1	120F	Staff Office adjacent to Storage Closet	CMU Block Wall	Non Suspect ACM	36	SF	N/A	SF		
1	1	120F	Staff Office adjacent to Storage Closet	Metal Ceiling	Non Suspect ACM	90	SF	N/A	SF		
1	1	120F	Staff Office adjacent to Storage Closet	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	1	120F	Staff Office adjacent to Storage Closet	Fiberglass Duct Insulation	Non Suspect ACM	160	SF	N/A	SF		
1	1	120F	Staff Office adjacent to Storage Closet	Ceiling Tile 2' x 4'	NAD	90	SF	N/A	SF		
1	1	120F	Staff Office adjacent to Storage Closet	Laminate Floor	Non Suspect ACM	90	SF	N/A	SF		
1	1	120F	Staff Office adjacent to Storage Closet	Sheetrock/Joint Compound Wall	NAD	240	SF	N/A	SF		
1	1	120G	Staff Office adjacent to Kitchenette	Metal Ceiling	Non Suspect ACM	90	SF	N/A	SF		
1	1	120G	Staff Office adjacent to Kitchenette	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	1	120G	Staff Office adjacent to Kitchenette	CMU Block Wall	Non Suspect ACM	36	SF	N/A	SF		
1	1	120G	Staff Office adjacent to Kitchenette	Fiberglass Duct Insulation	Non Suspect ACM	160	SF	N/A	SF		
1	1	120G	Staff Office adjacent to Kitchenette	Ceiling Tile 2' x 4'	NAD	90	SF	N/A	SF		
1	1	120G	Staff Office adjacent to Kitchenette	Sheetrock/Joint Compound Wall	NAD	240	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	1	120H	Staff Restroom across from Kitchenette	Laminate Floor	Non Suspect ACM	90	SF	N/A	SF		
1	1	120H	Staff Restroom across from Kitchenette	Brick Wall	Non Suspect ACM	90	SF	N/A	SF		
1	1	120H	Staff Restroom across from Kitchenette	Fiberglass Pipe Insulation	Non Suspect ACM	7	LF	N/A	LF		
1	1	120H	Staff Restroom across from Kitchenette	Metal Ceiling	Non Suspect ACM	36	SF	N/A	SF		
1	1	120H	Staff Restroom across from Kitchenette	Sheetrock/Joint Compound Wall	NAD	200	SF	N/A	SF		
1	1	120H	Staff Restroom across from Kitchenette	Floor Tile VAT 12" x 12"	Assumed	36	SF	0	SF	White	
1	1	120H	Staff Restroom across from Kitchenette	Ceiling Tile 2' x 4'	NAD	36	SF	N/A	SF		
1	1	120I	Staff Restroom adjacent to Office next to Copy Room	Metal Ceiling	Non Suspect ACM	36	SF	N/A	SF		
1	1	120I	Staff Restroom adjacent to Office next to Copy Room	Brick Wall	Non Suspect ACM	90	SF	N/A	SF		
1	1	120I	Staff Restroom adjacent to Office next to Copy Room	Fiberglass Pipe Insulation	Non Suspect ACM	14	LF	N/A	LF		
1	1	120I	Staff Restroom adjacent to Office next to Copy Room	Floor Tile VAT 12" x 12"	Assumed	36	SF	0	SF	White	
1	1	120I	Staff Restroom adjacent to Office next to Copy Room	Sheetrock/Joint Compound Wall	NAD	200	SF	N/A	SF		
1	1	120I	Staff Restroom adjacent to Office next to Copy Room	Ceiling Tile 2' x 4'	NAD	36	SF	N/A	SF		
1	1	120J	Storage Room adjacent to Restrooms	Fiberglass Duct Insulation	Non Suspect ACM	10	SF	N/A	SF		
1	1	120J	Storage Room adjacent to Restrooms	Sheetrock/Joint Compound Wall	NAD	255	SF	N/A	SF		1 sample sheetrock & 1 sample joint compound NAD 06/21/2023 TF/CRI
1	1	120J	Storage Room adjacent to Restrooms	Ceiling Tile 2' x 4'	NAD	8	SF	N/A	SF		
1	1	120J	Storage Room adjacent to Restrooms	Concrete Floor	Non Suspect ACM	25	SF	N/A	SF		
1	1	120J	Storage Room adjacent to Restrooms	Metal Ceiling	Non Suspect ACM	25	SF	N/A	SF		
1	1	120J	Storage Room adjacent to Restrooms	Brick Wall	Non Suspect ACM	40	SF	N/A	SF		
1	1	120K	Staff Office adjacent to Staff Restrooms and Copy Area	Metal Ceiling	Non Suspect ACM	120	SF	N/A	SF		
1	1	120K	Staff Office adjacent to Staff Restrooms and Copy Area	Fiberglass Duct Insulation	Non Suspect ACM	60	SF	N/A	SF		
1	1	120K	Staff Office adjacent to Staff Restrooms and Copy Area	Sheetrock/Joint Compound Wall	NAD	275	SF	N/A	SF		
1	1	120K	Staff Office adjacent to Staff Restrooms and Copy Area	Ceiling Tile 2' x 4'	NAD	120	SF	N/A	SF		
1	1	120K	Staff Office adjacent to Staff Restrooms and Copy Area	Laminate Floor	Non Suspect ACM	120	SF	N/A	SF		
1	1	121	Nurse's Office	Sheetrock/Joint Compound Wall	NAD	144	SF	N/A	SF		
1	1	121	Nurse's Office	Fiberglass Duct Insulation	Non Suspect ACM	80	SF	N/A	SF		
1	1	121	Nurse's Office	Fiberglass Pipe Insulation	Non Suspect ACM	30	LF	N/A	LF		
1	1	121	Nurse's Office	Plaster Ceiling	NAD	25	SF	N/A	SF		
1	1	121	Nurse's Office	Laminate Floor	Non Suspect ACM	25	SF	N/A	SF		
1	1	121	Nurse's Office	Sheetrock/Joint Compound Wall	NAD	120	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	1	121	Nurse's Office	Ceiling Tile 2' x 4'	NAD	25	SF	N/A	SF		
1	1	121A	Nurse's Office #2	Plaster Ceiling	NAD	150	SF	N/A	SF		
1	1	121A	Nurse's Office #2	Fiberglass Duct Insulation	Non Suspect ACM	20	SF	N/A	SF		
1	1	121A	Nurse's Office #2	Sheetrock/Joint Compound Wall	NAD	132	SF	N/A	SF		
1	1	121A	Nurse's Office #2	Floor Tile VAT 12" x 12"	Assumed	150	SF	0	SF	Multi	
1	1	121A	Nurse's Office #2	Sheetrock/Joint Compound Wall	NAD	450	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	1	121A	Nurse's Office #2	Ceiling Tile 2' x 4'	NAD	150	SF	N/A	SF		
1	1	121B	Nurse's Office #3	Plaster Ceiling	NAD	350	SF	N/A	SF		
1	1	121B	Nurse's Office #3	Fiberglass Duct Insulation	Non Suspect ACM	100	SF	N/A	SF		
1	1	121B	Nurse's Office #3	Sheetrock/Joint Compound Wall	NAD	85	SF	N/A	SF		
1	1	121B	Nurse's Office #3	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	1	121B	Nurse's Office #3	Floor Tile VAT 12" x 12"	NAD	350	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	121B	Nurse's Office #3	Mastic associated with Floor Tile	NAD	350	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	121B	Nurse's Office #3	Sheetrock/Joint Compound Wall	NAD	800	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	1	121B	Nurse's Office #3	Ceiling Tile 2' x 4'	NAD	350	SF	N/A	SF		
1	1	140	Book Storage	Plaster Wall	NAD	300	SF	N/A	SF		
1	1	140	Book Storage	Plaster Ceiling	NAD	75	SF	N/A	SF		
1	1	140	Book Storage	Paint associated with Floor, Concrete	Assumed	75	SF	0	SF		
1	1	140	Book Storage	Concrete Floor	Non Suspect ACM	75	SF	N/A	SF		
1	1	14A	Storage Room adjacent to Classroom 108	Fiberglass Pipe Insulation	Non Suspect ACM	50	LF	N/A	LF		
1	1	14A	Storage Room adjacent to Classroom 108	Expansion Seam Caulking	Assumed	243	LF	0	LF		
1	1	14A	Storage Room adjacent to Classroom 108	CMU Block Wall	Non Suspect ACM	500	SF	N/A	SF		
1	1	14A	Storage Room adjacent to Classroom 108	Concrete Ceiling	Non Suspect ACM	100	SF	N/A	SF		
1	1	14A	Storage Room adjacent to Classroom 108	Paint associated with Floor, Concrete	Assumed	100	SF	0	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	1	14A	Storage Room adjacent to Classroom 108	Concrete Floor	Non Suspect ACM	100	SF	N/A	SF		
1	1	14B	Staff Restroom adjacent to Classroom 107	Concrete Ceiling	Non Suspect ACM	50	SF	N/A	SF		
1	1	14B	Staff Restroom adjacent to Classroom 107	CMU Block Wall	Non Suspect ACM	90	SF	N/A	SF		
1	1	14B	Staff Restroom adjacent to Classroom 107	Paint associated with Wall, CMU	NAD	260	SF	N/A	SF		
1	1	14B	Staff Restroom adjacent to Classroom 107	CMU Block Wall	Non Suspect ACM	260	SF	N/A	SF		
1	1	14B	Staff Restroom adjacent to Classroom 107	Ceiling Tile 2' x 4'	NAD	50	SF	N/A	SF		
1	1	14B	Staff Restroom adjacent to Classroom 107	Ceramic Tile Floor	Non Suspect ACM	50	SF	N/A	SF		
1	1	14C	Boy's Restroom adjacent to Classroom 107	CMU Block Wall	Non Suspect ACM	350	SF	N/A	SF		
1	1	14C	Boy's Restroom adjacent to Classroom 107	Fiberglass Pipe Insulation	Non Suspect ACM	80	LF	N/A	LF		
1	1	14C	Boy's Restroom adjacent to Classroom 107	Concrete Ceiling	Non Suspect ACM	260	SF	N/A	SF		
1	1	14C	Boy's Restroom adjacent to Classroom 107	Paint associated with Wall, CMU	NAD	240	SF	N/A	SF		
1	1	14C	Boy's Restroom adjacent to Classroom 107	CMU Block Wall	Non Suspect ACM	240	SF	N/A	SF		
1	1	14C	Boy's Restroom adjacent to Classroom 107	Ceiling Tile 2' x 4'	NAD	260	SF	N/A	SF		
1	1	14C	Boy's Restroom adjacent to Classroom 107	Ceramic Tile Wall	Non Suspect ACM	680	SF	N/A	SF		
1	1	14C	Boy's Restroom adjacent to Classroom 107	Ceramic Tile Floor	Non Suspect ACM	260	SF	N/A	SF		
1	1	15A	Staff Restroom adjacent to Classrom 105	Concrete Ceiling	Non Suspect ACM	50	SF	N/A	SF		
1	1	15A	Staff Restroom adjacent to Classrom 105	CMU Block Wall	Non Suspect ACM	93	SF	N/A	SF		
1	1	15A	Staff Restroom adjacent to Classrom 105	Fireproofing	NAD	40	SF	N/A	SF		
1	1	15A	Staff Restroom adjacent to Classrom 105	Paint associated with Wall, CMU	NAD	240	SF	N/A	SF		
1	1	15A	Staff Restroom adjacent to Classrom 105	CMU Block Wall	Non Suspect ACM	240	SF	N/A	SF		
1	1	15A	Staff Restroom adjacent to Classrom 105	Ceiling Tile 2' x 4'	NAD	50	SF	N/A	SF		
1	1	15A	Staff Restroom adjacent to Classrom 105	Ceramic Tile Floor	Non Suspect ACM	50	SF	N/A	SF		
1	1	441	Girls Restroom adjacent to Classroom 101	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	1	EA	N/A	EA		
1	1	441	Girls Restroom adjacent to Classroom 101	Fiberglass Pipe Insulation	Non Suspect ACM	25	LF	N/A	LF		
1	1	441	Girls Restroom adjacent to Classroom 101	Ceramic Tile Wall	Non Suspect ACM	385	SF	N/A	SF		
1	1	441	Girls Restroom adjacent to Classroom 101	Plaster Wall	NAD	385	SF	N/A	SF		
1	1	441	Girls Restroom adjacent to Classroom 101	Paint associated with Ceiling, Concrete	NAD	117	SF	N/A	SF		
1	1	441	Girls Restroom adjacent to Classroom 101	Concrete Ceiling	Non Suspect ACM	180	SF	N/A	SF		
1	1	441	Girls Restroom adjacent to Classroom 101	Paint associated with Floor, Concrete	Assumed	180	SF	0	SF		
1	1	441	Girls Restroom adjacent to Classroom 101	Concrete Floor	Non Suspect ACM	180	SF	N/A	SF		
1	1	911SC	Boy's Restroom adjacent to Classroom 111	Duct Work	Non Suspect ACM	15	LF	N/A	LF		
1	1	911SC	Boy's Restroom adjacent to Classroom 111	Fiberglass Pipe Insulation	Non Suspect ACM	8	LF	N/A	LF		
1	1	911SC	Boy's Restroom adjacent to Classroom 111	Ceramic Tile Wall	Non Suspect ACM	450	SF	N/A	SF		
1	1	911SC	Boy's Restroom adjacent to Classroom 111	Plaster Wall	NAD	350	SF	N/A	SF		
1	1	911SC	Boy's Restroom adjacent to Classroom 111	Paint associated with Ceiling, Concrete	NAD	162	SF	N/A	SF		
1	1	911SC	Boy's Restroom adjacent to Classroom 111	Concrete Ceiling	Non Suspect ACM	150	SF	N/A	SF		
1	1	911SC	Boy's Restroom adjacent to Classroom 111	Paint associated with Floor, Concrete	Assumed	150	SF	0	SF		
1	1	911SC	Boy's Restroom adjacent to Classroom 111	Concrete Floor	Non Suspect ACM	150	SF	N/A	SF		
1	1	AUD	Auditorium	Heat Shield Insulation associated with Radiator Cover	Assumed	25	SF	0	SF		
1	1	AUD	Auditorium	Heat Shield Insulation associated with Radiator	Assumed	500	SF	0	SF		
1	1	AUD	Auditorium	Auditorium Plaster Walls	NAD	5500	SF	N/A	SF		
1	1	AUD	Auditorium	Auditorium Plaster Ceiling	Assumed	3650	SF	0	SF		Too high to sample - 25 Feet No Attic
1	1	AUD	Auditorium	Wood Floor	Non Suspect ACM	3650	SF	N/A	SF		
1	1	G01	Gymnasium	Duct Work	Non Suspect ACM	300	LF	N/A	LF		
1	1	G01	Gymnasium	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	18	EA	N/A	EA		
1	1	G01	Gymnasium	Fiberglass Pipe Insulation	Non Suspect ACM	300	LF	N/A	LF		
1	1	G01	Gymnasium	Paint associated with Wall, CMU	NAD	11500	SF	N/A	SF		
1	1	G01	Gymnasium	Expansion Seam Caulking	Assumed	500	LF	0	LF		
1	1	G01	Gymnasium	CMU Block Wall	Non Suspect ACM	11500	SF	N/A	SF		
1	1	G01	Gymnasium	Metal Ceiling	Non Suspect ACM	8000	SF	N/A	SF		
1	1	G01	Gymnasium	Rubber Floor	Non Suspect ACM	8000	SF	N/A	SF		
1	1	G01A	Gymnasium Office adjacent to Exit	Fireproofing	NAD	20	SF	N/A	SF		
1	1	G01A	Gymnasium Office adjacent to Exit	Concrete Ceiling	Non Suspect ACM	225	SF	N/A	SF		
1	1	G01A	Gymnasium Office adjacent to Exit	CMU Block Wall	Non Suspect ACM	156	SF	N/A	SF		
1	1	G01A	Gymnasium Office adjacent to Exit	Floor Tile VAT 12" x 12"	NAD	225	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	G01A	Gymnasium Office adjacent to Exit	Mastic associated with Floor Tile	NAD	225	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	G01A	Gymnasium Office adjacent to Exit	Mastic associated with Floor Tile	NAD	225	SF	N/A	SF		2 Samples Collected
1	1	G01A	Gymnasium Office adjacent to Exit	Paint associated with Wall, CMU	NAD	320	SF	N/A	SF		
1	1	G01A	Gymnasium Office adjacent to Exit	Expansion Seam Caulking	Assumed	32	LF	0	LF		
1	1	G01A	Gymnasium Office adjacent to Exit	CMU Block Wall	Non Suspect ACM	320	SF	N/A	SF		
1	1	G01A	Gymnasium Office adjacent to Exit	Ceiling Tile 2' x 4'	NAD	225	SF	N/A	SF		
1	1	G01B	Center Gymnasium Office	CMU Block Wall	Non Suspect ACM	165	SF	N/A	SF		
1	1	G01B	Center Gymnasium Office	Concrete Ceiling	Non Suspect ACM	225	SF	N/A	SF		
1	1	G01B	Center Gymnasium Office	CMU Block Wall	Non Suspect ACM	350	SF	N/A	SF		
1	1	G01B	Center Gymnasium Office	Floor Tile VAT 12" x 12"	NAD	225	SF	N/A	SF	Tan	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	G01B	Center Gymnasium Office	Mastic associated with Floor Tile	NAD	225	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	G01B	Center Gymnasium Office	Paint associated with Wall, CMU	NAD	350	SF	N/A	SF		
1	1	G01B	Center Gymnasium Office	Ceiling Tile 2' x 4'	NAD	225	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	1	G01C	Gymnasium Office adjacent to Restrooms	Concrete Ceiling	Non Suspect ACM	170	SF	N/A	SF		
1	1	G01C	Gymnasium Office adjacent to Restrooms	Sheetrock/Joint Compound Wall	NAD	36	SF	N/A	SF		
1	1	G01C	Gymnasium Office adjacent to Restrooms	Fiberglass Duct Insulation	Non Suspect ACM	16	SF	N/A	SF		
1	1	G01C	Gymnasium Office adjacent to Restrooms	CMU Block Wall	Non Suspect ACM	108	SF	N/A	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	1	G01C	Gymnasium Office adjacent to Restrooms	Floor Tile VAT 12" x 12"	Assumed	170	SF	0	SF	Tan	
1	1	G01C	Gymnasium Office adjacent to Restrooms	CMU Block Wall	Non Suspect ACM	300	SF	N/A	SF		
1	1	G01C	Gymnasium Office adjacent to Restrooms	Ceiling Tile 2' x 4'	NAD	170	SF	N/A	SF		
1	1	G01C	Gymnasium Office adjacent to Restrooms	Paint associated with Wall, CMU	NAD	300	SF	N/A	SF		
1	1	G01C	Gymnasium Office adjacent to Restrooms	Sheetrock/Joint Compound Wall	NAD	110	SF	N/A	SF		
1	1	G01CA	Gym Office Back Closet	CMU Block Wall	Non Suspect ACM	15	SF	N/A	SF		
1	1	G01CA	Gym Office Back Closet	Sheetrock/Joint Compound Wall	NAD	40	SF	N/A	SF		
1	1	G01CA	Gym Office Back Closet	Floor Tile VAT 12" x 12"	Assumed	6	SF	0	SF	Tan	
1	1	G01CAB	Gym Office Restroom	Sheetrock/Joint Compound Wall	NAD	36	SF	N/A	SF		
1	1	G01CAB	Gym Office Restroom	Concrete Ceiling	Non Suspect ACM	40	SF	N/A	SF		
1	1	G01CAB	Gym Office Restroom	CMU Block Wall	Non Suspect ACM	24	SF	N/A	SF		
1	1	G01CAB	Gym Office Restroom	Ceiling Tile 2' x 4'	NAD	40	SF	N/A	SF		
1	1	G01CAB	Gym Office Restroom	CMU Block Wall	Non Suspect ACM	90	SF	N/A	SF		
1	1	G01CAB	Gym Office Restroom	Sheetrock/Joint Compound Wall	NAD	100	SF	N/A	SF		
1	1	G01CAB	Gym Office Restroom	Ceramic Tile Wall	Non Suspect ACM	50	SF	N/A	SF		
1	1	G01CAB	Gym Office Restroom	Ceramic Tile Floor	Non Suspect ACM	40	SF	N/A	SF		
1	1	G01CAB	Gym Office Restroom	Paint associated with Wall, CMU	NAD	90	SF	N/A	SF		
1	1	G01CABC	Gym Office Storage	Concrete Ceiling	Non Suspect ACM	20	SF	N/A	SF		
1	1	G01CABC	Gym Office Storage	Sheetrock/Joint Compound Wall	NAD	120	SF	N/A	SF		
1	1	G01CABC	Gym Office Storage	CMU Block Wall	Non Suspect ACM	120	SF	N/A	SF		
1	1	G01CABC	Gym Office Storage	Concrete Floor	Non Suspect ACM	20	SF	N/A	SF		
1	1	G01D	Gymnasium Girl's Restroom	CMU Block Wall	Non Suspect ACM	60	SF	N/A	SF		
1	1	G01D	Gymnasium Girl's Restroom	Fiberglass Duct Insulation	Non Suspect ACM	10	SF	N/A	SF		
1	1	G01D	Gymnasium Girl's Restroom	Concrete Ceiling	Non Suspect ACM	45	SF	N/A	SF		
1	1	G01D	Gymnasium Girl's Restroom	CMU Block Wall	Non Suspect ACM	80	SF	N/A	SF		
1	1	G01D	Gymnasium Girl's Restroom	Paint associated with Wall, CMU	NAD	80	SF	N/A	SF		
1	1	G01D	Gymnasium Girl's Restroom	Ceramic Tile Wall	Non Suspect ACM	200	SF	N/A	SF		
1	1	G01D	Gymnasium Girl's Restroom	Ceiling Tile 2' x 4'	NAD	45	SF	N/A	SF		
1	1	G01D	Gymnasium Girl's Restroom	Ceramic Tile Floor	Non Suspect ACM	45	SF	N/A	SF		
1	1	G01E	Gymnasium Boy's Restroom	Fiberglass Duct Insulation	Non Suspect ACM	10	SF	N/A	SF		
1	1	G01E	Gymnasium Boy's Restroom	CMU Block Wall	Non Suspect ACM	60	SF	N/A	SF		
1	1	G01E	Gymnasium Boy's Restroom	Concrete Ceiling	Non Suspect ACM	45	SF	N/A	SF		
1	1	G01E	Gymnasium Boy's Restroom	Paint associated with Wall, CMU	NAD	80	SF	N/A	SF		
1	1	G01E	Gymnasium Boy's Restroom	Ceiling Tile 2' x 4'	NAD	45	SF	N/A	SF		
1	1	G01E	Gymnasium Boy's Restroom	Ceramic Tile Floor	Non Suspect ACM	45	SF	N/A	SF		
1	1	G01E	Gymnasium Boy's Restroom	Ceramic Tile Wall	Non Suspect ACM	200	SF	N/A	SF		
1	1	G01E	Gymnasium Boy's Restroom	CMU Block Wall	Non Suspect ACM	80	SF	N/A	SF		
1	1	G01G	Gymnasium Storage Room	Rubber Floor	Non Suspect ACM	220	SF	N/A	SF		
1	1	G01G	Gymnasium Storage Room	CMU Block Wall	Non Suspect ACM	720	SF	N/A	SF		
1	1	G01G	Gymnasium Storage Room	Concrete Ceiling	Non Suspect ACM	220	SF	N/A	SF		
1	1	G01G	Gymnasium Storage Room	Fireproofing associated with Support Post, Metal	NAD	75	SF	N/A	SF	Grey	3 samples NAD 3/9/2023 TF/CRI
1	1	G01G	Gymnasium Storage Room	Fireproofing	NAD	75	SF	N/A	SF		3 Samples Collected
1	1	H14	Hallway from Classroom 111 to Classroom 107	Ceiling Tile 2' x 4'	NAD	1140	SF	N/A	SF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	Fiberglass Duct Insulation	Non Suspect ACM	40	SF	N/A	SF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	CMU Block Wall	Non Suspect ACM	675	SF	N/A	SF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	Concrete Ceiling	Non Suspect ACM	1140	SF	N/A	SF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	Sheetrock/Joint Compound Wall	NAD	450	SF	N/A	SF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	Fiberglass Pipe Insulation	Non Suspect ACM	50	LF	N/A	LF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	Plaster Wall	NAD	3360	SF	N/A	SF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	Plaster Ceiling	NAD	1255	SF	N/A	SF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	Paint associated with Floor, Concrete	Assumed	1450	SF	0	SF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	Concrete Floor	Non Suspect ACM	1000	SF	N/A	SF		
1	1	H14	Hallway from Classroom 111 to Classroom 107	Leveling Compound associated with Floor Tile	NAD	1450	SF	N/A	SF	Grey	1 Sample Collected-Sampled NAD 6/12/2019 Syn/BB. 1 sample NAD 3/9/2023 TF/CRI
1	1	H14	Hallway from Classroom 111 to Classroom 107	Mastic associated with Floor Tile	NAD	1450	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	H14	Hallway from Classroom 111 to Classroom 107	Floor Tile VAT 12" x 12"	NAD	1450	SF	N/A	SF	White	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	H15	Hallway from Classroom 101 to Classroom 106	Fiberglass Duct Insulation	Non Suspect ACM	40	SF	N/A	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Concrete Ceiling	Non Suspect ACM	1450	SF	N/A	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	CMU Block Wall	Non Suspect ACM	675	SF	N/A	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Paint associated with Wall, CMU	NAD	2080	SF	N/A	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Ceiling Tile 2' x 4'	NAD	1450	SF	N/A	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	CMU Block Wall	Non Suspect ACM	2080	SF	N/A	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	3	EA	N/A	EA		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Mastic associated with Floor Tile	NAD	1450	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	H15	Hallway from Classroom 101 to Classroom 106	Fiberglass Pipe Insulation	Non Suspect ACM	60	LF	N/A	LF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Plaster Wall	NAD	3360	SF	N/A	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Plaster Ceiling	NAD	1255	SF	N/A	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Paint associated with Floor, Concrete	Assumed	1450	SF	0	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Concrete Floor	Non Suspect ACM	1000	SF	N/A	SF		
1	1	H15	Hallway from Classroom 101 to Classroom 106	Floor Tile VAT 12" x 12"	NAD	1450	SF	N/A	SF	White	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	1	H16	Hallway in front of Main Office	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	5	EA	N/A	EA		
1	1	H16	Hallway in front of Main Office	Fiberglass Pipe Insulation	Non Suspect ACM	60	LF	N/A	LF		
1	1	H16	Hallway in front of Main Office	Plaster Wall	NAD	2400	SF	N/A	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	1	H16	Hallway in front of Main Office	Plaster Ceiling	NAD	980	SF	N/A	SF		
1	1	H16	Hallway in front of Main Office	Paint associated with Floor, Concrete	Assumed	980	SF	0	SF		
1	1	H16	Hallway in front of Main Office	Concrete Floor	Non Suspect ACM	980	SF	N/A	SF		
1	1	S11	Haworth Stairwell A adjacent to Classroom 110	Pipe Fitting Insulation	Confirmed	11	EA	0	EA		
1	1	S11	Haworth Stairwell A adjacent to Classroom 110	Pipe Insulation 2-6 inch	Confirmed	30	LF	0	LF		
1	1	S11	Haworth Stairwell A adjacent to Classroom 110	Plaster Wall	NAD	1250	SF	N/A	SF		
1	1	S11	Haworth Stairwell A adjacent to Classroom 110	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	1	S11	Haworth Stairwell A adjacent to Classroom 110	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	1	S11	Haworth Stairwell A adjacent to Classroom 110	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	1	S12	Dyre Stairwell A adjacent to Classroom 102	CMU Block Wall	Non Suspect ACM	1250	SF	N/A	SF		
1	1	S12	Dyre Stairwell A adjacent to Classroom 102	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	1	S12	Dyre Stairwell A adjacent to Classroom 102	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	1	S13	Dyre Stairwell B adjacent to Classroom 104	Paint associated with Wall, CMU	NAD	1250	SF	N/A	SF		
1	1	S13	Dyre Stairwell B adjacent to Classroom 104	Expansion Seam Caulking	Assumed	30	LF	0	LF		
1	1	S13	Dyre Stairwell B adjacent to Classroom 104	CMU Block Wall	Non Suspect ACM	1250	SF	N/A	SF		
1	1	S13	Dyre Stairwell B adjacent to Classroom 104	Metal Ceiling	Non Suspect ACM	300	SF	N/A	SF		
1	1	S13	Dyre Stairwell B adjacent to Classroom 104	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	1	S13	Dyre Stairwell B adjacent to Classroom 104	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	1	S14	Haworth Stairwell B adjacent to Classroom 108	CMU Block Wall	Non Suspect ACM	1250	SF	N/A	SF		
1	1	S14	Haworth Stairwell B adjacent to Classroom 108	Paint associated with Wall, CMU	NAD	1250	SF	N/A	SF		
1	1	S14	Haworth Stairwell B adjacent to Classroom 108	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	1	S14	Haworth Stairwell B adjacent to Classroom 108	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	1	S15	Dyre Stairwell C adjacent to Classroom 106	Paint associated with Wall, CMU	NAD	1250	SF	N/A	SF		
1	1	S15	Dyre Stairwell C adjacent to Classroom 106	Expansion Seam Caulking	Assumed	60	LF	0	LF		
1	1	S15	Dyre Stairwell C adjacent to Classroom 106	CMU Block Wall	Non Suspect ACM	1250	SF	N/A	SF		
1	1	S15	Dyre Stairwell C adjacent to Classroom 106	Metal Ceiling	Non Suspect ACM	300	SF	N/A	SF		
1	1	S15	Dyre Stairwell C adjacent to Classroom 106	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	1	S15	Dyre Stairwell C adjacent to Classroom 106	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	2	201	Classroom 201	Glue Dots associated with Blackboard	Assumed	10	SF	0	SF		
1	2	201	Classroom 201	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	2	201	Classroom 201	Plaster Wall	NAD	1100	SF	N/A	SF		
1	2	201	Classroom 201	Plaster Ceiling	NAD	680	SF	N/A	SF		
1	2	201	Classroom 201	Floor Tile VAT 12" x 12"	NAD	680	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	2	201A	Classroom 201 Coat Room	Mastic associated with Floor Tile	Assumed	100	SF	0	SF	Yellow	
1	2	201A	Classroom 201 Coat Room	Pipe Fitting Insulation	Confirmed	8	EA	0	EA		
1	2	201A	Classroom 201 Coat Room	Pipe Insulation 2-6 inch	Confirmed	40	LF	0	LF		
1	2	201A	Classroom 201 Coat Room	Plaster Wall	NAD	500	SF	N/A	SF		
1	2	201A	Classroom 201 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	2	201A	Classroom 201 Coat Room	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	2	201B	ESOL Classroom adjacent to Classroom 204	Fiberglass Duct Insulation	Non Suspect ACM	160	SF	N/A	SF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Fiberglass Pipe Insulation	Non Suspect ACM	60	LF	N/A	LF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Concrete Ceiling	Non Suspect ACM	90	SF	N/A	SF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	12	EA	N/A	EA		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Duct Work	Non Suspect ACM	48	LF	N/A	LF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Fiberglass Duct Insulation	Non Suspect ACM	36	SF	N/A	SF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Sheetrock/Joint Compound Wall	NAD	225	SF	N/A	SF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Floor Tile VAT 12" x 12"	Assumed	300	SF	0	SF	Multi	
1	2	201B	ESOL Classroom adjacent to Classroom 204	Paint associated with Wall, CMU	NAD	900	SF	N/A	SF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Expansion Seam Caulking	Assumed	90	LF	0	LF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	CMU Block Wall	Non Suspect ACM	900	SF	N/A	SF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Ceiling Tile 2' x 4'	NAD	90	SF	N/A	SF		
1	2	201B	ESOL Classroom adjacent to Classroom 204	Floor Tile VAT 12" x 12"	Assumed	90	SF	0	SF	White	1 sample sheetrock & 1 sample joint compound NAD 06/21/2023 TF/CRI
1	2	202	Classroom 202	Sheetrock/Joint Compound Wall	NAD	275	SF	N/A	SF		
1	2	202	Classroom 202	Mastic associated with Floor Tile	Assumed	675	SF	0	SF	Yellow	
1	2	202	Classroom 202	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	2	202	Classroom 202	Plaster Wall	NAD	1000	SF	N/A	SF		
1	2	202	Classroom 202	Plaster Ceiling	NAD	675	SF	N/A	SF		
1	2	202	Classroom 202	Floor Tile VAT 12" x 12"	Assumed	675	SF	0	SF	Multi	
1	2	202A	Autistic Support Office 202A	Brick Wall	Non Suspect ACM	210	SF	N/A	SF		
1	2	202A	Autistic Support Office 202A	Metal Ceiling	Non Suspect ACM	130	SF	N/A	SF		
1	2	202A	Autistic Support Office 202A	Laminate Floor	Non Suspect ACM	260	SF	N/A	SF		
1	2	202A	Autistic Support Office 202A	Concrete Ceiling	Non Suspect ACM	130	SF	N/A	SF		
1	2	202A	Autistic Support Office 202A	Paint associated with Ceiling, Concrete	NAD	130	SF	N/A	SF		
1	2	202A	Autistic Support Office 202A	Sheetrock/Joint Compound Wall	NAD	700	SF	N/A	SF		
1	2	202A	Classroom 202 Coat Room	Mastic associated with Floor Tile	Assumed	150	SF	0	SF	Yellow	
1	2	202A	Classroom 202 Coat Room	Fiberglass Pipe Insulation	Non Suspect ACM	12	LF	N/A	LF		
1	2	202A	Classroom 202 Coat Room	Plaster Wall	NAD	675	SF	N/A	SF		
1	2	202A	Classroom 202 Coat Room	Plaster Ceiling	NAD	150	SF	N/A	SF		
1	2	202A	Classroom 202 Coat Room	Floor Tile VAT 12" x 12"	Assumed	150	SF	0	SF	Multi	
1	2	202A	Autistic Support Office 202A	Ceiling Tile 2' x 4'	NAD	260	SF	N/A	SF		
1	2	203	Classroom 203	Plaster Wall	NAD	310	SF	N/A	SF		
1	2	203	Classroom 203	Fiberglass Duct Insulation	Non Suspect ACM	100	SF	N/A	SF		
1	2	203	Classroom 203	Plaster Ceiling	NAD	660	SF	N/A	SF		
1	2	203	Classroom 203	Plaster Ceiling	NAD	660	SF	N/A	SF		



Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	2	203	Classroom 203	Sheetrock/Joint Compound Wall	NAD	300	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound 3/9/2023 TF/CRI
1	2	203	Classroom 203	Fiberglass Pipe Insulation	Non Suspect ACM	25	LF	N/A	LF		
1	2	203	Classroom 203	Plaster Wall	NAD	700	SF	N/A	SF		
1	2	203	Classroom 203	Ceiling Tile 2' x 4'	NAD	660	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	2	203	Classroom 203	Floor Tile VAT 12" x 12"	Assumed	660	SF	0	SF	Tan	
1	2	203B	Classroom 204A Coat Room	Plaster Wall	NAD	500	SF	N/A	SF		
1	2	203B	Classroom 204A Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	2	203B	Classroom 204A Coat Room	Wood Floor	Non Suspect ACM	100	SF	N/A	SF		
1	2	203C	Classroom 204A	Fiberglass Duct Insulation	Non Suspect ACM	160	SF	N/A	SF		
1	2	203C	Classroom 204A	Plaster Ceiling	NAD	750	SF	N/A	SF		
1	2	203C	Classroom 204A	Plaster Wall	NAD	325	SF	N/A	SF		
1	2	203C	Classroom 204A	Mastic associated with Floor Tile	NAD	750	SF	N/A	SF	Black	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	2	203C	Classroom 204A	Sheetrock/Joint Compound Wall	NAD	250	SF	N/A	SF		
1	2	203C	Classroom 204A	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	2	203C	Classroom 204A	Plaster Wall	NAD	875	SF	N/A	SF		
1	2	203C	Classroom 204A	Ceiling Tile 2' x 4'	NAD	750	SF	N/A	SF		
1	2	203C	Classroom 204A	Floor Tile VAT 12" x 12"	NAD	750	SF	N/A	SF	Tan	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	2	204	Classroom 204	Concrete Ceiling	Non Suspect ACM	1230	SF	N/A	SF		
1	2	204	Classroom 204	Fiberglass Pipe Insulation	Non Suspect ACM	115	LF	N/A	LF		
1	2	204	Classroom 204	Fiberglass Duct Insulation	Non Suspect ACM	250	SF	N/A	SF		
1	2	204	Classroom 204	CMU Block Wall	Non Suspect ACM	450	SF	N/A	SF		
1	2	204	Classroom 204	Paint associated with Wall, CMU	NAD	1500	SF	N/A	SF		
1	2	204	Classroom 204	Expansion Seam Caulking	Assumed	130	LF	0	LF		
1	2	204	Classroom 204	CMU Block Wall	Non Suspect ACM	1500	SF	N/A	SF		
1	2	204	Classroom 204	Sheetrock/Joint Compound Wall	NAD	300	SF	N/A	SF		1 sample collected ; 1 sample sheetrock & 1 sample joint compound NAD 06/21/2023 TF/CRI
1	2	204	Classroom 204	Ceiling Tile 2' x 4'	NAD	1230	SF	N/A	SF		
1	2	204	Classroom 204	Floor Tile VAT 12" x 12"	Assumed	1125	SF	0	SF	White	
1	2	204X	Telecommunications Room	Wood Floor	Non Suspect ACM	100	SF	N/A	SF		
1	2	204X	Telecommunications Room	Sheetrock/Joint Compound Wall	NAD	400	SF	N/A	SF		
1	2	204X	Telecommunications Room	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	2	204X	Telecommunications Room	Plaster Wall	NAD	500	SF	N/A	SF		
1	2	204X	Telecommunications Room	Plaster Ceiling	NAD	150	SF	N/A	SF		
1	2	204X	Telecommunications Room	Floor Tile VAT 12" x 12"	Assumed	50	SF	0	SF	White	
1	2	205A	Autistic Support Room 205A	Floor Tile VAT 12" x 12"	Assumed	490	SF	0	SF	White	
1	2	205A	Autistic Support Room 205A	Fiberglass Pipe Insulation	Non Suspect ACM	37	LF	N/A	LF		
1	2	205A	Autistic Support Room 205A	Fiberglass Duct Insulation	Non Suspect ACM	150	SF	N/A	SF		
1	2	205A	Autistic Support Room 205A	Concrete Ceiling	Non Suspect ACM	490	SF	N/A	SF		
1	2	205A	Autistic Support Room 205A	CMU Block Wall	Non Suspect ACM	300	SF	N/A	SF		
1	2	205A	Autistic Support Room 205A	Paint associated with Wall, CMU	NAD	1000	SF	0	SF		
1	2	205A	Autistic Support Room 205A	Ceiling Tile 2' x 4'	NAD	490	SF	N/A	SF		
1	2	205A	Autistic Support Room 205A	Expansion Seam Caulking	Assumed	100	LF	0	LF		
1	2	205A	Autistic Support Room 205A	CMU Block Wall	Non Suspect ACM	1000	SF	N/A	SF		
1	2	205B	Boy's Restroom adjacent to Classroom 211	Plaster Ceiling	NAD	192	SF	N/A	SF		
1	2	205B	Boy's Restroom adjacent to Classroom 211	Fiberglass Pipe Insulation	Non Suspect ACM	15	LF	N/A	LF		
1	2	205B	Boy's Restroom adjacent to Classroom 211	Ceramic Tile Wall	Non Suspect ACM	550	SF	N/A	SF		
1	2	205B	Boy's Restroom adjacent to Classroom 211	Paint associated with Wall, CMU	NAD	100	SF	N/A	SF		
1	2	205B	Boy's Restroom adjacent to Classroom 211	Expansion Seam Caulking	Assumed	20	LF	0	LF		
1	2	205B	Boy's Restroom adjacent to Classroom 211	CMU Block Wall	Non Suspect ACM	100	SF	N/A	SF		
1	2	205B	Boy's Restroom adjacent to Classroom 211	Plaster Wall	NAD	550	SF	N/A	SF		
1	2	205B	Boy's Restroom adjacent to Classroom 211	Paint associated with Floor, Concrete	Assumed	192	SF	0	SF		
1	2	205B	Boy's Restroom adjacent to Classroom 211	Concrete Floor	Non Suspect ACM	192	SF	N/A	SF		
1	2	205C	Information Technology Office	Fiberglass Pipe Insulation	Non Suspect ACM	24	LF	N/A	LF		
1	2	205C	Information Technology Office	Plaster Wall	NAD	750	SF	N/A	SF		
1	2	205C	Information Technology Office	Plaster Ceiling	NAD	210	SF	N/A	SF		
1	2	205C	Information Technology Office	Wood Floor	Non Suspect ACM	210	SF	N/A	SF		
1	2	206	Office 206	Fireproofing	NAD	12	SF	N/A	SF		
1	2	206	Office 206	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		
1	2	206	Office 206	Fiberglass Duct Insulation	Non Suspect ACM	40	SF	N/A	SF		
1	2	206	Office 206	CMU Block Wall	Non Suspect ACM	144	SF	N/A	SF		
1	2	206	Office 206	Concrete Ceiling	Non Suspect ACM	185	SF	N/A	SF		
1	2	206	Office 206	Plaster Ceiling	NAD	185	SF	N/A	SF		
1	2	206	Office 206	Paint associated with Wall, CMU	NAD	48	SF	N/A	SF		
1	2	206	Office 206	Expansion Seam Caulking	Assumed	300	LF	0	LF		
1	2	206	Office 206	CMU Block Wall	Non Suspect ACM	480	SF	N/A	SF		
1	2	206	Office 206	Ceiling Tile 2' x 4'	NAD	185	SF	N/A	SF		
1	2	206	Office 206	Floor Tile VAT 12" x 12"	Assumed	185	SF	0	SF	White	
1	2	206A	School Counselor	Duct Work	Non Suspect ACM	30	LF	N/A	LF		
1	2	206A	School Counselor	Fiberglass Duct Insulation	Non Suspect ACM	60	SF	N/A	SF		
1	2	206A	School Counselor	Fiberglass Pipe Insulation	Non Suspect ACM	8	LF	N/A	LF		
1	2	206A	School Counselor	Carpet	Non Suspect ACM	120	SF	N/A	SF		
1	2	206A	School Counselor	CMU Block Wall	Non Suspect ACM	680	SF	N/A	SF		
1	2	206A	School Counselor	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	2	EA	N/A	EA		
1	2	206A	School Counselor	Paint associated with Wall, CMU	NAD	680	SF	N/A	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	2	206A	School Counselor	Concrete Ceiling	Non Suspect ACM	120	SF	N/A	SF		
1	2	206A	School Counselor	Paint associated with Ceiling, Concrete	NAD	120	SF	N/A	SF		
1	2	207	Classroom 207	Concrete Ceiling	Non Suspect ACM	315	SF	N/A	SF		
1	2	207	Classroom 207	Fiberglass Duct Insulation	Non Suspect ACM	24	SF	N/A	SF		
1	2	207	Classroom 207	Fiberglass Pipe Insulation	Non Suspect ACM	5	LF	N/A	LF		
1	2	207	Classroom 207	CMU Block Wall	Non Suspect ACM	204	SF	N/A	SF		
1	2	207	Classroom 207	Paint associated with Wall, CMU	NAD	800	SF	N/A	SF		
1	2	207	Classroom 207	Expansion Seam Caulking	Assumed	80	LF	0	LF		
1	2	207	Classroom 207	CMU Block Wall	Non Suspect ACM	800	SF	N/A	SF		
1	2	207	Classroom 207	Ceiling Tile 2' x 4'	NAD	315	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	2	207	Classroom 207	Floor Tile VAT 12" x 12"	Assumed	315	SF	0	SF	White	
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	CMU Block Wall	Non Suspect ACM	215	SF	N/A	SF		
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	Concrete Ceiling	Non Suspect ACM	250	SF	N/A	SF		
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	1	EA	N/A	EA		
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	Fiberglass Pipe Insulation	Non Suspect ACM	3	LF	N/A	LF		
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	Sheetrock/Joint Compound Wall	NAD	40	SF	N/A	SF		
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	Paint associated with Wall, CMU	NAD	550	SF	N/A	SF		
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	Expansion Seam Caulking	Assumed	150	LF	0	LF		
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	CMU Block Wall	Non Suspect ACM	550	SF	N/A	SF		
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	Ceiling Tile 2' x 4'	NAD	250	SF	N/A	SF		
1	2	207A	Camelot (Hallway) in front of Classroom 207 & Haworth Stairwell C	Floor Tile VAT 12" x 12"	Assumed	250	SF	0	SF	White	
1	2	208	Science Lab Classroom 208	Fiberglass Pipe Insulation	Non Suspect ACM	30	LF	N/A	LF		
1	2	208	Science Lab Classroom 208	CMU Block Wall	Non Suspect ACM	408	SF	N/A	SF		
1	2	208	Science Lab Classroom 208	Fiberglass Duct Insulation	Non Suspect ACM	120	SF	N/A	SF		
1	2	208	Science Lab Classroom 208	Concrete Ceiling	Non Suspect ACM	1050	SF	N/A	SF		
1	2	208	Science Lab Classroom 208	Sink Undercoat Mastic associated with Sink	Assumed	4	SF	0	SF	Black	
1	2	208	Science Lab Classroom 208	Mastic associated with Floor Tile	NAD	1050	SF	N/A	SF		2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	2	208	Science Lab Classroom 208	Ceiling Tile 2' x 4'	NAD	1050	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	2	208	Science Lab Classroom 208	Paint associated with Wall, CMU	NAD	1600	SF	N/A	SF		
1	2	208	Science Lab Classroom 208	Expansion Seam Caulking	Assumed	984	LF	0	LF		
1	2	208	Science Lab Classroom 208	CMU Block Wall	Non Suspect ACM	1600	SF	N/A	SF		
1	2	208	Science Lab Classroom 208	Floor Tile VAT 12" x 12"	NAD	1050	SF	N/A	SF	White	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	2	208A	Classroom 208 Storage Room in Rear	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	10	EA	N/A	EA		
1	2	208A	Classroom 208 Storage Room in Rear	Concrete Ceiling	Non Suspect ACM	550	SF	N/A	SF		
1	2	208A	Classroom 208 Storage Room in Rear	Concrete Floor	Non Suspect ACM	215	SF	N/A	SF		
1	2	208A	Classroom 208 Storage Room in Rear	Fiberglass Duct Insulation	Non Suspect ACM	80	SF	N/A	SF		
1	2	208A	Classroom 208 Storage Room in Rear	Fiberglass Pipe Insulation	Non Suspect ACM	50	LF	N/A	LF		
1	2	208A	Classroom 208 Storage Room in Rear	Expansion Seam Caulking	Assumed	984	LF	0	LF		
1	2	208A	Classroom 208 Storage Room in Rear	CMU Block Wall	Non Suspect ACM	750	SF	N/A	SF		
1	2	208B	Classroom 208 Closet in Storage Room in Rear	Expansion Seam Caulking	Assumed	150	LF	0	LF		
1	2	208B	Classroom 208 Closet in Storage Room in Rear	CMU Block Wall	Non Suspect ACM	170	SF	N/A	SF		
1	2	208B	Classroom 208 Closet in Storage Room in Rear	Concrete Ceiling	Non Suspect ACM	10	SF	N/A	SF		
1	2	208B	Classroom 208 Closet in Storage Room in Rear	Paint associated with Floor, Concrete	Assumed	10	SF	0	SF		
1	2	208B	Classroom 208 Closet in Storage Room in Rear	Concrete Floor	Non Suspect ACM	10	SF	N/A	SF		
1	2	209	Classroom 209	Fiberglass Pipe Insulation	Non Suspect ACM	24	LF	N/A	LF		
1	2	209	Classroom 209	Plaster Wall	NAD	1100	SF	N/A	SF		
1	2	209	Classroom 209	Plaster Ceiling	NAD	675	SF	N/A	SF		
1	2	209	Classroom 209	Floor Tile VAT 12" x 12"	Assumed	675	SF	0	SF	Multi	
1	2	209A	Classroom 209 Coat Room	Paint associated with Wall, CMU	NAD	75	SF	N/A	SF		
1	2	209A	Classroom 209 Coat Room	CMU Block Wall	Non Suspect ACM	75	SF	N/A	SF		
1	2	209A	Classroom 209 Coat Room	Plaster Wall	NAD	450	SF	N/A	SF		
1	2	209A	Classroom 209 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	2	209A	Classroom 209 Coat Room	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	2	210	Classroom 210	Fiberglass Pipe Insulation	Non Suspect ACM	25	LF	N/A	LF		
1	2	210	Classroom 210	Plaster Wall	NAD	400	SF	N/A	SF		
1	2	210	Classroom 210	Plaster Ceiling	NAD	660	SF	N/A	SF		
1	2	210	Classroom 210	Floor Tile VAT 12" x 12"	Assumed	660	SF	0	SF	Multi	
1	2	210A	Teacher's Lounge Restroom (closest to windows)	Plaster Ceiling	NAD	50	SF	N/A	SF		
1	2	210A	Teacher's Lounge Restroom (closest to windows)	Sheetrock/Joint Compound Wall	NAD	60	SF	N/A	SF		
1	2	210A	Teacher's Lounge Restroom (closest to windows)	Fiberglass Duct Insulation	Non Suspect ACM	20	SF	N/A	SF		
1	2	210A	Teacher's Lounge Restroom (closest to windows)	Sheetrock/Joint Compound Wall	NAD	300	SF	N/A	SF		
1	2	210A	Teacher's Lounge Restroom (closest to windows)	Ceiling Tile 2' x 4'	NAD	50	SF	N/A	SF		
1	2	210A	Teacher's Lounge Restroom (closest to windows)	Floor Tile VAT 12" x 12"	Assumed	50	SF	0	SF	Blue	
1	2	210B	Teacher's Lounge Restroom (closest to hallway)	Plaster Ceiling	NAD	50	SF	N/A	SF		
1	2	210B	Teacher's Lounge Restroom (closest to hallway)	Sheetrock/Joint Compound Wall	NAD	60	SF	N/A	SF		



Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	2	210B	Teacher's Lounge Restroom (closest to hallway)	Fiberglass Duct Insulation	Non Suspect ACM	20	SF	N/A	SF		
1	2	210B	Teacher's Lounge Restroom (closest to hallway)	Sheetrock/Joint Compound Wall	NAD	300	SF	N/A	SF		
1	2	210B	Teacher's Lounge Restroom (closest to hallway)	Ceiling Tile 2' x 4'	NAD	50	SF	N/A	SF		
1	2	210B	Teacher's Lounge Restroom (closest to hallway)	Floor Tile VAT 12" x 12"	Assumed	50	SF	0	SF	Blue	
1	2	210C	Teacher's Lounge	Wood Floor	Non Suspect ACM	550	SF	N/A	SF		
1	2	210C	Teacher's Lounge	Sheetrock/Joint Compound Wall	NAD	290	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CR!
1	2	210C	Teacher's Lounge	Plaster Wall	NAD	850	SF	N/A	SF		
1	2	210C	Teacher's Lounge	Plaster Ceiling	NAD	550	SF	N/A	SF		
1	2	210D	Special Education Classroom across from Classroom 210	Brick Wall	Non Suspect ACM	210	SF	N/A	SF		
1	2	210D	Special Education Classroom across from Classroom 210	Paint associated with Ceiling, Concrete	NAD	130	SF	N/A	SF		
1	2	210D	Special Education Classroom across from Classroom 210	Laminate Floor	Non Suspect ACM	260	SF	N/A	SF		
1	2	210D	Special Education Classroom across from Classroom 210	Sheetrock/Joint Compound Wall	NAD	700	SF	N/A	SF		
1	2	210D	Special Education Classroom across from Classroom 210	Ceiling Tile 2' x 4'	NAD	260	SF	N/A	SF		
1	2	210D	Special Education Classroom across from Classroom 210	Metal Ceiling	Non Suspect ACM	130	SF	N/A	SF		
1	2	210D	Special Education Classroom across from Classroom 210	Concrete Ceiling	Non Suspect ACM	130	SF	N/A	SF		
1	2	211	Classroom 211	Fiberglass Pipe Insulation	Non Suspect ACM	8	LF	N/A	LF		
1	2	211	Classroom 211	Pipe Fitting Insulation	Confirmed	4	EA	0	EA		
1	2	211	Classroom 211	Pipe Insulation 2-6 inch	Confirmed	15	LF	1	LF		
1	2	211	Classroom 211	Plaster Wall	NAD	700	SF	N/A	SF		
1	2	211	Classroom 211	Plaster Ceiling	NAD	650	SF	N/A	SF		
1	2	211	Classroom 211	Leveling Compound associated with Floor Tile	NAD	650	SF	N/A	SF	Grey	
1	2	211	Classroom 211	Mastic associated with Floor Tile	Assumed	650	SF	0	SF	White	
1	2	211	Classroom 211	Floor Tile VAT 12" x 12"	Assumed	650	SF	0	SF	Blue	
1	2	211A	Classroom 211 Coat Room	Plaster Wall	NAD	500	SF	N/A	SF		
1	2	211A	Classroom 211 Coat Room	Pipe Fitting Insulation	Confirmed	4	EA	0	EA		
1	2	211A	Classroom 211 Coat Room	Pipe Insulation 2-6 inch	Confirmed	14	LF	1	LF		
1	2	211A	Classroom 211 Coat Room	Plaster Ceiling	NAD	135	SF	N/A	SF		
1	2	211A	Classroom 211 Coat Room	Floor Tile VAT 12" x 12"	Assumed	135	SF	0	SF	Multi	
1	2	212	Classroom 212	Mastic associated with Floor Tile	Assumed	675	SF	0	SF	Yellow	
1	2	212	Classroom 212	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	2	212	Classroom 212	Glue Dots associated with Blackboard	Assumed	10	SF	0	SF		
1	2	212	Classroom 212	Plaster Wall	NAD	1250	SF	N/A	SF		
1	2	212	Classroom 212	Plaster Ceiling	NAD	675	SF	N/A	SF		
1	2	212	Classroom 212	Floor Tile VAT 12" x 12"	Assumed	675	SF	0	SF	Multi	
1	2	212A	Classroom 212 Closet	Mastic associated with Floor Tile	Assumed	32	SF	0	SF	Yellow	
1	2	212A	Classroom 212 Closet	Pipe Fitting Insulation	Confirmed	4	EA	0	EA		
1	2	212A	Classroom 212 Closet	Pipe Fitting Insulation	Confirmed	20	EA	0	EA		
1	2	212A	Classroom 212 Closet	Pipe Insulation 2-6 inch	Confirmed	20	LF	1	LF		
1	2	212A	Classroom 212 Closet	Plaster Wall	NAD	200	SF	N/A	SF		
1	2	212A	Classroom 212 Closet	Plaster Ceiling	NAD	32	SF	N/A	SF		
1	2	212A	Classroom 212 Closet	Floor Tile VAT 12" x 12"	Assumed	32	SF	0	SF	Multi	
1	2	212B	Classroom 212 Coat Room	Fiberglass Pipe Insulation	Non Suspect ACM	9	LF	N/A	LF		
1	2	212B	Classroom 212 Coat Room	Mastic associated with Floor Tile	Assumed	75	SF	0	SF	Yellow	
1	2	212B	Classroom 212 Coat Room	Plaster Wall	NAD	400	SF	N/A	SF		
1	2	212B	Classroom 212 Coat Room	Plaster Ceiling	NAD	75	SF	N/A	SF		
1	2	212B	Classroom 212 Coat Room	Floor Tile VAT 12" x 12"	Assumed	75	SF	0	SF	Multi	
1	2	250	Book Closet adjacent to Classroom 211	Plaster Wall	NAD	300	SF	N/A	SF		
1	2	250	Book Closet adjacent to Classroom 211	Plaster Ceiling	NAD	42	SF	N/A	SF		
1	2	250	Book Closet adjacent to Classroom 211	Concrete Floor	Non Suspect ACM	42	SF	N/A	SF		
1	2	251	Custodial Closet across from Classroom 202	Fiberglass Pipe Insulation	Non Suspect ACM	15	LF	N/A	LF		
1	2	251	Custodial Closet across from Classroom 202	Pipe Fitting Insulation	Confirmed	2	EA	0	EA		
1	2	251	Custodial Closet across from Classroom 202	Pipe Insulation 2-6 inch	Confirmed	17	LF	0	LF		
1	2	251	Custodial Closet across from Classroom 202	Pipe Insulation >6 inches	Confirmed	12	LF	0	LF		
1	2	251	Custodial Closet across from Classroom 202	Plaster Wall	NAD	350	SF	N/A	SF		
1	2	251	Custodial Closet across from Classroom 202	Plaster Ceiling	NAD	45	SF	N/A	SF		
1	2	251	Custodial Closet across from Classroom 202	Paint associated with Floor, Concrete	Assumed	45	SF	0	SF		
1	2	251	Custodial Closet across from Classroom 202	Concrete Floor	Non Suspect ACM	45	SF	N/A	SF		
1	2	252	Storage Closet Across from Classrom 201	Plaster Wall	NAD	435	SF	N/A	SF		
1	2	252	Storage Closet Across from Classrom 201	Plaster Ceiling	NAD	48	SF	N/A	SF		
1	2	252	Storage Closet Across from Classrom 201	Paint associated with Floor, Concrete	Assumed	48	SF	0	SF		
1	2	252	Storage Closet Across from Classroom 201	Concrete Floor	Non Suspect ACM	48	SF	N/A	SF		
1	2	27A	Custodial Closet adjacent to S24	Concrete Ceiling	Non Suspect ACM	100	SF	N/A	SF		
1	2	27A	Custodial Closet adjacent to S24	Concrete Floor	Non Suspect ACM	100	SF	N/A	SF		
1	2	27A	Custodial Closet adjacent to S24	Expansion Seam Caulking	Assumed	90	LF	0	LF		
1	2	27A	Custodial Closet adjacent to S24	CMU Block Wall	Non Suspect ACM	540	SF	N/A	SF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	CMU Block Wall	Non Suspect ACM	90	SF	N/A	SF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	Fiberglass Pipe Insulation	Non Suspect ACM	2	LF	N/A	LF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	Concrete Ceiling	Non Suspect ACM	45	SF	N/A	SF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	Concrete Ceiling	Non Suspect ACM	45	SF	N/A	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	2	27B	Girl's Restroom adjacent to Classroom 209	Paint associated with Ceiling, Concrete	NAD	45	SF	N/A	SF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	Ceramic Tile Floor	Non Suspect ACM	45	SF	N/A	SF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	Paint associated with Floor, Concrete	Assumed	240	SF	0	SF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	Paint associated with Wall, CMU	NAD	240	SF	N/A	SF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	Expansion Seam Caulking	Assumed	90	LF	0	LF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	CMU Block Wall	Non Suspect ACM	240	SF	N/A	SF		
1	2	27B	Girl's Restroom adjacent to Classroom 209	Ceiling Tile 2' x 4'	NAD	45	SF	N/A	SF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	CMU Block Wall	Non Suspect ACM	192	SF	N/A	SF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	Concrete Ceiling	Non Suspect ACM	250	SF	N/A	SF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	Ceramic Tile Wall	Non Suspect ACM	500	SF	N/A	SF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	Ceramic Tile Floor	Non Suspect ACM	250	SF	N/A	SF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	Ceiling Tile 2' x 4'	NAD	250	SF	N/A	SF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	Paint associated with Wall, CMU	NAD	600	SF	N/A	SF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	Expansion Seam Caulking	Assumed	60	LF	0	LF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	CMU Block Wall	Non Suspect ACM	215	SF	N/A	SF		
1	2	27C	Boy's Restroom adjacent to Classroom 208	Metal Ceiling	Non Suspect ACM	240	SF	N/A	SF		
1	2	29A	Girl's Restroom adjacent to Classroom 204	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	2	29A	Girl's Restroom adjacent to Classroom 204	Concrete Ceiling	Non Suspect ACM	240	SF	N/A	SF		
1	2	29A	Girl's Restroom adjacent to Classroom 204	CMU Block Wall	Non Suspect ACM	192	SF	N/A	SF		
1	2	29A	Girl's Restroom adjacent to Classroom 204	CMU Block Wall	Non Suspect ACM	215	SF	N/A	SF		
1	2	29A	Girl's Restroom adjacent to Classroom 204	Paint associated with Wall, CMU	NAD	215	SF	N/A	SF		
1	2	29A	Girl's Restroom adjacent to Classroom 204	Ceiling Tile 2' x 4'	NAD	240	SF	N/A	SF		
1	2	29A	Girl's Restroom adjacent to Classroom 204	Ceramic Tile Wall	Non Suspect ACM	435	SF	N/A	SF		
1	2	29A	Girl's Restroom adjacent to Classroom 204	Ceramic Tile Floor	Non Suspect ACM	240	SF	N/A	SF		
1	2	29B	Staff Restroom adjacent to Classroom 204	CMU Block Wall	Non Suspect ACM	84	SF	N/A	SF		
1	2	29B	Staff Restroom adjacent to Classroom 204	Concrete Ceiling	Non Suspect ACM	50	SF	N/A	SF		
1	2	29B	Staff Restroom adjacent to Classroom 204	Paint associated with Wall, CMU	NAD	240	SF	N/A	SF		
1	2	29B	Staff Restroom adjacent to Classroom 204	CMU Block Wall	Non Suspect ACM	240	SF	N/A	SF		
1	2	29B	Staff Restroom adjacent to Classroom 204	Ceiling Tile 2' x 4'	NAD	50	SF	N/A	SF		
1	2	29B	Staff Restroom adjacent to Classroom 204	Ceramic Tile Floor	Non Suspect ACM	50	SF	N/A	SF		
1	2	29C	Custodial Closet adjacent to Classroom 204	Fiberglass Pipe Insulation	Non Suspect ACM	40	LF	N/A	LF		
1	2	29C	Custodial Closet adjacent to Classroom 204	Paint associated with Wall, CMU	NAD	435	SF	N/A	SF		
1	2	29C	Custodial Closet adjacent to Classroom 204	Expansion Seam Caulking	Assumed	245	LF	0	LF		
1	2	29C	Custodial Closet adjacent to Classroom 204	CMU Block Wall	Non Suspect ACM	435	SF	N/A	SF		
1	2	29C	Custodial Closet adjacent to Classroom 204	Paint associated with Ceiling, Concrete	NAD	60	SF	N/A	SF		
1	2	29C	Custodial Closet adjacent to Classroom 204	Concrete Ceiling	Non Suspect ACM	60	SF	N/A	SF		
1	2	29C	Custodial Closet adjacent to Classroom 204	Paint associated with Floor, Concrete	Assumed	60	SF	0	SF		
1	2	29C	Custodial Closet adjacent to Classroom 204	Concrete Floor	Non Suspect ACM	60	SF	N/A	SF		
1	2	H204A	Hallway at Telecommunications Room	Wood Floor	Non Suspect ACM	12	SF	N/A	SF		
1	2	H204A	Hallway at Telecommunications Room	Plaster Wall	NAD	800	SF	N/A	SF		
1	2	H204A	Hallway at Telecommunications Room	Plaster Ceiling	NAD	120	SF	N/A	SF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Concrete Ceiling	Non Suspect ACM	870	SF	N/A	SF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	CMU Block Wall	Non Suspect ACM	510	SF	N/A	SF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Fireproofing	NAD	10	SF	N/A	SF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Fiberglass Pipe Insulation	Non Suspect ACM	85	LF	N/A	LF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Ceiling Tile 2' x 4'	NAD	870	SF	N/A	SF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Fiberglass Pipe Insulation	Non Suspect ACM	40	LF	N/A	LF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Plaster Wall	NAD	3880	SF	N/A	SF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Plaster Ceiling	NAD	1110	SF	N/A	SF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Paint associated with Floor, Concrete	Assumed	990	SF	0	SF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Concrete Floor	Non Suspect ACM	2000	SF	N/A	SF		
1	2	H27	Hallway from Classroom 207 to Classroom 212	Leveiling Compound associated with Floor Tile	NAD	950	SF	N/A	SF	Grey	
1	2	H27	Hallway from Classroom 207 to Classroom 212	Mastic associated with Floor Tile	NAD	950	SF	N/A	SF	Yellow	1 Sample Collected-Sampled NAD 6/12/2019 Syn/BB. 1 sample floor tile and 1 sample mastic NAD 3/9/2023 TF/CRI
1	2	H27	Hallway from Classroom 207 to Classroom 212	Floor Tile VAT 12" x 12"	NAD	950	SF	N/A	SF	White	1 Sample Collected-Sampled NAD 6/12/2019 Syn/BB. 1 sample floor tile and 1 sample mastic NAD 3/9/2023 TF/CRI
1	2	H28	Hallway from Classroom 212 to 202	Fiberglass Pipe Insulation	Non Suspect ACM	55	LF	N/A	LF		
1	2	H28	Hallway from Classroom 212 to 202	Plaster Wall	NAD	2100	SF	N/A	SF		
1	2	H28	Hallway from Classroom 212 to 202	Plaster Ceiling	NAD	1056	SF	N/A	SF		
1	2	H28	Hallway from Classroom 212 to 202	Paint associated with Floor, Concrete	Assumed	1056	SF	0	SF		
1	2	H28	Hallway from Classroom 212 to 202	Concrete Floor	Non Suspect ACM	1056	SF	N/A	SF		
1	2	H29	Hallway at Classroom 203	Plaster Ceiling	NAD	550	SF	N/A	SF		
1	2	H29	Hallway at Classroom 203	Fiberglass Duct Insulation	Non Suspect ACM	360	SF	N/A	SF		
1	2	H29	Hallway at Classroom 203	Plaster Wall	NAD	330	SF	N/A	SF		
1	2	H29	Hallway at Classroom 203	Ceiling Tile 2' x 4'	NAD	550	SF	N/A	SF		
1	2	H29	Hallway at Classroom 203	Fiberglass Pipe Insulation	Non Suspect ACM	30	LF	N/A	LF		
1	2	H29	Hallway at Classroom 203	Plaster Wall	NAD	2400	SF	N/A	SF		
1	2	H29	Hallway at Classroom 203	Paint associated with Wall, CMU	NAD	9850	SF	N/A	SF		
1	2	H29	Hallway at Classroom 203	Expansion Seam Caulking	Assumed	985	LF	0	LF		
1	2	H29	Hallway at Classroom 203	Paint associated with Floor, Concrete	Assumed	2000	SF	0	SF		
1	2	H29	Hallway at Classroom 203	Concrete Floor	Non Suspect ACM	2000	SF	N/A	SF		
1	2	H29A	Hallway at Classroom 204	CMU Block Wall	Non Suspect ACM	650	SF	N/A	SF		
1	2	H29A	Hallway at Classroom 204	Fiberglass Duct Insulation	Non Suspect ACM	80	SF	N/A	SF		
1	2	H29A	Hallway at Classroom 204	Concrete Ceiling	Non Suspect ACM	1200	SF	N/A	SF		
1	2	H29A	Hallway at Classroom 204	Plaster Ceiling	NAD	1200	SF	N/A	SF		
1	2	H29A	Hallway at Classroom 204	Paint associated with Wall, CMU	NAD	2000	SF	0	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	2	H29A	Hallway at Classroom 204	Mastic associated with Floor Tile	NAD	1200	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	2	H29A	Hallway at Classroom 204	CMU Block Wall	Non Suspect ACM	2000	SF	N/A	SF		
1	2	H29A	Hallway at Classroom 204	Plaster Wall	NAD	460	SF	N/A	SF		
1	2	H29A	Hallway at Classroom 204	Fiberglass Pipe Insulation	Non Suspect ACM	40	LF	N/A	LF		
1	2	H29A	Hallway at Classroom 204	Ceiling Tile 2' x 4'	NAD	1200	SF	N/A	SF		
1	2	H29A	Hallway at Classroom 204	Floor Tile VAT 12" x 12"	NAD	1200	SF	N/A	SF	White	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	2	S21	Stairwell adjacent to Classroom 212	Fiberglass Pipe Insulation	Non Suspect ACM	22	LF	N/A	LF		
1	2	S21	Stairwell adjacent to Classroom 212	Plaster Wall	NAD	1250	SF	N/A	SF		
1	2	S21	Stairwell adjacent to Classroom 212	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	2	S21	Stairwell adjacent to Classroom 212	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	2	S21	Stairwell adjacent to Classroom 212	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	2	S22	Dyre Stairwell A adjacent to Classroom 202	Plaster Wall	NAD	1250	SF	N/A	SF		
1	2	S22	Dyre Stairwell A adjacent to Classroom 202	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	2	S22	Dyre Stairwell A adjacent to Classroom 202	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	2	S22	Dyre Stairwell A adjacent to Classroom 202	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	2	S23	Dyre Stairwell B adjacent to Computer Lab Classroom 203	Plaster Wall	NAD	1250	SF	N/A	SF		
1	2	S23	Dyre Stairwell B adjacent to Computer Lab Classroom 203	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	2	S23	Dyre Stairwell B adjacent to Computer Lab Classroom 203	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	2	S23	Dyre Stairwell B adjacent to Computer Lab Classroom 203	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	2	S24	Haworth Stairwell B adjacent to Classroom 209	Paint associated with Wall, CMU	NAD	1250	SF	N/A	SF		
1	2	S24	Haworth Stairwell B adjacent to Classroom 209	CMU Block Wall	Non Suspect ACM	1250	SF	N/A	SF		
1	2	S24	Haworth Stairwell B adjacent to Classroom 209	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	2	S24	Haworth Stairwell B adjacent to Classroom 209	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	2	S24	Haworth Stairwell B adjacent to Classroom 209	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	2	S25	Haworth Stairwell B adjacent to Classroom 207	Paint associated with Wall, CMU	NAD	1250	SF	N/A	SF		
1	2	S25	Haworth Stairwell B adjacent to Classroom 207	CMU Block Wall	Non Suspect ACM	1250	SF	N/A	SF		
1	2	S25	Haworth Stairwell B adjacent to Classroom 207	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	2	S25	Haworth Stairwell B adjacent to Classroom 207	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	2	S25	Haworth Stairwell B adjacent to Classroom 207	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	2	S26	Dyre Stairwell C adjacent to Classroom 204	CMU Block Wall	Non Suspect ACM	216	SF	N/A	SF		
1	2	S26	Dyre Stairwell C adjacent to Classroom 204	Ceiling Tile 2' x 4'	NAD	300	SF	N/A	SF		
1	2	S26	Dyre Stairwell C adjacent to Classroom 204	Concrete Ceiling	Non Suspect ACM	300	SF	N/A	SF		
1	2	S26	Dyre Stairwell C adjacent to Classroom 204	Paint associated with Wall, CMU	NAD	1250	SF	0	SF		
1	2	S26	Dyre Stairwell C adjacent to Classroom 204	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	2	S26	Dyre Stairwell C adjacent to Classroom 204	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	Fireproofing	NAD	4	SF	N/A	SF		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	Concrete Ceiling	Non Suspect ACM	360	SF	N/A	SF		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	CMU Block Wall	Non Suspect ACM	250	SF	N/A	SF		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	Fiberglass Pipe Insulation	Non Suspect ACM	6	LF	N/A	LF		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	4	EA	N/A	EA		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	Paint associated with Wall, CMU	NAD	680	SF	N/A	SF		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	Expansion Seam Caulking	Assumed	68	LF	0	LF		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	CMU Block Wall	Non Suspect ACM	680	SF	N/A	SF		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	Ceiling Tile 2' x 4'	NAD	360	SF	N/A	SF		
1	3	300	Elevator Lobby adjacent to Dyre Stairwell B	Floor Tile VAT 12" x 12"	Assumed	360	SF	0	SF	White	
1	3	300A	Elevator Lobby Restroom	CMU Block Wall	Non Suspect ACM	84	SF	N/A	SF		
1	3	300A	Elevator Lobby Restroom	Concrete Ceiling	Non Suspect ACM	65	SF	N/A	SF		
1	3	300A	Elevator Lobby Restroom	Ceramic Tile Floor	Non Suspect ACM	65	SF	N/A	SF		
1	3	300A	Elevator Lobby Restroom	Ceramic Tile Wall	Non Suspect ACM	280	SF	N/A	SF		
1	3	300A	Elevator Lobby Restroom	Paint associated with Wall, CMU	NAD	80	SF	N/A	SF		
1	3	300A	Elevator Lobby Restroom	Expansion Seam Caulking	Assumed	35	LF	0	LF		
1	3	300A	Elevator Lobby Restroom	CMU Block Wall	Non Suspect ACM	80	SF	N/A	SF		
1	3	300A	Elevator Lobby Restroom	Ceiling Tile 2' x 4'	NAD	65	SF	N/A	SF		
1	3	300B	Storage Room in Elevator Lobby	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	6	EA	N/A	EA		
1	3	300B	Storage Room in Elevator Lobby	Fiberglass Pipe Insulation	Non Suspect ACM	36	LF	N/A	LF		
1	3	300B	Storage Room in Elevator Lobby	Concrete Floor	Non Suspect ACM	60	SF	N/A	SF		
1	3	300B	Storage Room in Elevator Lobby	CMU Block Wall	Non Suspect ACM	385	SF	N/A	SF		
1	3	300B	Storage Room in Elevator Lobby	Concrete Ceiling	Non Suspect ACM	60	SF	N/A	SF		
1	3	301	Classroom 301	Floor Tile VAT 12" x 12"	NAD	675	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	301	Classroom 301	Fiberglass Pipe Insulation	Non Suspect ACM	8	LF	N/A	LF		
1	3	301	Classroom 301	Glue Dots associated with Blackboard	Assumed	20	SF	0	SF		
1	3	301	Classroom 301	Plaster Wall	NAD	1100	SF	N/A	SF		
1	3	301	Classroom 301	Plaster Ceiling	NAD	675	SF	N/A	SF		
1	3	301	Classroom 301	Mastic associated with Floor Tile	NAD	675	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	301A	Classroom 301 Coat Room	Plaster Wall	NAD	500	SF	N/A	SF		
1	3	301A	Classroom 301 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	3	301A	Classroom 301 Coat Room	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	3	301A	Classroom 301 Coat Room	Pipe Fitting Insulation	NAD	25	EA	N/A	EA		
1	3	302	Classroom 302	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	3	302	Classroom 302	Plaster Wall	NAD	750	SF	N/A	SF		
1	3	302	Classroom 302	Plaster Ceiling	NAD	655	SF	N/A	SF		
1	3	302	Classroom 302	Mastic associated with Floor Tile	Assumed	655	SF	0	SF	Yellow	
1	3	302	Classroom 302	Floor Tile VAT 12" x 12"	Assumed	655	SF	0	SF	Blue	
1	3	302A	Special Education Classroom across from Classroom 306	Concrete Ceiling	Non Suspect ACM	276	SF	N/A	SF		
1	3	302A	Special Education Classroom across from Classroom 306	Paint associated with Ceiling, Concrete	NAD	276	SF	N/A	SF		
1	3	302A	Special Education Classroom across from Classroom 306	Brick Wall	Non Suspect ACM	228	SF	N/A	SF		
1	3	302A	Special Education Classroom across from Classroom 306	Wood Floor	Non Suspect ACM	276	SF	N/A	SF		
1	3	302A	Special Education Classroom across from Classroom 306	Sheetrock/Joint Compound Wall	NAD	600	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	3	302A	Special Education Classroom across from Classroom 306	Ceiling Tile 2' x 4'	NAD	276	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	3	302B	Classroom 302 Coat Room	Mastic associated with Floor Tile	Assumed	155	SF	0	SF		
1	3	302B	Classroom 302 Coat Room	Fiberglass Pipe Insulation	Non Suspect ACM	12	LF	N/A	LF		
1	3	302B	Classroom 302 Coat Room	Plaster Wall	NAD	550	SF	N/A	SF		
1	3	302B	Classroom 302 Coat Room	Plaster Ceiling	NAD	155	SF	N/A	SF		
1	3	302B	Classroom 302 Coat Room	Floor Tile VAT 12" x 12"	Assumed	155	SF	0	SF	Multi	
1	3	303	Classroom 303	Mastic associated with Floor Tile	Assumed	720	SF	0	SF		
1	3	303	Classroom 303	Sink Undercoat Mastic associated with Sink	Assumed	2	SF	0	SF	Black	
1	3	303	Classroom 303	Fiberglass Pipe Insulation	Non Suspect ACM	8	LF	N/A	LF		
1	3	303	Classroom 303	Plaster Wall	NAD	650	SF	N/A	SF		
1	3	303	Classroom 303	Plaster Ceiling	NAD	720	SF	N/A	SF		
1	3	303	Classroom 303	Floor Tile VAT 12" x 12"	Assumed	720	SF	0	SF	Multi	
1	3	303A	Classroom 303A coat closet	Carpet	Non Suspect ACM	265	SF	N/A	SF		
1	3	303A	Classroom 303A coat closet	Sheetrock/Joint Compound Wall	NAD	660	SF	N/A	SF		
1	3	303A	Classroom 303A coat closet	Plaster Ceiling	NAD	265	SF	N/A	SF		
1	3	303B	Office 303A	Concrete Ceiling	Non Suspect ACM	260	SF	N/A	SF		
1	3	303B	Office 303A	Sheetrock/Joint Compound Wall	NAD	228	SF	N/A	SF		
1	3	303B	Office 303A	Paint associated with Ceiling, Concrete	NAD	260	SF	N/A	SF		
1	3	303B	Office 303A	Sheetrock/Joint Compound Wall	NAD	660	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	3	303B	Office 303A	Ceiling Tile 2' x 4'	NAD	260	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	3	303B	Office 303A	Carpet	Non Suspect ACM	260	SF	N/A	SF		
1	3	304	Classroom 304	Mastic associated with Floor Tile	Assumed	675	SF	0	SF		
1	3	304	Classroom 304	Fiberglass Pipe Insulation	Non Suspect ACM	8	LF	N/A	LF		
1	3	304	Classroom 304	Plaster Wall	NAD	750	SF	N/A	SF		
1	3	304	Classroom 304	Plaster Ceiling	NAD	675	SF	N/A	SF		
1	3	304	Classroom 304	Floor Tile VAT 12" x 12"	Assumed	675	SF	0	SF	Multi	
1	3	304A	Classroom 304 Coat Room	Mastic associated with Floor Tile	Assumed	100	SF	0	SF		
1	3	304A	Classroom 304 Coat Room	Plaster Wall	NAD	530	SF	N/A	SF		
1	3	304A	Classroom 304 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	3	304A	Classroom 304 Coat Room	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	3	305	Classroom 305	Sheetrock/Joint Compound Wall	NAD	575	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	3	305	Classroom 305	Plaster Wall	NAD	336	SF	N/A	SF		
1	3	305	Classroom 305	Plaster Ceiling	NAD	335	SF	N/A	SF		
1	3	305	Classroom 305	Floor Tile VAT 12" x 12"	Assumed	335	SF	0	SF	Multi	
1	3	305A	Classroom 305 A	Concrete Ceiling	Non Suspect ACM	380	SF	N/A	SF		
1	3	305A	Classroom 305 A	CMU Block Wall	Non Suspect ACM	132	SF	N/A	SF		
1	3	305A	Classroom 305 A	CMU Block Wall	Non Suspect ACM	900	SF	N/A	SF		
1	3	305A	Classroom 305 A	Sheetrock/Joint Compound Wall	NAD	100	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	3	305A	Classroom 305 A	Paint associated with Wall, CMU	NAD	800	SF	N/A	SF		
1	3	305A	Classroom 305 A	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	3	EA	N/A	EA		
1	3	305A	Classroom 305 A	Ceiling Tile 2' x 4'	NAD	380	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	3	305A	Classroom 305 A	Mastic associated with Floor Tile	NAD	380	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	305A	Classroom 305 A	Fiberglass Pipe Insulation	Non Suspect ACM	8	LF	N/A	LF		
1	3	305A	Classroom 305 A	Plaster Ceiling	NAD	380	SF	N/A	SF		
1	3	305A	Classroom 305 A	Floor Tile VAT 12" x 12"	NAD	380	SF	N/A	SF	White	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	305B	Classroom 305 A Office	Duct Work associated with Active	Non Suspect ACM	25	LF	N/A	LF		
1	3	305B	Classroom 305 A Office	Paint associated with Wall, CMU	NAD	390	SF	N/A	SF		
1	3	305B	Classroom 305 A Office	Expansion Seam Caulking	Assumed	225	LF	0	LF		
1	3	305B	Classroom 305 A Office	CMU Block Wall	Non Suspect ACM	460	SF	N/A	SF		
1	3	305B	Classroom 305 A Office	Concrete Ceiling	Non Suspect ACM	80	SF	N/A	SF		
1	3	305B	Classroom 305 A Office	Carpet	Non Suspect ACM	80	SF	N/A	SF		
1	3	305C	Classroom 305 A Restroom	CMU Block Wall	Non Suspect ACM	100	SF	N/A	SF		
1	3	305C	Classroom 305 A Restroom	Concrete Ceiling	Non Suspect ACM	120	SF	N/A	SF		
1	3	305C	Classroom 305 A Restroom	CMU Block Wall	Non Suspect ACM	115	SF	N/A	SF		
1	3	305C	Classroom 305 A Restroom	Paint associated with Wall, CMU	NAD	115	SF	N/A	SF		
1	3	305C	Classroom 305 A Restroom	Ceramic Tile Wall	Non Suspect ACM	280	SF	N/A	SF		
1	3	305C	Classroom 305 A Restroom	Ceiling Tile 2' x 4'	NAD	120	SF	N/A	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	3	305C	Classroom 305 A Restroom	Ceramic Tile Floor	Non Suspect ACM	120	SF	N/A	SF		
1	3	306	Classroom 306	Glue Dots associated with Blackboard	Assumed	45	SF	0	SF		
1	3	306	Classroom 306	Radiator associated with Active	Non Suspect ACM	10	EA	N/A	EA		
1	3	306	Classroom 306	Fiberglass Pipe Insulation	Non Suspect ACM	8	LF	N/A	LF		
1	3	306	Classroom 306	Plaster Wall	NAD	320	SF	N/A	SF		
1	3	306	Classroom 306	Plaster Ceiling	NAD	760	SF	N/A	SF		
1	3	306	Classroom 306	Floor Tile VAT 12" x 12"	Assumed	760	SF	0	SF	Multi	
1	3	307	Classroom 307	Floor Tile VAT 12" x 12"	NAD	670	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	307	Classroom 307	Sheetrock/Joint Compound Wall	NAD	300	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	3	307	Classroom 307	Mastic associated with Floor Tile	NAD	670	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	307	Classroom 307	Radiator	Non Suspect ACM	10	EA	N/A	EA		
1	3	307	Classroom 307	Fiberglass Pipe Insulation	Non Suspect ACM	17	LF	N/A	LF		
1	3	307	Classroom 307	Glue Dots associated with Blackboard	Assumed	30	SF	0	SF		
1	3	307	Classroom 307	Plaster Wall	NAD	900	SF	N/A	SF		
1	3	307	Classroom 307	Plaster Ceiling	NAD	670	SF	N/A	SF		
1	3	308	Classroom 308	Mastic associated with Floor Tile	NAD	675	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	308	Classroom 308	Radiator	Non Suspect ACM	10	EA	N/A	EA		
1	3	308	Classroom 308	Fiberglass Pipe Insulation	Non Suspect ACM	8	LF	N/A	LF		
1	3	308	Classroom 308	Glue Dots associated with Blackboard	Assumed	20	SF	0	SF		
1	3	308	Classroom 308	Plaster Wall	NAD	1100	SF	N/A	SF		
1	3	308	Classroom 308	Plaster Ceiling	NAD	675	SF	N/A	SF		
1	3	308	Classroom 308	Floor Tile VAT 12" x 12"	NAD	675	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	308B	Classroom 308 Coat Room	Fiberglass Pipe Insulation	Non Suspect ACM	7	LF	N/A	LF		
1	3	308B	Classroom 308 Coat Room	Plaster Wall	NAD	550	SF	N/A	SF		
1	3	308B	Classroom 308 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	3	308B	Classroom 308 Coat Room	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	3	309	Classroom 309	Radiator	Non Suspect ACM	20	EA	N/A	EA		
1	3	309	Classroom 309	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	3	309	Classroom 309	Glue Dots associated with Blackboard	Assumed	10	SF	0	SF		
1	3	309	Classroom 309	Plaster Wall	NAD	1100	SF	N/A	SF		
1	3	309	Classroom 309	Plaster Ceiling	NAD	700	SF	N/A	SF		
1	3	309	Classroom 309	Floor Tile VAT 12" x 12"	Assumed	700	SF	0	SF	Multi	
1	3	309A	Classroom 309 Coat Room	Plaster Wall	NAD	400	SF	N/A	SF		
1	3	309A	Classroom 309 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	3	309A	Classroom 309 Coat Room	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	3	310	Classroom 310	Pipe Insulation 2-6 inch	Confirmed	12	LF	0	LF		3 samples Confirmed 3/9/2023 TF/CRI
1	3	310	Classroom 310	Glue Dots associated with Blackboard	Assumed	20	SF	0	SF		
1	3	310	Classroom 310	Plaster Wall	NAD	1400	SF	N/A	SF		
1	3	310	Classroom 310	Plaster Ceiling	NAD	690	SF	N/A	SF		
1	3	310	Classroom 310	Floor Tile VAT 12" x 12"	Assumed	690	SF	0	SF	Multi	
1	3	310A	Boy's Restroom adjacent to Classroom 308	Radiator	Non Suspect ACM	5	EA	N/A	EA		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Duct Work	Non Suspect ACM	15	LF	N/A	LF		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	1	EA	N/A	EA		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Ceramic Tile Wall	Non Suspect ACM	450	SF	N/A	SF		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Paint associated with Wall, CMU	NAD	100	SF	N/A	SF		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Expansion Seam Caulking	Assumed	10	LF	0	LF		
1	3	310A	Boy's Restroom adjacent to Classroom 308	CMU Block Wall	Non Suspect ACM	100	SF	N/A	SF		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Plaster Wall	NAD	350	SF	N/A	SF		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Plaster Ceiling	NAD	150	SF	N/A	SF		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Paint associated with Floor, Concrete	NAD	150	SF	N/A	SF		
1	3	310A	Boy's Restroom adjacent to Classroom 308	Concrete Floor	Non Suspect ACM	150	SF	N/A	SF		
1	3	310B	Classroom 310 Coat Room	Plaster Wall	NAD	500	SF	N/A	SF		
1	3	310B	Classroom 310 Coat Room	Plaster Ceiling	NAD	130	SF	N/A	SF		
1	3	310B	Classroom 310 Coat Room	Floor Tile VAT 12" x 12"	Assumed	130	SF	0	SF	Multi	
1	3	311	Classroom 311	Sink Undercoat Mastic	Assumed	2	SF	0	SF	Black	
1	3	311	Classroom 311	Mastic associated with Floor Tile	NAD	755	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	311	Classroom 311	Fiberglass Pipe Insulation	Non Suspect ACM	32	LF	N/A	LF		
1	3	311	Classroom 311	Glue Dots associated with Blackboard	Assumed	20	SF	0	SF		
1	3	311	Classroom 311	Plaster Wall	NAD	1350	SF	N/A	SF		
1	3	311	Classroom 311	Plaster Ceiling	NAD	755	SF	N/A	SF		
1	3	311	Classroom 311	Floor Tile VAT 12" x 12"	NAD	755	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	3	311A	Copy Room	Plaster Wall	NAD	300	SF	N/A	SF		
1	3	311A	Copy Room	Plaster Ceiling	NAD	48	SF	N/A	SF		
1	3	311A	Copy Room	Paint associated with Floor, Concrete	NAD	48	SF	N/A	SF		
1	3	311A	Copy Room	Concrete Floor	Non Suspect ACM	48	SF	N/A	SF		
1	3	311B	Classroom 311 Coat Room	Plaster Wall	NAD	450	SF	N/A	SF		
1	3	311B	Classroom 311 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	3	311B	Classroom 311 Coat Room	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	3	312	Classroom 312	Fiberglass Pipe Insulation	Non Suspect ACM	30	LF	N/A	LF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	3	312	Classroom 312	Glue Dots associated with Blackboard	Assumed	20	SF	0	SF		
1	3	312	Classroom 312	Plaster Wall	NAD	1100	SF	N/A	SF		
1	3	312	Classroom 312	Plaster Ceiling	NAD	690	SF	N/A	SF		
1	3	312	Classroom 312	Floor Tile VAT 12" x 12"	Assumed	690	SF	0	SF	Multi	
1	3	312A	Classroom 312 Coat Room	Plaster Wall	NAD	500	SF	N/A	SF		
1	3	312A	Classroom 312 Coat Room	Plaster Ceiling	NAD	130	SF	N/A	SF		
1	3	312A	Classroom 312 Coat Room	Floor Tile VAT 12" x 12"	Assumed	130	SF	0	SF	Multi	
1	3	313	Classroom 313	Fiberglass Pipe Insulation	Non Suspect ACM	25	LF	N/A	LF		
1	3	313	Classroom 313	Glue Dots associated with Blackboard	Assumed	20	SF	0	SF		
1	3	313	Classroom 313	Plaster Wall	NAD	1400	SF	N/A	SF		
1	3	313	Classroom 313	Plaster Ceiling	NAD	700	SF	N/A	SF		
1	3	313	Classroom 313	Floor Tile VAT 12" x 12"	Assumed	700	SF	0	SF	Multi	
1	3	313A	Classroom 313 Coat Room	Plaster Wall	NAD	500	SF	N/A	SF		
1	3	313A	Classroom 313 Coat Room	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	3	313A	Classroom 313 Coat Room	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	3	320	Girl's Restroom adjacent to Classroom 301	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	1	EA	N/A	EA		
1	3	320	Girl's Restroom adjacent to Classroom 301	Fiberglass Pipe Insulation	Non Suspect ACM	40	LF	N/A	LF		
1	3	320	Girl's Restroom adjacent to Classroom 301	Ceramic Tile Wall	Non Suspect ACM	430	SF	N/A	SF		
1	3	320	Girl's Restroom adjacent to Classroom 301	Paint associated with Wall, CMU	NAD	100	SF	N/A	SF		
1	3	320	Girl's Restroom adjacent to Classroom 301	Expansion Seam Caulking	Assumed	10	LF	0	LF		
1	3	320	Girl's Restroom adjacent to Classroom 301	Plaster Wall	NAD	430	SF	N/A	SF		
1	3	320	Girl's Restroom adjacent to Classroom 301	Plaster Ceiling	NAD	192	SF	N/A	SF		
1	3	320	Girl's Restroom adjacent to Classroom 301	Paint associated with Floor, Concrete	NAD	190	SF	N/A	SF		
1	3	320	Girl's Restroom adjacent to Classroom 301	Concrete Floor	Non Suspect ACM	192	SF	N/A	SF		
1	3	350	Storage Closet adjacent to Classroom 302	Plaster Wall	NAD	300	SF	N/A	SF		
1	3	350	Storage Closet adjacent to Classroom 302	Metal Ceiling	Non Suspect ACM	48	SF	N/A	SF		
1	3	350	Storage Closet adjacent to Classroom 302	Paint associated with Floor, Concrete	NAD	45	SF	N/A	SF		
1	3	350	Storage Closet adjacent to Classroom 302	Concrete Floor	Non Suspect ACM	48	SF	N/A	SF		
1	3	H10	Hallway from Classrooms 305 A to 308	Floor Tile VAT 12" x 12"	Assumed	460	SF	0	SF	White	
1	3	H10	Hallway from Classrooms 305 A to 308	Concrete Ceiling	Non Suspect ACM	165	SF	N/A	SF		
1	3	H10	Hallway from Classrooms 305 A to 308	Ceiling Tile 2' x 4'	NAD	165	SF	N/A	SF		
1	3	H10	Hallway from Classrooms 305 A to 308	CMU Block Wall	Non Suspect ACM	42	SF	N/A	SF		
1	3	H10	Hallway from Classrooms 305 A to 308	Fireproofing	NAD	10	SF	N/A	SF		
1	3	H10	Hallway from Classrooms 305 A to 308	Fiberglass Pipe Insulation	Non Suspect ACM	30	LF	N/A	LF		
1	3	H10	Hallway from Classrooms 305 A to 308	Plaster Wall	NAD	2200	SF	N/A	SF		
1	3	H10	Hallway from Classrooms 305 A to 308	Plaster Ceiling	NAD	1100	SF	N/A	SF		
1	3	H10	Hallway from Classrooms 305 A to 308	Paint associated with Floor, Concrete	NAD	1100	SF	N/A	SF		
1	3	H10	Hallway from Classrooms 305 A to 308	Concrete Floor	Non Suspect ACM	1100	SF	N/A	SF		
1	3	H11	Hallway from Classrooms 309 to 313	Plaster Wall	NAD	1600	SF	N/A	SF		
1	3	H11	Hallway from Classrooms 309 to 313	Plaster Ceiling	NAD	945	SF	N/A	SF		
1	3	H11	Hallway from Classrooms 309 to 313	Paint associated with Floor, Concrete	NAD	940	SF	N/A	SF		
1	3	H11	Hallway from Classrooms 309 to 313	Concrete Floor	Non Suspect ACM	945	SF	N/A	SF		
1	3	H12	Hallway from Classrooms 301 to 304	Fiberglass Pipe Insulation	Non Suspect ACM	45	LF	N/A	LF		
1	3	H12	Hallway from Classrooms 301 to 304	Plaster Wall	NAD	2600	SF	N/A	SF		
1	3	H12	Hallway from Classrooms 301 to 304	Plaster Ceiling	NAD	1385	SF	N/A	SF		
1	3	H12	Hallway from Classrooms 301 to 304	Paint associated with Floor, Concrete	NAD	1385	SF	N/A	SF		
1	3	H12	Hallway from Classrooms 301 to 304	Concrete Floor	Non Suspect ACM	1065	SF	N/A	SF		
1	3	H12	Hallway from Classrooms 301 to 304	Mastic associated with Floor Tile	Assumed	320	SF	0	SF	Yellow	
1	3	H12	Hallway from Classrooms 301 to 304	Floor Tile VAT 12" x 12"	Assumed	320	SF	0	SF	White	
1	3	S31	Haworth Stairwell A adjacent to Classrom 308	Radiator	Non Suspect ACM	10	EA	N/A	EA		
1	3	S31	Haworth Stairwell A adjacent to Classrom 308	Fiberglass Pipe Insulation	Non Suspect ACM	12	LF	N/A	LF		
1	3	S31	Haworth Stairwell A adjacent to Classrom 308	Plaster Wall	NAD	600	SF	N/A	SF		
1	3	S31	Haworth Stairwell A adjacent to Classrom 308	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	3	S31	Haworth Stairwell A adjacent to Classrom 308	Paint associated with Floor, Concrete	NAD	300	SF	N/A	SF		
1	3	S31	Haworth Stairwell A adjacent to Classrom 308	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	3	S32	Dyre Stairwell A adjacent to Classroom 301	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	3	S32	Dyre Stairwell A adjacent to Classroom 301	Plaster Wall	NAD	900	SF	N/A	SF		
1	3	S32	Dyre Stairwell A adjacent to Classroom 301	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	3	S32	Dyre Stairwell A adjacent to Classroom 301	Paint associated with Floor, Concrete	NAD	300	SF	N/A	SF		
1	3	S32	Dyre Stairwell A adjacent to Classroom 301	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	3	S33	Dyre Stairwell B adjacent to Classroom 304	Fireproofing	NAD	4	SF	N/A	SF		
1	3	S33	Dyre Stairwell B adjacent to Classroom 304	CMU Block Wall	Non Suspect ACM	210	SF	N/A	SF		
1	3	S33	Dyre Stairwell B adjacent to Classroom 304	Concrete Ceiling	Non Suspect ACM	270	SF	N/A	SF		
1	3	S33	Dyre Stairwell B adjacent to Classroom 304	Paint associated with Wall, CMU	NAD	1400	SF	N/A	SF		
1	3	S33	Dyre Stairwell B adjacent to Classroom 304	CMU Block Wall	Non Suspect ACM	1400	SF	N/A	SF		
1	3	S33	Dyre Stairwell B adjacent to Classroom 304	Ceiling Tile 2' x 4'	NAD	270	SF	N/A	SF		
1	3	S33	Dyre Stairwell B adjacent to Classroom 304	Paint associated with Floor, Concrete	NAD	270	SF	N/A	SF		
1	3	S33	Dyre Stairwell B adjacent to Classroom 304	Concrete Floor	Non Suspect ACM	270	SF	N/A	SF		
1	3	S34	Haworth Stairwell B adjacent to Classroom 305	Fireproofing	NAD	7	SF	N/A	SF		
1	3	S34	Haworth Stairwell B adjacent to Classroom 305	CMU Block Wall	Non Suspect ACM	220	SF	N/A	SF		
1	3	S34	Haworth Stairwell B adjacent to Classroom 305	Concrete Ceiling	Non Suspect ACM	280	SF	N/A	SF		
1	3	S34	Haworth Stairwell B adjacent to Classroom 305	Ceiling Tile 2' x 4'	NAD	280	SF	N/A	SF		
1	3	S34	Haworth Stairwell B adjacent to Classroom 305	Paint associated with Wall, CMU	NAD	1400	SF	N/A	SF		
1	3	S34	Haworth Stairwell B adjacent to Classroom 305	CMU Block Wall	Non Suspect ACM	1400	SF	N/A	SF		
1	3	S34	Haworth Stairwell B adjacent to Classroom 305	Paint associated with Floor, Concrete	NAD	270	SF	N/A	SF		
1	3	S34	Haworth Stairwell B adjacent to Classroom 305	Concrete Floor	Non Suspect ACM	270	SF	N/A	SF		
1	B	006A	Speech Classroom	CMU Block Wall	Non Suspect ACM	288	SF	N/A	SF		



Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	B	006A	Speech Classroom	Paint associated with Wall, CMU	NAD	288	SF	0	SF		
1	B	006A	Speech Classroom	Paint associated with Wall, Brick	NAD	96	SF	N/A	SF		
1	B	006A	Speech Classroom	Brick Wall	Non Suspect ACM	96	SF	N/A	SF		
1	B	006A	Speech Classroom	Paint associated with Ceiling, Concrete	NAD	144	SF	N/A	SF		
1	B	006A	Speech Classroom	Concrete Ceiling	Non Suspect ACM	122	SF	N/A	SF		
1	B	006A	Speech Classroom	Carpet	Non Suspect ACM	144	SF	N/A	SF		
1	B	013S	Fan Room Stairs	Paint associated with Wall, Brick	NAD	400	SF	N/A	SF		
1	B	013S	Fan Room Stairs	Brick Wall	Non Suspect ACM	400	SF	N/A	SF		
1	B	013S	Fan Room Stairs	Paint associated with Floor, Concrete	Assumed	100	SF	0	SF		
1	B	013S	Fan Room Stairs	Concrete Floor	Non Suspect ACM	100	SF	N/A	SF		
1	B	014A	Storage Closet Left	Paint associated with Wall, CMU	NAD	290	SF	N/A	SF		
1	B	014A	Storage Closet Left	Fiberglass Pipe Insulation	Non Suspect ACM	5	LF	N/A	LF		
1	B	014A	Storage Closet Left	Paint associated with Ceiling, Concrete	NAD	80	SF	N/A	SF		
1	B	014A	Storage Closet Left	Concrete Ceiling	Non Suspect ACM	40	SF	N/A	SF		
1	B	019A	Staff Restroom	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	2	EA	N/A	EA		
1	B	019A	Staff Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	70	LF	N/A	LF		
1	B	019A	Staff Restroom	Paint associated with Wall, Brick	NAD	300	SF	N/A	SF		
1	B	019A	Staff Restroom	Brick Wall	Non Suspect ACM	300	SF	N/A	SF		
1	B	019A	Staff Restroom	Paint associated with Ceiling, Concrete	NAD	40	SF	N/A	SF		
1	B	019A	Staff Restroom	Concrete Ceiling	Non Suspect ACM	40	SF	N/A	SF		
1	B	019A	Staff Restroom	Paint associated with Floor, Concrete	Assumed	40	SF	0	SF		
1	B	019A	Staff Restroom	Concrete Floor	Non Suspect ACM	40	SF	N/A	SF		
1	B	1	Girl's Restroom	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	5	EA	N/A	EA		
1	B	1	Girl's Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	50	LF	N/A	LF		
1	B	1	Girl's Restroom	Paint associated with Wall, Brick	NAD	1050	SF	N/A	SF		
1	B	1	Girl's Restroom	Brick Wall	Non Suspect ACM	800	SF	N/A	SF		
1	B	1	Girl's Restroom	Paint associated with Ceiling, Concrete	NAD	528	SF	N/A	SF		
1	B	1	Girl's Restroom	Concrete Ceiling	Non Suspect ACM	528	SF	N/A	SF		
1	B	1	Girl's Restroom	Paint associated with Floor, Concrete	Assumed	528	SF	0	SF		
1	B	1	Girl's Restroom	Concrete Floor	Non Suspect ACM	528	SF	N/A	SF		
1	B	12	Boy's Restroom	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	2	EA	N/A	EA		
1	B	12	Boy's Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	B	12	Boy's Restroom	Paint associated with Wall, Brick	NAD	950	SF	N/A	SF		
1	B	12	Boy's Restroom	Brick Wall	Non Suspect ACM	800	SF	N/A	SF		
1	B	12	Boy's Restroom	Paint associated with Ceiling, Concrete	NAD	528	SF	N/A	SF		
1	B	12	Boy's Restroom	Concrete Ceiling	Non Suspect ACM	528	SF	N/A	SF		
1	B	12	Boy's Restroom	Paint associated with Floor, Concrete	Assumed	528	SF	0	SF		
1	B	12	Boy's Restroom	Concrete Floor	Non Suspect ACM	528	SF	N/A	SF		
1	B	13	Fan Room	Paint associated with Fan Unit, Exterior	NAD	800	SF	N/A	SF		
1	B	13	Fan Room	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	20	EA	N/A	EA		
1	B	13	Fan Room	Fiberglass Pipe Insulation	Non Suspect ACM	150	LF	N/A	LF		
1	B	13	Fan Room	Pipe Fitting Insulation	Confirmed	5	EA	0	EA		
1	B	13	Fan Room	Pipe Insulation >6 inches	Confirmed	70	LF	0	LF		
1	B	13	Fan Room	Paint associated with Wall, Brick	NAD	2000	SF	N/A	SF		
1	B	13	Fan Room	Brick Wall	Non Suspect ACM	2000	SF	N/A	SF		
1	B	13	Fan Room	Paint associated with Ceiling, Concrete	NAD	1247	SF	N/A	SF		
1	B	13	Fan Room	Concrete Ceiling	Non Suspect ACM	1247	SF	N/A	SF		
1	B	13	Fan Room	Concrete Floor	Non Suspect ACM	1247	SF	N/A	SF		
1	B	16	Staff Restroom	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	2	EA	N/A	EA		
1	B	16	Staff Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	40	LF	N/A	LF		
1	B	16	Staff Restroom	Paint associated with Wall, Brick	NAD	300	SF	N/A	SF		
1	B	16	Staff Restroom	Brick Wall	Non Suspect ACM	300	SF	N/A	SF		
1	B	16	Staff Restroom	Paint associated with Ceiling, Concrete	NAD	100	SF	N/A	SF		
1	B	16	Staff Restroom	Concrete Ceiling	Non Suspect ACM	98	SF	N/A	SF		
1	B	16	Staff Restroom	Paint associated with Floor, Concrete	Assumed	100	SF	0	SF		
1	B	16	Staff Restroom	Concrete Floor	Non Suspect ACM	98	SF	N/A	SF		
1	B	17	Custodial Storage	CMU Block Wall	Non Suspect ACM	500	SF	N/A	SF		
1	B	17	Custodial Storage	Metal Ceiling	Non Suspect ACM	110	SF	N/A	SF		
1	B	17	Custodial Storage	Concrete Floor	Non Suspect ACM	110	SF	N/A	SF		
1	B	2	Boy's Restroom	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	5	EA	N/A	EA		
1	B	2	Boy's Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	50	LF	N/A	LF		
1	B	2	Boy's Restroom	Paint associated with Wall, Brick	NAD	800	SF	N/A	SF		
1	B	2	Boy's Restroom	Brick Wall	Non Suspect ACM	800	SF	N/A	SF		
1	B	2	Boy's Restroom	Paint associated with Ceiling, Concrete	NAD	528	SF	N/A	SF		
1	B	2	Boy's Restroom	Concrete Ceiling	Non Suspect ACM	528	SF	N/A	SF		
1	B	2	Boy's Restroom	Paint associated with Floor, Concrete	Assumed	528	SF	0	SF		
1	B	2	Boy's Restroom	Concrete Floor	Non Suspect ACM	528	SF	N/A	SF		
1	B	8	Boiler Room	Paint associated with Wall, Concrete	NAD	1000	SF	N/A	SF		
1	B	8	Boiler Room	Fiberglass Duct Insulation	Non Suspect ACM	600	SF	N/A	SF		
1	B	8	Boiler Room	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	25	EA	N/A	EA		
1	B	8	Boiler Room	Fiberglass Pipe Insulation	Non Suspect ACM	600	LF	N/A	LF		
1	B	8	Boiler Room	Paint associated with Wall, Brick	NAD	3000	SF	N/A	SF		
1	B	8	Boiler Room	Brick Wall	Non Suspect ACM	2300	SF	N/A	SF		
1	B	8	Boiler Room	Paint associated with Ceiling, Concrete	NAD	1750	SF	N/A	SF		
1	B	8	Boiler Room	Concrete Ceiling	Non Suspect ACM	1849	SF	N/A	SF		
1	B	8	Boiler Room	Boiler Breaching	NAD	15	SF	N/A	SF		2 samples NAD 3/9/2023 TF/CRI ; 1 sample NAD 06/21/2023 TF/CRI

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	B	8	Boiler Room	Concrete Floor	Non Suspect ACM	1849	SF	N/A	SF		
1	B	9	Basement Office	Fiberglass Duct Insulation	Non Suspect ACM	65	SF	N/A	SF		
1	B	9	Basement Office	Plaster Ceiling	NAD	550	SF	N/A	SF		
1	B	9	Basement Office	CMU Block Wall	Non Suspect ACM	440	SF	N/A	SF		
1	B	9	Basement Office	Paint associated with Wall, CMU	NAD	440	SF	N/A	SF		
1	B	9	Basement Office	Paint associated with Wall, Brick	NAD	400	SF	N/A	SF		
1	B	9	Basement Office	Brick Wall	Non Suspect ACM	400	SF	N/A	SF		
1	B	9	Basement Office	Ceiling Tile 2' x 4'	NAD	550	SF	N/A	SF		
1	B	9	Basement Office	Floor Tile VAT 12" x 12"	Assumed	300	SF	0	SF	Multi	
1	B		Cafeteria	Fireproofing	NAD	450	SF	N/A	SF		
1	B		Cafeteria	Fiberglass Pipe Insulation	Non Suspect ACM	50	LF	N/A	LF		
1	B		Cafeteria	Concrete Ceiling	Non Suspect ACM	5000	SF	N/A	SF		
1	B		Cafeteria	CMU Block Wall	Non Suspect ACM	1070	SF	N/A	SF		
1	B		Cafeteria	Fiberglass Duct Insulation	Non Suspect ACM	1680	SF	N/A	SF		
1	B		Cafeteria	Paint associated with Wall, CMU	NAD	3500	SF	N/A	SF		
1	B		Cafeteria	Expansion Seam Caulking	Assumed	350	LF	0	LF		
1	B		Cafeteria	CMU Block Wall	Non Suspect ACM	3500	SF	N/A	SF		
1	B		Cafeteria	Ceiling Tile 2' x 4'	NAD	5000	SF	N/A	SF		
1	B		Cafeteria	Floor Tile VAT 12" x 12"	Assumed	5000	SF	0	SF	White	
1	B	G-6	Classroom G-6	Fiberglass Duct Insulation	Non Suspect ACM	100	SF	N/A	SF		
1	B	G-6	Classroom G-6	CMU Block Wall	Non Suspect ACM	360	SF	N/A	SF		
1	B	G-6	Classroom G-6	Concrete Ceiling	Non Suspect ACM	850	SF	N/A	SF		
1	B	G-6	Classroom G-6	Floor Tile VAT 12" x 12"	Assumed	80	SF	0	SF	Tan	
1	B	G-6	Classroom G-6	Paint associated with Wall, CMU	NAD	1100	SF	N/A	SF		
1	B	G-6	Classroom G-6	Expansion Seam Caulking	Assumed	95	LF	0	LF		
1	B	G-6	Classroom G-6	CMU Block Wall	Non Suspect ACM	1100	SF	N/A	SF		
1	B	G-6	Classroom G-6	Ceiling Tile 2' x 4'	NAD	850	SF	N/A	SF		
1	B	G-6	Classroom G-6	Floor Tile VAT 12" x 12"	Assumed	850	SF	0	SF	White	
1	B	G-6A	G6 Restroom	Concrete Ceiling	Non Suspect ACM	48	SF	N/A	SF		
1	B	G-6A	G6 Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		
1	B	G-6A	G6 Restroom	CMU Block Wall	Non Suspect ACM	84	SF	N/A	SF		
1	B	G-6A	G6 Restroom	Ceramic Tile Wall	Non Suspect ACM	200	SF	N/A	SF		
1	B	G-6A	G6 Restroom	Ceramic Tile Floor	Non Suspect ACM	48	SF	N/A	SF		
1	B	G-6A	G6 Restroom	Ceiling Tile 2' x 4'	NAD	48	SF	N/A	SF	1 sample NAD 3/9/2023 TF/CRI	
1	B	G-6A	G6 Restroom	CMU Block Wall	Non Suspect ACM	100	SF	N/A	SF		
1	B	G-7	Classroom G-7	Fiberglass Pipe Insulation	Non Suspect ACM	100	LF	N/A	LF		
1	B	G-7	Classroom G-7	CMU Block Wall	Non Suspect ACM	360	SF	N/A	SF		
1	B	G-7	Classroom G-7	Concrete Ceiling	Non Suspect ACM	875	SF	N/A	SF		
1	B	G-7	Classroom G-7	Fiberglass Duct Insulation	Non Suspect ACM	100	SF	N/A	SF		
1	B	G-7	Classroom G-7	Paint associated with Wall, CMU	NAD	1115	SF	N/A	SF		
1	B	G-7	Classroom G-7	Expansion Seam Caulking	Assumed	95	LF	0	LF		
1	B	G-7	Classroom G-7	CMU Block Wall	Non Suspect ACM	1115	SF	N/A	SF		
1	B	G-7	Classroom G-7	Ceiling Tile 2' x 4'	NAD	875	SF	N/A	SF		
1	B	G-7	Classroom G-7	Floor Tile VAT 12" x 12"	Assumed	875	SF	0	SF	White	
1	B	G-7A	G7 Bathroom	Concrete Ceiling	Non Suspect ACM	48	SF	N/A	SF		
1	B	G-7A	G7 Bathroom	CMU Block Wall	Non Suspect ACM	84	SF	N/A	SF		
1	B	G-7A	G7 Bathroom	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		
1	B	G-7A	G7 Bathroom	Ceramic Tile Floor	Non Suspect ACM	48	SF	N/A	SF		
1	B	G-7A	G7 Bathroom	CMU Block Wall	Non Suspect ACM	100	SF	N/A	SF		
1	B	G-7A	G7 Bathroom	Ceramic Tile Wall	Non Suspect ACM	200	SF	N/A	SF		
1	B	G-7A	G7 Bathroom	Ceiling Tile 2' x 4'	NAD	48	SF	N/A	SF		
1	B	G1	G1	Floor Tile VAT 12" x 12"	Assumed	540	SF	0	SF	Multi	
1	B	G1	G1	Glue Dots associated with Blackboard	Assumed	10	SF	0	SF		
1	B	G1	G1	Pipe Fitting Insulation	Confirmed	2	EA	0	EA		
1	B	G1	G1	Pipe Insulation 2-6 inch	Confirmed	10	LF	0	LF		
1	B	G1	G1	Fiberglass Pipe Insulation	Non Suspect ACM	60	LF	N/A	LF		
1	B	G1	G1	Plaster Wall	NAD	1100	SF	N/A	SF		
1	B	G1	G1	Plaster Ceiling	NAD	966	SF	N/A	SF		
1	B	G1-ABC	G1 Small Office	Sheetrock/Joint Compound Wall	NAD	220	SF	N/A	SF		
1	B	G1-ABC	G1 Small Office	Plaster Ceiling	NAD	100	SF	N/A	SF		
1	B	G1-ABC	G1 Small Office	Plaster Wall	NAD	75	SF	N/A	SF		
1	B	G1-ABC	G1 Small Office	Floor Tile VAT 12" x 12"	Assumed	100	SF	0	SF	Multi	
1	B	G10	Classroom/Hall G10	Plaster Ceiling	NAD	960	SF	N/A	SF		
1	B	G10	Classroom/Hall G10	Pipe Fitting Insulation	Confirmed	4	EA	0	EA		
1	B	G10	Classroom/Hall G10	Pipe Insulation 2-6 inch	Confirmed	18	LF	0	LF		
1	B	G10	Classroom/Hall G10	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	5	EA	N/A	EA		
1	B	G10	Classroom/Hall G10	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	B	G10	Classroom/Hall G10	Paint associated with Wall, Brick	NAD	400	SF	N/A	SF		
1	B	G10	Classroom/Hall G10	Brick Wall	Non Suspect ACM	1100	SF	N/A	SF		
1	B	G10	Classroom/Hall G10	Paint associated with Ceiling, Concrete	NAD	260	SF	N/A	SF		
1	B	G10	Classroom/Hall G10	Concrete Ceiling	Non Suspect ACM	960	SF	N/A	SF		
1	B	G10	Classroom/Hall G10	Floor Tile VAT 12" x 12"	Assumed	260	SF	0	SF	Multi	
1	B	G10 E	G10 E Office	Pipe Fitting Insulation	Confirmed	3	EA	0	EA		
1	B	G10 E	G10 E Office	Plaster Ceiling	NAD	165	SF	N/A	SF		
1	B	G10 E	G10 E Office	Fiberglass Duct Insulation	Non Suspect ACM	44	SF	N/A	SF		
1	B	G10 E	G10 E Office	Fiberglass Pipe Insulation	Non Suspect ACM	15	LF	N/A	LF		
1	B	G10 E	G10 E Office	Sheetrock/Joint Compound Wall	NAD	240	SF	N/A	SF		



Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	B	G10 E	G10 E Office	Paint associated with Wall, Brick	NAD	250	SF	N/A	SF		
1	B	G10 E	G10 E Office	Ceiling Tile 2' x 4'	NAD	165	SF	N/A	SF		
1	B	G10 E	G10 E Office	Brick Wall	Non Suspect ACM	240	SF	N/A	SF		
1	B	G10 E	G10 E Office	Floor Tile VAT 12" x 12"	Assumed	165	SF	0	SF	Multi	
1	B	G10A	G10A Office	Fiberglass Pipe Insulation	Non Suspect ACM	60	LF	N/A	LF		
1	B	G10A	G10A Office	Pipe Fitting Insulation	Confirmed	8	EA	0	EA		
1	B	G10A	G10A Office	Pipe Fitting Insulation	Confirmed	1	EA	0	EA		
1	B	G10A	G10A Office	Plaster Ceiling	NAD	160	SF	N/A	SF		
1	B	G10A	G10A Office	Sheetrock/Joint Compound Wall	NAD	150	SF	N/A	SF		
1	B	G10A	G10A Office	Paint associated with Wall, Brick	NAD	260	SF	N/A	SF		
1	B	G10A	G10A Office	Floor Tile VAT 12" x 12"	NAD	160	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G10A	G10A Office	Mastic associated with Floor Tile	NAD	160	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G10A	G10A Office	Ceiling Tile 2' x 4'	NAD	160	SF	N/A	SF		
1	B	G10A Office Closet	G10A Office Closer	Brick Wall	Non Suspect ACM	50	SF	N/A	SF		
1	B	G10A Office Closet	G10A Office Closer	Concrete Floor	Non Suspect ACM	25	SF	N/A	SF		
1	B	G10A Office Closet	G10A Office Closer	Concrete Ceiling	Non Suspect ACM	25	SF	N/A	SF		
1	B	G10A Office Closet	G10A Office Closer	Paint associated with Wall, Brick	NAD	50	SF	N/A	SF		
1	B	G10B	G10B Office	Fiberglass Pipe Insulation	Non Suspect ACM	12	LF	N/A	LF		
1	B	G10B	G10B Office	Plaster Ceiling	NAD	110	SF	N/A	SF		
1	B	G10B	G10B Office	Pipe Fitting Insulation	Confirmed	4	EA	0	EA		
1	B	G10B	G10B Office	Sheetrock/Joint Compound Wall	NAD	340	SF	N/A	SF		
1	B	G10B	G10B Office	Ceiling Tile 2' x 4'	NAD	110	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	B	G10B	G10B Office	Floor Tile VAT 12" x 12"	Assumed	110	SF	0	SF	Multi	
1	B	G10C	G10C Office	Fiberglass Duct Insulation	Non Suspect ACM	16	SF	N/A	SF		
1	B	G10C	G10C Office	Fiberglass Pipe Insulation	Non Suspect ACM	12	LF	N/A	LF		
1	B	G10C	G10C Office	Plaster Ceiling	NAD	110	SF	N/A	SF		
1	B	G10C	G10C Office	Sheetrock/Joint Compound Wall	NAD	340	SF	N/A	SF		
1	B	G10C	G10C Office	Floor Tile VAT 12" x 12"	Assumed	110	SF	0	SF	Multi	
1	B	G10C	G10C Office	Ceiling Tile 2' x 4'	NAD	110	SF	N/A	SF		
1	B	G10D	G10D Office	Fiberglass Pipe Insulation	Non Suspect ACM	12	LF	N/A	LF		
1	B	G10D	G10D Office	Plaster Ceiling	NAD	110	SF	N/A	SF		
1	B	G10D	G10D Office	Pipe Fitting Insulation	Confirmed	8	EA	0	EA		
1	B	G10D	G10D Office	Fiberglass Duct Insulation	Non Suspect ACM	24	SF	N/A	SF		
1	B	G10D	G10D Office	Ceiling Tile 2' x 4'	NAD	110	SF	N/A	SF		
1	B	G10D	G10D Office	Floor Tile VAT 12" x 12"	Assumed	110	SF	0	SF	Multi	1 sample sheetrock and 1 sample joint compound 3/9/2023 TF/CRI
1	B	G10D	G10D Office	Sheetrock/Joint Compound Wall	NAD	340	SF	N/A	SF		
1	B	G11A	G11 Back Office	Paint associated with Wall, Brick	NAD	100	SF	N/A	SF		
1	B	G11A	G11 Back Office	CMU Block Wall	Non Suspect ACM	400	SF	N/A	SF		
1	B	G11A	G11 Back Office	Paint associated with Wall, CMU	NAD	400	SF	N/A	SF		
1	B	G11A	G11 Back Office	Floor Tile VAT 12" x 12"	Assumed	130	SF	0	SF	White	
1	B	G11A	G11 Back Office	Brick Wall	Non Suspect ACM	100	SF	N/A	SF		
1	B	G12	Ballet Room G12	Plaster Ceiling	NAD	2675	SF	N/A	SF		
1	B	G12	Ballet Room G12	Fiberglass Duct Insulation	Non Suspect ACM	745	SF	N/A	SF		
1	B	G12	Ballet Room G12	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	B	G12	Ballet Room G12	Paint associated with Wall, CMU	NAD	720	SF	N/A	SF		
1	B	G12	Ballet Room G12	CMU Block Wall	Non Suspect ACM	720	SF	N/A	SF		
1	B	G12	Ballet Room G12	Rubber Floor	Non Suspect ACM	1800	SF	N/A	SF		
1	B	G12	Ballet Room G12	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	26	EA	N/A	EA		
1	B	G12	Ballet Room G12	Fiberglass Pipe Insulation	Non Suspect ACM	115	LF	N/A	LF		
1	B	G12	Ballet Room G12	Paint associated with Wall, Brick	NAD	1170	SF	N/A	SF		
1	B	G12	Ballet Room G12	Brick Wall	Non Suspect ACM	1170	SF	N/A	SF		
1	B	G12	Ballet Room G12	Ceiling Tile 2' x 4'	NAD	2675	SF	N/A	SF		
1	B	G12	Ballet Room G12	Linoleum	NAD	900	SF	N/A	SF	Blue	2 samples NAD 3/9/2023 TF/CRI
1	B	G12A	Ballet Office #1	Fiberglass Duct Insulation	Non Suspect ACM	80	SF	N/A	SF		
1	B	G12A	Ballet Office #1	Plaster Ceiling	NAD	144	SF	N/A	SF		
1	B	G12A	Ballet Office #1	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	11	EA	N/A	EA		
1	B	G12A	Ballet Office #1	Fiberglass Pipe Insulation	Non Suspect ACM	25	LF	N/A	LF		
1	B	G12A	Ballet Office #1	Paint associated with Wall, Brick	NAD	240	SF	N/A	SF		
1	B	G12A	Ballet Office #1	Brick Wall	Non Suspect ACM	240	SF	N/A	SF		
1	B	G12A	Ballet Office #1	Ceiling Tile 2' x 4'	NAD	144	SF	N/A	SF		
1	B	G12A	Ballet Office #1	Carpet	Non Suspect ACM	144	SF	N/A	SF		
1	B	G12AB	Ballet Office Duct Room	Brick Wall	Non Suspect ACM	750	SF	N/A	SF		
1	B	G12AB	Ballet Office Duct Room	Concrete Floor	Non Suspect ACM	150	SF	N/A	SF		
1	B	G12AB	Ballet Office Duct Room	Paint associated with Wall, Brick	NAD	750	SF	N/A	SF		
1	B	G12AB	Ballet Office Duct Room	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	22	EA	N/A	EA		
1	B	G12AB	Ballet Office Duct Room	Duct Work	Non Suspect ACM	45	LF	N/A	LF		
1	B	G12AB	Ballet Office Duct Room	Fiberglass Duct Insulation	Non Suspect ACM	300	SF	N/A	SF		
1	B	G12AB	Ballet Office Duct Room	Plaster Ceiling	NAD	750	SF	N/A	SF		
1	B	G12AB	Ballet Office Duct Room	Fiberglass Pipe Insulation	Non Suspect ACM	60	LF	N/A	LF		
1	B	G12B	Speech Office/Classroom in Ballet Room G12	Fiberglass Duct Insulation	Non Suspect ACM	30	SF	N/A	SF		
1	B	G12B	Speech Office/Classroom in Ballet Room G12	Plaster Ceiling	NAD	144	SF	N/A	SF		
1	B	G12B	Speech Office/Classroom in Ballet Room G12	Paint associated with Wall, Brick	NAD	350	SF	N/A	SF		
1	B	G12B	Speech Office/Classroom in Ballet Room G12	Brick Wall	Non Suspect ACM	350	SF	N/A	SF		
1	B	G12B	Speech Office/Classroom in Ballet Room G12	Ceiling Tile 2' x 4'	NAD	144	SF	N/A	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	B	G12B	Speech Office/Classroom in Ballet Room G12	Carpet	Non Suspect ACM	60	SF	N/A	SF		
1	B	G1A	Music Room G1 Closet	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		
1	B	G1A	Music Room G1 Closet	Plaster Wall	NAD	300	SF	N/A	SF		
1	B	G1A	Music Room G1 Closet	Plaster Ceiling	NAD	60	SF	N/A	SF		
1	B	G1A	Music Room G1 Closet	Floor Tile VAT 12" x 12"	Assumed	60	SF	0	SF	Multi	
1	B	G1AB	G1 Main Windowed Office	Sheetrock/Joint Compound Wall	NAD	300	SF	N/A	SF		1 sample sheetrock & 1 sample joint compound NAD 06/21/2023 TF/CRI
1	B	G1AB	G1 Main Windowed Office	Floor Tile VAT 12" x 12"	Assumed	210	SF	0	SF	Multi	
1	B	G1AB	G1 Main Windowed Office	Plaster Ceiling	NAD	180	SF	N/A	SF		
1	B	G1AB	G1 Main Windowed Office	Plaster Wall	NAD	300	SF	N/A	SF		
1	B	G1B	Music Room G1 Coat Room	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	2	EA	N/A	EA		
1	B	G1B	Music Room G1 Coat Room	Fiberglass Pipe Insulation	Non Suspect ACM	35	LF	N/A	LF		
1	B	G1B	Music Room G1 Coat Room	Plaster Wall	NAD	300	SF	N/A	SF		
1	B	G1B	Music Room G1 Coat Room	Plaster Ceiling	NAD	60	SF	N/A	SF		
1	B	G1B	Music Room G1 Coat Room	Floor Tile VAT 12" x 12"	Assumed	60	SF	0	SF	Multi	
1	B	G2	Classroom G2	Sheetrock/Joint Compound Wall	NAD	250	SF	N/A	SF		1 sample sheetrock and 1 sample joint compound NAD 3/9/2023 TF/CRI
1	B	G2	Classroom G2	Mastic associated with Floor Tile	NAD	660	SF	N/A	SF	Black	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G2	Classroom G2	Fiberglass Pipe Insulation	Non Suspect ACM	10	LF	N/A	LF		
1	B	G2	Classroom G2	Pipe Insulation 2-6 inch	Confirmed	10	LF	0	LF		
1	B	G2	Classroom G2	Plaster Wall	NAD	1100	SF	N/A	SF		
1	B	G2	Classroom G2	Plaster Ceiling	NAD	936	SF	N/A	SF		
1	B	G2	Classroom G2	Floor Tile VAT 12" x 12"	NAD	660	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G3	Classroom G3	Sheetrock/Joint Compound Wall	NAD	175	SF	N/A	SF		2 samples sheetrock and 2 samples joint compound NAD 3/9/2023 TF/CRI
1	B	G3	Classroom G3	Mastic associated with Floor Tile	NAD	936	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G3	Classroom G3	Glue Dots associated with Blackboard	Assumed	10	SF	0	SF		
1	B	G3	Classroom G3	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	2	EA	N/A	EA		
1	B	G3	Classroom G3	Fiberglass Pipe Insulation	Non Suspect ACM	50	LF	N/A	LF		
1	B	G3	Classroom G3	Pipe Insulation 2-6 inch	Confirmed	30	LF	0	LF		
1	B	G3	Classroom G3	Plaster Wall	NAD	1100	SF	N/A	SF		
1	B	G3	Classroom G3	Plaster Ceiling	NAD	936	SF	N/A	SF		
1	B	G3	Classroom G3	Floor Tile VAT 12" x 12"	NAD	936	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G3A	Classroom G3 Coat Room/Classroom	Plaster Wall	NAD	300	SF	N/A	SF		
1	B	G3A	Classroom G3 Coat Room/Classroom	Plaster Ceiling	NAD	90	SF	N/A	SF		
1	B	G3A	Classroom G3 Coat Room/Classroom	Floor Tile VAT 12" x 12"	Assumed	90	SF	0	SF	Multi	
1	B	G4	Classroom G4	Concrete Ceiling	Non Suspect ACM	830	SF	N/A	SF		
1	B	G4	Classroom G4	CMU Block Wall	Non Suspect ACM	360	SF	N/A	SF		
1	B	G4	Classroom G4	Fiberglass Duct Insulation	Non Suspect ACM	204	SF	N/A	SF		
1	B	G4	Classroom G4	Fiberglass Pipe Insulation	Non Suspect ACM	70	LF	N/A	LF		
1	B	G4	Classroom G4	Mastic associated with Floor Tile	NAD	830	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G4	Classroom G4	Floor Tile VAT 12" x 12"	NAD	830	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G4	Classroom G4	Paint associated with Wall, CMU	NAD	1080	SF	N/A	SF		
1	B	G4	Classroom G4	Expansion Seam Caulking	Assumed	95	LF	0	LF		
1	B	G4	Classroom G4	CMU Block Wall	Non Suspect ACM	1080	SF	N/A	SF		
1	B	G4	Classroom G4	Ceiling Tile 2' x 4'	NAD	830	SF	N/A	SF		1 sample NAD 3/9/2023 TF/CRI
1	B	G4A	Classroom G4 Closet A adjacent to Entrance	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	B	G4A	Classroom G4 Closet A adjacent to Entrance	Expansion Seam Caulking	Assumed	120	LF	0	LF		
1	B	G4A	Classroom G4 Closet A adjacent to Entrance	CMU Block Wall	Non Suspect ACM	1200	SF	N/A	SF		
1	B	G4A	Classroom G4 Closet A adjacent to Entrance	Concrete Ceiling	Non Suspect ACM	80	SF	N/A	SF		
1	B	G4A	Classroom G4 Closet A adjacent to Entrance	Concrete Floor	Non Suspect ACM	80	SF	N/A	SF		
1	B	G4B	Classroom G4 Closet B in Rear of Classroom adjacent to Windows	Expansion Seam Caulking	Assumed	60	LF	0	LF		
1	B	G4B	Classroom G4 Closet B in Rear of Classroom adjacent to Windows	CMU Block Wall	Non Suspect ACM	600	SF	N/A	SF		
1	B	G4B	Classroom G4 Closet B in Rear of Classroom adjacent to Windows	Concrete Ceiling	Non Suspect ACM	40	SF	N/A	SF		
1	B	G4B	Classroom G4 Closet B in Rear of Classroom adjacent to Windows	Concrete Floor	Non Suspect ACM	40	SF	N/A	SF		
1	B	G4C	Classroom G4 Restroom in Rear of Classroom	Concrete Ceiling	Non Suspect ACM	50	SF	N/A	SF		
1	B	G4C	Classroom G4 Restroom in Rear of Classroom	Fiberglass Pipe Insulation	Non Suspect ACM	3	LF	N/A	LF		
1	B	G4C	Classroom G4 Restroom in Rear of Classroom	Ceiling Tile 2' x 4'	NAD	50	SF	N/A	SF		
1	B	G4C	Classroom G4 Restroom in Rear of Classroom	Ceramic Tile Wall	Non Suspect ACM	750	SF	N/A	SF		
1	B	G4C	Classroom G4 Restroom in Rear of Classroom	Ceramic Tile Floor	Non Suspect ACM	50	SF	N/A	SF		
1	B	G4D	Classroom G4 Closet C in Rear of Classroom adjacent to Hallway	Expansion Seam Caulking	Assumed	30	LF	0	LF		
1	B	G4D	Classroom G4 Closet C in Rear of Classroom adjacent to Hallway	CMU Block Wall	Non Suspect ACM	300	SF	N/A	SF		
1	B	G4D	Classroom G4 Closet C in Rear of Classroom adjacent to Hallway	Concrete Ceiling	Non Suspect ACM	20	SF	N/A	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	B	G4D	Classroom G4 Closet C in Rear of Classroom adjacent to	Concrete Floor	Non Suspect ACM	20	SF	N/A	SF		
1	B	G5	Hallway	Fiberglass Duct Insulation	Non Suspect ACM	200	SF	N/A	SF		
1	B	G5	Classroom G5	Fiberglass Pipe Insulation	Non Suspect ACM	70	LF	N/A	SF		
1	B	G5	Classroom G5	CMU Block Wall	Non Suspect ACM	360	SF	N/A	SF		
1	B	G5	Classroom G5	Concrete Ceiling	Non Suspect ACM	768	SF	N/A	SF		
1	B	G5	Classroom G5	Paint associated with Wall, CMU	NAD	1070	SF	N/A	SF		
1	B	G5	Classroom G5	Expansion Seam Caulking	Assumed	95	LF	0	LF		
1	B	G5	Classroom G5	CMU Block Wall	Non Suspect ACM	1070	SF	N/A	SF		
1	B	G5	Classroom G5	Ceiling Tile 2' x 4'	NAD	768	SF	N/A	SF		
1	B	G5	Classroom G5	Floor Tile VAT 12" x 12"	Assumed	768	SF	0	SF	White	
1	B	G5A	Classroom G5 Closet A adjacent to Windows	Expansion Seam Caulking	Assumed	60	LF	0	LF		
1	B	G5A	Classroom G5 Closet A adjacent to Windows	CMU Block Wall	Non Suspect ACM	60	SF	N/A	SF		
1	B	G5A	Classroom G5 Closet A adjacent to Windows	Concrete Ceiling	Non Suspect ACM	10	SF	N/A	SF		
1	B	G5A	Classroom G5 Closet A adjacent to Windows	Concrete Floor	Non Suspect ACM	10	SF	N/A	SF		
1	B	G5B	Classroom G5 Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	40	LF	N/A	LF		
1	B	G5B	Classroom G5 Restroom	Concrete Ceiling	Non Suspect ACM	50	SF	N/A	SF		
1	B	G5B	Classroom G5 Restroom	Fiberglass Duct Insulation	Non Suspect ACM	18	SF	N/A	SF		
1	B	G5B	Classroom G5 Restroom	Ceiling Tile 2' x 4'	NAD	50	SF	N/A	SF		
1	B	G5B	Classroom G5 Restroom	Ceramic Tile Wall	Non Suspect ACM	150	SF	N/A	SF		
1	B	G5B	Classroom G5 Restroom	Ceramic Tile Floor	Non Suspect ACM	50	SF	N/A	SF		
1	B	G5C	Classroom G5 Closet B adjacent to Hallway	Expansion Seam Caulking	Assumed	30	LF	0	LF		
1	B	G5C	Classroom G5 Closet B adjacent to Hallway	CMU Block Wall	Non Suspect ACM	300	SF	N/A	SF		
1	B	G5C	Classroom G5 Closet B adjacent to Hallway	Concrete Ceiling	Non Suspect ACM	20	SF	N/A	SF		
1	B	G5C	Classroom G5 Closet B adjacent to Hallway	Concrete Floor	Non Suspect ACM	20	SF	N/A	SF		
1	B	G6B	G6 Storage	Concrete Ceiling	Non Suspect ACM	48	SF	N/A	SF		
1	B	G6B	G6 Storage	Concrete Floor	Non Suspect ACM	48	SF	N/A	SF		
1	B	G6B	G6 Storage	CMU Block Wall	Non Suspect ACM	200	SF	N/A	SF		
1	B	G6B	G6 Storage	Fiberglass Pipe Insulation	Non Suspect ACM	4	LF	N/A	LF		
1	B	G8	Classroom G8	Mastic associated with Floor Tile	NAD	830	SF	N/A	SF	Black	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G8	Classroom G8	Floor Tile VAT 12" x 12"	NAD	830	SF	N/A	SF	Multi	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	G8	Classroom G8	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	5	EA	N/A	EA		
1	B	G8	Classroom G8	Fiberglass Pipe Insulation	Non Suspect ACM	80	LF	N/A	LF		
1	B	G8	Classroom G8	Paint associated with Wall, Brick	NAD	720	SF	N/A	SF		
1	B	G8	Classroom G8	Brick Wall	Non Suspect ACM	720	SF	N/A	SF		
1	B	G8	Classroom G8	Plaster Ceiling	NAD	830	SF	N/A	SF		
1	B	G8A	Classroom G8 Coat Room	Plaster Wall	NAD	200	SF	N/A	SF		
1	B	G8A	Classroom G8 Coat Room	Plaster Ceiling	NAD	25	SF	N/A	SF		
1	B	G8A	Classroom G8 Coat Room	Floor Tile VAT 12" x 12"	Assumed	25	SF	0	SF	Multi	
1	B	G8B	Classroom G8 Closet	Plaster Wall	NAD	300	SF	N/A	SF		
1	B	G8B	Classroom G8 Closet	Plaster Ceiling	NAD	40	SF	N/A	SF		
1	B	G8B	Classroom G8 Closet	Floor Tile VAT 12" x 12"	Assumed	40	SF	0	SF	Multi	
1	B	G9	Classroom G9	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	B	G9	Classroom G9	Paint associated with Wall, Brick	NAD	600	SF	N/A	SF		
1	B	G9	Classroom G9	Brick Wall	Non Suspect ACM	600	SF	N/A	SF		
1	B	G9	Classroom G9	Plaster Ceiling	NAD	720	SF	N/A	SF		
1	B	G9	Classroom G9	Floor Tile VAT 12" x 12"	Assumed	720	SF	0	SF	Multi	
1	B	G9A	Classroom G9 Coat Room	Plaster Wall	NAD	300	SF	N/A	SF		
1	B	G9A	Classroom G9 Coat Room	Paint associated with Ceiling, Concrete	NAD	100	SF	N/A	SF		
1	B	G9A	Classroom G9 Coat Room	Concrete Ceiling	Non Suspect ACM	100	SF	N/A	SF		
1	B	G9A	Classroom G9 Coat Room	Floor Tile VAT 12" x 12"	Assumed	40	SF	0	SF	Multi	
1	B	H01	Hallway from Classrooms G8 to G9	Paint associated with Ductwork, Exterior	NAD	1000	SF	N/A	SF		
1	B	H01	Hallway from Classrooms G8 to G9	Pipe Fitting Insulation	Confirmed	5	EA	0	EA		
1	B	H01	Hallway from Classrooms G8 to G9	Pipe Insulation 2-6 inch	Confirmed	45	LF	0	LF		
1	B	H01	Hallway from Classrooms G8 to G9	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	10	EA	N/A	EA		
1	B	H01	Hallway from Classrooms G8 to G9	Fiberglass Pipe Insulation	Non Suspect ACM	400	LF	N/A	LF		
1	B	H01	Hallway from Classrooms G8 to G9	Paint associated with Wall, Brick	NAD	1600	SF	N/A	SF		
1	B	H01	Hallway from Classrooms G8 to G9	Brick Wall	Non Suspect ACM	1500	SF	N/A	SF		
1	B	H01	Hallway from Classrooms G8 to G9	Paint associated with Ceiling, Concrete	NAD	860	SF	N/A	SF		
1	B	H01	Hallway from Classrooms G8 to G9	Concrete Ceiling	Non Suspect ACM	860	SF	N/A	SF		
1	B	H01	Hallway from Classrooms G8 to G9	Paint associated with Floor, Concrete	Assumed	860	SF	0	SF		
1	B	H01	Hallway from Classrooms G8 to G9	Concrete Floor	Non Suspect ACM	860	SF	N/A	SF		
1	B	H02	Hallway at Ballet Room	Paint associated with Ductwork, Exterior	NAD	1000	SF	N/A	SF		
1	B	H02	Hallway at Ballet Room	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	5	EA	N/A	EA		
1	B	H02	Hallway at Ballet Room	Fiberglass Pipe Insulation	Non Suspect ACM	150	LF	N/A	LF		
1	B	H02	Hallway at Ballet Room	Paint associated with Wall, Brick	NAD	2000	SF	N/A	SF		
1	B	H02	Hallway at Ballet Room	Brick Wall	Non Suspect ACM	1400	SF	N/A	SF		
1	B	H02	Hallway at Ballet Room	Paint associated with Ceiling, Concrete	NAD	1064	SF	N/A	SF		
1	B	H02	Hallway at Ballet Room	Concrete Ceiling	Non Suspect ACM	1064	SF	N/A	SF		
1	B	H02	Hallway at Ballet Room	Paint associated with Floor, Concrete	Assumed	1064	SF	0	SF		
1	B	H02	Hallway at Ballet Room	Concrete Floor	Non Suspect ACM	1064	SF	N/A	SF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Paint associated with Ductwork, Exterior	NAD	1000	SF	N/A	SF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Pipe Fitting Insulation	Confirmed	6	EA	0	EA		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Pipe Insulation >6 inches	Confirmed	12	LF	0	LF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Pipe Insulation 2-6 inch	Confirmed	35	LF	0	LF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	B	H03	Hallway from Music Room G1 to Classroom G5	Fiberglass Pipe Fitting Insulation	Non Suspect ACM	25	EA	N/A	EA		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Fiberglass Pipe Insulation	Non Suspect ACM	700	LF	N/A	LF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Paint associated with Wall, Brick	NAD	2400	SF	N/A	SF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Brick Wall	Non Suspect ACM	2400	SF	N/A	SF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Paint associated with Ceiling, Concrete	NAD	1280	SF	N/A	SF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Concrete Ceiling	Non Suspect ACM	1280	SF	N/A	SF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Paint associated with Floor, Concrete	Assumed	1080	SF	0	SF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Concrete Floor	Non Suspect ACM	1080	SF	N/A	SF		
1	B	H03	Hallway from Music Room G1 to Classroom G5	Floor Tile VAT 12" x 12"	Assumed	200	SF	0	SF	White	
1	B	HB0	Hallway from Classrooms G-6 to G-7	CMU Block Wall	Non Suspect ACM	675	SF	N/A	SF		
1	B	HB0	Hallway from Classrooms G-6 to G-7	Fiberglass Pipe Insulation	Non Suspect ACM	200	LF	N/A	LF		
1	B	HB0	Hallway from Classrooms G-6 to G-7	Concrete Ceiling	Non Suspect ACM	1350	SF	N/A	SF		
1	B	HB0	Hallway from Classrooms G-6 to G-7	Fiberglass Duct Insulation	Non Suspect ACM	96	SF	N/A	SF		
1	B	HB0	Hallway from Classrooms G-6 to G-7	Paint associated with Wall, CMU	NAD	2500	SF	N/A	SF		
1	B	HB0	Hallway from Classrooms G-6 to G-7	Expansion Seam Caulking	Assumed	220	LF	0	LF		
1	B	HB0	Hallway from Classrooms G-6 to G-7	CMU Block Wall	Non Suspect ACM	2200	SF	N/A	SF		
1	B	HB0	Hallway from Classrooms G-6 to G-7	Ceiling Tile 2' x 4'	NAD	1350	SF	N/A	SF		
1	B	HB0	Hallway from Classrooms G-6 to G-7	Floor Tile VAT 12" x 12"	Assumed	1350	SF	0	SF	White	
1	B	HB1	Hallway adjacent to Cafeteria	CMU Block Wall	Non Suspect ACM	600	SF	N/A	SF		
1	B	HB1	Hallway adjacent to Cafeteria	Fiberglass Pipe Insulation	Non Suspect ACM	300	LF	N/A	LF		
1	B	HB1	Hallway adjacent to Cafeteria	Concrete Ceiling	Non Suspect ACM	1000	SF	N/A	SF		
1	B	HB1	Hallway adjacent to Cafeteria	Paint associated with Wall, CMU	NAD	2000	SF	N/A	SF		
1	B	HB1	Hallway adjacent to Cafeteria	Expansion Seam Caulking	Assumed	140	LF	0	LF		
1	B	HB1	Hallway adjacent to Cafeteria	CMU Block Wall	Non Suspect ACM	2000	SF	N/A	SF		
1	B	HB1	Hallway adjacent to Cafeteria	Ceiling Tile 2' x 4'	NAD	1000	SF	N/A	SF		
1	B	HB1	Hallway adjacent to Cafeteria	Floor Tile VAT 12" x 12"	Assumed	1000	SF	0	SF	White	
1	B	HB2	Hallway from Classrooms G-4 to G-5	CMU Block Wall	Non Suspect ACM	675	SF	N/A	SF		
1	B	HB2	Hallway from Classrooms G-4 to G-5	Fiberglass Pipe Insulation	Non Suspect ACM	1080	LF	N/A	LF		
1	B	HB2	Hallway from Classrooms G-4 to G-5	Concrete Ceiling	Non Suspect ACM	1350	SF	N/A	SF		
1	B	HB2	Hallway from Classrooms G-4 to G-5	Fiberglass Duct Insulation	Non Suspect ACM	400	SF	N/A	SF		
1	B	HB2	Hallway from Classrooms G-4 to G-5	Mastic associated with Floor Tile	NAD	1350	SF	N/A	SF	Yellow	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	HB2	Hallway from Classrooms G-4 to G-5	Paint associated with Wall, CMU	NAD	2500	SF	N/A	SF		
1	B	HB2	Hallway from Classrooms G-4 to G-5	Expansion Seam Caulking	Assumed	220	LF	0	LF		
1	B	HB2	Hallway from Classrooms G-4 to G-5	CMU Block Wall	Non Suspect ACM	2200	SF	N/A	SF		
1	B	HB2	Hallway from Classrooms G-4 to G-5	Ceiling Tile 2' x 4'	NAD	1350	SF	N/A	SF		
1	B	HB2	Hallway from Classrooms G-4 to G-5	Floor Tile VAT 12" x 12"	NAD	1350	SF	N/A	SF	White	2 samples floor tile and 2 samples mastic NAD 3/9/2023 TF/CRI
1	B	Kitchen	Kitchen	Fireproofing	NAD	220	SF	N/A	SF		
1	B	Kitchen	Kitchen	Fiberglass Pipe Insulation	Non Suspect ACM	210	LF	N/A	LF		
1	B	Kitchen	Kitchen	Concrete Ceiling	Non Suspect ACM	2000	SF	N/A	SF		
1	B	Kitchen	Kitchen	Fiberglass Duct Insulation	Non Suspect ACM	400	SF	N/A	SF		
1	B	Kitchen	Kitchen	CMU Block Wall	Non Suspect ACM	540	SF	N/A	SF		
1	B	Kitchen	Kitchen	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	B	Kitchen	Kitchen	Paint associated with Wall, CMU	NAD	1800	SF	N/A	SF		
1	B	Kitchen	Kitchen	Expansion Seam Caulking	Assumed	180	LF	0	LF		
1	B	Kitchen	Kitchen	CMU Block Wall	Non Suspect ACM	1800	SF	N/A	SF		
1	B	Kitchen	Kitchen	Ceiling Tile 2' x 4'	NAD	2000	SF	N/A	SF		
1	B	Kitchen	Kitchen	Ceramic Tile Floor	Non Suspect ACM	2000	SF	N/A	SF		
1	B	Men's	Men's Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	80	LF	N/A	LF		
1	B	Men's	Men's Restroom	Concrete Ceiling	Non Suspect ACM	100	SF	N/A	SF		
1	B	Men's	Men's Restroom	Paint associated with Wall, CMU	NAD	400	SF	N/A	SF		
1	B	Men's	Men's Restroom	Expansion Seam Caulking	Assumed	60	LF	0	LF		
1	B	Men's	Men's Restroom	CMU Block Wall	Non Suspect ACM	400	SF	N/A	SF		
1	B	Men's	Men's Restroom	Ceiling Tile 2' x 4'	NAD	100	SF	N/A	SF		
1	B	Men's	Men's Restroom	Ceramic Tile Floor	Non Suspect ACM	100	SF	N/A	SF		
1	B	S01	Stairwell adjacent to Classroom G10	Plaster Wall	NAD	600	SF	N/A	SF		
1	B	S01	Stairwell adjacent to Classroom G10	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	B	S01	Stairwell adjacent to Classroom G10	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	B	S01	Stairwell adjacent to Classroom G10	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	B	S02	Dyre Stairwell A adjacent to Classroom G1	Plaster Wall	NAD	600	SF	N/A	SF		
1	B	S02	Dyre Stairwell A adjacent to Classroom G1	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	B	S02	Dyre Stairwell A adjacent to Classroom G1	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	B	S02	Dyre Stairwell A adjacent to Classroom G1	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	B	S03	Boiler Room Stairs	Fiberglass Pipe Insulation	Non Suspect ACM	20	LF	N/A	LF		
1	B	S03	Boiler Room Stairs	Paint associated with Wall, Brick	NAD	400	SF	N/A	SF		
1	B	S03	Boiler Room Stairs	Brick Wall	Non Suspect ACM	400	SF	N/A	SF		
1	B	S03	Boiler Room Stairs	Paint associated with Ceiling, Concrete	NAD	100	SF	N/A	SF		
1	B	S03	Boiler Room Stairs	Concrete Ceiling	Non Suspect ACM	100	SF	N/A	SF		
1	B	S03	Boiler Room Stairs	Paint associated with Floor, Concrete	Assumed	100	SF	0	SF		
1	B	S03	Boiler Room Stairs	Concrete Floor	Non Suspect ACM	100	SF	N/A	SF		
1	B	S04	Dyre Stairwell C adjacent to Classroom G5	Paint associated with Wall, CMU	NAD	600	SF	N/A	SF		
1	B	S04	Dyre Stairwell C adjacent to Classroom G5	Expansion Seam Caulking	Assumed	60	LF	0	LF		
1	B	S04	Dyre Stairwell C adjacent to Classroom G5	CMU Block Wall	Non Suspect ACM	600	SF	N/A	SF		
1	B	S04	Dyre Stairwell C adjacent to Classroom G5	Metal Ceiling	Non Suspect ACM	240	SF	N/A	SF		
1	B	S04	Dyre Stairwell C adjacent to Classroom G5	Paint associated with Floor, Concrete	Assumed	240	SF	0	SF		
1	B	S04	Dyre Stairwell C adjacent to Classroom G5	Concrete Floor	Non Suspect ACM	240	SF	N/A	SF		

Element	Floor	Space #	On Site Room Name	Material Description	Confirmed/Assumed/ NAD/Non Suspect ACM	Amount of Material	Unit of Measurement (UOM)	Amount of Damage	UOM	Color	Comments/Description/Notes
1	B	S05	Dyre Stairwell B adjacent to Classroom G3	Plaster Wall	NAD	600	SF	N/A	SF		
1	B	S05	Dyre Stairwell B adjacent to Classroom G3	Plaster Ceiling	NAD	300	SF	N/A	SF		
1	B	S05	Dyre Stairwell B adjacent to Classroom G3	Paint associated with Floor, Concrete	Assumed	300	SF	0	SF		
1	B	S05	Dyre Stairwell B adjacent to Classroom G3	Concrete Floor	Non Suspect ACM	300	SF	N/A	SF		
1	B	SB0	Stairwell adjacent to Men's Restroom	Paint associated with Wall, CMU	NAD	400	SF	N/A	SF		
1	B	SB0	Stairwell adjacent to Men's Restroom	Expansion Seam Caulking	Assumed	30	LF	0	LF		
1	B	SB0	Stairwell adjacent to Men's Restroom	CMU Block Wall	Non Suspect ACM	300	SF	N/A	SF		
1	B	SB0	Stairwell adjacent to Men's Restroom	Metal Ceiling	Non Suspect ACM	120	SF	N/A	SF		
1	B	SB0	Stairwell adjacent to Men's Restroom	Paint associated with Floor, Concrete	Assumed	120	SF	0	SF		
1	B	SB0	Stairwell adjacent to Men's Restroom	Concrete Floor	Non Suspect ACM	120	SF	N/A	SF		
1	B	SB1	Stairwell adjacent to Classroom G-6	Paint associated with Wall, CMU	NAD	600	SF	N/A	SF		
1	B	SB1	Stairwell adjacent to Classroom G-6	Expansion Seam Caulking	Assumed	60	LF	0	LF		
1	B	SB1	Stairwell adjacent to Classroom G-6	CMU Block Wall	Non Suspect ACM	600	SF	N/A	SF		
1	B	SB1	Stairwell adjacent to Classroom G-6	Metal Ceiling	Non Suspect ACM	240	SF	N/A	SF		
1	B	SB3	Stairwell adjacent to Women's Restroom	Paint associated with Wall, CMU	NAD	300	SF	N/A	SF		
1	B	SB3	Stairwell adjacent to Women's Restroom	Expansion Seam Caulking	Assumed	30	LF	0	LF		
1	B	SB3	Stairwell adjacent to Women's Restroom	CMU Block Wall	Non Suspect ACM	300	SF	N/A	SF		
1	B	SB3	Stairwell adjacent to Women's Restroom	Metal Ceiling	Non Suspect ACM	120	SF	N/A	SF		
1	B	SB3	Stairwell adjacent to Women's Restroom	Paint associated with Floor, Concrete	Assumed	120	SF	0	SF		
1	B	SB3	Stairwell adjacent to Women's Restroom	Concrete Floor	Non Suspect ACM	120	SF	N/A	SF		
1	B	Women's	Women's Restroom	CMU Block Wall	Non Suspect ACM	120	SF	N/A	SF		
1	B	Women's	Women's Restroom	Fiberglass Pipe Insulation	Non Suspect ACM	25	LF	N/A	LF		
1	B	Women's	Women's Restroom	Fireproofing	NAD	40	SF	N/A	SF		
1	B	Women's	Women's Restroom	Concrete Ceiling	Non Suspect ACM	100	SF	N/A	SF		
1	B	Women's	Women's Restroom	Paint associated with Wall, CMU	NAD	360	SF	N/A	SF		
1	B	Women's	Women's Restroom	Expansion Seam Caulking	Assumed	60	LF	0	LF		
1	B	Women's	Women's Restroom	CMU Block Wall	Non Suspect ACM	600	SF	N/A	SF		
1	B	Women's	Women's Restroom	Ceiling Tile 2' x 4'	NAD	100	SF	N/A	SF		
1	B	Women's	Women's Restroom	Ceramic Tile Floor	Non Suspect ACM	240	SF	N/A	SF		



## APPENDIX B

---

### LAB RESULTS



# Electronic Chain of Custody

Environmental Testing Laboratories, Inc.



37575 W Huron River Drive  
Romulus, Michigan 48174  
(734) 955-6600, Fax: (734) 955-6604

**Submitting Client :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE - 19713

**Project Location:** Edmunds, H

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**Sample Type:** ACM

**ETL Project:** 255866

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1471894	28500001	2054	111	Classroom 111	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 15:40
1471895	28500002	2054	111	Classroom 111	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 15:41
1471896	28500003	2502	111	Classroom 111	Mastic a/w Floor Tile - Yellow	2023-03-09 15:42
1471897	28500004	2502	111	Classroom 111	Mastic a/w Floor Tile - Yellow	2023-03-09 15:42
1471898	28500005	2051	111B	Classroom 111 Coat Room	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 15:45
1471899	28500006	2051	111B	Classroom 111 Coat Room	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 15:46
1471900	28500007	2502	111B	Classroom 111 Coat Room	Mastic a/w Floor Tile - Yellow	2023-03-09 15:46
1471901	28500008	2502	111B	Classroom 111 Coat Room	Mastic a/w Floor Tile - Yellow	2023-03-09 15:47
1471902	28500009	2036	108A	Classroom 108 Coat Room	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 15:54
1471903	28500010	2036	108A	Classroom 108 Coat Room	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 15:55

**Project Location:** Edmunds, H

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**Sample Type:** ACM

**ETL Project:** 255866

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1471904	28500011	2502	108A	Classroom 108 Coat Room	Mastic a/w Floor Tile - Yellow	2023-03-09 15:55
1471905	28500012	2502	108A	Classroom 108 Coat Room	Mastic a/w Floor Tile - Yellow	2023-03-09 15:56
1471906	28500013	2076	105	Classroom 105	Floor Tile VAT 12" x 12" a/w N/A - Tan	2023-03-09 16:00
1471907	28500014	2076	105	Classroom 105	Floor Tile VAT 12" x 12" a/w N/A - Tan	2023-03-09 16:02
1471908	28500015	2520	105	Classroom 105	Mastic a/w Floor Tile - N/A	2023-03-09 16:03
1471909	28500016	2520	105	Classroom 105	Mastic a/w Floor Tile - N/A	2023-03-09 16:03
1471910	28500017	1702	105	Classroom 105	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-09 16:05
1471911	28500018	20116	G01B	Center Gymnasium Office	Floor Tile VAT 12" x 12" a/w N/A - Tan	2023-03-09 16:10
1471912	28500019	20116	G01B	Center Gymnasium Office	Floor Tile VAT 12" x 12" a/w N/A - Tan	2023-03-09 16:11
1471913	28500020	2502	G01B	Center Gymnasium Office	Mastic a/w Floor Tile - Yellow	2023-03-09 16:12
1471914	28500021	2502	G01B	Center Gymnasium Office	Mastic a/w Floor Tile - Yellow	2023-03-09 16:13
1471915	28500022	1702	G01B	Center Gymnasium Office	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-09 16:14
1471916	28500023	2084	104	Classroom 104	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 16:19
1471917	28500024	2084	104	Classroom 104	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 16:19



**Project Location:** Edmunds, H

**ETL Project:** 255866

**Ship Date:** 2023-03-14

**ULCS:** 7250

**Tracking Number:** 1ZF11A090299054478, UPS

**EP #:** EP2023-0924-7250

**Sample Type:** ACM

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1471918	28500025	2502	104	Classroom 104	Mastic a/w Floor Tile - Yellow	2023-03-09 16:20
1471919	28500026	2502	104	Classroom 104	Mastic a/w Floor Tile - Yellow	2023-03-09 16:22
1471920	28500027	2056	H15	Hallway from Classroom 101 to Classroom 106	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-09 16:24
1471921	28500028	2056	H15	Hallway from Classroom 101 to Classroom 106	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-09 16:25
1471922	28500029	2502	H15	Hallway from Classroom 101 to Classroom 106	Mastic a/w Floor Tile - Yellow	2023-03-09 16:26
1471923	28500030	2502	H15	Hallway from Classroom 101 to Classroom 106	Mastic a/w Floor Tile - Yellow	2023-03-09 16:26
1471924	28500031	20114	121B	Nurse's Office #3	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 16:32
1471925	28500032	20114	121B	Nurse's Office #3	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 16:32
1471926	28500033	2503	121B	Nurse's Office #3	Mastic a/w Floor Tile - Yellow	2023-03-09 16:34
1471927	28500034	2503	121B	Nurse's Office #3	Mastic a/w Floor Tile - Yellow	2023-03-09 16:35
1471928	28500035	1702	121B	Nurse's Office #3	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-09 16:35
1471929	28500036	2101	121B	Nurse's Office #3	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 16:57
1471930	28500037	2101	121B	Nurse's Office #3	Joint Compound Wall a/w N/A - N/A	2023-03-09 16:57
1471931	28500039	2101	121	Nurse's Office	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 17:06

**Project Location:** Edmunds, H

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**Sample Type:** ACM

**ETL Project:** 255866

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1471932	28500040	2101	121	Nurse's Office	Joint Compound Wall a/w N/A - N/A	2023-03-09 17:06
1471933	28500041	2101	121A	Nurse's Office #2	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 17:10
1471934	28500042	2101	121A	Nurse's Office #2	Joint Compound Wall a/w N/A - N/A	2023-03-09 17:10
1471935	28500043	1903	AUD	Auditorium	Auditorium Plaster Walls a/w N/A - N/A	2023-03-09 17:17
1471936	28500044	1903	AUD	Auditorium	Auditorium Plaster Walls a/w N/A - N/A	2023-03-09 17:19
1471937	28500045	1903	AUD	Auditorium	Auditorium Plaster Walls a/w N/A - N/A	2023-03-09 17:21
1471938	28500046	1903	AUD	Auditorium	Auditorium Plaster Walls a/w N/A - N/A	2023-03-09 17:22
1471939	28500047	1903	AUD	Auditorium	Auditorium Plaster Walls a/w N/A - N/A	2023-03-09 17:26
1471940	28500048	1903	AUD	Auditorium	Auditorium Plaster Walls a/w N/A - N/A	2023-03-09 17:29
1471941	28500049	1903	AUD	Auditorium	Auditorium Plaster Walls a/w N/A - N/A	2023-03-09 17:33
1471942	28500050	2101	120K	Copy Room in front of Storage Room	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 17:49
1471943	28500052	2101	120G	Staff Office C	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 17:57
1471944	28500053	2101	120G	Staff Office C	Joint Compound Wall a/w N/A - N/A	2023-03-09 17:57
1471945	28500054	2101	102A	Dean's Office	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 18:04

**Project Location:** Edmunds, H

**ETL Project:** 255866

**Ship Date:** 2023-03-14

**ULCS:** 7250

**Tracking Number:** 1ZF11A090299054478, UPS

**EP #:** EP2023-0924-7250

**Sample Type:** ACM

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1471946	28500056	2101	120D	Staff Office adjacent to Vice Principal's Office	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 18:08
1471947	28500058	0601	8	Boiler Room	Boiler Breeching a/w N/A - N/A	2023-03-09 18:18
1471948	28500059	0601	8	Boiler Room	Boiler Breeching a/w N/A - N/A	2023-03-09 18:20
1471949	28500060	2104	G3	Classroom G3	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 18:29
1471950	28500061	2104	G3	Classroom G3	Joint Compound Wall a/w N/A - N/A	2023-03-09 18:29
1471951	28500062	2104	G3	Classroom G3	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 18:32
1471952	28500063	2104	G3	Classroom G3	Joint Compound Wall a/w N/A - N/A	2023-03-09 18:32
1471953	28500064	2092	G3	Classroom G3	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 18:35
1471954	28500065	2092	G3	Classroom G3	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 18:35
1471955	28500066	2501	G3	Classroom G3	Mastic a/w Floor Tile - Yellow	2023-03-09 18:36
1471956	28500067	2501	G3	Classroom G3	Mastic a/w Floor Tile - Yellow	2023-03-09 18:37
1471957	28500068	2003	HB2	Hallway from Classrooms G-4 to G-5	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-09 18:40
1471958	28500069	2501	HB2	Hallway from Classrooms G-4 to G-5	Mastic a/w Floor Tile - Yellow	2023-03-09 18:41
1471959	28500070	2501	HB2	Hallway from Classrooms G-4 to G-5	Mastic a/w Floor Tile - Yellow	2023-03-09 18:43

**Project Location:** Edmunds, H

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**Sample Type:** ACM

**ETL Project:** 255866

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1471960	28500071	2003	HB2	Hallway from Classrooms G-4 to G-5	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-09 18:42
1471961	28500072	2093	G2	Classroom G2	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 18:47
1471962	28500073	2093	G2	Classroom G2	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 18:49
1471963	28500074	2522	G2	Classroom G2	Mastic a/w Floor Tile - Black	2023-03-09 18:49
1471964	28500075	2522	G2	Classroom G2	Mastic a/w Floor Tile - Black	2023-03-09 18:50
1471965	28500076	2104	G2	Classroom G2	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 18:53
1471966	28500077	2104	G2	Classroom G2	Joint Compound Wall a/w N/A - N/A	2023-03-09 18:53
1471967	28500078	20120	G4	Classroom G4	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 18:59
1471968	28500079	20120	G4	Classroom G4	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 19:00
1471969	28500080	2501	G4	Classroom G4	Mastic a/w Floor Tile - Yellow	2023-03-09 19:00
1471970	28501001	2501	G4	Classroom G4	Mastic a/w Floor Tile - Yellow	2023-03-09 19:07
1471971	28501002	1701	G4	Classroom G4	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-09 19:08
1471972	28501003	1701	G-6A	G6 Restroom	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-09 19:12
1471973	28501004	20137	G8	Classroom G8	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 19:18

**Project Location:** Edmunds, H

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**Sample Type:** ACM

**ETL Project:** 255866

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1471974	28501005	20137	G8	Classroom G8	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 19:19
1471975	28501006	2523	G8	Classroom G8	Mastic a/w Floor Tile - Black	2023-03-09 19:19
1471976	28501007	2523	G8	Classroom G8	Mastic a/w Floor Tile - Black	2023-03-09 19:20
1471977	28501008	20125	G10A	G10A Office	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 19:23
1471978	28501009	20125	G10A	G10A Office	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-09 19:23
1471979	28501010	2501	G10A	G10A Office	Mastic a/w Floor Tile - Yellow	2023-03-09 19:24
1471980	28501011	2501	G10A	G10A Office	Mastic a/w Floor Tile - Yellow	2023-03-09 19:24
1471981	28501012	2104	G10B	G10B Office	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 19:28
1471982	28501014	1701	G10B	G10B Office	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-09 19:29
1471983	28501015	2104	G10D	G10D Office	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-09 19:32
1471984	28501016	2104	G10D	G10D Office	Joint Compound Wall a/w N/A - N/A	2023-03-09 19:32
1471985	28501017	2201	G12	Ballet Room G12	Linoleum a/w N/A - Blue	2023-03-09 19:37
1471986	28501018	2201	G12	Ballet Room G12	Linoleum a/w N/A - Blue	2023-03-09 19:37
1471987	28501019	2603	H14	Hallway from Classroom 111 to Classroom 107	Leveling Compound a/w Floor Tile - Grey	2023-03-09 19:53

**Project Location:** Edmunds, H

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**Sample Type:** ACM

**ETL Project:** 255866

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1471988	29340001	0414	G01G	Gymnasium Storage Room	Fireproofing a/w Support Post, Metal - Grey	2023-03-08 15:36
1471989	29340002	0414	G01G	Gymnasium Storage Room	Fireproofing a/w Support Post, Metal - Grey	2023-03-08 15:37
1471990	29340003	0414	G01G	Gymnasium Storage Room	Fireproofing a/w Support Post, Metal - Grey	2023-03-08 15:38
1471991	29340004	20109	307	Classroom 307	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 15:53
1471992	29340005	20109	307	Classroom 307	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 15:53
1471993	29340006	2506	307	Classroom 307	Mastic a/w Floor Tile - Yellow	2023-03-08 15:58
1471994	29340007	2506	307	Classroom 307	Mastic a/w Floor Tile - Yellow	2023-03-08 15:59
1471995	29340008	2083	308	Classroom 308	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 16:04
1471996	29340009	2083	308	Classroom 308	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 16:04
1471997	29340010	2506	308	Classroom 308	Mastic a/w Floor Tile - Yellow	2023-03-08 16:08
1471998	29340011	2506	308	Classroom 308	Mastic a/w Floor Tile - Yellow	2023-03-08 16:09
1471999	29340012	2074	311	Classroom 311	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 16:19
1472000	29340013	2074	311	Classroom 311	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 16:19
1472001	29340014	2506	311	Classroom 311	Mastic a/w Floor Tile - Yellow	2023-03-08 16:21

**Project Location:** Edmunds, H

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**Sample Type:** ACM

**ETL Project:** 255866

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1472002	29340015	2506	311	Classroom 311	Mastic a/w Floor Tile - Yellow	2023-03-08 16:21
1472003	29340016	20134	301	Classroom 301	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 16:29
1472004	29340017	20134	301	Classroom 301	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 16:29
1472005	29340018	2511	301	Classroom 301	Mastic a/w Floor Tile - Yellow	2023-03-08 16:30
1472006	29340019	2511	301	Classroom 301	Mastic a/w Floor Tile - Yellow	2023-03-08 16:30
1472007	29340020	2095	305A	Classroom 305 A	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-08 16:35
1472008	29340021	2095	305A	Classroom 305 A	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-08 16:35
1472009	29340022	2506	305A	Classroom 305 A	Mastic a/w Floor Tile - Yellow	2023-03-08 16:38
1472010	29340023	2506	305A	Classroom 305 A	Mastic a/w Floor Tile - Yellow	2023-03-08 16:38
1472011	29340024	2103	305A	Classroom 305 A	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-08 16:45
1472012	29340025	2103	305A	Classroom 305 A	Joint Compound Wall a/w N/A - N/A	2023-03-08 16:45
1472013	29340026	2103	305	Classroom 305	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-08 16:51
1472014	29340027	2103	305	Classroom 305	Joint Compound Wall a/w N/A - N/A	2023-03-08 16:51
1472015	29340028	2103	307	Classroom 307	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-08 16:56

**Project Location:** Edmunds, H

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**Sample Type:** ACM

**ETL Project:** 255866

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1472016	29340029	2103	307	Classroom 307	Joint Compound Wall a/w N/A - N/A	2023-03-08 16:56
1472017	29340030	2103	303B	Office 303A	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-08 17:01
1472018	29340031	2103	303B	Office 303A	Joint Compound Wall a/w N/A - N/A	2023-03-08 17:01
1472019	29340032	2103	302A	Special Education Classroom 302A	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-08 17:06
1472020	29340033	2103	302A	Special Education Classroom 302A	Joint Compound Wall a/w N/A - N/A	2023-03-08 17:06
1472021	29340034	1704	305A	Classroom 305 A	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-08 17:08
1472022	29340035	1704	303B	Office 303A	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-08 17:11
1472023	29340036	1704	302A	Special Education Classroom 302A	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-08 17:15
1472024	29340037	0904	310	Classroom 310	Pipe Insulation 2-6 inch a/w N/A - N/A	2023-03-08 17:28
1472025	29340038	0904	310	Classroom 310	Pipe Insulation 2-6 inch a/w N/A - N/A	2023-03-08 17:31
1472026	29340039	0904	310	Classroom 310	Pipe Insulation 2-6 inch a/w N/A - N/A	2023-03-08 17:33
1472027	29340040	2007	208	Science Lab Classroom 208	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-08 18:02
1472028	29340041	2007	208	Science Lab Classroom 208	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-08 18:03
1472029	29340042	2519	208	Science Lab Classroom 208	Mastic a/w Floor Tile - N/A	2023-03-08 18:04



**Project Location:** Edmunds, H

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**Sample Type:** ACM

**ETL Project:** 255866

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1472030	29340043	2519	208	Science Lab Classroom 208	Mastic a/w Floor Tile - N/A	2023-03-08 18:04
1472031	29340044	1703	208	Science Lab Classroom 208	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-08 18:06
1472032	29340045	1703	207	Classroom 207	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-08 18:11
1472033	29340046	2094	H27	Hallway from Classroom 207 to Classroom 212	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-08 18:14
1472034	29340047	2512	H27	Hallway from Classroom 207 to Classroom 212	Mastic a/w Floor Tile - Yellow	2023-03-08 18:15
1472035	29340048	2059	201	Classroom 201	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 18:23
1472036	29340049	2059	201	Classroom 201	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 18:23
1472037	29340050	2504	201	Classroom 201	Mastic a/w Floor Tile - Yellow	2023-03-08 18:24
1472038	29340051	2504	201	Classroom 201	Mastic a/w Floor Tile - Yellow	2023-03-08 18:27
1472039	29340052	2102	203	Classroom 203	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-08 18:33
1472040	29340053	2102	203	Classroom 203	Joint Compound Wall a/w N/A - N/A	2023-03-08 18:33
1472041	29340054	1703	203	Classroom 203	Ceiling Tile 2' x 4' a/w N/A - N/A	2023-03-08 18:35
1472042	29340055	2035	H29	Hallway at Classroom 203	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-08 18:39
1472043	29340056	2035	H29	Hallway at Classroom 203	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-08 18:39

**Project Location:** Edmunds, H

**ETL Project:** 255866

**Ship Date:** 2023-03-14

**Tracking Number:** 1ZF11A090299054478, UPS

**ULCS:** 7250

**Sample Type:** ACM

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1472044	29340057	2505	H29	Hallway at Classroom 203	Mastic a/w Floor Tile - Yellow	2023-03-08 18:40
1472045	29340058	2505	H29	Hallway at Classroom 203	Mastic a/w Floor Tile - Yellow	2023-03-08 18:40
1472046	29340059	2102	210C	Teacher's Lounge	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-03-08 18:47
1472047	29340060	2102	210C	Teacher's Lounge	Joint Compound Wall a/w N/A - N/A	2023-03-08 18:47
1472048	29340061	2046	203C	Classroom 204A	Floor Tile VAT 12" x 12" a/w N/A - Tan	2023-03-08 20:13
1472049	29340062	2046	203C	Classroom 204A	Floor Tile VAT 12" x 12" a/w N/A - Tan	2023-03-08 20:13
1472050	29340063	2521	203C	Classroom 204A	Mastic a/w Floor Tile - Black	2023-03-08 20:16
1472051	29340064	2521	203C	Classroom 204A	Mastic a/w Floor Tile - Black	2023-03-08 20:16
1472052	29340065	20117	G01A	Gymnasium Office adjacent to Exit	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 20:53
1472053	29340066	20117	G01A	Gymnasium Office adjacent to Exit	Floor Tile VAT 12" x 12" a/w N/A - Multi	2023-03-08 20:53
1472054	29340067	2502	G01A	Gymnasium Office adjacent to Exit	Mastic a/w Floor Tile - Yellow	2023-03-08 20:54
1472055	29340068	2502	G01A	Gymnasium Office adjacent to Exit	Mastic a/w Floor Tile - Yellow	2023-03-08 20:55
1472056	29340069	2014	H14	Hallway from Classroom 111 to Classroom 107	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-08 21:00
1472057	29340070	2014	H14	Hallway from Classroom 111 to Classroom 107	Floor Tile VAT 12" x 12" a/w N/A - White	2023-03-08 21:02

Project Location: Edmunds, H

Ship Date: 2023-03-14

Tracking Number: 1ZF11A090299054478, UPS

Sample Type: ACM

ETL Project: 255866

ULCS: 7250

EP #: EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1472058	29340071	2507	H14	Hallway from Classroom 111 to Classroom 107	Mastic a/w Floor Tile - Yellow	2023-03-08 21:02
1472059	29340072	2507	H14	Hallway from Classroom 111 to Classroom 107	Mastic a/w Floor Tile - Yellow	2023-03-08 21:02

Sample Collector: Fortna, Teagan

Analysts

Seal Intact: Yes

Preservative (if required): Yes

Containers Labeled : Yes

Project Location: Edmunds, H

Ship Date: 2023-03-14



Tracking Number: 1ZF11A090299054478, UPS

Sample Type: ACM

ETL Project: 255866

ULCS: 7250

EP #: EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
<hr/>						
						
Received By: Rovena Shparthi						
Received Date: 2023-03-17 12:36						
						
Alex Noble						
						
Chris Canilao						
						
Emmett Zainea						
						
Emily Spotts						
						
James Farinas						
						
Relinquished By: Jessica Dilworth						
Relinquished Date: 2023-03-24 16:16						



## REVISED REPORT

**To:** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job:** 255866  
**Client Project:** EP2023-0924-7250

**Attention:** Patrick Frederick  
**Project Location:** Edmunds, H

Lab Sample Number	Client Sample Number	Sample Type	Completed
1471894	28500001	Asbestos	03/24/2023
1471895	28500002	Asbestos	03/24/2023
1471896	28500003	Asbestos	03/24/2023
1471897	28500004	Asbestos	03/24/2023
1471898	28500005	Asbestos	03/24/2023
1471899	28500006	Asbestos	03/24/2023
1471900	28500007	Asbestos	03/24/2023
1471901	28500008	Asbestos	03/24/2023
1471902	28500009	Asbestos	03/24/2023
1471903	28500010	Asbestos	03/24/2023
1471904	28500011	Asbestos	03/24/2023
1471905	28500012	Asbestos	03/24/2023
1471906	28500013	Asbestos	03/24/2023
1471907	28500014	Asbestos	03/24/2023
1471908	28500015	Asbestos	03/24/2023
1471909	28500016	Asbestos	03/24/2023

Lab Sample Number	Client Sample Number	Sample Type	Completed
1471910	28500017	Asbestos	03/24/2023
1471911	28500018	Asbestos	03/24/2023
1471912	28500019	Asbestos	03/24/2023
1471913	28500020	Asbestos	03/24/2023
1471914	28500021	Asbestos	03/24/2023
1471915	28500022	Asbestos	03/24/2023
1471916	28500023	Asbestos	03/24/2023
1471917	28500024	Asbestos	03/24/2023
1471918	28500025	Asbestos	03/24/2023
1471919	28500026	Asbestos	03/24/2023
1471920	28500027	Asbestos	03/24/2023
1471921	28500028	Asbestos	03/24/2023
1471922	28500029	Asbestos	03/24/2023
1471923	28500030	Asbestos	03/24/2023
1471924	28500031	Asbestos	03/24/2023
1471925	28500032	Asbestos	03/24/2023
1471926	28500033	Asbestos	03/24/2023
1471927	28500034	Asbestos	03/24/2023
1471928	28500035	Asbestos	03/24/2023
1471929	28500036	Asbestos	03/24/2023
1471930	28500037	Asbestos	03/24/2023
1471931	28500039	Asbestos	03/24/2023
1471932	28500040	Asbestos	03/24/2023
1471933	28500041	Asbestos	03/24/2023
1471934	28500042	Asbestos	03/24/2023
1471935	28500043	Asbestos	04/27/2023

Lab Sample Number	Client Sample Number	Sample Type	Completed
1471936	28500044	Asbestos	04/27/2023
1471937	28500045	Asbestos	04/27/2023
1471938	28500046	Asbestos	04/27/2023
1471939	28500047	Asbestos	04/27/2023
1471940	28500048	Asbestos	04/27/2023
1471941	28500049	Asbestos	04/27/2023
1471942	28500050	Asbestos	03/24/2023
1471943	28500052	Asbestos	03/24/2023
1471944	28500053	Asbestos	03/24/2023
1471945	28500054	Asbestos	03/24/2023
1471946	28500056	Asbestos	03/24/2023
1471947	28500058	Asbestos	03/24/2023
1471948	28500059	Asbestos	03/24/2023
1471949	28500060	Asbestos	03/24/2023
1471950	28500061	Asbestos	03/24/2023
1471951	28500062	Asbestos	03/24/2023
1471952	28500063	Asbestos	03/24/2023
1471953	28500064	Asbestos	03/24/2023
1471954	28500065	Asbestos	03/24/2023
1471955	28500066	Asbestos	03/24/2023
1471956	28500067	Asbestos	03/24/2023
1471957	28500068	Asbestos	03/24/2023
1471958	28500069	Asbestos	03/24/2023
1471959	28500070	Asbestos	03/24/2023
1471960	28500071	Asbestos	03/24/2023
1471961	28500072	Asbestos	03/24/2023

Lab Sample Number	Client Sample Number	Sample Type	Completed
1471962	28500073	Asbestos	03/24/2023
1471963	28500074	Asbestos	03/24/2023
1471964	28500075	Asbestos	03/24/2023
1471965	28500076	Asbestos	03/24/2023
1471966	28500077	Asbestos	03/24/2023
1471967	28500078	Asbestos	03/24/2023
1471968	28500079	Asbestos	03/24/2023
1471969	28500080	Asbestos	03/24/2023
1471970	28501001	Asbestos	03/24/2023
1471971	28501002	Asbestos	03/24/2023
1471972	28501003	Asbestos	03/24/2023
1471973	28501004	Asbestos	03/24/2023
1471974	28501005	Asbestos	03/24/2023
1471975	28501006	Asbestos	03/24/2023
1471976	28501007	Asbestos	03/24/2023
1471977	28501008	Asbestos	03/24/2023
1471978	28501009	Asbestos	03/24/2023
1471979	28501010	Asbestos	03/24/2023
1471980	28501011	Asbestos	03/24/2023
1471981	28501012	Asbestos	03/24/2023
1471982	28501014	Asbestos	03/24/2023
1471983	28501015	Asbestos	03/24/2023
1471984	28501016	Asbestos	03/24/2023
1471985	28501017	Asbestos	03/24/2023
1471986	28501018	Asbestos	03/24/2023
1471987	28501019	Asbestos	03/24/2023



Lab Sample Number	Client Sample Number	Sample Type	Completed
1471988	29340001	Asbestos	03/24/2023
1471989	29340002	Asbestos	03/24/2023
1471990	29340003	Asbestos	03/24/2023
1471991	29340004	Asbestos	03/24/2023
1471992	29340005	Asbestos	03/24/2023
1471993	29340006	Asbestos	03/24/2023
1471994	29340007	Asbestos	03/24/2023
1471995	29340008	Asbestos	03/24/2023
1471996	29340009	Asbestos	03/24/2023
1471997	29340010	Asbestos	03/24/2023
1471998	29340011	Asbestos	03/24/2023
1471999	29340012	Asbestos	03/24/2023
1472000	29340013	Asbestos	03/24/2023
1472001	29340014	Asbestos	03/24/2023
1472002	29340015	Asbestos	03/24/2023
1472003	29340016	Asbestos	03/24/2023
1472004	29340017	Asbestos	03/24/2023
1472005	29340018	Asbestos	03/24/2023
1472006	29340019	Asbestos	03/24/2023
1472007	29340020	Asbestos	03/24/2023
1472008	29340021	Asbestos	03/24/2023
1472009	29340022	Asbestos	03/24/2023
1472010	29340023	Asbestos	03/24/2023
1472011	29340024	Asbestos	03/24/2023
1472012	29340025	Asbestos	03/24/2023
1472013	29340026	Asbestos	03/24/2023

Lab Sample Number	Client Sample Number	Sample Type	Completed
1472014	29340027	Asbestos	03/24/2023
1472015	29340028	Asbestos	03/24/2023
1472016	29340029	Asbestos	03/24/2023
1472017	29340030	Asbestos	03/24/2023
1472018	29340031	Asbestos	03/24/2023
1472019	29340032	Asbestos	03/24/2023
1472020	29340033	Asbestos	03/24/2023
1472021	29340034	Asbestos	03/24/2023
1472022	29340035	Asbestos	03/24/2023
1472023	29340036	Asbestos	03/24/2023
1472024	29340037	Asbestos	03/24/2023
1472025	29340038	Asbestos	03/24/2023
1472026	29340039	Asbestos	03/24/2023
1472027	29340040	Asbestos	03/24/2023
1472028	29340041	Asbestos	03/24/2023
1472029	29340042	Asbestos	03/24/2023
1472030	29340043	Asbestos	03/24/2023
1472031	29340044	Asbestos	03/24/2023
1472032	29340045	Asbestos	03/24/2023
1472033	29340046	Asbestos	03/24/2023
1472034	29340047	Asbestos	03/24/2023
1472035	29340048	Asbestos	03/24/2023
1472036	29340049	Asbestos	03/24/2023
1472037	29340050	Asbestos	03/24/2023
1472038	29340051	Asbestos	03/24/2023
1472039	29340052	Asbestos	03/24/2023

Lab Sample Number	Client Sample Number	Sample Type	Completed
1472040	29340053	Asbestos	03/24/2023
1472041	29340054	Asbestos	03/24/2023
1472042	29340055	Asbestos	03/24/2023
1472043	29340056	Asbestos	03/24/2023
1472044	29340057	Asbestos	03/24/2023
1472045	29340058	Asbestos	03/24/2023
1472046	29340059	Asbestos	03/24/2023
1472047	29340060	Asbestos	03/24/2023
1472048	29340061	Asbestos	03/24/2023
1472049	29340062	Asbestos	03/24/2023
1472050	29340063	Asbestos	03/24/2023
1472051	29340064	Asbestos	03/24/2023
1472052	29340065	Asbestos	03/24/2023
1472053	29340066	Asbestos	03/24/2023
1472054	29340067	Asbestos	03/24/2023
1472055	29340068	Asbestos	03/24/2023
1472056	29340069	Asbestos	03/24/2023
1472057	29340070	Asbestos	03/24/2023
1472058	29340071	Asbestos	03/24/2023
1472059	29340072	Asbestos	03/24/2023

Reviewed by:

Madeline Palmer

Lab Sample Number	Client Sample Number	Sample Type	Completed
-------------------	----------------------	-------------	-----------

Revision History

Revised Date	Revised By	Revision Comment
05/17/2023	Alex Noble	Fixed 99% Error-AN
05/05/2023	Rovena Shparthi	Stop @ 1st for a pipe insulation
05/05/2023	Rovena Shparthi	Billing
05/05/2023	Rovena Shparthi	New JNP Update
04/27/2023	Chris Canilao	Seperated skim coat and plaster on samples 28500043-49

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471894 28500001 Classroom 111 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Tan Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471895 28500002 Classroom 111 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471896 28500003 Classroom 111 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471897 28500004 Classroom 111 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471898 28500005 Classroom 111 Coat Room Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471899 28500006 Classroom 111 Coat Room Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471900 28500007 Classroom 111 Coat Room Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471901 28500008 Classroom 111 Coat Room Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471902 28500009 Classroom 108 Coat Room Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Yellow Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471903 28500010 Classroom 108 Coat Room Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471904 28500011 Classroom 108 Coat Room Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471905 28500012 Classroom 108 Coat Room Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

To : Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

ETL Job : 255866

Client Project : EP2023-0924-7250

Date Collected : 03/09/2023

Date Received : 03/17/2023

Attention: Patrick Frederick

Project Location : Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471906 28500013 Classroom 105 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Tan Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471907 28500014 Classroom 105 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Tan Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471908 28500015 Classroom 105 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow/White Non-Fibrous Non-Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471909 28500016 Classroom 105 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow/White Non-Fibrous Non-Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471910 28500017 Classroom 105 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Homogenous	PLM 97% Fiberglass	PLM 3% Other	PLM None Detected
1471911 28500018 Center Gymnasium Office Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Tan Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471912 28500019 Center Gymnasium Office Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Tan Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471913 28500020 Center Gymnasium Office Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471914 28500021 Center Gymnasium Office Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471915 28500022 Center Gymnasium Office Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Homogenous	PLM 97% Fiberglass	PLM 3% Other	PLM None Detected
1471916 28500023 Classroom 104 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471917 28500024 Classroom 104 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected



## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471918 28500025 Classroom 104 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471919 28500026 Classroom 104 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471920 28500027 Hallway from Classroom 101 to Classroom 106 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471921 28500028 Hallway from Classroom 101 to Classroom 106 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471922 28500029 Hallway from Classroom 101 to Classroom 106 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471923 28500030 Hallway from Classroom 101 to Classroom 106 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471924 28500031 Nurse's Office #3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Yellow Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471925 28500032 Nurse's Office #3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Yellow Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471926 28500033 Nurse's Office #3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471927 28500034 Nurse's Office #3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471928 28500035 Nurse's Office #3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Homogenous	PLM 97% Fiberglass	PLM 3% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471929 28500036 Nurse's Office #3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471929 28500036 Nurse's Office #3 Layer-2 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471930 28500037 Nurse's Office #3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471931 28500039 Nurse's Office Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471931 28500039 Nurse's Office Layer-2 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471932 28500040 Nurse's Office Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471933 28500041 Nurse's Office #2 Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 80% Cellulose	PLM 20% Other	PLM None Detected
1471934 28500042 Nurse's Office #2 Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471935 28500043 Auditorium Layer-1 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Auditorium Plaster Walls	Gray Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1471935 28500043 Auditorium Layer-2 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Skim Coat	White Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1471936 28500044 Auditorium Layer-1 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Auditorium Plaster Walls	Gray Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1471936 28500044 Auditorium Layer-2 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Skim Coat	White Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471937 28500045 Auditorium Layer-1 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Auditorium Plaster Walls	Gray Non-Fibrous Non-Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471937 28500045 Auditorium Layer-2 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Skim Coat	White Non-Fibrous Non-Homogenous	PLM 4% Cellulose	PLM 96% Other	PLM None Detected
1471938 28500046 Auditorium Layer-1 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Auditorium Plaster Walls	Gray Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1471938 28500046 Auditorium Layer-2 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Skim Coat	White Non-Fibrous Non-Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471939 28500047 Auditorium Layer-1 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Auditorium Plaster Walls	Gray Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1471939 28500047 Auditorium Layer-2 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Skim Coat	White Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471940 28500048 Auditorium Layer-1 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Auditorium Plaster Walls	Gray Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1471940 28500048 Auditorium Layer-2 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Skim Coat	White Non-Fibrous Non-Homogenous	PLM 4% Cellulose	PLM 96% Other	PLM None Detected
1471941 28500049 Auditorium Layer-1 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Auditorium Plaster Walls	Gray Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1471941 28500049 Auditorium Layer-2 Analyst: Chris Canilao Date Analyzed : 04/27/2023	Skim Coat	White Non-Fibrous Non-Homogenous	PLM 4% Cellulose	PLM 96% Other	PLM None Detected
1471942 28500050 Copy Room in front of Storage Room Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 70% Cellulose	PLM 30% Other	PLM None Detected
1471943 28500052 Staff Office C Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 70% Cellulose	PLM 30% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471944 28500053 Staff Office C Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471945 28500054 Dean's Office Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 80% Cellulose	PLM 20% Other	PLM None Detected
1471946 28500056 Staff Office adjacent to Vice Principal's Office Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 80% Cellulose	PLM 20% Other	PLM None Detected
1471947 28500058 Boiler Room Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Boiler Breeching	Tan Fibrous Homogenous	PLM 60% Cellulose PLM 30% Fiberglass	PLM 10% Other	PLM None Detected
1471947 28500058 Boiler Room Layer-2 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Boiler Breeching	Gray Fibrous Homogenous	PLM 50% Cellulose PLM 30% Fiberglass	PLM 20% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471948 28500059 Boiler Room Layer-1 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Boiler Breeching	Tan Fibrous Homogenous	PLM 50% Cellulose PLM 40% Fiberglass	PLM 10% Other	PLM None Detected
1471948 28500059 Boiler Room Layer-2 Analyst: Chris Canilao Date Analyzed : 03/24/2023	Boiler Breeching	Gray Fibrous Homogenous	PLM 60% Cellulose PLM 30% Fiberglass	PLM 10% Other	PLM None Detected
1471949 28500060 Classroom G3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471949 28500060 Classroom G3 Layer-2 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471950 28500061 Classroom G3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected



## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471951 28500062 Classroom G3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471951 28500062 Classroom G3 Layer-2 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471952 28500063 Classroom G3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471953 28500064 Classroom G3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471954 28500065 Classroom G3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471955 28500066 Classroom G3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471956 28500067 Classroom G3 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471957 28500068 Hallway from Classrooms G-4 to G-5 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471958 28500069 Hallway from Classrooms G-4 to G-5 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471959 28500070 Hallway from Classrooms G-4 to G-5 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471960 28500071 Hallway from Classrooms G-4 to G-5 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471961 28500072 Classroom G2 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471962 28500073 Classroom G2 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471963 28500074 Classroom G2 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Black Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471964 28500075 Classroom G2 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Black Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471965 28500076 Classroom G2 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471965 28500076 Classroom G2 Layer-2 Analyst: Alex Noble Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected
1471966 28500077 Classroom G2 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471967 28500078 Classroom G4 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471968 28500079 Classroom G4 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471969 28500080 Classroom G4 Layer-1 Analyst: Alex Noble Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 3% Cellulose	PLM 97% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471970 28501001 Classroom G4 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Blue Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471970 28501001 Classroom G4 Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Brown Non-Fibrous Non-Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471970 28501001 Classroom G4 Layer-3 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471970 28501001 Classroom G4 Layer-4 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Tan Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471971 28501002 Classroom G4 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Non-Homogenous	PLM Trace Cellulose PLM 90% Fiberglass PLM 2% Mineral wool	PLM 8% Other	PLM None Detected
1471972 28501003 G6 Restroom Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Homogenous	PLM Trace Cellulose PLM 90% Fiberglass PLM 2% Mineral wool	PLM 8% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471973 28501004 Classroom G8 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Yellow Non-Fibrous Non-Homogenous	PLM Trace Cellulose PLM Trace Fiberglass	PLM 100% Other	PLM None Detected
1471973 28501004 Classroom G8 Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Black Non-Fibrous Non-Homogenous	PLM 2% Cellulose PLM Trace Fiberglass	PLM 98% Other	PLM None Detected
1471974 28501005 Classroom G8 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Yellow Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471974 28501005 Classroom G8 Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Black Non-Fibrous Non-Homogenous	PLM Trace Cellulose PLM Trace Fiberglass	PLM 100% Other	PLM None Detected
1471975 28501006 Classroom G8 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Blue Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471975 28501006 Classroom G8 Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Black Non-Fibrous Non-Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471976 28501007 Classroom G8 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Blue Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471976 28501007 Classroom G8 Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Black Non-Fibrous Non-Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471977 28501008 G10A Office Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471977 28501008 G10A Office Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Tan Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471978 28501009 G10A Office Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471978 28501009 G10A Office Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Tan Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471979 28501010 G10A Office Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471979 28501010 G10A Office Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Blue Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471980 28501011 G10A Office Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471980 28501011 G10A Office Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Blue Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471981 28501012 G10B Office Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471981 28501012 G10B Office Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Non-Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected



## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471982 28501014 G10B Office Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Non-Homogenous	PLM 60% Cellulose PLM 20% Fiberglass	PLM 20% Other	PLM None Detected
1471983 28501015 G10D Office Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471983 28501015 G10D Office Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Non-Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471984 28501016 G10D Office Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471984 28501016 G10D Office Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471985 28501017 Ballet Room G12 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Linoleum	Blue Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471985 28501017 Ballet Room G12 Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Linoleum	Black Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471985 28501017 Ballet Room G12 Layer-3 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Linoleum	White Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471985 28501017 Ballet Room G12 Layer-4 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Tan Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471986 28501018 Ballet Room G12 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Linoleum	Blue Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471986 28501018 Ballet Room G12 Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Linoleum	Black Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471986 28501018 Ballet Room G12 Layer-3 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Linoleum	White Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471986 28501018 Ballet Room G12 Layer-4 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Tan Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471987 28501019 Hallway from Classroom 111 to Classroom 107 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Leveling Compound	Gray Non-Fibrous Non-Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471988 29340001 Gymnasium Storage Room Layer-1 Analyst: James Farinas Date Analyzed : 03/24/2023	Fireproofing	Grey Fibrous Homogenous	PLM Trace Cellulose PLM 75% Fiberglass	PLM 25% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471989 29340002 Gymnasium Storage Room Layer-1 Analyst: James Farinas Date Analyzed : 03/24/2023	Fireproofing	Grey Fibrous Homogenous	PLM Trace Cellulose PLM 75% Fiberglass	PLM 25% Other	PLM None Detected
1471990 29340003 Gymnasium Storage Room Layer-1 Analyst: James Farinas Date Analyzed : 03/24/2023	Fireproofing	Grey Fibrous Homogenous	PLM Trace Cellulose PLM 75% Fiberglass	PLM 25% Other	PLM None Detected
1471991 29340004 Classroom 307 Layer-1 Analyst: James Farinas Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Blue Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471991 29340004 Classroom 307 Layer-2 Analyst: James Farinas Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471992 29340005 Classroom 307 Layer-1 Analyst: James Farinas Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Yellow Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471992 29340005 Classroom 307 Layer-2 Analyst: James Farinas Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 1% Cellulose	PLM 99% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471993 29340006 Classroom 307 Layer-1 Analyst: James Farinas Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471993 29340006 Classroom 307 Layer-2 Analyst: James Farinas Date Analyzed : 03/24/2023	Mastic	White Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471994 29340007 Classroom 307 Layer-1 Analyst: James Farinas Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1471995 29340008 Classroom 308 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Multi Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471996 29340009 Classroom 308 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Multi Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471997 29340010 Classroom 308 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1471998 29340011 Classroom 308 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1471999 29340012 Classroom 311 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Multi Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472000 29340013 Classroom 311 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Multi Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472001 29340014 Classroom 311 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Non-Homogenous	PLM 30% Cellulose	PLM 70% Other	PLM None Detected
1472002 29340015 Classroom 311 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472003 29340016 Classroom 301 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Multi Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472004 29340017 Classroom 301 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Multi Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472005 29340018 Classroom 301 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472006 29340019 Classroom 301 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472007 29340020 Classroom 305 A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1472008 29340021 Classroom 305 A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1472009 29340022 Classroom 305 A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Brown Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472010 29340023 Classroom 305 A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Mastic	Brown Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472011 29340024 Classroom 305 A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Non-Homogenous	PLM 2% Cellulose PLM Trace Fiberglass	PLM 98% Other	PLM None Detected
1472011 29340024 Classroom 305 A Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Fibrous Non-Homogenous	PLM 10% Cellulose	PLM 90% Other	PLM None Detected
1472012 29340025 Classroom 305 A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1472013 29340026 Classroom 305 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Non-Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472013 29340026 Classroom 305 Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Fibrous Non-Homogenous	PLM 15% Cellulose	PLM 85% Other	PLM None Detected



## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472014 29340027 Classroom 305 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472015 29340028 Classroom 307 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Non-Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472015 29340028 Classroom 307 Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1472016 29340029 Classroom 307 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472017 29340030 Office 303A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1472017 29340030 Office 303A Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Non-Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

To : Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

ETL Job : 255866

Client Project : EP2023-0924-7250

Date Collected : 03/09/2023

Date Received : 03/17/2023

Attention: Patrick Frederick

Project Location : Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472018 29340031 Office 303A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1472019 29340032 Special Education Classroom 302A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Non-Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1472019 29340032 Special Education Classroom 302A Layer-2 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Non-Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472020 29340033 Special Education Classroom 302A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM Trace Cellulose	PLM 100% Other	PLM None Detected
1472021 29340034 Classroom 305 A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Non-Homogenous	PLM 2% Cellulose PLM 85% Fiberglass	PLM 13% Other	PLM None Detected
1472022 29340035 Office 303A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Non-Homogenous	PLM 85% Cellulose PLM 5% Fiberglass	PLM 10% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472023 29340036 Special Education Classroom 302A Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Non-Homogenous	PLM 2% Cellulose PLM 85% Fiberglass	PLM 13% Other	PLM None Detected
1472024 29340037 Classroom 310 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023	Pipe Insulation 2-6 inch	Tan Fibrous Non-Homogenous	PLM 80% Cellulose	PLM 10% Other	PLM 10% Chrysotile
1472025 29340038 Classroom 310 Layer-1 Analyst: Emily Spotts Date Analyzed : 03/24/2023  Layer Not Analyzed		Positive Stop			
1472026 29340039 Classroom 310 Analyst: Emily Spotts Date Analyzed : 03/24/2023  Sample Not Analyzed		Positive Stop			
1472027 29340040 Science Lab Classroom 208 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472028 29340041 Science Lab Classroom 208 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472029 29340042 Science Lab Classroom 208 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Brown Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472030 29340043 Science Lab Classroom 208 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Brown Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472031 29340044 Science Lab Classroom 208 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Homogenous	PLM 50% Fiberglass	PLM 50% Other	PLM None Detected
1472032 29340045 Classroom 207 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Homogenous	PLM 50% Fiberglass	PLM 50% Other	PLM None Detected
1472033 29340046 Hallway from Classroom 207 to Classroom 212 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472034 29340047 Hallway from Classroom 207 to Classroom 212 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472035 29340048 Classroom 201 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Gray Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472036 29340049 Classroom 201 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Gray Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472037 29340050 Classroom 201 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472038 29340051 Classroom 201 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472039 29340052 Classroom 203 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472040 29340053 Classroom 203 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

To : Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

Attention: Patrick Frederick

Project Location : Edmunds, H

ETL Job : 255866

Client Project : EP2023-0924-7250

Date Collected : 03/09/2023

Date Received : 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472041 29340054 Classroom 203 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Ceiling Tile 2' x 4'	Gray Fibrous Homogenous	PLM 50% Fiberglass	PLM 50% Other	PLM None Detected
1472042 29340055 Hallway at Classroom 203 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472043 29340056 Hallway at Classroom 203 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472044 29340057 Hallway at Classroom 203 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472045 29340058 Hallway at Classroom 203 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472046 29340059 Teacher's Lounge Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Sheetrock/Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

To : Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

ETL Job : 255866

Client Project : EP2023-0924-7250

Date Collected : 03/09/2023

Date Received : 03/17/2023

Attention: Patrick Frederick

Project Location : Edmunds, H

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472047 29340060 Teacher's Lounge Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472048 29340061 Classroom 204A Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Tan Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472049 29340062 Classroom 204A Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Tan Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472050 29340063 Classroom 204A Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Black Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472051 29340064 Classroom 204A Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Black Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472052 29340065 Gymnasium Office adjacent to Exit Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Multi Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 255866

**Client Project :** EP2023-0924-7250

**Date Collected :** 03/09/2023

**Date Received :** 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472053 29340066 Gymnasium Office adjacent to Exit Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	Multi Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472054 29340067 Gymnasium Office adjacent to Exit Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous		PLM 100% Other	PLM None Detected
1472055 29340068 Gymnasium Office adjacent to Exit Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous		PLM 100% Other	PLM None Detected
1472056 29340069 Hallway from Classroom 111 to Classroom 107 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472057 29340070 Hallway from Classroom 111 to Classroom 107 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Floor Tile VAT 12" x 12"	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1472058 29340071 Hallway from Classroom 111 to Classroom 107 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected



## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

To : Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200

Newark, DE 19713

Attention: Patrick Frederick

Project Location : Edmunds, H

ETL Job : 255866

Client Project : EP2023-0924-7250

Date Collected : 03/09/2023

Date Received : 03/17/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1472059 29340072 Hallway from Classroom 111 to Classroom 107 Analyst: Emmett Zainea Date Analyzed : 03/24/2023	Mastic	Yellow Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected



Eleni Kiliaris

Lab Supervisor/Other Signatory

Analyst :



Alex Noble



Chris Canilao



Emmett Zainea



Emily Spotts



James Farinas

400 Point Count Results by EPA 600/R-93/116 PLM (denoted by "PC")  
Item 198.1: PLM Methods for Identifying and Quantitating Asbestos in Bulk Samples  
Item 198.6: PLM Methods for Identifying and Quantitating Asbestos in Non-Friable Organically Bound Bulk Samples  
EPA 600/R-93/116: Method for Determination of Asbestos in Bulk Building Materials  
EPA 600/M4-82-020: Interim Method for Determination of Asbestos in Bulk Insulation Samples  
A % Asbestos result of "Trace" indicates that the analyzed material was found to contain less than 1% asbestos and would not be considered an Asbestos Containing Material (ACM).

ETL, Inc. maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced without written approval by ETL. Inc. Test Method EPA 600/R-93-116 & EPA 600/M4-82/020 or NYSDOH-ELAP item 198.1 and/or 198.6 was used to analyze all samples. Matrix interference and/or resolution limits (i.e. detecting asbestos in non-friable organically bound materials) may yield false results in certain circumstances. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing. Interpretation and use of test results are the responsibility of the client. ETL, Inc. is not responsible for the accuracy of the results when requested to physically separate and analyze layered samples. Any PLM results below 10% should be re-analyzed using the EPA recommended Point Count method. Any material that has greater than 1% asbestos content is considered to be an Asbestos Containing Material (ACM). These materials are regulated by both OSHA and the EPA and must be treated accordingly. Results are related to only to samples that were tested. An estimate of uncertainty can be provided at the client's request.

# Electronic Chain of Custody

Environmental Testing Laboratories, Inc.



37575 W Huron River Drive  
Romulus, Michigan 48174  
(734) 955-6600, Fax: (734) 955-6604

**Submitting Client :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE - 19713

**Project Location:** Edmunds, H

**ETL Project:** 258586

**Ship Date:** 2023-06-21

**Tracking Number:** 1ZF11A090292557429, UPS

**ULCS:** 7250

**Sample Type:** ACM

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1524740	28533001	2102	202	Classroom 202	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-06-21 08:05
1524741	28533002	2102	202	Classroom 202	Joint Compound Wall a/w N/A - N/A	2023-06-21 08:05
1524742	28533003	2102	204	Classroom 204	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-06-21 08:08
1524743	28533004	2102	204	Classroom 204	Joint Compound Wall a/w N/A - N/A	2023-06-21 08:08
1524744	28533005	2101	120	Main Office Reception Area	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-06-21 08:24
1524745	28533006	2101	120	Main Office Reception Area	Joint Compound Wall a/w N/A - N/A	2023-06-21 08:24
1524746	28533007	2101	120E	Staff Office A	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-06-21 08:28
1524747	28533008	2101	120E	Staff Office A	Joint Compound Wall a/w N/A - N/A	2023-06-21 08:28
1524748	28533009	2101	120J	Storage Room adjacent to Restrooms	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-06-21 08:32
1524749	28533010	2101	120J	Storage Room adjacent to Restrooms	Joint Compound Wall a/w N/A - N/A	2023-06-21 08:32

**Project Location:** Edmunds, H

**Ship Date:** 2023-06-21

**Tracking Number:** 1ZF11A090292557429, UPS

**Sample Type:** ACM

**ETL Project:** 258586

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1524750	28533011	2104	G1AB	G1 Main Windowed Office	Sheetrock/Joint Compound Wall a/w N/A - N/A	2023-06-21 08:43
1524751	28533012	2104	G1AB	G1 Main Windowed Office	Joint Compound Wall a/w N/A - N/A	2023-06-21 08:43
1524752	28533013	0601	8	Boiler Room	Boiler Breeching a/w N/A - N/A	2023-06-21 08:49



**Sample Collector:** Fortna, Teagan

**Seal Intact:** Yes

**Preservative (if required):** Yes

**Containers Labeled :** Yes

**Analysts**



**Received By:** Luke Powell

**Received Date:** 2023-06-30 10:27



OJ Ivey



**Relinquished By:** Jessica Dilworth

**Relinquished Date:** 2023-07-06 19:11



**ENVIRONMENTAL TESTING  
LABORATORIES, INC.**

37575 W HURON RIVER DRIVE  
ROMULUS, MICHIGAN 48174  
(734) 955-6600  
FAX: (734) 955-6604

To: Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

ETL Job: 258586  
Client Project: EP2023-0924-7250

Attention: Patrick Frederick  
Project Location: Edmunds, H

Lab Sample Number	Client Sample Number	Sample Type	Completed
1524740	28533001	Asbestos	07/06/2023
1524741	28533002	Asbestos	07/06/2023
1524742	28533003	Asbestos	07/06/2023
1524743	28533004	Asbestos	07/06/2023
1524744	28533005	Asbestos	07/06/2023
1524745	28533006	Asbestos	07/06/2023
1524746	28533007	Asbestos	07/06/2023
1524747	28533008	Asbestos	07/06/2023
1524748	28533009	Asbestos	07/06/2023
1524749	28533010	Asbestos	07/06/2023
1524750	28533011	Asbestos	07/06/2023
1524751	28533012	Asbestos	07/06/2023
1524752	28533013	Asbestos	07/06/2023

Reviewed by:



Madeline Palmer

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 258586

**Client Project :** EP2023-0924-7250

**Date Collected :** 06/21/2023

**Date Received :** 06/30/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1524740 28533001 Classroom 202 Analyst: OJ Ivey Date Analyzed : 07/06/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 10% Cellulose	PLM 90% Other	PLM None Detected
1524741 28533002 Classroom 202 Layer-1 Analyst: OJ Ivey Date Analyzed : 07/06/2023	Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 4% Cellulose	PLM 96% Other	PLM None Detected
1524741 28533002 Classroom 202 Layer-2 Analyst: OJ Ivey Date Analyzed : 07/06/2023	Tape	White Fibrous Homogenous	PLM 35% Cellulose	PLM 65% Other	PLM None Detected
1524742 28533003 Classroom 204 Analyst: OJ Ivey Date Analyzed : 07/06/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 10% Cellulose	PLM 90% Other	PLM None Detected
1524743 28533004 Classroom 204 Layer-1 Analyst: OJ Ivey Date Analyzed : 07/06/2023	Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
1524743 28533004 Classroom 204 Layer-2 Analyst: OJ Ivey Date Analyzed : 07/06/2023	Tape	White Fibrous Homogenous	PLM 45% Cellulose	PLM 55% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 258586

**Client Project :** EP2023-0924-7250

**Date Collected :** 06/21/2023

**Date Received :** 06/30/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1524744 28533005 Main Office Reception Area Analyst: OJ Ivey Date Analyzed : 07/06/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 9% Cellulose	PLM 91% Other	PLM None Detected
1524745 28533006 Main Office Reception Area Analyst: OJ Ivey Date Analyzed : 07/06/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 5% Cellulose	PLM 95% Other	PLM None Detected
No "Tape"					
1524746 28533007 Staff Office A Analyst: OJ Ivey Date Analyzed : 07/06/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 10% Cellulose	PLM 90% Other	PLM None Detected
1524747 28533008 Staff Office A Layer-1 Analyst: OJ Ivey Date Analyzed : 07/06/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 4% Cellulose	PLM 96% Other	PLM None Detected
1524747 28533008 Staff Office A Layer-2 Analyst: OJ Ivey Date Analyzed : 07/06/2023	Tape	Beige Fibrous Homogenous	PLM 45% Cellulose	PLM 55% Other	PLM None Detected
1524748 28533009 Storage Room adjacent to Restrooms Analyst: OJ Ivey Date Analyzed : 07/06/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 7% Cellulose	PLM 93% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

To : Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

Attention: Patrick Frederick

Project Location : Edmunds, H

ETL Job : 258586

Client Project : EP2023-0924-7250

Date Collected : 06/21/2023

Date Received : 06/30/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1524749 28533010 Storage Room adjacent to Restrooms Analyst: OJ Ivey Date Analyzed : 07/06/2023	Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 1% Cellulose	PLM 99% Other	PLM None Detected
1524750 28533011 G1 Main Windowed Office Analyst: OJ Ivey Date Analyzed : 07/06/2023	Sheetrock/Joint Compound Wall	Gray Non-Fibrous Homogenous	PLM 10% Cellulose	PLM 90% Other	PLM None Detected
1524751 28533012 G1 Main Windowed Office Analyst: OJ Ivey Date Analyzed : 07/06/2023	Joint Compound Wall	White Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1524752 28533013 Boiler Room Analyst: OJ Ivey Date Analyzed : 07/06/2023	Boiler Breeching	Beige Fibrous Homogenous	PLM 25% Cellulose	PLM 75% Other	PLM None Detected

*Eleni Kiliaris*

Eleni Kiliaris

Lab Supervisor/Other Signatory

Analyst :

*Orlando James Ivey Jr.*

OJ Ivey

400 Point Count Results by EPA 600/R-93/116 PLM (denoted by "PC")

Item 198.1: PLM Methods for Identifying and Quantitating Asbestos in Bulk Samples

Item 198.6: PLM Methods for Identifying and Quantitating Asbestos in Non-Friable Organically Bound Bulk Samples

EPA 600/R-93/116: Method for Determination of Asbestos in Bulk Building Materials

EPA 600/M4-82-020: Interim Method for Determination of Asbestos in Bulk Insulation Samples

A % Asbestos result of "Trace" indicates that the analyzed material was found to contain less than 1% asbestos and would not be considered an Asbestos Containing Material (ACM).

ETL, Inc. maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced without written approval by ETL, Inc. Test Method EPA 600/R-93-116 & EPA 600/M4-82/020 or NYSDOH-ELAP item 198.1 and/or 198.6 was used to analyze all samples. Matrix interference and/or resolution limits (i.e. detecting asbestos in non-friable organically bound materials) may yield false results in certain circumstances. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing. Interpretation and use of test results are the responsibility of the client. ETL, Inc. is not responsible for the accuracy of the results when requested to physically separate and analyze layered samples. Any PLM results below 10% should be re-analyzed using the EPA recommended Point Count method. Any material that has greater than 1% asbestos content is considered to be an Asbestos Containing Material (ACM). These materials are regulated by both OSHA and the EPA and must be treated accordingly. Results are related to only to samples that were tested. An estimate of uncertainty can be provided at the client's request.



# Electronic Chain of Custody

**Submitting Client :** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE - 19713

**Environmental Testing Laboratories, Inc.**



37575 W Huron River Drive  
Romulus, Michigan 48174  
(734) 955-6600, Fax: (734) 955-6604

**Project Location:** Edmunds, H

**ETL Project:** 260476

**Ship Date:** 2023-08-08

**Tracking Number:** 1ZF11A090296209977, UPS

**ULCS:** 7250

**Sample Type:** ACM

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1568704	28638001	0423	S34	Haworth Stairwell B adjacent to Classroom 305	Fireproofing a/w N/A - N/A	2023-08-07 12:32
1568705	28638002	0423	H10	Hallway from Classrooms 305 A to 308	Fireproofing a/w N/A - N/A	2023-08-07 12:34
1568706	28638003	0420	302A	Special Education Classroom across from Classroom 306	Paint a/w Ceiling, Concrete - N/A	2023-08-07 12:37
1568707	28638004	0420	302A	Special Education Classroom across from Classroom 306	Paint a/w Ceiling, Concrete - N/A	2023-08-07 12:37
1568708	28638005	0419	303B	Office 303A	Paint a/w Ceiling, Concrete - N/A	2023-08-07 12:41
1568709	28638006	0423	300	Elevator Lobby adjacent to Dyre Stairwell B	Fireproofing a/w N/A - N/A	2023-08-07 12:45
1568710	28638007	0422	H27	Hallway from Classroom 207 to Classroom 212	Fireproofing a/w N/A - N/A	2023-08-07 13:00
1568711	28638008	0422	H27	Hallway from Classroom 207 to Classroom 212	Fireproofing a/w N/A - N/A	2023-08-07 13:00
1568712	28638009	0422	206	Office 206	Fireproofing a/w N/A - N/A	2023-08-07 13:01
1568713	28638010	0417	202A	Autistic Support Office 202A	Paint a/w Ceiling, Concrete - N/A	2023-08-07 13:12

**Project Location:** Edmunds, H

**Ship Date:** 2023-08-08

**Tracking Number:** 1ZF11A090296209977, UPS

**Sample Type:** ACM

**ETL Project:** 260476

**ULCS:** 7250

**EP #:** EP2023-0924-7250

Lab Sample Number	Client Sample Number	HID	Space ID	Room Name	Component	Time Recorded
1568714	28638011	0417	202A	Autistic Support Office 202A	Paint a/w Ceiling, Concrete - N/A	2023-08-07 13:12
1568715	28638012	0421	210D	Special Education Classroom across from Classroom 210	Paint a/w Ceiling, Concrete - N/A	2023-08-07 13:24
1568716	28638013	0416	15A	Staff Restroom adjacent to Classrom 105	Fireproofing a/w N/A - N/A	2023-08-07 13:34
1568717	28638014	0416	15A	Staff Restroom adjacent to Classrom 105	Fireproofing a/w N/A - N/A	2023-08-07 13:34
1568718	28638015	0416	G01A	Gymnasium Office adjacent to Exit	Fireproofing a/w N/A - N/A	2023-08-07 13:42
1568719	28638016	0415	Women's	Women's Restroom	Fireproofing a/w N/A - N/A	2023-08-07 13:49
1568720	28638017	0415	Cafeteria	Cafeteria	Fireproofing a/w N/A - N/A	2023-08-07 13:58
1568721	28638018	0415	Kitchen	Kitchen	Fireproofing a/w N/A - N/A	2023-08-07 14:08



**Sample Collector:** Pike, Emma

**Seal Intact:** Yes

**Preservative (if required):** Yes

**Containers Labeled :** Yes

**Analysts**



**Received By:** Luke Powell

**Received Date:** 2023-08-18 10:45



Chris Canilao



**Relinquished By:** Jessica Dilworth

**Relinquished Date:** 2023-08-25 16:03



**ENVIRONMENTAL TESTING  
LABORATORIES, INC.**

37575 W HURON RIVER DRIVE  
ROMULUS, MICHIGAN 48174  
(734) 955-6600  
FAX: (734) 955-6604

**To:** Tetra Tech, Inc.  
240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**ETL Job:** 260476  
**Client Project:** EP2023-0924-7250

**Attention:** Patrick Frederick  
**Project Location:** Edmunds, H

Lab Sample Number	Client Sample Number	Sample Type	Completed
1568704	28638001	Asbestos	08/25/2023
1568705	28638002	Asbestos	08/25/2023
1568706	28638003	Asbestos	08/25/2023
1568707	28638004	Asbestos	08/25/2023
1568708	28638005	Asbestos	08/25/2023
1568709	28638006	Asbestos	08/25/2023
1568710	28638007	Asbestos	08/25/2023
1568711	28638008	Asbestos	08/25/2023
1568712	28638009	Asbestos	08/25/2023
1568713	28638010	Asbestos	08/25/2023
1568714	28638011	Asbestos	08/25/2023
1568715	28638012	Asbestos	08/25/2023
1568716	28638013	Asbestos	08/25/2023
1568717	28638014	Asbestos	08/25/2023
1568718	28638015	Asbestos	08/25/2023
1568719	28638016	Asbestos	08/25/2023

Lab Sample Number	Client Sample Number	Sample Type	Completed
1568720	28638017	Asbestos	08/25/2023
1568721	28638018	Asbestos	08/25/2023

Reviewed by:   
Madeline Palmer

Summary			
Method	Sample	Layer	Mastic
PLM	18		

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 260476

**Client Project :** EP2023-0924-7250

**Date Collected :** 08/07/2023

**Date Received :** 08/18/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1568704 28638001 Haworth Stairwell B adjacent to Classroom 305 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected
1568705 28638002 Hallway from Classrooms 305 A to 308 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected
1568706 28638003 Special Education Classroom across from Classroom 306 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Paint	White/Black Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1568707 28638004 Special Education Classroom across from Classroom 306 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Paint	White/Black Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1568708 28638005 Office 303A Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Paint	White/Black Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1568709 28638006 Elevator Lobby adjacent to Dyre Stairwell B Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 40% Cellulose PLM 50% Fiberglass	PLM 10% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 260476

**Client Project :** EP2023-0924-7250

**Date Collected :** 08/07/2023

**Date Received :** 08/18/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1568710 28638007 Hallway from Classroom 207 to Classroom 212 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected
1568711 28638008 Hallway from Classroom 207 to Classroom 212 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 20% Cellulose PLM 70% Fiberglass	PLM 10% Other	PLM None Detected
1568712 28638009 Office 206 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected
1568713 28638010 Autistic Support Office 202A Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Paint	Gray Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1568714 28638011 Autistic Support Office 202A Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Paint	Gray Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected
1568715 28638012 Special Education Classroom across from Classroom 210 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Paint	Gray Non-Fibrous Homogenous	PLM 2% Cellulose	PLM 98% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

**To :** Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

**Attention:** Patrick Frederick

**Project Location :** Edmunds, H

**ETL Job :** 260476

**Client Project :** EP2023-0924-7250

**Date Collected :** 08/07/2023

**Date Received :** 08/18/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
1568716 28638013 Staff Restroom adjacent to Classrom 105 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected
1568717 28638014 Staff Restroom adjacent to Classrom 105 Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected
1568718 28638015 Gymnasium Office adjacent to Exit Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected
1568719 28638016 Women's Restroom Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected
1568720 28638017 Cafeteria Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected
1568721 28638018 Kitchen Layer-1 Analyst: Chris Canilao Date Analyzed : 08/25/2023	Fireproofing	Gray Fibrous Homogenous	PLM 30% Cellulose PLM 60% Fiberglass	PLM 10% Other	PLM None Detected

## Certificate of Analysis

### Polarized Light Microscopy Asbestos Analysis Report

To : Tetra Tech, Inc.

240 Continental Dr. Ste. 102, 200  
Newark, DE 19713

Attention: Patrick Frederick

Project Location : Edmunds, H

ETL Job : 260476

Client Project : EP2023-0924-7250

Date Collected : 08/07/2023

Date Received : 08/18/2023

Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Asbestos
--------	-------------	------------	-----------	---------------	------------



Eleni Kiliaris

Lab Supervisor/Other Signatory

Analyst :



Chris Canilao

400 Point Count Results by EPA 600/R-93/116 PLM (denoted by "PC")

Item 198.1: PLM Methods for Identifying and Quantitating Asbestos in Bulk Samples

Item 198.6: PLM Methods for Identifying and Quantitating Asbestos in Non-Friable Organically Bound Bulk Samples

EPA 600/R-93/116: Method for Determination of Asbestos in Bulk Building Materials

EPA 600/M4-82-020: Interim Method for Determination of Asbestos in Bulk Insulation Samples

A % Asbestos result of "Trace" indicates that the analyzed material was found to contain less than 1% asbestos and would not be considered an Asbestos Containing Material (ACM).

ETL, Inc. maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced without written approval by ETL, Inc. Test Method EPA 600/R-93-116 & EPA 600/M4-82/020 or NYSDOH-ELAP item 198.1 and/or 198.6 was used to analyze all samples. Matrix interference and/or resolution limits (i.e. detecting asbestos in non-friable organically bound materials) may yield false results in certain circumstances. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing. Interpretation and use of test results are the responsibility of the client. ETL, Inc. is not responsible for the accuracy of the results when requested to physically separate and analyze layered samples. Any PLM results below 10% should be re-analyzed using the EPA recommended Point Count method. Any material that has greater than 1% asbestos content is considered to be an Asbestos Containing Material (ACM). These materials are regulated by both OSHA and the EPA and must be treated accordingly. Results are related to only to samples that were tested. An estimate of uncertainty can be provided at the client's request.





## APPENDIX C

---

### FIGURES





The Figures have been redacted for school safety purposes.

A copy of this unredacted re-inspection report is available at your school.





## APPENDIX D

---

### ANNUAL NOTIFICATION





**OFFICE OF ENVIRONMENTAL  
MANAGEMENT AND SERVICES**

**440 N. Broad St, Suite 373  
Philadelphia, PA 19130**

**Legal Notice: Annual AHERA Notification Letter**

**Asbestos Report Available for Your School**

2022/2023 School Year

Dear Parents/Guardians, School Staff, Temporary Workers and or Contractors:

Pursuant to Federal Environmental Protection Agency (EPA) regulations, codified at 40 C.F.R. 763.84, the District is required to provide notification of public access to environmental records. Members of the school staff, parents/guardians, temporary workers and/or contractors must be informed each year of their access rights. This letter is to acknowledge the availability of your facility's Asbestos Hazard Emergency Response Act (AHERA) Management Plan.

The School District, as the Local Education Agency (LEA), maintains AHERA reports for public inspection in the Office of the Principal or Building Administrator, and in the Administrative Offices at 440 N. Broad Street.

If you have any questions, feel free to contact the Office of Environmental Management and Services @ 215 400 4750 or by emailing [environmental@philasd.org](mailto:environmental@philasd.org) . Find your school's AHERA Report at <https://www.philasd.org/capitalprograms/programsservices/environmental/ahera/>



## APPENDIX E

---

### CERTIFICATES



# ***Certificate of Training***

**CRITERION LABORATORIES, INC.**

**HEREBY CERTIFIES THAT**

**Ian Forster**

**XXX-XX-XXXX**

**HAS SUCCESSFULLY COMPLETED A 16 HOUR COURSE ENTITLED**

**Asbestos Management Planner Initial**

**INCLUDING CLASSROOM INSTRUCTION**


**10/11/2012 to 10/12/2012**

**Exam passed on this 12th day of October 2012 - Score - 94**

**Approved for AHERA Accreditation Under TSCA Title II**

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
[www.criterionlabs.com](http://www.criterionlabs.com)

**DIRECTOR:**

  
**James A. Weltz, CIH, President**

# ***Certificate of Training***

**CRITERION LABORATORIES, INC.**

**HEREBY CERTIFIES THAT**

**Ian Forster**

**HAS SUCCESSFULLY COMPLETED A 4 HOUR TELECONFERENCE COURSE ENTITLED**

**Asbestos Management Planner Refresher**

**INCLUDING CLASSROOM INSTRUCTION**


**on this 6th day of December 2022**

**Approved for AHERA Accreditation Under TSCA Title II**

**400 Street Road  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
[www.criterionlabs.com](http://www.criterionlabs.com)**

*Rev. 20170501  
Course is conducted in English*

**DIRECTOR:**

  
**James A. Weltz, CIH, President**

# ***Certificate of Training***

**CRITERION LABORATORIES, INC.**

**HEREBY CERTIFIES THAT**

**Ian Forster**

**HAS SUCCESSFULLY COMPLETED A 4 HOUR TELECONFERENCE COURSE ENTITLED**

**Asbestos Building Inspector Refresher**

**INCLUDING CLASSROOM INSTRUCTION**


**on this 6th day of December 2022**

**Approved for AHERA Accreditation Under TSCA Title II**

**400 Street Road  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com**

*Rev. 20170501  
Course is conducted in English*

**DIRECTOR:**

  
**James A. Weltz, CIH, President**



**PENNSYLVANIA ASBESTOS CERTIFICATION**

**035653**

Sex	Height	Eyes	Birth Date
M	6'01"	BLU	11/08/1979

Expires	Issue Date
12/07/2022	12/28/2021

Class  
INSPECTOR



IAN FORSTER  
C/O CRITERION LABS INC  
400 STREET ROAD  
BENSALEM PA 19020



Expiration Date:  
11/10/2022

# Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Teagan Fortna

HAS SUCCESSFULLY COMPLETED A 24 HOUR COURSE ENTITLED

Asbestos Building Inspector Initial

INCLUDING CLASSROOM INSTRUCTION

11/08/2021 to 11/10/2021

Exam passed on this 10th day of November 2021 - Score - 90

Approved for AHERA Accreditation Under TSCA Title II

400 Street Road  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com

Rev. 20170501

Course is conducted in English

DIRECTOR:



James A. Weltz, CIH, President



# ***Certificate of Training***

**CRITERION LABORATORIES, INC.**

**HEREBY CERTIFIES THAT**

**Teagan Fortna**

**HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED**

**Asbestos Building Inspector Refresher**

**INCLUDING CLASSROOM INSTRUCTION**


**on this 8th day of November 2022**

**Approved for AHERA Accreditation Under TSCA Title II**

400 Street Road  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
[www.criterionlabs.com](http://www.criterionlabs.com)

Rev. 20170501  
Course is conducted in English

DIRECTOR:

  
James A. Weltz, CIH, President

# PENNSYLVANIA ASBESTOS CERTIFICATION

063213

Birth Date  
06/26/1999

TEAGAN R FORTNA



Expires  
11/08/2023

Issue Date  
11/29/2022

Sex  
M

Height  
6' 02"


Eyes  
BLU

*Teagan Fortna*

Class  
INSPECTOR



***Asbestos Investigator***  
***Certified by AMS***



**Teagan Fortna**

Certificate #: AIC22-000030  
Issue Date: 08/29/2022  
Expiration: 03/31/2023



City of Philadelphia  
Dept. of Public Health  
Air Management  
Services



# Certificate of Completion

*awarded to*

**Barbara Gancarz**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Management Planner Initial Course**

**under TSCA Title II**

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken New Jersey 08110  
(856) 665-3449

**11/10-11/22**

*Course Date*

**11/11/22**

*Exam Date*

**11/11/23**


*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-1122-7-004**

*Certificate Number*

  
**Mark K. Schlager**  
*Training Director*

# ***Certificate of Training***

**CRITERION LABORATORIES, INC.**

**HEREBY CERTIFIES THAT**

**Barbara Gancarz**

**HAS SUCCESSFULLY COMPLETED A 24 HOUR COURSE ENTITLED**

**Asbestos Building Inspector Initial**

**INCLUDING CLASSROOM INSTRUCTION**

**10/31/2022 to 11/02/2022**


**Exam passed on this 2nd day of November 2022 - Score - 90**

**Approved for AHERA Accreditation Under TSCA Title II**

**400 Street Road  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
[www.criterionlabs.com](http://www.criterionlabs.com)**

*Rev. 20170501  
Course is conducted in English*

**DIRECTOR:**

  
**James A. Weltz, CIH, President**

PENNSYLVANIA ASBESTOS CERTIFICATION

064552

Birth Date  
12/15/1971



BARBARA D GANCARZ  
C/O CRITERION LABS INC  
400 STREET RD  
BENSALEM PA 19020

Expires  
11/11/2023

Issue Date  
11/21/2022

Sex  
F

Height  
5' 03"

Eyes  
GRN

*Barbara D. Gancarz*

Class  
MANAGEMENT PLANNER



# Certificate of Completion

*awarded to*

**Isa Haj**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Management Planner Initial Course**

**under TSCA Title II**

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken New Jersey 08110  
(856) 665-3449

2/24-25/22

*Course Date*

2/25/22

*Exam Date*

2/25/23


*Expiration Date*

Not Provided

*Social Security Number*

ACC-0222-7-003

*Certificate Number*

  
\_\_\_\_\_  
*Mark K. Schlager*

*Training Director*

# ***Certificate of Training***

**CRITERION LABORATORIES, INC.**

**HEREBY CERTIFIES THAT**

**Isa Haj**

**HAS SUCCESSFULLY COMPLETED A 4 HOUR TELECONFERENCE COURSE ENTITLED**

**Asbestos Management Planner Refresher**

**INCLUDING CLASSROOM INSTRUCTION**

**on this 6th day of December 2022**

**Approved for AHERA Accreditation Under TSCA Title II**

**400 Street Road  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com**


*Rev. 20230216  
Course is conducted in English*

**DIRECTOR:** *Adam Wetz*

*Adam Wetz, President*



21 02501085410  
23040



**If found, please contact:**

Department of Labor & Industry  
Certification, Accreditation & Licensing Division  
651 Boas Street, Room 1606  
Harrisburg, PA 17121.  
(717) 772-3396



# ***Certificate of Training***

**CRITERION LABORATORIES, INC.**

**HEREBY CERTIFIES THAT**

**Christian T. Rodebaugh**

**HAS SUCCESSFULLY COMPLETED A 24 HOUR COURSE ENTITLED**

**Asbestos Building Inspector Initial**

**INCLUDING CLASSROOM INSTRUCTION**

**01/03/2023 to 01/05/2023**

**Exam passed on this 5th day of January 2023 - Score - 90**

**Approved for AHERA Accreditation Under TSCA Title II**

**400 Street Road  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com**

*Rev. 20170501  
Course is conducted in English*

**DIRECTOR:**



**James A. Weltz, CIH, President**



# *Certificate of Training*

## CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Julie Wankmiller

HAS SUCCESSFULLY COMPLETED A 24 HOUR COURSE ENTITLED

Asbestos Building Inspector Initial

INCLUDING CLASSROOM INSTRUCTION

01/03/2023 to 01/05/2023

Exam passed on this 5th day of January 2023 - Score - 94

Approved for AHERA Accreditation Under TSCA Title II

DIRECTOR:



James A. Weltz, CIH, President

400 Street Road  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
[www.criterionlabs.com](http://www.criterionlabs.com)

Rev. 20170501

Course is conducted in English





## APPENDIX F

---

### PHILADELPHIA SCHOOL DISTRICT ASBESTOS MANAGEMENT PROGRAM





THE SCHOOL DISTRICT OF  
PHILADELPHIA

# Asbestos Hazard Emergency Response Act "AHERA"

## ASBESTOS MANAGEMENT PROGRAM

2021-2022

*Prepared By*

School District of Philadelphia and Tetra Tech, Inc.





## TABLE OF CONTENTS

<b>1.</b>	<b>Introduction.....</b>	<b>F-5</b>
<b>2.</b>	<b>Summary of Asbestos Management Program .....</b>	<b>F-6</b>
<b>3.</b>	<b>Asbestos Management Program Execution .....</b>	<b>F-7</b>
	a. General Execution .....	F-7
<b>4.</b>	<b>Summary of Program Execution .....</b>	<b>F-8</b>
	a. Asbestos Management Program Execution .....	F-8
<b>5.</b>	<b>Responsibilities .....</b>	<b>F-9</b>
	a. Office of Environmental Management and Services .....	F-9
	b. Asbestos Worker/Supervisor - "A-TEAM" .....	F-9
	c. Asbestos Designated Person .....	F-9
	d. Supervisor or Project Manager (Capital, Maintenance and Facilities).....	F-10
	e. Employee – Capital .....	F-10
	f. Employee – Maintenance .....	F-11
	g. Employee – Facilities & Custodial .....	F-11
<b>6.</b>	<b>Requirements .....</b>	<b>F-12</b>
	a. Employee Exposure Monitoring.....	F-12
	b. Employee Notification .....	F-12
	c. Observation and Monitoring .....	F-12
	d. Training Program.....	F-12
	e. Record-Keeping .....	F-12
<b>7.</b>	<b>AHERA OPERATIONS AND MAINTENANCE PLAN .....</b>	<b>F-13</b>
	a. CONTROLS.....	F-13
<b>8.</b>	<b>O&amp;M RESPONSE ACTIONS .....</b>	<b>F-15</b>
	a. Facility Maintenance Isolation of Area Responsibilities .....	F-15
	b. Unlikely Contact with ACM/PACM .....	F-15
	c. Accidental Disturbance of ACM/PACM .....	F-15
	d. Planned Disturbance of ACM/PACM .....	F-15
	e. Miscellaneous ACM/PACM .....	F-15
	f. Vinyl Asbestos Floor Tile.....	F-16
	g. Mastics/Adhesives.....	F-16
	h. Woven Vibration Dampers.....	F-16







i.	Other Work Practices .....	F-16
j.	Suspected Fiber Release Episodes .....	F-16
9.	<b>REFERENCES and RESOURCES .....</b>	<b>F-17</b>



## DEFINITIONS / ACRONYMS

<b>ACM/PACM:</b>	Asbestos Containing Material/Presumed Asbestos Containing Material
<b>AHERA:</b>	Asbestos Hazard Emergency Response Act
<b>AIR FORM:</b>	Asbestos Inspection Report Form
<b>Amended Water:</b>	Water to which a surfactant (soap) has been added
<b>AMP:</b>	Asbestos Management Plan
<b>Asbestos Designated Person:</b>	Individuals assigned by the district to oversee asbestos-related issues.
<b>Asbestos Regulated Area:</b>	Location that is posted as an asbestos or asbestos-contaminated work area in which only approved and accredited personnel are permitted to enter
<b>A-TEAM:</b>	School District of Philadelphia asbestos workers
<b>CIP:</b>	Capital Improvement Program
<b>Consultant:</b>	Environmental consulting firm hired by the District
<b>EPA:</b>	Environmental Protection Agency
<b>Fiber Release Event</b>	Any uncontrolled or unintentional disturbance of ACBM resulting in visible emission.
<b>In House Personnel:</b>	School District of Philadelphia workers
<b>LEA:</b>	Local Education Agency
<b>O&amp;M:</b>	Operations and Maintenance
<b>OEMS:</b>	Office of Environmental Management and Services
<b>OSHA:</b>	Occupational Safety and Health Administration
<b>PEL:</b>	Permissible Exposure Limit
<b>SDP:</b>	School District of Philadelphia
<b>STEL:</b>	Short Term Exposure Limit

# 1. Introduction

The School District of Philadelphia, Asbestos Policy Statement:

**“The School District of Philadelphia is dedicated to providing a safe and healthful work environment for its employees, students, faculty, contractors and visitors. In recognition of the potential health problems associated with asbestos, the School District of Philadelphia is committed to a comprehensive asbestos control and management program. This program is implemented and maintained through the School District of Philadelphia’s Office of Environmental Management and Services (OEMS).”**

OEMS has the responsibility to oversee established procedures for asbestos abatement, asbestos inspection, air monitoring, renovation, and demolition activities within all School District of Philadelphia-owned or leased facilities.

The goals of these procedures are:

1. People and the environment are not exposed to asbestos fibers
2. Asbestos waste is handled and disposed of properly
3. Members of the School District of Philadelphia community have access to the Office of Environmental Management and Services for information, assistance, guidance, and interpretation regarding asbestos-related matters
4. Members of the School District of Philadelphia community have access to the Asbestos Management Plans as required and outlined in the US EPA AHERA regulations including annual written notification to all parents
5. Compliance with all applicable Federal, State, and Local Asbestos Regulations

The requirements outlined in this manual are mandatory in nature where the word “SHALL” is used and are advisory in nature where the word “SHOULD” is used.

## 2. Summary of Asbestos Management Program

The School District of Philadelphia's Asbestos Management Program was established to meet the requirements of Federal Regulations.

These regulations include, but are not limited to:

- US Environmental Protection Agency Asbestos Hazard Emergency Response Act (US EPA AHERA) and National Emissions Standard for Hazardous Air Pollutants Subpart M, Part 61 (NESHAP).
- US Department of Labor, Occupational Safety and Health Administration (OSHA) General Industry Standard (29 CFR 1910.1001) and the OSHA Asbestos Standard for the Construction Industry (29 CFR 1926.1101).
- The Commonwealth of Pennsylvania, Department of Labor and Industry, Asbestos Occupations, Accreditation and Certification Act.
- The City of Philadelphia, Department of Public Health, Asbestos Control Regulations.

## 3. Asbestos Management Program Execution

### a. General Execution

The Office of Environmental Management and Services (OEMS) develops, implements, and manages environmental programs for the School District of Philadelphia faculty, staff, and students and assists with ensuring that all contractors comply with Federal, State, and Local Environmental Regulations. OEMS provides the oversight of School District of Philadelphia employees (Asbestos A-TEAM), environmental consultants, and asbestos abatement contractors for all projects within the School District of Philadelphia concerning Asbestos Containing Materials.

The control of asbestos safety and health hazards at the School District of Philadelphia is primarily through the implementation of engineering, work practice, and administrative controls.

This written program establishes the procedures necessary to:

1. Meet established federal regulations for occupational exposure to asbestos fibers.
2. Meet the requirements of the City of Philadelphia Asbestos Control Regulations which encompasses the disturbance and/or abatement of asbestos-containing building materials.
3. Provide the necessary health and safety protection to the School District of Philadelphia staff, faculty, students, contractors, and visitors.

## 4. Summary of Program Execution

### a. Asbestos Management Program Execution

The Asbestos Management Program is administered by the Office of Environmental Management and Services (OEMS). OEMS provides the following services primarily through professional consultants:

- Exposure monitoring services
- Building inspection and surveys (bulk sampling) for the identification of asbestos-containing materials
- Asbestos project design services
- Asbestos abatement project and air monitoring services
- Emergency response to suspected fiber release episodes
- Education and information
- Medical monitoring
- Training for School District of Philadelphia personnel

## 5. Responsibilities

### a. Office of Environmental Management and Services

OEMS is responsible for performing the following functions:

1. Developing and administering the Asbestos Management Program.
2. Providing asbestos-related services to all School District of Philadelphia departments.
3. Conducting required training of the Asbestos Management Program while working jointly with departments to schedule training.
4. Identifying and posting areas where labeling and signage is required.
5. Medical Monitoring of OEMS "A-TEAM" and other departments Asbestos Program staff.
6. Certification and training as required for OEMS "A-TEAM" and other departments Asbestos program staff.
7. Record keeping as outlined in Section 3.5 and all records as by required by US EPA AHERA regulations.

### b. Asbestos Worker/Supervisor - "A-TEAM"

1. "A-TEAM" workers and supervisors adhere to the following requirements:
  - a) Attend an initial Worker/Supervisor Asbestos Course
  - b) Maintain the annual recertification per EPA AHERA requirements and Commonwealth of Pennsylvania Asbestos Occupations, Accreditation, and Certifications Act
  - c) Undergo an annual Asbestos Medical Evaluation
  - d) Undergo annual Respirator Medical Clearance
  - e) Undergo annual Respirator Fit Testing

### c. Asbestos Designated Person

The Asbestos Designated Person is responsible for:

1. Assuring the health and safety of employees, students, and visitors in the School District of Philadelphia facilities under his or her control, as it pertains to asbestos exposure.
2. Staying informed of all areas under his or her jurisdiction where potential asbestos exposures may exist and initiating protection programs that adhere to the Asbestos Management Program requirements of this manual.
3. Assuring that the Asbestos Management Program requirements are adhered to by investigators, project managers, supervisors, division heads, and School District of Philadelphia personnel under their supervision.
4. Ensuring that all employees within the Asbestos Management Program comply with US EPA AHERA regulations by attending the required training.
5. Posting of:
  - a) Warning labels and signage

- b) Commonwealth of Pennsylvania Asbestos Abatement and Demolition/Renovation Notification form
- c) Asbestos Inspection Reports (AIR) form (when required by the City of Philadelphia)

#### **d. Supervisor or Project Manager (Capital, Maintenance and Facilities)**

Each person in charge of a Departments of Capital, Maintenance, and/or Facilities project, maintenance, repair, renovation, demolition, or other activity where asbestos-containing material may be present is responsible for:

Identifying, with the assistance of OEMS, asbestos-containing building materials prior to any disturbance of these materials. Various Federal (EPA and OSHA) and Local (City of Philadelphia Asbestos Control) Regulations require Asbestos Inspections prior to renovation and demolition activities. This shall be accomplished by following the Asbestos Management Program Procedures as follows:

1. Oversee that the requirements of the Asbestos Management Program Procedures are followed by all personnel, trades, and contractors who are involved with the project.
2. Review of the required Asbestos Inspection Report (AIR) form as provided by the City of Philadelphia, and AHERA Management Plan documents prior to activities that may disturb any Asbestos Containing Materials.
3. Perform all project-related duties as outlined in the Project Management Responsibilities.
4. Keep the department chairperson or director informed on any actions proposed or taken regarding the Asbestos Management Plan.

#### **e. Employee – Capital**

School District of Philadelphia Capital employees and consultants shall:

1. Confirm that no suspect or asbestos-containing building materials are disturbed during the projects they are performing or managing. This shall be accomplished by notifying their supervisor and OEMS by the issuance of a work order permit and verifying that the materials that may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
2. Immediately notify OEMS and their supervisor in the event of a suspected fiber release episode upon discovery of visible damage to asbestos-containing materials.

The types of projects represented as part of the Capital Improvement Program are as follows:

1. Complete renovation of an existing building that addresses all facility component concerns and educational program needs.
2. Major renovation of an existing building addressing significant facility component and educational improvements.
3. Addition to an existing building (either as an attachment or stand-alone structure) to accommodate needed program space.
4. Conversion of an existing facility to accommodate a change in an educational program.
5. Facility component improvement of specific facility needs (i.e., electrical or HVAC system upgrades, ADA improvements, life safety improvements, exterior renovations, etc.).



## **f. Employee – Maintenance**

School District of Philadelphia Maintenance employees shall:

1. Confirm that no suspect or asbestos-containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS and verifying that the materials that may be disturbed are non-asbestos-containing. If this information is not available or verification has not been made, these materials should not be disturbed.
2. Immediately notify OEMS and their supervisor in the event of a suspected fiber release episode or upon discovery of visible damage to asbestos-containing materials.
3. All employees involved in maintenance activities shall attend the required Asbestos Awareness training program within 60 days of employment.

## **g. Employee – Facilities & Custodial**

School District of Philadelphia Facilities and Custodial employees shall:

1. Confirm that no suspect or asbestos-containing building materials are disturbed in the course of their duties or the work they are performing. This shall be accomplished by notifying their supervisor and OEMS and verifying that the materials that may be disturbed are non-asbestos-containing. If this information is not available or verification has not been made, these materials should not be disturbed.
2. Immediately notify OEMS and their supervisor in the event of a suspected fiber release episode or upon discovery of visible damage to asbestos-containing materials.
3. All employees involved in Facilities and Custodial activities shall attend the required Asbestos Awareness training program within 60 days of employment.

## 6. Requirements

### a. Employee Exposure Monitoring

When information indicates that an employee's exposure to asbestos fibers may equal or exceed an 8-hour time-weighted average of 0.1 fibers per cubic centimeter (f/cc) (per OSHA 1910.1001 & 1926.1101), OEMS shall develop and implement an asbestos exposure monitoring program. The sampling strategy shall be designed to identify employees by work task (job classification) that may be exposed to asbestos fibers that exceed an 8-hour time-weighted average of 0.1 f/cc.

### b. Employee Notification

OEMS shall notify, in writing, each employee exposed to asbestos fibers at or above an 8-hour time-weighted average of 0.1 f/cc.

### c. Observation and Monitoring

OEMS shall provide employees or their representatives with the opportunity to observe any exposure monitoring conducted and the results of this exposure monitoring.

### d. Training Program

OEMS shall institute a training program that meets the requirements of AHERA for all employees who perform maintenance operations in a facility or school which contains asbestos-containing materials or presumed asbestos-containing materials and 1910.1001 (j), and the Commonwealth of Pennsylvania Department of Labor and Industry, PA Act 194, and the City of Philadelphia Asbestos Control Regulations. The affected departments shall have employee participation in this program. For the OEMS A-TEAM and other departments, such as Asbestos Support Trades, Asbestos Program staff training shall be conducted annually for each employee as required by all Federal, State, and Local requirements for each discipline.

All Asbestos Awareness training as required by AHERA shall be performed within 60 days of employment and shall include:

- Health effects of asbestos
- Locations of ACM and PACM in the building/facility
- Recognition of ACM and PACM damage and deterioration
- Proper response to a suspected fiber release episode
- Procedure to be followed to isolate areas affected by a fiber release

### e. Record-Keeping

OEMS shall maintain an accurate record of all employee exposure monitoring and the results of that monitoring. OEMS and/or the School District of Philadelphia Human Resources Department shall maintain the records of the employee medical monitoring program. OEMS shall maintain all employee training records. All records shall be provided upon request to employees, former employees, and representatives designated by the individual employee.

## 7. AHERA OPERATIONS AND MAINTENANCE PLAN

### a. CONTROLS

#### 1. Work Order System

Minimizing the disturbance of ACM/PACM during normal maintenance and renovation activities is the primary goal and task encountered by OEMS. Operations and maintenance employees and contractors should be warned to avoid conducting any maintenance work which may disturb ACM/PACM. Initiating a work order system, where all work orders or requests are channeled through the Office of Environmental Management and Services (OEMS), will be one of the methods used to control and minimize the disturbance of ACM/PACM.

Any work performed by in-house personnel or contractors that could or will impact ACM/PACM shall be coordinated by OEMS. A completed Asbestos Inspection Report (AIR) Form, as provided by the City of Philadelphia, shall be issued to all in-house personnel and all contractors whose work could impact ACM/PACM. This form should accompany each contract issued to an outside contractor and posted on the job site. It is the responsibility of the recipient to provide this information to all the subcontractors that they employ.

All work order requests for maintenance and renovation activities in areas where ACM/PACM is suspected or known to be present are to be submitted to OEMS prior to proceeding with any work. OEMS is responsible for reviewing asbestos survey records for information about the presence of ACM/PACM in the area where the work is to be performed. OEMS may choose to physically inspect the area to confirm existing records reflect actual conditions. If no asbestos is present, further action by OEMS is not required, and the planned actions can proceed. If ACM/PACM is found to be present in the area, OEMS will proceed with the work order application and obtain an approved and accredited asbestos contractor or assign the OEMS "A-TEAM" to abate the ACM/PACM; abatement may be in the form of encapsulation, removal, or repair.

#### 2. Regulated Areas

The SDP will identify and regulate all areas where airborne concentrations of ACM/PACM exceed the Permissible Exposure Limit (PEL)\* (Per OSHA determined to be 0.1 f/cc), exceed the short-term exposure limit (STEL) (Per OSHA determined to be 1.0 f/cc), or there is a reasonable possibility that the (PEL) or (STEL) may be exceeded. All ACM/PACM removal activities involving thermal system insulation (Class I), surfacing material (Class I), and miscellaneous materials, such as floor tile, roofing, siding mastic, etc. (Class II), and repair and maintenance operations where thermal system insulation and surfacing material is likely to be disturbed (Class III) will be performed in accordance with federal, state, and local regulations. All asbestos abatement work and activities will be designed and managed as asbestos-regulated areas. These areas will be demarcated and labeled.



### 3. Warning Signs

Warning signs shall be displayed at all approaches to each asbestos-regulated area. The asbestos abatement contractor will provide OSHA warning signs in all regulated areas during removal, repair, and other maintenance activities, in English and the indigenous language of the population affected. OEMS will provide an Asbestos Inspection Report (AIR) to all contractors who must inform all employees, supervisors, and subcontractors working in locations contiguous to asbestos-regulated areas of the potential hazards and work practices required.

### 4. Warning Labels

Warning labels and signage shall be affixed to all raw materials, mixtures, scrap, waste, debris, and other products containing asbestos material, or to their containers. Generally, the asbestos abatement contractor or OEMS A-TEAM personnel will provide all warning labels for ACM/PACM.



## 8. O&M RESPONSE ACTIONS

The Asbestos Management Program O&M procedures are outlined in this section. Additional requirements specific to asbestos abatement activities are included in the Project Design documents for all Asbestos Abatement work. Regular inspection and reporting of ACM/PACM deterioration, disturbance, or other problems must be diligently practiced by all employees including custodial and maintenance personnel.

### a. Facility Maintenance Isolation of Area Responsibilities

Maintenance personnel are often required to work in areas where ACM/PACM may potentially be disturbed. Most maintenance activities are conducted by in-house staff, outside contractors, or a combination.

Suspected fiber release episodes, such as pipe fitting or valve breaks, emergency boiler work, or mechanical equipment repair will be responded to by OEMS A-TEAM personnel or asbestos abatement contractor personnel. The owner's maintenance staff will: (1) isolate the suspected fiber release area, (2) post warning signs to prevent unauthorized access, and (3) notify their supervisor and OEMS. OEMS will have the suspected fiber release area remain isolated and properly cleaned by an approved and accredited asbestos abatement contractor or by OEMS A-TEAM personnel.

### b. Unlikely Contact with ACM/PACM

Maintenance activities or repairs that can be performed without contacting or disturbing the ACM/PACM require little more than normal care and good workmanship (Class VI work). For example, valves that are either uncovered or covered with non-asbestos insulation can be packed or repaired without disturbing asbestos insulation on nearby pipes. The major directive is to have maintenance and custodial personnel that are familiar with procedures such as isolating the area, posting warning signs, and notifying OEMS in the event of any accidental ACM/PACM disturbance.

### c. Accidental Disturbance of ACM/PACM

Maintenance and facilities personnel shall notify OEMS any time a fiber release is suspected.

### d. Planned Disturbance of ACM/PACM

Maintenance activities that may impact ACM/PACM include access to a valve, flange, duct, or related system component.

Where asbestos-containing insulation must be removed to maintain or repair the thermal system, the ACM/PACM will ultimately be disturbed. ACM/PACM removal work shall be conducted by OEMS A-TEAM personnel or an approved, accredited, and licensed asbestos abatement contractor.

### e. Miscellaneous ACM/PACM

Miscellaneous types of ACM/PACM may include vinyl asbestos floor tiles, mastics/adhesives, transite material, and woven vibration dampers. Disturbance of these materials should be avoided. Routine maintenance

activities involving these materials do not pose a problem if handled properly. Questions on the proper removal and disposal of miscellaneous ACM/PACM should be directed to OEMS. OEMS will contact an approved, licensed, and accredited asbestos abatement contractor or utilize OEMS A-TEAM personnel to assist with miscellaneous ACM/PACM clean-up activities.

#### **f. Vinyl Asbestos Floor Tile**

Asbestos-containing floor tiles in good condition are considered non-friable (when dry cannot be crushed to powder by hand) unless they are abraded, drilled, sawed, sanded, or disturbed by any activity that breaks up the material. Routine maintenance of these materials should employ the use of non-abrasive buffers and wet cleaning techniques. Broken or loose floor tiles will be removed and disposed of as asbestos waste by OEMS. The remaining debris should be vacuumed with a HEPA vacuum and the area wet mopped using amended water.

#### **g. Mastics/Adhesives**

Mastics and adhesives containing asbestos in good condition are considered non-friable (when dry cannot be crushed to powder by hand) and do not pose a potential health concern unless abraded, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

#### **h. Woven Vibration Dampers**

Woven vibration dampers in good condition are considered non-friable and do not pose a potential health concern unless they are brittle enough to be crushed, or work involving cutting drilling, sawing, sanding, or otherwise abrading these materials is planned. Questions on the proper removal should be directed to OEMS.

#### **i. Other Work Practices**

Any special work not included in this section should be brought to the attention of OEMS for review prior to the initiation of any work that may involve the disturbance of ACM/PACM.

#### **j. Suspected Fiber Release Episodes**

Facilities and maintenance staff should report to OEMS the presence of any suspected asbestos debris, water, or physical damage to ACM/PACM, or any other evidence of a suspected fiber release. OEMS will have the OEMS A-TEAM personnel, or an approved, licensed, and accredited abatement contractor respond to the site to clean up debris and make repairs as soon as possible. OEMS will also contact an environmental consultant to conduct air monitoring and prepare a report and submit it at project completion to OEMS for each response action. OEMS will forward the report for each site location AHERA Management Plan accordingly.

## 9. REFERENCES and RESOURCES

Applicable regulations for asbestos projects impacted by renovation, demolition, and maintenance activities:

- **Philadelphia Air Management Services – Asbestos Control Unit**  
<http://www.phila.gov/health/units/ams/Asbestos/asbestos.html>
- **Pennsylvania Asbestos Occupations, Accreditation, and Certification Act 194**  
<http://www.dli.state.pa.us/landi/cwp/view.asp?a=185&q=56262&landiNav=>
- **The United States Environmental Protection Agency**  
<http://www.epa.gov/asbestos/>
- **Occupational Safety and Health Administration (OSHA)**  
<http://www.osha.gov/SLTC/asbestos>