



POCATELLO/CHUBBUCK SCHOOL DISTRICT 25
LEARNING TODAY FOR THE POSSIBILITIES OF TOMORROW

**Administration Offices
3115 Pole Line Road
Pocatello, Idaho 83201**

Addendum No. 2

March 15, 2024

RE: 2024 HVAC – Central Plant Equipment, Heat Pump, and Outdoor Air Units Replacement at Jefferson Elementary

FROM: Business Services
(208) 235-3270

This Addendum becomes a part of the Contract Documents and modifies the original Bidding Specifications, as noted below. This addendum consists of one (1) page. Acknowledge Addendum on the Bid Proposal. **Failure to acknowledge Addendum(s) on the bid sheet may subject the bidder to disqualification.**

1. The fire suppression system will be drained by Pocatello/Chubbuck School District #25. The District will contract 3D Fire Protection to fill and re-certify the FP system. All contact with the local Fire Department will be made by Pocatello/Chubbuck School District #25.
 - a. The contractor shall make all arrangements for coordination with Pocatello/Chubbuck School District #25 for new piping for the fire protection system.
2. Access for placement of the new air handling equipment on the mechanical mezzanine (HP & OSA Units) shall be made thru the removal of the north and south entrance ceilings. Contractor shall be responsible for removal and replacement of the ceiling structure and metal covering. Contractor may suggest other means for the movement of equipment to the mezzanine area.
3. All temperature controls will be provided and installed by Clima-Tech Corporation. The cost of the task will be covered by Pocatello/Chubbuck School District #25. Contractor shall make the arrangements for coordination with the temperature control contractor with all new equipment installation.
4. Acceptable Equipment Manufacturers:
 - a. Cooling Tower – EVAPCO (Stainless Steel Type)
 - b. VFD's – Yaskawa
 - c. Expansion Tanks / Air Separators – Thrush / Wessels
 - d. Hydronic Specialties – JL Wingert / Trerice
5. Heat pump air / hydronic system and OSA units shall be Tested, Adjusted, and Balanced by a NEBB professional TAB firm with offices within 10 miles of the project. Original design CFM drawings available upon request.

NO OTHER CHANGES

END OF ADDENDUM No.1 – March 12, 2024, js