

Nick H. Barnard Architect LLC

697 W. 175 N., BLACKFOOT, ID 83221

E-MAIL: nhb63@outlook.com

TEL: 208.242.6564

ADDENDUM NO. THREE

TO: Bidders

DATE: March 22, 2024

**RE: Highland High School
Athletic Field Facility
1800 Bench Road
Pocatello, Idaho**

This Addendum forms a part of the Contract Documents and modifies the original Bidding Drawings dated **February 2024**, as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification. The following information is being issued to General Contractors only. It is the obligation of the Contractor to notify his Subcontractors and suppliers of items relating to their bids prior to bid opening. This Addendum consists of 3 page(s) and no drawing(s).

I - CHANGES TO PRIOR ADDENDA: NONE

II - CHANGES TO BIDDING REQUIREMENTS: NONE

III - CHANGES TO CONDITIONS OF THE CONTRACT: NONE

IV - CHANGES TO AGREEMENT & OTHER CONTRACT FORMS: NONE

V - CHANGES TO SPECIFICATIONS:

Item V-1. See questions from Andersen Construction, 1 page attached.

Item V-2. See questions from ESI Construction, 1 page attached.

VI - CHANGES TO DRAWINGS:

Item VI-1. See questions from Andersen Construction, 1 page attached.

Item VI-2. See questions from ESI Construction, 1 page attached.

END of ADDENDUM



Highland HS Athletic Facility
Pocatello, ID
Pre Bid RFI Log

Last updated: 3/20/2024

Item	Description	Response Detail
A - Architectural		
A-1	The Door Schedule on Sheet A8.1 and specifications do not indicate the hardware group required for each door. Please provide the hardware groups and group to be used for each door.	See Section 08 0601
A-2	Sheet A4.1, Roof Note #2 requires 1/4" Densdeck to be applied as part of the roof assembly. Specification section 076113 does not reference a requirement for Densdeck. Please confirm if the Densdeck will be required as noted in the drawings.	Densdeck required to meet fire rated roof system.
A-3	Please confirm if 1/4" densdeck will be required as part of the roof assembly for the storage building.	See Addendum 2.
A-4	Specification sections for Metal Roofing, Metal Siding, Metal Soffit, Steel Flashing, and Steel Fascia each note different approved manufacturers that do not appear to match. These discrepancies may lead to an inconsistent appearance between these scope of work. Please provide a list of approved manufacturer for each of these sections so a consistent manufacturer can be carried across these scopes.	Coordination shall be by submittals as usual.
A-5	Specification section 076113 refers to scope for ridge vents, ridges, valley, curbs, parapets and skylights. Please confirm these scopes do not apply to this project.	Provide 20-year roof system as specified.
A-6	Specification section 074619 contains information for Horizontal Siding. Please confirm this scope does not apply to this project.	Refer to building elevations.
A-7	Specification section 076210 contains a reference to section 075000 for flashings. Section 075000 does not appear in the documents provided. Please confirm this scope does not apply to this project.	Provide 20-year roof system as specified.
A-8	Sheet A5.1 notes Flooring Type F1 as a "Armorseal HS" sealed concrete. This product would require grinding of the concrete floor prior to install and grinding would result in a different appearance compared to a simple sealed concrete. Please confirm if the product and resulting finish is the intended design or if a different flooring should be accounted for in pricing.	Specified product requires a "profile" on the concrete, provide acid etch or light sanding per Mfr recommendations.
C - Civil/Landscape		
C-1	The civil drawings do indicate tie-in points for water and sewer utilities. Please confirm locations and tie-in details for existing utilities. Sheet	See note C-1 below.
C-2	Please provide the geotechnical report if one is available	Not available.
E - Electrical		
E-1	Please confirm the location of the ICPO service point and utility transformer noted on the one-line diagram shown on Sheet E3.1	See Addendum one.
M - Miscellaneous		
M-1	Please confirm no fire suppression or fire alarm is required for this project.	None required.

C-1. Sewer & water available at the building. Site verification of size required. Alternate one required for sewer. See Addendum 1.