

REQUEST FOR BIDS

The Moon Area School District is accepting sealed bids for: Walk-in Freezer for J.H. Brooks Elementary School

Specifications and instructions may be obtained by contacting the Food Services Department at 8353 University Boulevard, Moon Township, PA 15108, during scheduled business hours, calling 412-264-9440 Ext. 1129, or by clicking the link below. Click here to download the request for bid information.

Responses for the RFP are due by 2:00pm on Friday, April 26th, 2024. The board reserves the right to waive any provision and/ or accept or reject any proposal or parts thereof.

1 ea	<p>Indoor -10°F Freezer, Freezer (-10°F) with Floor Insulation: 4 inches foamed-in-place urethane (X) Class 1 Approximate overall size: 11' 7" x 6' 3 3/4" x 8' 6 1/2"(H) provide drawing</p> <p>Finishes 6' 3 3/4" Exterior Wall, Exposed Section of 11' 7" Exterior Wall - 20ga Embossed SS Remaining Exterior - 26ga Embossed Galvalume Interior Walls & Ceiling - 26ga Embossed White Galvalume Interior Floor - 10ga 5-Bar Tread with foamed in 3/4" plywood underlay</p> <p>Entrance Doors Compt 1 - door 1 (Exterior of Door & Frame: 20ga Embossed SS, Interior of Door & Frame: 26ga Embossed White Galvalume) 34" x 77" LHH freezer door with 51 3/4" frame - includes V1600 hydraulic door closer with Z-1009 hook, (3) W-59 polished hinges, Norfab 14" x 24" heated viewport, W-29NC latch, Locking Hasp, 3' 0"(H) 10ga 5-Bar Tread kickplates int & ext door & frame, Weiss 24DT-SP-LT digital therm/switch, Fermod PRP & VXS100 (LED)</p> <p>Accessories Interior 34" x 27" 5 Bar Tread Ramp ONE(1) 48" Universal LED Light with Bulbs (Shipped loose)- universal (X) 3' H 10ga 5-Bar Tread Kickplates on (1) 6'3-3/4" Ext Front Wall (1) 3"x 3"x 9'H Smooth S/S Inside Corner Trim (1) 1"x 2"x 9'H Smooth S/S Inside Corner Trim (X) Closure Panel Smooth S/S on (1) 6'3-3/4" side (12"H)</p>
1 ea	<p>Refrigeration Equipment (1)QTY RFO300L4S-EANT 208-230/3/60 Scroll Air Cooled Condensing Unit (9,000 BTUH @ -20° SST, +95° Amb, R448A) with PSC Condensing Motors, Standard Tafco Options and Features (No ED Kit) (1) QTY RL6E090DDARE 208-230/1/60 Russell Next Gen All Temp Electric Defrost Unit Cooler with 2-Speed EC Motors and EcoNet Control Package Including Sporlan EEV, Suction Pressure Transducer; Suction, Entering Air, Coil Temp Thermistors; Local On-Board Two-Row LCD Display and Push Button Adjustments</p>
1 ea	Five Year Compressor Warranty
1 ea	Delivery on Dedicated Tafco Truck
1 ea	<p>Refrigeration Receive Walk-In and Erect Per Specifications Install Refrigeration Line-Set Per Manufacturers Specifications Install Evaporator Coil Per Drawing Set Condensing Unit On Top Of Main Roof Evacuate Refrigerant Lines and Start Up Unit Run Drain Lines In Copper Verify Proper Operation Crane Fee included *Disconnects Must Be Placed With-In 5' Of Condenser* **Roofers Must Provide Roofing Cap and Seal Penetration - 4" Schedule 40 PVC**</p>

	<p>***Permits By Others***</p>
--	--------------------------------