Response to RFI

Date: April 10, 2024

To: All Bidders

From: Chris Davis

Re: 2023-24-004 El Camino Roofing Phase 2

Please see the questions and responses below:

1. Please confirm that all drip edge conditions are to be cut back 6” and removed and new strip in ply of cap sheet is to be furnish & installed prior to receiving coating?
    a. Confirmed
2. Please confirm that any and all blisters are to be cross cut prior to restoration?
    a. Confirmed
3. Please confirm the intent is to have all base flashings, curb flashings, and penetrations to be removed and new flashings torched down prior to coating?
    a. Confirmed
4. Please confirm there is no summer school at this location?
    a. Confirmed, no summer school at this site.

Thank you.