

HARVEY BROTHERS TRUCKING & WRECKING CO INC

1233 WALKER AVE
KANSAS CITY, KS 66104

Phone: 913-371-4852
Fax: 913-371-3252
E-mail:
harveybros@yahoo.com

King/Weeks School Demolition Project Information

Harvey Brothers Trucking & Wrecking is the demolition contractor for the King/Weeks School project at 4201 Indiana Ave. KCMO. Our goal is to complete this project in a safe and timely manner with as little inconvenience to the surrounding neighbors as possible. Harvey Brothers is a professional demolition contractor and we take pride in being environmentally and socially responsible on all work we perform. If you have any questions or concerns during this project, please call Lynn McGinnis at 913-371-4852.

1. The schedule for this project is to begin March 18, 2024 and to be completed by July 31, 2024 (barring any adverse weather conditions).
2. The hours of operation for this project will be Monday – Friday, 7 am to 5 pm and 8 am to 4 pm Saturdays.
3. The existing security fence surrounding the property will remain in place throughout the duration of the project.
4. Prior to demolition, various utility companies will be verifying termination of services and marking locations of underground services within and around the property.
5. Environmental abatement has been completed and all waste has been removed and properly disposed of.
6. Demolition will be performed using various mechanical excavators with specialty demolition attachments.
7. All steel, metal, brick, stone, concrete, and asphalt will be hauled offsite and recycled.
8. All material and debris will be loaded within the fenced areas.
9. All truck and vehicle traffic will be isolated to the north gated entrance on E. 41st St.
10. Haul route: West on E 41st St. North on Indiana Ave, West on 39th St to 71 Hwy.
11. Dust control will be a priority throughout the duration of this project. Excessive dust and wind conditions will be monitored at all times and appropriate controls will be implemented as necessary. Controls include various wetting methods
12. Once demolition is complete and all debris has been removed, approved clean fill material will be imported to backfill all remaining voids. The site will then be graded for proper drainage and prepared for seeding.
13. All work will be completed in strict accordance with all city, state, and regulatory requirements.