



SCOPE OF WORK

MAINTENANCE AND OPERATIONS ASPHALT PROJECTS CUPCCAA INFORMAL BID

FRYBERGER ELEMENTARY SCHOOL 6952 Hood Drive Westminster, CA 92683

SCOPE OF WORK

- Cold plane remove playground, approx. 29,135 SF of existing damaged asphalt up to a 4” depth. Haul away grindings.
- Compact existing subgrade with double drum rollers.
- Furnish and install approx. 290 LF of 2x4 redwood header at landscape edges.
- 4. Tack coat and machine-pave playground, approx. 29,135 SF with up to 4” of hot mix asphalt and roll to a mooth finish.
- Stripe playground per existing layout with (1) coat of water-based traffic paint. Includes: (2) basketball courts, (2) four square, (2) dodge ball courts, (4) handball court, (2) hop scotches, (5) tether ball, and all number stencils.
- 6. Power clean, prepare and apply approx. 29,135 SF with (2) coats of Guard top seal 30 days after asphalt has cured.
- Re-stripe per existing layout with (1) coat of water-based traffic paint.