ADDENDUM TO THE BID DOCUMENTS	Page: 1	Total Pages: 23
Addendum No: **# 2**	Date this Addendum Issued: **October 4, 2022**	
Issuing Office: Matanuska-Susitna Borough School District (MSBSD) Purchasing Department 690 Cope Industrial Way Palmer, Alaska 99645 Phone: (907) 861-5120 Facsimile: (907) 861-5184	Previous Addenda Issued: One 1 October 3, 2022	
Return Acknowledgment To: **Issuing Department** Bid Title: **Snow and Ice Removal and Sanding Services** Bid No: **B23-03**	Date and Hour of Bid Due Date: ~~**October 10, 2022 at 2:00 p.m.**~~ **Revised: October 12, 2022 at 2:00 p.m.** As Advertised (Frontiersman): **September 23 and 25, 2022** As Advertised (ADN): **September 23 and 25, 2022**	

The following corrections, changes, additions, deletions, revisions, and/or clarifications are hereby made a part of the contract documents. In case of conflicts between this addendum and previously issued documents, this addendum shall take precedence. The bidder must acknowledge receipt of this addendum in the space provided on Appendix #1. Failure to do so may subject the bidder to disqualification.

Clarifications:
Revised Bid opening is Wednesday, October 12, 2022 at 2:00 p.m.

Attachments:
Attachment A: Revised Scope of Services (6 pages)

Attachment C: Revised Bid Form (16 pages)

Questions:
1. Q: Scope of Services, Section 4. A. allows for a minimum of two hours, and a maximum of 24 hours to respond and complete services. Section 4. B. suggests that two hours is the maximum response time. Please clarify response time requirements under this contract.

A: Please review Attachment A: Revised Scope of Services, Section 4. The contractor must start plowing services within two (2) hours and complete the service within 24 hrs.

2. Q: The bid form references Scope of Services, Sections 10A-10C for spring cleanup and hourly equipment rates. Please confirm if these bid items instead refer to Sections 12A-12C.

A: Yes, the correct section is 12. Please review Attachment C, Revised Bid Form.

3. Q: Scope of Services, Section 12. B. indicates that all sand and gravel is to be removed by the contractor at no cost to the MSBSD. However, the bid form includes a spring clean-up cost for sweeping. Please clarify if sweeping services will be paid under this contract.

A: Sand and gravel must be removed by the contractor at no cost to the MSBSD. If additional services are need the MSBSD Foremen will direct the contractor as to which services are needed and hourly rates will apply. Please ensure Attachment C: Revised Bid Form from Addendum 2 is returned with your bid response.

END OF ADDENDUM #2

APPROVED BY: Signature on File	DATE: October 4, 2022

ATTACHMENT A:
REVISED SCOPE OF SERVICES

1. DESCRIPTION

The Matanuska-Susitna Borough School District (MSBSD) is seeking bids from qualified contractors to provide snow and ice removal and sanding services on a per occurrence basis for Big Lake Elementary School, Houston Jr./Sr. High School, Meadow Lakes Elementary School, Willow Elementary, Su-Valley Jr./Sr. High School, Talkeetna Elementary School, Trapper Creek Elementary School, Redington Jr./Sr. High School, Dena'ina Elementary School, Goose Bay Elementary School, Knik Elementary School, Snowshoe Elementary School, Butte Elementary School, Machetanz Elementary School, Fronteras Spanish Immersion Charter School, Admin Annex West, Sutton Elementary School, **Birchtree Charter School** and the Warehouse/Nutrition Services Complex. Contractors agree, by the submittal of their bid, that the MSBSD shall be their first priority client when snow and ice removal and sanding is called for under the terms of the bid. Contractors shall not be excused from performance because of other commitments.

2. EQUIPMENT

Equipment must be as specified in Section 13 and shall be of equal size and quantity or greater. Substitution of other equipment must be approved in advance by the MSBSD. All equipment used shall be in good operating condition and shall meet all safety and OSHA requirements. The contractor must have the capability of keeping their equipment in good operating order for the duration of the agreement or be able to have the ability to obtain a suitable replacement piece of equipment**. A list of equipment designated for each area(s) must accompany the bid. The list shall specify the standard nomenclature for each piece of equipment, i.e. make, model, year, size, etc.** The MSBSD reserves the right to evaluate equipment and reject bids if, in the opinion of the MSBSD, the equipment is inadequate. A 4 x 4 truck with a plow may be used as a secondary piece of equipment for clean-up and smaller spaces such as sidewalks, loading docks, etc. The MSBSD reserves the right to cancel a contract if inadequate equipment is being used to clear school parking lots. See Section 15 for further information. The contractor shall understand the fuel price fluctuations in the present economy. There will be no contract change order authorized for a fuel increase, unless the increase is greater than 25% according to the national average noted on the day of contract execution.

3. ADDITIONAL SUBMITTAL REQUIREMENTS

The following must be included with the bid or the bid may be considered non-responsive and be rejected:

A. Equipment list that specifies the standard nomenclature for each piece of equipment, i.e. make, model, year, size, etc. for each site the contractor intents to bid on.

4. RESPONSE TIME

A. **The contractor will automatically respond to a snowfall of three (3)" or greater in a twenty-four (24) hour period**. The MSBSD may also call the contractor if the MSBSD determines that services are needed for a particular site or service area. The contractor shall be allowed ~~a minimum of~~ **TWO (2) HOURS** to commence snow and ice removal and/or sanding operations from the time directed by the MSBSD. Unless exempted in this document, or by prior approval, all action shall be accomplished within TWENTY-FOUR (24) HOURS of start-up.

B. In the event that the contractor does not respond within two (2) hours and the MSBSD has to call out another contractor, or is obligated to use MSBSD Facilities personnel, to perform snow and ice removal and/or sanding services, the contractor shall be responsible for any and all expenses incurred by the MSBSD for such work. The contractor may also be assessed liquidated damages per Section 15**.**

5. HOURS OF OPERATION

Snow and ice removal and/or sanding operations are to be performed outside of regular business or school hours unless otherwise approved by the designated person for that area. Snow and ice removal and/or sanding services at all High School and Middle School sites are to be completed by 6:00 AM. Snow and ice removal and/or sanding services at all Elementary School sites are to be completed by 7:00 AM. Persons listed on the "Designated Contact Personnel Page" (to be provided at award of contract) are the authorized MSBSD representatives for "call outs", if required. **The contractor will automatically respond to a snowfall of three (3)" or greater in a twenty-four (24) hour period.**

6. SNOW/ICE REMOVAL DEPTH

The contractor shall remove the snow and ice down to ONE-QUARTER (1/4) INCH minus snowpack of the existing surface at each school. Extreme caution must be exercised to avoid damage to curbs, sidewalks, underground utilities, light poles, clean-out pipes, etc. The successful contractor must flag all obstructions (such as cleanouts, fire hydrants, guidelines, utility posts, etc.) before beginning any work on any contracts. Damages caused by the contractor shall be repaired fully in a neat, workmanship-like manner at the contractor's expense. Satisfactory repair of damage will be determined by the MSBSD Facilities Department Director, James Estes, or his designee. In the event a repair cannot be made by the contractor in a timely manner, as determined by the Facilities Department, and the Facilities Department must make repairs, the contractor will be billed for time and material repair expenses. Contractors who fail to remove snow and ice as indicated in this section shall be required to remove slush at no additional charge when requested by the designated person for that location.

7. STACKING OF SNOW/DISPOSAL AREAS

Disposal areas have been designated at each site. If designated areas are not adhered to, the contractor will be required to move snow, at no charge to the MSBSD, to the authorized area. If designated snow storage areas are not fully and efficiently used, the contractor will be required to re-stack or remove snow from school district property at contractor's expense. If, due to exceptionally heavy snowfall, the designated areas become full, the MSBSD Facilities Foreman for that area will designate new areas at each site location. Additionally, it is the responsibility of the contractor to keep all entrances and exits to driveways and parking lots clear. If snow is not stacked in such a way as to keep entrances and exits clear, the contractor will be required to re-stack or remove snow from school district property at contractor's expense.

8. FREQUENCY OF SNOW REMOVAL

In general, snow removal will be required when three (3) inches of snow has accumulated or when called-out. In such cases, time is of the essence and response and completion requirements are crucial. Call-outs may also occur when, in the opinion of the designated person, the accumulation of the ice and snow is unduly hampering driving conditions. The MSBSD does not guarantee that the call-out for snow removal services for one site or service area will mean a call-out for snow removal services in all locations. It is the contractor's

responsibility to verify snowfall at schools within their awarded services areas, whether through physical inspection or some other means.

9. SIDEWALK SNOW REMOVAL

Sidewalk snow removal and sanding will be performed at all sites. Sidewalks must be cleared and sanded any time parking lot snow removal occurs. Sanding services must be in accordance with Section 11, Material Specification. Sidewalk snow removal and sanding will not be billed as a separate unit item.

10. SANDING

Once plowing is completed, sanding shall be done. The contractor may also be called out specifically for sanding, as weather requires. The contractor shall provide the price for sanding each area they propose to bid on. Sanding will be billed as a separate unit item. Sand shall be granulated and flowable. No chunks or clumping will be permitted. Sufficient even coverage as determined by the MSBSD will be regularly inspected after application. The contractor will not be paid for sanding services that do not meet these requirements.

11. MATERIAL SPECIFICATION

A. Sand utilized by the contractor shall be screened, sharp and clean granules to satisfy specifications listed below.

B. Sand shall be free of debris such as clay balls, mulch, roots, sticks, deleterious material and organic matter. Frozen clumps or material will not be allowed.

C. Salt may be added to the sand mix at the expense of the contractor.

Non-washed Sand Gradation Specifications
(washing is not required)

Sieve Designation	Percent Passing by Weight
5/16”	98 – 100
#200	0 - 5

12. SPRING CLEAN-UP AND ADDITIONAL SERVICES

The authorization and timeline for all Spring Clean-Up and Additional Services will be directed by the MSBSD Facilities Department Director, James Estes, or his designee. Hourly Rates requested for these services are for informational purposes only and will not be used in determining award of the bid.

A. Snow Removal

The MSBSD Facilities Department may direct the contractor to haul away snow from the normal disposal areas to another location on or off school grounds. The designated person for that area will direct the contractor as to the locations and extent of snow removal required.

B. Sand Removal

All sand and gravel will be removed by contractor at no additional expense to MSBSD. Sand and gravel must be cleared no later than June 10th.

C. Additional Services

From time to time, the MSBSD Facilities Department may require ~~snow removal~~ **additional** services beyond the scope of this agreement for clearing

playgrounds, hockey rinks, etc. The designated person for that area will contact and direct the contractor as to the locations and extent of ~~snow removal~~ **services** required.

13. FACILITY, LOCATION, AND EQUIPMENT REQUIRED

Item No.	Facility	Location	Equipment Required
1.	Big Lake Elementary School	3808 South Big Lake Road Big Lake, AK 99652	4 yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
2.	Butte Elementary School	4006 South Butte Road Palmer, AK 99645	4 yard front end loader 4 x 4 truck with plow*
3.	Dena'ina Elementary School	7068 S. Knik Knack Mud Shack Road Wasilla, AK 99654	4 yard front end loader 4 x 4 truck with plow*
4.	Fronteras Spanish Immersion Charter School	2315 N. Seward Meridian Parkway Wasilla, AK 99654	4-yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
5.	Goose Bay Elementary School	6350 W. Hollywood Blvd. Wasilla, AK 99654	4-yard front end loader 4 x 4 truck with plow*
6.	Houston Jr./Sr. High School	12501 W. Hawk Lane Houston, AK 99694	4-yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
7.	Houston Middle School and Houston High School Complex	12801 and 12501 Hawk Ln, Big Lake, AK 99652	4-yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
8.	Admin Annex West	2239 N. Seward Meridian Parkway Wasilla, AK 99654	4-yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow
9.	Knik Elementary School	6350 W. Hollywood Blvd. Wasilla, AK 99654	4-yard front end loader 4 x 4 truck with plow*
10.	Machetanz Elementary School	4961 E. Nelson Road Wasilla, AK 99654	4-yard front end loader 4 x 4 truck with plow*
11.	Meadow Lakes Elementary School	1741 N. Pittman Road Wasilla, AK 99623	4 yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
12.	Redington Jr./Sr. High School	10015 Redington School Drive Wasilla, AK 99654	4 yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
13.	Snowshoe Elementary School	2001 W. Fairview Loop Wasilla, AK 99654	4 yard front end loader 4 x 4 truck with plow*
14.	Sutton Elementary School	11672 N. Wright Way Sutton, AK 99674	4 yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
15.	Su-Valley Jr./Sr. High School	42728 S. Parks Highway Talkeetna, AK 99676	4 yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
16.	Talkeetna Elementary School	13930 E. Timberwolf Loop Talkeetna, AK 99676	4 yard front end loader Grader or Dump Truck w/Belly Blade

			4 x 4 truck with plow*
17.	Trapper Creek Elementary School	6742 E. Petersville Road Trapper Creek, AK 99683	4 yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
18.	Willow Elementary School	31706 W. Parks Highway Willow, AK 99688	4 yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
19.	Warehouse/Nutrition Services Complex	690 Cope Industrial Way Palmer, AK 99645	4 yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow*
20.	**Birchtree Charter School**	**7000 Wonder Circle Palmer, AK 99645**	**4 yard front end loader Grader or Dump Truck w/Belly Blade 4 x 4 truck with plow***

*** A 4 x 4 truck with a plow may be used as a secondary piece of equipment for clean-up and smaller spaces such as sidewalks, loading docks, etc. In some circumstances, the MSBSD may approve the use of a 4x4 truck with a plow as a primary piece of equipment.**

14. CONTRACT AWARD

Contractors may bid on any service area or combination of service areas. The MSBSD will recommend award of a contract to the lowest responsive and responsible bidder for each service area. Contracts may be awarded to more than one contractor and not all schools or sites may be awarded at this time. The MSBSD reserves the right to award each service area independently.

15. CONTRACT TERM

A. The term of any contract(s) resulting from this solicitation shall be for one (1) year period, beginning November 1, 2022 and ending June 30, 2023. The MSBSD reserves the right to renew the contract for three (3) additional one (1) year terms, upon mutual written agreement between the MSBSD and the contractor. The MSBSD may exercise this option by giving written notice to the contractor prior to the expiration of the then-existing term, if it is found to be in the MSBSD's best interest.

B. The MSBSD reserves the right to add sites as needed during the life of this agreement. Area specifications will be determined by the MSBSD, followed by negotiation with the existing contractor with intent of making the added site a part of this agreement. If the MSBSD and the existing contractors (if any) cannot agree on a price for the added site, then the MSBSD reserves the right to negotiate with other contractors. At the time of extension, the contractor must again meet all the requirements contained in this bid packet.

16. CONTRACT MANAGEMENT

At the commencement of any resulting contract, the MSBSD and the successful bidder shall each designate a contract administrator. Such persons shall be the respective party's single point of contact for purposes of management of the contract. The bidder's contract administrator shall assume responsibility for the coordination of all contract issues under the contract.

A. There will be a mandatory preservice meeting to address the scope of work and review expectations. The meeting will be held at the MSBSD Facilities Department located at 3901 E. Bogard Road in Wasilla. The contract administrator and snowplowing supervisor are required to attend the meeting before work

begins. Failure to attend the meeting could result in the contract being cancelled and awarded to the next lowest responsive bidder.

B. All invoices for the season must be submitted to the MSBSD Accounting Department by June 30th.

17. FAILURE TO PERFORM/DEFAULT

A. The contractor is required to have in effect at all times the required documentation, insurance, bonds, licenses and equipment. Failure to meet these requirements and failure to correct such deficiencies within ten (10) days of written notification may result in termination of the agreement.

B. The MSBSD reserves the right to employ the services of another contractor for a specific site or service area if the primary contractor for that site or service area fails to respond within the timelines required herein. Any additional costs incurred by the MSBSD as a result will be the responsibility of the primary contractor. Failure to respond to snow removal in a timely manner may be cause for terminating the agreement.

C. The MSBSD reserves the right to terminate the agreement if the contractor is using inadequate equipment to perform contract work. Failure to remedy issues due to inadequate equipment within ten (10) days of written notification may result in termination of the agreement.

D. In the event that the contractors' work is found to be unsatisfactory by the MSBSD, the contractor will be notified in writing by the MSBSD and have twenty-four (24) hours to correct such work. If the situation is not resolved to the satisfaction of the MSBSD, liquidated damages may be assessed per Section 16 of this Scope of Services.

18. LIQUIDATED DAMAGES

A. In the event that the contractor fails to perform snow and ice removal and/or sanding services in a timely manner in accordance with Section 3, the contractor may be assessed liquidated damages in the amount of one and one-half (1½) times the contractor's occurrence rate for every day the MSBSD is without services.

B. In the event that the contractor fails to correct non-conforming work in accordance with Section 15, the contractor may be assessed liquidated damages in the amount of one and one-half (1½) times the contractor's occurrence rate for every day the work remains uncorrected.

ATTACHMENT C: REVISED BID FORM

The undersigned hereby proposes to furnish Snow and Ice Removal and Sanding Services within the locations referenced in the Bid Documents for the MSBSD in full accordance with the documents for the consideration of the amounts as indicated on the attached Bid Form.

Contractors may bid on any service area or combination of service areas. The MSBSD will recommend award to the lowest responsive and responsible bidder for each service area. Award will be based on the total base bid price for each service area. Contracts may be awarded to more than one contractor and not all schools or sites may be awarded at this time. The MSBSD reserves the right to award each service area independently.

While additional services are not anticipated, please list your hourly rate for the equipment listed under Additional Rates on the Bid Form. The Contractor awarded the site will be expected to provide any extra services as described in the bid documents; Scope of Services, Section 12 as needed for that site. The awarded Contractor's hourly rates for additional services will only be used in the event extra services are requested by the MSBSD.

Hourly-rated pricing is for informational purposes only and will not be used in determining the award of the bid.

Company: _____ Date: _____

Printed Name

Contractor: _____

Signature

BASE BID

SERVICE AREA I:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
1.	Talkeetna Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
2.	Trapper Creek Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
3.	Su Valley Jr./Sr. High School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA I				**$_____**	

SERVICE AREA II:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
4.	Willow Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA II				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA III:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
5.	Big Lake Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
6.	Houston Jr./Sr. High School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
7.	Houston Middle School and Houston High School Complex	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
8.	Meadow Lakes Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA III				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA IV:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
9.	Dena'ina Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
10.	Redington Jr./Sr. High School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA IV				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA V:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
11.	Goose Bay Elementary and Knik Elementary School Complex	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA V				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA VI:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
12.	Snowshoe Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA VI				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA VII:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
13.	Sutton Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA VII				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA VIII:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
14.	Butte Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA VIII				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA IX:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
15.	Machetanz Elementary School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA IX				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA X:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
16.	Warehouse/Nutrition Services Complex	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA X				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA XI:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
17.	Fronteras Spanish Immersion Charter School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
18.	Admin Annex West	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA XI				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

SERVICE AREA XII:

Bid Item No.	School Location	Bid Item	Est. Qty.*	Per Occurrence Unit Price	Extended Price
19.	Birchtree Charter School	Snow and Ice Removal	10	$_____	$_____
		Sanding	12	$_____	$_____
TOTAL BASE BID - SERVICE AREA XII				**$_____**	

*Amounts listed are estimates only and are used solely for the purposes of evaluating the bids. Amounts listed are not to be construed as any guarantee of minimum requirements of services to be purchased by the MSBSD.

ADDITIONAL RATES

SERVICE AREA I:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
A.	Talkeetna Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:
B.	Trapper Creek Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:
C.	Su Valley Jr./Sr. High School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:

		Pickup Truck:
		Sweeper Truck:

SERVICE AREA II:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
E.	Willow Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA III:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
F.	Big Lake Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:

		Sweeper Truck:
G.	Houston Jr./Sr. High School and Houston Middle School and Houston High School Complex	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:
H.	Meadow Lakes Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA IV:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
I.	Dena'ina Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:

		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:
J.	Redington Jr./Sr. High School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA V:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
K.	Goose Bay Elementary and Knik Elementary School Complex	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA VI:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
L.	Snowshoe Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA VII:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
M.	Sutton Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA VIII:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
N.	Butte Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA IX:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
O.	Machetanz Elementary School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA X:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
P.	Warehouse/Nutrition Services Complex	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA XI:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
Q.	Fronteras Spanish Immersion Charter School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:
R.	Admin Annex West	Grader:
		Loader:

		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck:

SERVICE AREA XII:

Bid Item No.	School Location	Hourly Equipment Rates (Scope of Services, Section 12)
S.	Birchtree Charter School	Grader:
		Loader:
		Dump Truck:
		Belly Blade Grader:
		Belly Blade Dump Truck:
		Pickup Truck:
		Sweeper Truck: