

DL Construction Supply LLC
d/b/a Parco Building System
Attn: Dan Luckman
6140 1st St.
Newfane, NY 14108

SPECIFICATIONS

Building:

- 20' x 40' x 10' Post frame building **Price: \$41,858 total**
- Steel roofing and siding **Price: \$9,870**
- Drip Stop on roof panels **Price: \$800**
- Wainscot all sides **Price: \$1,900**
- 1- 3'x3' Cupola (pulling pump) **Price: \$1,500**
- 12" Eave and gable overhangs **Price: \$1,520**
- 2 - 3'0" Man doors with locksets **Price: \$1,900**
- 1 - 8'x 8' Insulated Overhead door **Price: \$1,843**
- Columns engineered for building **Price: \$1,400**
- Headers engineered for building **Price: \$1,500**
- Trusses 4' on center engineered for building (4/12 Pitch) **Price: \$2,035**
- Concrete Footing under and around base of post (post holes approximately 48" deep) **Price: \$1,350**
- 2x4 wall girts and 2x4 roof purlins 2 foot on center **Price: \$1,050**
- 2x8 pressure treated splash board at grade level **Price: \$240**
- Stamped plans **Price: \$1,450**
- Prevailing wage **Price: \$13,500**

Total Erected Price: \$41,858

Options:

- 4" concrete floor with vapor barrier, steel mesh, control joints and sealed **Additional Price: \$12,385**
- 1 - Divider wall with steel on 1 side **Additional Price: \$1,965**