

Asbestos Hazard Emergency Response Act Three-Year Asbestos Re-Inspection and Management Plan Update

**for
Daniels Farm Elementary School**

**For Compliance with
State of Connecticut Department of Public Health
Asbestos-Containing Materials in Schools Regulation
(Sections 19a - 333-1 through 19a - 333-13)
and
EPA Asbestos Hazard Emergency Response Act
(Title 40 CFR, Part 763, Subpart E)**

**Trumbull Public Schools
Trumbull, Connecticut**

June 2024



59 Elm Street – Suite 500
New Haven, CT 06510

June 11, 2024

Mr. David P. Cote, PE.
Director of Operations
Trumbull Public Schools
710 Daniels Farm Road
Trumbull, CT 06611

RE: Three-Year AHERA Asbestos Re-Inspection and Management Plan Update
Re-Inspection Date: April 11, 2024
Daniels Farm Elementary School
710 Daniels Farm Road, Trumbull, CT.
Fuss & O'Neill Project No. 20201149.A30

Dear Mr. Cote:

Enclosed is the three-year AHERA Asbestos Re-Inspection and Asbestos Management Plan (AMP) Update report prepared by Fuss & O'Neill, Inc. at the Daniels Farm Elementary School located at 710 Daniels Farm Road in Trumbull, Connecticut (the "Site"). The inspection was performed for the Trumbull Public Schools (the "Client"). This report is an important document that must be kept on file at the school as well as at a central location where the AMPs are maintained.

If you should have any questions regarding this report, please do not hesitate to contact me. Thank you for this opportunity to have served your environmental needs.

Sincerely,



Eduardo Miguel Marques
Senior Environmental Analyst

EMM/nw

Enclosure

Table of Contents

Asbestos Hazard Emergency Response Act Three-Year Re-Inspection and Management Plan Update School Name

1	Introduction.....	1
1.1	Background.....	1
1.2	Local Education Agency (LEA) Responsibilities	1
1.3	Accreditation.....	2
2	Building and Mechanical System Description.....	3
3	Three Year Re-Inspection	3
3.1	Re-Inspection Procedures	3
4	Re-Inspection Report	3
4.1	Review of Existing Records	3
4.2	Re-Inspection Summary	3
4.3	Newly Identified or Re-sampled ACBM Materials	7
4.4	Physical Assessment of ACBM	8
5	Management Plan Update	8
5.1	Recommended Response Actions	8
5.2	Periodic Surveillance	9
5.3	Preventive Measures.....	10
5.4	Abatement (Removal) Cost Estimates	10
6	EPA Accreditation Requirements	10

Appendices

End of Report

APPENDIX A	EXISTING RECORDS CHECKLIST
APPENDIX B	RE-INSPECTION FORM 1A
APPENDIX C	RE-INSPECTION FORM 1B
APPENDIX D	RE-INSPECTION FORM 2
APPENDIX E	SAMPLE 6-MONTH PERIODIC SURVEILLANCE FORM
APPENDIX F	PREVENTIVE MEASURES
APPENDIX G	ASBESTOS INSPECTOR AND MANAGEMENT PLANNER STATE LICENSES AND EPA ACCREDITATIONS

1 Introduction

1.1 Background

The Clean Air Act required the United States Environmental Protection Agency (EPA) to develop standards to address the potential health risks associated with adverse effects of asbestos exposure as an indoor contaminant. In October 1986, the EPA promulgated the Asbestos Hazard Emergency Response Act (AHERA) located at Title 40 CFR, Part 763, Subpart E.

The AHERA regulations required that local education agencies (LEAs) conduct inspections of each school building that they lease, own, or otherwise use as a school building to identify friable (easily crumbled or crushed to powder by hand pressure) and non-friable asbestos-containing building materials (ACBM) locations. The original inspections were required to have been completed prior to October 12, 1988.

AHERA also requires that any building leased or acquired on or after October 12, 1988, that is to be used as a school building shall be inspected for friable and non-friable ACBM prior to use as a school building. In the event of an emergency use of a building that has not been inspected for ACBM, the building shall be inspected within 30 days after commencement of such use.

The regulatory requirements remain in effect for private or public-school systems, a church-affiliated school of any denomination, a school dedicated to the education of children with special needs, or a charter school. In the State of Connecticut, the Department of Public Health (CTDPH) is responsible for AHERA regulation enforcement.

1.2 Local Education Agency (LEA) Responsibilities

The LEA is responsible for compliance with the AHERA regulation. The following responsibilities must be followed:

1. The LEA must designate a person to ensure that all of the AHERA requirements are properly implemented. The Designated Person must receive adequate training to perform their duties.
2. The LEA must ensure that the asbestos management plans (AMPs) are maintained in a central location, as well as at each facility, and such plans and records are available for inspection or review at all times.
3. The LEA must inform all workers, building occupants or their legal representative in writing at least once per school year about asbestos-related activities, and the availability of the AHERA AMPs for the school buildings.
4. The LEA must ensure proper accreditations for all persons who perform asbestos inspections, asbestos re-inspections, develop/update AMPs, develop response actions, and perform required response actions including operations and maintenance (O&M) activities that may disturb asbestos.

5. The LEA must provide training for all custodial and maintenance staff who regularly perform building maintenance where ACBM are present. The training must be provided upon initial hire, as well as annual updates.
6. The LEA must provide information (disclosure) to any workers who may perform work and may come into contact with asbestos in school buildings where ACBM or presumed ACBM are present.
7. The LEA must ensure that known ACBM or presumed ACBM are provided with warning labels in routine maintenance areas.
8. The LEA must ensure that periodic surveillance is performed at least once every six months, after AMP implementation, in all school buildings that it leases, owns, or otherwise uses that contain ACBM or presumed ACBM.
9. The LEA must ensure that once every three years, after an AMP is implemented, a Re-Inspection is performed at each school building that it leases owns or otherwise uses that contains ACBM or presumed ACBM.

Refer to above-mentioned regulation for full requirements and responsibilities.

1.3 Accreditation

- A. LEA: Trumbull Public Schools
 Address: 710 Daniels Farm Road
 Trumbull, CT
 Phone: (203) 452-4300
- B. Designated Person: Mr. David P. Cote, PE.
 Address: 710 Daniels Farm Road
 Trumbull, CT
 Phone: (203) 452-4300
- C. Asbestos Consultant:

 Firm: Fuss & O'Neill, Inc.
 Address: 59 Elm Street – Suite 500
 New Haven, CT
 Phone: (203) 374-3748
 Fax: (860) 533-5143
- D. Asbestos Inspector:

 Inspector: Sandra L. Guzman
 CTDPH License #: 000335
 Expiration Date: 08/31/2024

E. Asbestos Inspector/Management Planner:

Planner: Eduardo Miguel Marques
CTDPH License #: 000201
Expiration: 02/28/2025

2 Building and Mechanical System Description

The original Daniels Farm Elementary School is a one-story building and was reportedly constructed in 1962. The building contains approximately 60,000 square feet (SF) of total floor area. The building is heated by gas-fired hot water and rooftop heating, ventilation and air conditioning (HVAC) units.

3 Three Year Re-Inspection

3.1 Re-Inspection Procedures

This three-year asbestos re-inspection was conducted in accordance with EPA requirements of the AHERA regulation, Title 40 CFR, Part 763, Section 763.85 (b).

On April 11, 2024, Fuss & O'Neill, Inc. (Fuss & O'Neill) representatives Ms. Sandra Guzman performed the re-inspection.

A. During the re-inspection, Fuss & O'Neill conducted the following required tasks:

1. A visual re-inspection and reassessment of all known friable or assumed ACBM.
2. A visual re-inspection of ACBM that was previously considered non-friable to determine if the present condition of the material has become friable.
3. Identification and assessment of any newly identified homogeneous area that contains friable ACBM since the last inspection or re-inspection.

4 Re-Inspection Report

4.1 Review of Existing Records

An important part of this AHERA re-inspection involved researching prior documentation that is required to be present at the school, as well as at the central recordkeeping location where AMPs are stored.

Please see *Appendix A* for the checklist for existing records.

4.2 Re-Inspection Summary

The on-site portion of the re-inspection was documented on forms modeled after examples provided by the EPA and reviewed with the CTDPH. The first form, **Re-Inspection Form 1A**, identifies previous inspection data gathered during the initial AHERA inspection and subsequent re-inspection (see *Appendix B*). This form is useful to reference response actions (if any), which have been performed since the last inspection, as

well as identifying the last known conditions of ACBM in the building. It additionally provides the inspector a "quick glance" reference when performing the re-inspection.

The second EPA form, **Re-Inspection Form 1B**, is used to list all known or assumed asbestos-containing materials that were previously unidentified (See *Appendix C*). It also lists the ACBM in areas newly acquired by the school for student use either permanently or temporarily.

The third EPA form, **Re-Inspection Form 2**, was used to provide information and justification regarding re-assessment of the ACBM (see *Appendix D*). This form also provides response action recommendations, including a tentative schedule for completing response actions that recommend removal or repair.

No bulk samples were collected during this re-inspection.

Using EPA protocol and criteria, the following materials existing in Daniels Farm Elementary School at the time of this three-year re-inspection have been determined and/or assumed to be **ACBM**. Please refer to the above-mentioned Re-Inspection Forms for specific locations of the materials.

Table 1
Asbestos-Containing Building Materials

Material	Location	Reference	Asbestos Content
Grout & Thinset, Mortar associated with 1"x1" Blue Ceramic Floor Tile	Handicap Bathroom, Boy's Hallway #1 Bathroom, And Nurse's Bathroom	EnviroMed 2015 3-Year Re-Inspection	Assumed
Grout & Thinset, Mortar associated with 1"x1" Gray Ceramic Floor Tile	Classroom 9, 11 - 20 Bathrooms	EnviroMed 2015 3-Year Re-Inspection	Assumed
Grout & Thinset, Mortar associated with 1"x1" Gray Ceramic Flooring Tile with Red, Blue & Brown Spots	Boy's Hallway #3 Bathroom, And Girl's Hallway #3 Bathroom	EnviroMed 2015 3-Year Re-Inspection	Assumed
Grout & Thinset, Mortar Associated with 1"x1" Green Ceramic Floor Tile	Girl's Hallway #1 Bathroom	EnviroMed 2015 3-Year Re-Inspection	Assumed
12" x 12" Blue Vinyl Floor Tile with White Specks & associated Mastic	Classroom 21, 23, 27, 28 and 29	EnviroMed 2015 3-Year Re-Inspection	Assumed
12" x 12" Cream Vinyl Floor Tile with Brown & Gray Specks & associated Mastic	Hallway #2	EnviroMed 2015 3-Year Re-Inspection	Assumed
12" x 12" Dark Blue Vinyl Floor Tile & associated Mastic	Learning Center #2, Reading Room #23, And Classroom #32	EnviroMed 2015 3-Year Re-Inspection	Assumed
12"x12" Dark Blue Vinyl Floor Tile with Specks & associated Mastic	Classroom 1 - 4, 6, 9 - 20, 26, 30, Gym/All Purpose Room and Stage	EnviroMed 2015 3-Year Re-Inspection	Assumed
12" x 12" Gray Floor Tile with Gray Specks & associated Mastic	Multipurpose Room	EnviroMed 2015 3-Year Re-Inspection	Assumed
12" x 12" Beige Floor Tile with Brown Specks & associated Mastic	Equipment Storage and Storage 11	EnviroMed 2015 3-Year Re-Inspection	Assumed
12" x 12" Green Vinyl Floor Tile & associated Mastic	Media Storage Room	EnviroMed 2015 3-Year Re-Inspection	Assumed

Material	Location	Reference	Asbestos Content
12" x 12" Light Blue Vinyl Floor Tile with White & Gray Specks & associated Mastic	Gym Back Entry Foyer, Nurse's Office, Stage, Storage #2, and Room 5	EnviroMed 2015 3-Year Re-Inspection	Assumed
12" x 12" Peach Vinyl Floor Tile with Brown & White Specks	Classroom #8	EnviroMed 2015 3-Year Re-Inspection	Assumed
12" x 12" Tan Vinyl Floor Tile with Dark Gray Specks & associated Mastic	Teachers' Lounge	EnviroMed 2015 3-Year Re-Inspection	Assumed
9" x 9" Gray Floor Tile with Orange & Black Streaks & associated Mastic	Supply Closet (Storage Room 1)	EnviroMed 2015 3-Year Re-Inspection	Assumed
9" x 9" Gray Floor Tile with White & Black Streaks & associated Mastic	Kitchen Office	EnviroMed 2015 3-Year Re-Inspection	Assumed
Carpet Adhesive (Blue & Green Carpets)	Conference Room, Office, Principal's Office, Classroom Room #33, PPS, Computer Lab, Media Center, Social Worker Office, Office 22, 24, 26, and 33	EnviroMed 2015 3-Year Re-Inspection	Assumed
Gray Linoleum Flooring & associated Adhesive	Classroom #31	EnviroMed 2015 3-Year Re-Inspection	Assumed
Green Linoleum Flooring & associated Adhesive	Media Center Office	Fuss & O'Neil 6-Month Periodic Surveillance October 2022	Assumed
Gray with Specks Linoleum Flooring & associated Adhesive	Staff Work Room, Art Room	Fuss & O'Neil 6-Month Periodic Surveillance October 2022	Assumed
Gray Ramp Textured Flooring & associated Adhesive	Ramp to Music Room	Fuss & O'Neil 6-Month Periodic Surveillance October 2022	Assumed
6" x 6" Brown Quarry Floor Tile/Grout/Adhesive	Storage #5	EnviroMed 2015 3-Year Re-Inspection	Assumed
6" x 6" Red Quarry Floor Tile/Grout/Adhesive	Custodian Closets, Kitchen, Kitchen Laundry	EnviroMed 2015 3-Year Re-Inspection	Assumed
Terrazzo Flooring	Hallway #1, Hallway #3	EnviroMed 2015 3-Year Re-Inspection	Assumed
4" Gray Cove Base Molding & associated Adhesive	Closet, Gym Back Entry Foyer, Gym/All Purpose Room, Kitchen Office, Stage	EnviroMed 2015 3-Year Re-Inspection	Assumed
4" Green Cove Base Molding & associated Adhesive	Media Storage Room, PPS, Computer Lab, Media Center	EnviroMed 2015 3-Year Re-Inspection	Assumed
4" Light Brown Cove Base Molding & associated Adhesive	Hallway #2	EnviroMed 2015 3-Year Re-Inspection	Assumed
4" Black Cove Base Molding & associated Adhesive	Nurse's Office, Teachers' Lounge, and Classroom #31	EnviroMed 2015 3-Year Re-Inspection	Assumed
4" Blue Cove Base Molding & associated Adhesive	Classroom 1, 2, 4, 6, 10, 19, 21, 26, 27, 29, 32, 33, Conference Room, Learning Center, Office, Principal's Office, Reading Room, and Staff Work Room	EnviroMed 2015 3-Year Re-Inspection	Assumed

Material	Location	Reference	Asbestos Content
4" Brown Cove Base Molding & associated Adhesive	Classroom 8	EnviroMed 2015 3-Year Re-Inspection	Assumed
Acoustical/Decorative Wall Tiles	Gym/All Purpose Room	EnviroMed 2015 3-Year Re-Inspection	Assumed
4" x 4" Blue Wall Tiles/Grout/Adhesive	Boy's Hallway #3 Bathroom	EnviroMed 2015 3-Year Re-Inspection	Assumed
4" x 4" Pink Wall Tiles/Grout/Adhesive	Girl's Hallway #3 Bathroom	EnviroMed 2015 3-Year Re-Inspection	Assumed
Tan Window Frame Caulking Compound	Classroom #2, Classroom #4, Classroom #6, Media Center #13, and Staff Work Room	EnviroMed 2015 3-Year Re-Inspection	Assumed
Chalkboard, Tack Board & associated Adhesives	Classrooms 1 – 30, Classroom 32, Learning Center #2, Computer Lab, Media Center, Reading Room, and Art Room	EnviroMed 2015 3-Year Re-Inspection	Assumed
Gray Sink Undercoating	Classrooms 1 – 33	EnviroMed 2015 3-Year Re-Inspection	Assumed
White Sink Undercoating	Staff Work Room, and Media Center Office	EnviroMed 2015 3-Year Re-Inspection	Assumed
Black Sink Undercoating	Staff Room	Fuss & O'Neil 6-Month Periodic Surveillance October 2022	Assumed
Light Gray Sink Undercoating	PPS	EnviroMed 2015 3-Year Re-Inspection	Assumed
Textured Suspended Ceiling Tile	Storage #5	EnviroMed 2015 3-Year Re-Inspection	Assumed
12" x 12' Fixed Ceiling Tile Glue Dots	Gym/All Purpose Room, and Kitchen Exit Doorway	EnviroMed 2015 3-Year Re-Inspection	Assumed
2' x 2' Non-Textured Ceiling Tile	Kitchen	EnviroMed 2015 3-Year Re-Inspection	Assumed
2' x 2' Texture Suspended Ceiling Tile with Pinholes	Hallway #1, Nurse's Office and Bathroom, Office, Principal's Office, Custodian Closet, and Staff Work Room	EnviroMed 2015 3-Year Re-Inspection	Assumed
2' x 2' Textured Suspended Ceiling Tile with Small Pinholes	Classroom 1 - 8, Classroom 10, 31 and 33, Custodian Closet, Accessible Bathroom, Boys' and Girls' Hallway #1 Bathroom, Media Storage Room, PPS, Teachers' Lounge, Computer Lab, and Media Center	EnviroMed 2015 3-Year Re-Inspection	Assumed
2' x 4' Suspended Ceiling Tile with Pinholes	Classrooms 9, 11, 13, 15 – 20, 26, 27, 30 and Associated Bathrooms, Conference Room, Reading Room, Boys' Hallway #3 Bathroom, Staff Work Room	EnviroMed 2015 3-Year Re-Inspection	Assumed

Material	Location	Reference	Asbestos Content
Cement Ceiling	Gym/All Purpose Room	EnviroMed 2015 3-Year Re-Inspection	Assumed
Tectum Ceiling Panels	Gym Back Entry Foyer	EnviroMed 2015 3-Year Re-Inspection	Assumed
Plaster Ceiling	Storage Room #2	EnviroMed 2015 3-Year Re-Inspection	Assumed
Pipe Fitting Insulation	Storage Rooms 8 and 9 (Suspected to exist in other locations within wall cavities associated with pipe system)	Fuss & O'Neil 6-Month Periodic Surveillance October 2022	Assumed

Using the EPA protocol, samples of the following suspect materials were collected and analyzed. The analytical results indicated that these materials are **non-ACBM**:

Table 2
Non-Asbestos-Containing Building Materials (Previous Re-Inspections)

Material	Location	Reference
Stage Red Curtain	Stage	Eagle Environmental, February 29, 2024

Mr. Eduardo Miguel Marques reviewed the information obtained during this Re-Inspection. Mr. Marques is an EPA-accredited and CTDPH-licensed Asbestos Inspector/Management Planner.

4.3 Newly Identified or Re-sampled ACBM Materials

The following newly identified suspect ACBM have been identified in the building:

- 12" x 12" Gray Floor Tile with Gray Specks & associated Mastic;
- 12" x 12" Beige Floor Tile with Brown Specks & associated Mastic;
- Green Linoleum Flooring & associated Adhesive;
- Gray Ramp Textured Flooring & associated Adhesive;
- Black Sink Undercoating; and
- Pipe Fitting Insulation.

These materials must be assumed to contain asbestos until laboratory analysis determines otherwise. These materials have been added to Table 1 as assumed ACBM.

AHERA regulations pertain to interior identified or assumed ACBM and limited exterior ACBM. AHERA regulations do include ACBM located on exterior porticos, covered walkways, and mechanical equipment used to condition interior building air.

Any suspect material encountered during renovation/demolition/maintenance activities that is not specifically identified in the AMP as a non-ACM should be assumed to contain asbestos unless sample results indicate otherwise.

Additional Information:

- Asbestos-containing floor tile and associated mastics may exist below non-moveable objects such as cabinets, platforms, sheetrock walls, lockers, etc.;
- Samples of exterior building materials not covered under AHERA, such as caulking and glazing compounds, roofing materials and materials behind exterior walls and panels should be collected and analyzed to determine asbestos content prior to performing activities that would disturb them;
- Asbestos-containing vapor barriers and waterproofing materials may exist beneath wood floors, behind walls, exterior below ground surface foundations, etc.; and
- Subsurface cementitious pipe (i.e., asbestos cement pipe).

4.4 Physical Assessment of ACBM

During the inspection, suspect ACBM were separated into three EPA categories. These categories are thermal system insulation (TSI), surfacing ACBM, and miscellaneous ACBM. TSI includes all materials used to prevent heat loss or gain or water condensation on mechanical systems. Examples of TSI are pipe and fitting insulations, boiler insulation, and duct insulation. Surfacing ACBM is commonly used for fireproofing, decorative, and acoustical applications. Miscellaneous materials include all ACBM not listed in TSI or surfacing, such as sheet flooring, vinyl asbestos flooring, ceiling tiles, and construction mastics/adhesives.

Finally, ACBM were quantified in linear and/or square feet, depending on the nature of the material.

The ACBM identified during the inspection and still remaining in the school were re-assessed using the CTDPH and AHERA guidelines for assessment of ACBM. The following assessment categories are listed:

1. Damaged or significantly damaged TSI ACBM
2. Damaged friable surfacing ACBM
3. Significantly damaged friable surfacing ACBM
4. Damaged or significantly damaged friable miscellaneous ACBM
5. ACBM with potential for damage
6. ACBM with potential for significant damage
7. Any remaining friable ACBM or friable suspected ACBM

Material locations, assessments, and recommended response actions are listed in the Re-Inspection forms.

5 Management Plan Update

5.1 Recommended Response Actions

Based on the inspection report, physical walk-through inspection, and existing ACBM conditions, the following response actions are recommended:

1. Removal - Not Applicable
2. Repair - Not Applicable
3. Enclosure - Not Applicable
4. Encapsulation - Not Applicable
5. Operations and Maintenance (O & M) - All remaining ACBM

It should be noted that only ACBM with assessments of 1 or 2 are recommended for removal or repair. The remaining ACBM should be included in the O & M Program. The condition of these ACBM will be monitored until all of the ACBM have been completely removed from the building. A successful O & M Program includes the following elements:

- A. Cleaning: All areas of the school where friable ACBM or assumed friable ACBM are present should be cleaned at least once after completion of the initial inspection. Additional cleaning may be necessary if the Management Planner makes a written recommendation indicating the methods and frequency of such cleaning.

- B. O & M Activities: The LEA shall ensure that the procedures described below are followed to protect building occupants from O & M activities that may disturb known or assumed ACBM:
 - 1. Restrict entry into the area either by physically isolating or by scheduling.
 - 2. Post asbestos warning signs to prevent entry by unauthorized persons.
 - 3. Deactivate or temporarily shut off or divert the air-handling system to the area.
 - 4. Use proper work practices and engineering controls, such as wet methods, protective clothing, High Efficiency Particulate Air (HEPA) vacuums, mini enclosures/glove bags, etc. to inhibit fiber migration.
 - 5. Place asbestos debris and other contaminated materials into a sealed, leak-tight container for disposal.

- C. Minor Fiber Release Episode: The LEA shall ensure that the procedures described below are followed in the event of a minor fiber release episode (i.e., disturbance of less than or equal to 3 linear/square feet of friable ACBM):
 - 1. Saturate the debris using wet method.
 - 2. Place the debris in a sealed, leak-tight container and clean the area.
 - 3. Repair the area of damaged ACBM with materials such as asbestos-free spackling, plaster or insulation or seal with an encapsulant.

- D. Major Fiber Release Episode: The LEA shall ensure that the procedures described below are followed in the event of a major fiber release episode (i.e., disturbance of greater than 3 linear/square feet of friable ACBM):
 - 1. Restrict entry into the area and post asbestos warning signs.
 - 2. Deactivate or temporarily shut off or divert the air handling system from the area to prevent fiber migration.
 - 3. The response action for any major fiber release episode must be prepared by EPA-accredited Asbestos Project Designers and conducted by EPA-accredited personnel.
 - 4. The LEA shall notify the CTDPH of any major fiber release episode within twenty-four hours of its occurrence and, if necessary, provide written notification as required by applicable federal and/or state regulations.

5.2 Periodic Surveillance

At least once every six months after an AMP is implemented, the LEA will conduct periodic surveillance in the school that contains ACBM or assumed ACBM. The person conducting periodic surveillance will visually

inspect all areas in the school where ACBM have been identified in the AMP, record the date of surveillance, their name, any changes in the ACBM condition and submit the record to the LEA Designated Person for inclusion in the AMP.

Please see *Appendix E* for the sample Periodic Surveillance Form that may be used for conducting periodic surveillance.

5.3 Preventive Measures

The LEA shall institute appropriate preventive measures to eliminate the reasonable likelihood that ACBM will become damaged, deteriorated, or delaminated.

Please see *Appendix F* for preventive measures designed for various types of ACBM that may exist in the school.

5.4 Abatement (Removal) Cost Estimates

At the time of the April 11, 2024, re-inspection, no materials were observed to be damaged (other than O&M repairs); therefore, estimated abatement cost have not been provided.

6 EPA Accreditation Requirements

The EPA accreditations and the CTDPH Asbestos Inspector licenses for Sandra Guzman and Eduardo Miguel Marques are provided in *Appendix G*.

Report prepared by Environmental Analyst I, Sandra Guzman.

Reviewed by:



Eduardo Miguel Marques
Senior Environmental Analyst



Kathleen C. Pane
Associate | Department Manager

Appendix A

Existing Records Checklist

Existing Records Checklist

Local Education Agency (LEA): Trumbull Public Schools
710 Daniels Farm Road
Trumbull, CT 06611

School Building: Daniels Farm Elementary School

The following documentation is required to be present in both the LEA's office, as well as in a centralized location in the school administrative office. The information included in this checklist will be verified to be present and complete as part of a three-year Re-Inspection.

DOCUMENTATION		LOCATION	
		School	LEA Office
1	Original AHERA Operations and Maintenance Plan/Inspection Report	No	No
2	Three Year Re-Inspection (First and All Subsequent Inspections)	No	Limited
3	Parents and Teachers Notifications (Annually Since Last Re-Inspection)	No	Yes
4	Designated Person Identification and Proper Training (Person Must Be Named and Have Appropriate Training)	No	-
5	Designated Person Periodic Surveillance (Once Every Six Months)	No	Yes
6	Maintenance Staff Awareness Training Records	No	Yes
7	Outside Vendor Awareness Notification	No	Yes
8	Asbestos Warning Signs and Labels (Required Posting in Boiler Rooms and Mechanical Spaces Only)	No	NA
9	Response Action Records (Includes Any Abatement Conducted Since Last 3-Year Re-Inspection)	No	Yes

Comments: **No** indicate not present/available at the time of this inspection. LEA office found to contain only limited records of 3-year re-inspection, 6-month surveillance and response actions conducted from 2015 to present. **NA** Indicates not applicable.

Inspector (LEA Office): Sandra Guzman

Date: April 8, 2024

Inspector (School): Sandra Guzman

Date: April 11, 2024

Appendix B

Re-Inspection Form 1A

Re-Inspection Form 1 (A) – List of Identified ACBM

Page 1 of 8

School: Daniels Farm Elementary School
Address: 710 Daniels Farm Road, Trumbull, CT

Date(s) of Original Inspection: Unknown
Date(s) of Subsequent Re-Inspections: 2015, 2021, 2024

Homogeneous Material			Material Category	Friability	Assessment Category (1-7)	Recorded Locations	Response Actions Taken/Renovations/Other Comments
Sample Number	Asbestos Content	Material Description					
N/A	Assumed	Grout & Thinset, Mortar associated with 1"x1" Blue Ceramic Floor Tile	Misc.	NF	5	Handicap Bathroom, Boy's Hallway #1 Bathroom, And Nurse's Bathroom	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Grout & Thinset, Mortar associated with 1"x1" Gray Ceramic Floor Tile	Misc.	NF	5	Classroom 9, 11 - 20 Bathrooms	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Grout & Thinset, Mortar associated with 1"x1" Gray Ceramic Flooring Tile with Red, Blue & Brown Spots	Misc.	NF	5	Boy's Hallway #3 Bathroom, And Girl's Hallway #3 Bathroom	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Grout & Thinset, Mortar Associated with 1"x1" Green Ceramic Floor Tile	Misc.	NF	5	Girl's Hallway #1 Bathroom	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	12" x 12" Blue Vinyl Floor Tile with White Specks & associated Mastic	Misc.	NF	5	Classroom 21, 23, 27, 28 and 29	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	12" x 12" Cream Vinyl Floor Tile with Brown & Gray Specks & associated Mastic	Misc.	NF	5	Hallway #2	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance

Re-Inspection Form 1 (A) – List of Identified ACBM

Page 2 of 8

School: Daniels Farm Elementary School
Address: 710 Daniels Farm Road, Trumbull, CT

Date(s) of Original Inspection: Unknown
Date(s) of Subsequent Re-Inspections: 2015, 2021, 2024

Homogeneous Material			Material Category	Friability	Assessment Category (1-7)	Recorded Locations	Response Actions Taken/Renovations/Other Comments
Sample Number	Asbestos Content	Material Description					
N/A	Assumed	12" x 12" Dark Blue Vinyl Floor Tile & associated Mastic	Misc.	NF	5	Learning Center #2, Reading Room #23, and Classroom #32	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	12"x12" Dark Blue Vinyl Floor Tile with Specks & associated Mastic	Misc.	NF	5	Classroom 1 - 4, 6, 9 - 20, 26, 30, Gym/All Purpose Room and Stage	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	12" x 12" Green Vinyl Floor Tile & associated Mastic	Misc.	NF	5	Media Storage Room	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	12" x 12" Light Blue Vinyl Floor Tile with White & Gray Specks & associated Mastic	Misc.	NF	5	Gym Back Entry Foyer, Nurse's Office, Stage, Storage #2 and Room 5	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	12" x 12" Peach Vinyl Floor Tile with Brown & White Specks	Misc.	NF	5	Classroom #8	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	12" x 12" Tan Vinyl Floor Tile with Dark Gray Specks & associated Mastic	Misc.	NF	5	Teacher's Lounge	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance

Re-Inspection Form 1 (A) – List of Identified ACBM

Page 3 of 8

School: Daniels Farm Elementary School
Address: 710 Daniels Farm Road, Trumbull, CT

Date(s) of Original Inspection: Unknown
Date(s) of Subsequent Re-Inspections: 2015, 2021, 2024

Homogeneous Material			Material Category	Friability	Assessment Category (1-7)	Recorded Locations	Response Actions Taken/Renovations/Other Comments
Sample Number	Asbestos Content	Material Description					
N/A	Assumed	9" x 9" Gray Floor Tile with Orange & Black Streaks & associated Mastic	Misc.	NF	5	Supply Closet (Storage Room 1)	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	9" x 9" Gray Floor Tile with White & Black Streaks & associated Mastic	Misc.	NF	5	Kitchen Office	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Carpet Adhesive (Blue & Green Carpets)	Misc.	NF	5	Conference Room, Office, Principal's Office, Classroom Room #33, PPS, Computer Lab, Media Center, Social Worker Office, Office 22, 24, 26 and 33	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Gray Linoleum Flooring & associated Adhesive	Misc.	NF	5	Classroom #31	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A		Gray with Specks Linoleum Flooring & associated Adhesive	Misc.	NF	5	Staff Work Room, Art Room	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	6" x 6" Brown Quarry Floor Tile/Grout/Adhesive	Misc.	NF	5	Storage #5	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance

Re-Inspection Form 1 (A) – List of Identified ACBM

Page 4 of 8

School: Daniels Farm Elementary School
Address: 710 Daniels Farm Road, Trumbull, CT

Date(s) of Original Inspection: Unknown
Date(s) of Subsequent Re-Inspections: 2015, 2021, 2024

Homogeneous Material			Material Category	Friability	Assessment Category (1-7)	Recorded Locations	Response Actions Taken/Renovations/Other Comments
Sample Number	Asbestos Content	Material Description					
N/A	Assumed	6" x 6" Red Quarry Floor Tile/Grout/Adhesive	Misc.	NF	5	Custodian Closets, Kitchen, Kitchen Laundry	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Terrazzo Flooring	Misc.	NF	5	Hallway #1, Hallway #3	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	4" Gray Cove Base Molding & associated Adhesive	Misc.	NF	5	Closet, Gym Back Entry Foyer, Gym/All Purpose Room, Kitchen Office, Stage	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	4" Green Cove Base Molding & associated Adhesive	Misc.	NF	5	Media Storage Room, PPS, Computer Lab, Media Center	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	4" Light Brown Cove Base Molding & associated Adhesive	Misc.	NF	5	Hallway #2	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	4" Black Cove Base Molding & associated Adhesive	Misc.	NF	5	Nurse's Office, Teachers' Lounge and Classroom #31	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance

Re-Inspection Form 1 (A) – List of Identified ACBM

Page 5 of 8

School: Daniels Farm Elementary School
Address: 710 Daniels Farm Road, Trumbull, CT

Date(s) of Original Inspection: Unknown
Date(s) of Subsequent Re-Inspections: 2015, 2021, 2024

Homogeneous Material			Material Category	Friability	Assessment Category (1-7)	Recorded Locations	Response Actions Taken/Renovations/Other Comments
Sample Number	Asbestos Content	Material Description					
N/A	Assumed	4" Blue Cove Base Molding & associated Adhesive	Misc.	NF	5	Classroom 1, 2, 4, 6, 10, 19, 21, 26, 27, 29, 32, 33, Conference Room, Learning Center, Office, Principal's Office, Reading Room, and Staff Work Room	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	4" Brown Cove Base Molding & associated Adhesive	Misc.	NF	5	Classroom 8	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Acoustical/Decorative Wall Tiles	Misc.	NF	5	Gym/All Purpose Room	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	4"x 4" Blue Wall Tiles/Grout/Adhesive	Misc.	NF	5	Boy's Hallway #3 Bathroom	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	4"x 4" Pink Wall Tiles/Grout/Adhesive	Misc.	NF	5	Girl's Hallway #3 Bathroom	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Tan Window Frame Caulking Compound	Misc.	NF	5	Classroom #2, Classroom #4, Classroom #6, Media Center #13 and Staff Work Room	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance

Re-Inspection Form 1 (A) – List of Identified ACBM

Page 6 of 8

School: Daniels Farm Elementary School
Address: 710 Daniels Farm Road, Trumbull, CT

Date(s) of Original Inspection: Unknown
Date(s) of Subsequent Re-Inspections: 2015, 2021, 2024

Homogeneous Material			Material Category	Friability	Assessment Category (1-7)	Recorded Locations	Response Actions Taken/Renovations/Other Comments
Sample Number	Asbestos Content	Material Description					
N/A	Assumed	Chalkboard, Tack Board & associated Adhesives	Misc.	NF	5	Classrooms 1 – 30, Classroom 32, Learning Center #2, Computer Lab, Media Center, Reading Room and Art Room	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Gray Sink Undercoating	Misc.	NF	5	Classrooms 1 – 33	Not Regulated By AHERA; For Informational Purposes Only. Material Must Be Managed/Disposed of As ACBM Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	White Sink Undercoating	Misc.	NF	5	Staff Work Room, and Media Center Office	Not Regulated By AHERA; For Informational Purposes Only. Material Must Be Managed/Disposed of As ACBM Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Light Gray Sink Undercoating	Misc.	NF	5	PPS	Not Regulated By AHERA; For Informational Purposes Only. Material Must Be Managed/Disposed of As ACBM

Re-Inspection Form 1 (A) – List of Identified ACBM

Page 7 of 8

School: Daniels Farm Elementary School
Address: 710 Daniels Farm Road, Trumbull, CT

Date(s) of Original Inspection: Unknown
Date(s) of Subsequent Re-Inspections: 2015, 2021, 2024

Homogeneous Material			Material Category	Friability	Assessment Category (1-7)	Recorded Locations	Response Actions Taken/Renovations/Other Comments
Sample Number	Asbestos Content	Material Description					
							Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Textured Suspended Ceiling Tile	Misc.	NF	5	Storage #5	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	12" x 12' Fixed Ceiling Tile Glue Dots	Misc.	NF	5	Gym/All Purpose Room and Kitchen Exit Doorway	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	2' x 2' Non-Textured Ceiling Tile	Misc.	NF	5	Kitchen	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	2' x 2' Texture Suspended Ceiling Tile with Pinholes	Misc.	NF	5	Hallway #1, Nurse's Office and Bathroom, Office, Principal's Office, Custodian Closet and Staff Work Room	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	2' x 2' Textured Suspended Ceiling Tile with Small Pinholes	Misc.	NF	5	Classroom 1 - 8, Classroom 10, 31 and 33, Custodian Closet, Accessible Bathroom, Boys' and Girls' Hallway #1 Bathroom, Media Storage Room, PPS, Teachers' Lounge, Computer Lab and Media Center	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance

Re-Inspection Form 1 (A) – List of Identified ACBM

Page 8 of 8

School: Daniels Farm Elementary School
Address: 710 Daniels Farm Road, Trumbull, CT

Date(s) of Original Inspection: Unknown
Date(s) of Subsequent Re-Inspections: 2015, 2021, 2024

Homogeneous Material			Material Category	Friability	Assessment Category (1-7)	Recorded Locations	Response Actions Taken/Renovations/Other Comments
Sample Number	Asbestos Content	Material Description					
N/A	Assumed	2' x 4' Suspended Ceiling Tile with Pinholes	Misc.	NF	5	Classrooms 9, 11, 13, 15 – 20, 26, 27, 30 and Associated Bathrooms, Conference Room, Reading Room, Boys' Hallway #3 Bathroom, Staff Work Room	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Cement Ceiling	Misc.	NF	5	Gym/All Purpose Room	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Tectum Ceiling Panels	Misc.	NF	5	Gym Back Entry Foyer	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance
N/A	Assumed	Plaster Ceiling	Surf.	F	5	Storage Room #2	Maintain under O & M Plan; Recommend sampling for asbestos content prior to disturbance

Information abstracted by: Sandra Guzman

Date: April 11, 2024

Material Category: TSI = Thermal System Insulation, Surf. = Surfacing, Misc. = Miscellaneous

Friability: F = Friable, NF = Non-Friable

AHERA Assessment Categories: 1 = Damaged or significantly damaged TSI ACBM; 2 = Damaged friable surfacing ACBM; 3 = Significantly damaged friable surfacing ACBM; 4 = Damaged or significantly damaged friable miscellaneous ACBM; 5 = ACBM with potential for damage; 6 = ACBM with potential for significant damage; 7 = Any remaining friable ACBM or friable suspected ACBM

Appendix C

Re-Inspection Form 1B

Re-Inspection Form 1 (B) – List of Previously-Unidentified Suspect ACBM

Page 1 of 1

School: Daniels Farm Elementary School

Date(s) of Original AHERA Inspection: Unknown

Address: 710 Daniels Farm Road, Trumbull, CT

Date(s) of Re-Inspection: 2015, 2021, 2024

Homogeneous Material		Asbestos Content (%)	Material Category	Estimated Quantity (SF/LF)	Friability	Assessment Category (1-7)	Recorded Locations of Material for Each Assessment Category
Sample Number	Material Description						
N/A	12" x 12" Gray Floor Tile with Gray Specks & associated Mastic	Assumed	Misc.	2,200 SF	NF	5	Multipurpose Room
N/A	12" x 12" Beige Floor Tile with Brown Specks & associated Mastic	Assumed	Misc.	60 SF	NF	5	Equipment Storage and Storage 11
N/A	Green Linoleum Flooring & associated Adhesive	Assumed	Misc.	300 SF	NF	5	Media Center Office
N/A	Gray Ramp Textured Flooring & associated Adhesive	Assumed	Misc.	240 SF	NF	5	Ramp to Music Room
N/A	Black Sink Undercoating	Assumed	Misc.	1 EA	NF	5	Staff Room
N/A	Pipe Fitting Insulation	Assumed	TSI	2 EA	F	5	Storage Rooms 8 and 9 (Suspected to exist in other locations within wall cavities associated with pipe system)

Inspected by: Sandra Guzman

Date: April 11, 2024

Material Category: TSI = Thermal System Insulation, S = Surfacing, M = Miscellaneous

LF = Linear Feet; SF = Square Feet

Friability: F = Friable, NF = Non-Friable

AHERA Assessment Categories: 1 = Damaged or significantly damaged TSI ACBM; 2 = Damaged friable surfacing ACBM; 3 = Significantly damaged friable surfacing ACBM; 4 = Damaged or significantly damaged friable miscellaneous ACBM; 5 = ACBM with potential for damage; 6 = ACBM with potential for significant damage; 7 = Any remaining friable ACBM or friable suspected ACBM

Appendix D

Re-Inspection Form 2

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 1 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Grout & Thinset, Mortar associated with 1"x1" Blue Ceramic Floor Tile

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Handicap Bathroom, Boy's Hallway #1 Bathroom, And Nurse's Bathroom	NF	370 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACMB: Findings and Management Planner Recommendations



Page 2 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: Grout & Thinset, Mortar associated with 1"x1" Gray Ceramic Floor Tile

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classroom 9, 11 - 20 Bathrooms	NF	165 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACMB collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 3 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: Grout & Thinset, Mortar associated with 1"x1" Gray Ceramic Flooring Tile with Red, Blue & Brown Spots

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Boy's Hallway #3 Bathroom, And Girl's Hallway #3 Bathroom	NF	720 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 4 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Grout & Thinset, Mortar Associated with 1"x1" Green Ceramic Floor Tile

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Girl's Hallway #1 Bathroom	NF	280 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 5 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12" Blue Vinyl Floor Tile with White Specks & associated Mastic

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classroom 21, 23, 27, 28 and 29	NF	3,500	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 6 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12" Cream Vinyl Floor Tile with Brown & Gray Specks & associated Mastic

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Hallway #2	NF	1,840 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACM: Findings and Management Planner Recommendations



Page 7 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12" Dark Blue Vinyl Floor Tile & associated Mastic

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Learning Center #2, Reading Room #23 and Classroom #32	NF	1,280 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 8 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: 12"x12" Dark Blue Vinyl Floor Tile with Specks & associated Mastic

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classroom 1 - 4, 6, 9 - 20, 26, 30, Gym/All Purpose Room and Stage	NF	21,430 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 9 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12" Gray Floor Tile with Gray Specks & associated Mastic

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Multipurpose Room	NF	2,200 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACM: Findings and Management Planner Recommendations



Page 10 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12" Beige Floor Tile with Brown Specks & associated Mastic

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Equipment Storage and Storage 11	NF	60 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 11 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12" Green Vinyl Floor Tile & associated Mastic

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Media Storage Room	NF	105 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 12 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12" Light Blue Vinyl Floor Tile with White & Gray Specks & associated Mastic

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Gym Back Entry Foyer, Nurse's Office, Stage, Storage #2 and Room 5	NF	1,200 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 13 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12" Peach Vinyl Floor Tile with Brown & White Specks

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classroom #8	NF	780 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 14 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12" Tan Vinyl Floor Tile with Dark Gray Specks & associated Mastic

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Teacher's Lounge	NF	450 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 15 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: 9" x 9" Gray Floor Tile with Orange & Black Streaks & associated Mastic

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Supply Closet (Storage Room 1)	NF	200 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 16 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 9" x 9" Gray Floor Tile with White & Black Streaks & associated Mastic

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Kitchen Office	NF	380 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 17 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Carpet Adhesive (Blue & Green Carpets)

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Conference Room, Office, Principal's Office, Classroom Room #33, PPS, Computer Lab, Media Center, Social Worker Office, Office 22, 24, 26 and 33	NF	1,800 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 18 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: Gray Linoleum Flooring & associated Adhesive

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classroom #31	NF	960 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 19 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Green Linoleum Flooring & associated Adhesive

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Media Center Office	NF	300 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 20 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Gray with Specks Linoleum Flooring & associated Adhesive

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Staff Work Room, Art Room	NF	600 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 21 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: Gray Ramp Textured Flooring & associated Adhesive

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Ramp to Music Room	NF	240 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 22 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 6" x 6" Brown Quarry Floor Tile/Grout/Adhesive

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Storage #5	NF	110 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 23 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 6" x 6" Red Quarry Floor Tile/Grout/Adhesive

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Custodian Closets, Kitchen, Kitchen Laundry	NF	450 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 24 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Terrazzo Flooring

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Hallway #1, Hallway #3	NF	2,800 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 25 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 4" Gray Cove Base Molding & associated Adhesive

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Closet, Gym Back Entry Foyer, Gym/All Purpose Room, Kitchen Office, Stage	NF	5,600 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 26 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: 4" Green Cove Base Molding & associated Adhesive

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Media Storage Room, PPS, Computer Lab, Media Center	NF	2,200 LF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 27 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 4" Light Brown Cove Base Molding & associated Adhesive

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Hallway #2	NF	8,000 LF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 28 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 4" Black Cove Base Molding & associated Adhesive

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Nurse's Office, Teachers' Lounge, and Classroom #31	NF	1,200 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 29 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 4" Blue Cove Base Molding & associated Adhesive

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classroom 1, 2, 4, 6, 10, 19, 21, 26, 27, 29, 32, 33, Conference Room, Learning Center, Office, Principal's Office, Reading Room and Staff Work Room	NF	7,100 LF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 30 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: 4" Brown Cove Base Molding & associated Adhesive

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classroom 8	NF	550 LF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 31 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Acoustical/Decorative Wall Tiles

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Gym/All Purpose Room	NF	700 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACM: Findings and Management Planner Recommendations



Page 32 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 4"x 4" Blue Wall Tiles/Grout/Adhesive

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Boy's Hallway #3 Bathroom	NF	630 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 33 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: 4"x 4" Pink Wall Tiles/Grout/Adhesive

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Girl's Hallway #3 Bathroom	NF	630 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 34 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Tan Window Frame Caulking Compound

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classroom #2, Classroom #4, Classroom #6, Media Center #13, and Staff Work Room	NF	400 LF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 35 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: Chalkboard, Tack Board & associated Adhesives

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classrooms 1 – 30, Classroom 32, Learning Center #2, Computer Lab, Media Center, Reading Room and Art Room	NF	3,300 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 36 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Gray Sink Undercoating

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classrooms 1 – 33	NF	23 EA	5	ACBM with Potential for Damage	Not Regulated By AHERA; For Informational Purposes Only. Material Must Be Managed/Disposed of as ACBM. Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 37 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: White Sink Undercoating

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Staff Work Room and Media Center Office	NF	1 EA	5	ACBM with Potential for Damage	Not Regulated By AHERA; For Informational Purposes Only. Material Must Be Managed/Disposed of as ACBM. Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 38 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Black Sink Undercoating

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Staff Room	NF	1 EA	5	ACBM with Potential for Damage	Not Regulated By AHERA; For Informational Purposes Only. Material Must Be Managed/Disposed of as ACBM. Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 39 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Light Gray Sink Undercoating

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
PPS	NF	1 EA	5	ACBM with Potential for Damage	Not Regulated By AHERA; For Informational Purposes Only. Material Must Be Managed/Disposed of as ACM. Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 40 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: Textured Suspended Ceiling Tile

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Storage #5	NF	110 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 41 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 12" x 12' Fixed Ceiling Tile Glue Dots

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Gym/All Purpose Room, and Kitchen Exit Doorway	NF	4,825 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 42 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 2' x 2' Non-Textured Ceiling Tile

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Kitchen	NF	360 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 43 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: 2' x 2' Texture Suspended Ceiling Tile with Pinholes

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Hallway #1, Nurse's Office and Bathroom, Office, Principal's Office, Custodian Closet and Staff Work Room	NF	2,325 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 44 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: 2' x 2' Textured Suspended Ceiling Tile with Small Pinholes

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classroom 1 - 8, Classroom 10, 31 and 33, Custodian Closet, Accessible Bathroom, Boys and Girls Hallway #1 Bathroom, Media Storage Room, PPS, Teacher's Lounge, Computer Lab and Media Center	NF	13,120 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 45 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: 2' x 4' Suspended Ceiling Tile with Pinholes

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Classrooms 9, 11, 13, 15 – 20, 26, 27, 30 and Associated Bathrooms, Conference Room, Reading Room, Boys Hallway #3 Bathroom, Staff Work Room	NF	8,200 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? <u>(No)</u>					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 46 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Cement Ceiling

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Gym/All Purpose Room	NF	5,000 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 47 of 49

School: Daniels Farm Elementary School

Date of Re-Inspection: April 11, 2024

Homogeneous Material: Tectum Ceiling Panels

Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Gym Back Entry Foyer	NF	80 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 48 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: Plaster Ceiling

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Storage Room #2	F	200 SF	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (No)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Re-Inspection Form 2. Re-Inspection of ACBM: Findings and Management Planner Recommendations



Page 49 of 49

 School: Daniels Farm Elementary School

 Date of Re-Inspection: April 11, 2024

 Homogeneous Material: Pipe Fitting Insulation

 Sample ID Number: Assumed

ACBM RE-INSPECTION FINDINGS					MANAGEMENT PLANNER RECOMMENDATIONS	
ACBM Location(s) by Assessment Category	Friability	Estimated Quantity	Assessment Category	Physical Description	Recommended Response Action(s)	Date Action Completed
Storage Rooms 8 and 9 (Suspected to exist in other locations within wall cavities associated with pipe system)	F	2 EA	5	ACBM with Potential for Damage	Maintain under O & M Plan. Recommend sampling to determine asbestos content prior to disturbance	On-going
Were additional samples of this ACBM collected? (<u>No</u>)					Date of Management Planner Review: _____	
Inspector's Name: <u>Sandra Guzman</u> Inspector Signature: <u></u> Accreditation #/State: <u>000335</u> Expiration Date: <u>08/31/2024</u>					Management Planner Name: <u>Eduardo Miguel Marques</u> Management Planner Signature: <u></u> Accreditation #/State: <u>000201</u> Expiration Date: <u>02/28/2025</u>	
I, the LEA's Designated Person, have read and understood the recommendations made above: _____ Date: _____						

Appendix E

Sample 6-Month Periodic Surveillance Form

Sample 6- Month Periodic Surveillance Form

Local Education Agency (LEA): Trumbull Public Schools

Facility Address: Daniels Farm Elementary School, 710 Daniels Farm Road, Trumbull, CT

Date of Surveillance: _____

ACBM Damage Report

Asbestos-Containing Building Material	Location	Previous Condition	Present Condition	Change in Condition (Yes/No)	Estimated Damaged Quantity	Comments
Grout & Thinset, Mortar associated with 1"x1" Blue Ceramic Floor Tile	Handicap Bathroom, Boy's Hallway #1 Bathroom, And Nurse's Bathroom					
Grout & Thinset, Mortar associated with 1"x1" Gray Ceramic Floor Tile	Classroom 9, 11 - 20 Bathrooms					
Grout & Thinset, Mortar associated with 1"x1" Gray Ceramic Flooring Tile with Red, Blue & Brown Spots	Boy's Hallway #3 Bathroom, And Girl's Hallway #3 Bathroom					
Grout & Thinset, Mortar Associated with 1"x1" Green Ceramic Floor Tile	Girl's Hallway #1 Bathroom					
12" x 12" Blue Vinyl Floor Tile with White Specks & associated Mastic	Classroom 21, 23, 27, 28 and 29					
12" x 12" Cream Vinyl Floor Tile with Brown & Gray Specks & associated Mastic	Hallway #2					
12" x 12" Dark Blue Vinyl Floor Tile & associated Mastic	Learning Center #2, Reading Room #23 and Classroom #32					
12"x12" Dark Blue Vinyl Floor Tile with Specks & associated Mastic	Classroom 1 - 4, 6, 9 - 20, 26, 30, Gym/All Purpose Room and Stage					

Asbestos-Containing Building Material	Location	Previous Condition	Present Condition	Change in Condition (Yes/No)	Estimated Damaged Quantity	Comments
12" x 12" Gray Floor Tile with Gray Specks & associated Mastic	Multipurpose Room					
12" x 12" Beige Floor Tile with Brown Specks & associated Mastic	Equipment Storage and Storage 11					
12" x 12" Green Vinyl Floor Tile & associated Mastic	Media Storage Room					
12" x 12" Light Blue Vinyl Floor Tile with White & Gray Specks & associated Mastic	Gym Back Entry Foyer, Nurse's Office, Stage, Storage #2 and Room 5					
12" x 12" Peach Vinyl Floor Tile with Brown & White Specks	Classroom #8					
12" x 12" Tan Vinyl Floor Tile with Dark Gray Specks & associated Mastic	Teacher's Lounge					
9" x 9" Gray Floor Tile with Orange & Black Streaks & associated Mastic	Supply Closet (Storage Room 1)					
9" x 9" Gray Floor Tile with White & Black Streaks & associated Mastic	Kitchen Office					
Carpet Adhesive (Blue & Green Carpets)	Conference Room, Office, Principal's Office, Classroom Room #33, PPS, Computer Lab, Media Center, Social Worker Office, Office 22, 24, 26 and 33					
Gray Linoleum Flooring & associated Adhesive	Classroom #31					
Green Linoleum Flooring & associated Adhesive	Media Center Office					
Gray with Specks Linoleum Flooring & associated Adhesive	Staff Work Room, Art Room					

Asbestos-Containing Building Material	Location	Previous Condition	Present Condition	Change in Condition (Yes/No)	Estimated Damaged Quantity	Comments
Gray Ramp Textured Flooring & associated Adhesive	Ramp to Music Room					
6" x 6" Brown Quarry Floor Tile/Grout/Adhesive	Storage #5					
6" x 6" Red Quarry Floor Tile/Grout/Adhesive	Custodian Closets, Kitchen, Kitchen Laundry					
Terrazzo Flooring	Hallway #1, Hallway #3					
4" Gray Cove Base Molding & associated Adhesive	Closet, Gym Back Entry Foyer, Gym/All Purpose Room, Kitchen Office, Stage					
4" Green Cove Base Molding & associated Adhesive	Media Storage Room, PPS, Computer Lab, Media Center					
4" Light Brown Cove Base Molding & associated Adhesive	Hallway #2					
4" Black Cove Base Molding & associated Adhesive	Nurse's Office, Teachers' Lounge and Classroom #31					
4" Blue Cove Base Molding & associated Adhesive	Classroom 1, 2, 4, 6, 10, 19, 21, 26, 27, 29, 32, 33, Conference Room, Learning Center, Office, Principal's Office, Reading Room and Staff Work Room					
4" Brown Cove Base Molding & associated Adhesive	Classroom 8					
Acoustical/Decorative Wall Tiles	Gym/All Purpose Room					
4"x 4" Blue Wall Tiles/Grout/Adhesive	Boy's Hallway #3 Bathroom					
4"x 4" Pink Wall Tiles/Grout/Adhesive	Girl's Hallway #3 Bathroom					
Tan Window Frame Caulking Compound	Classroom #2, Classroom #4, Classroom #6, Media Center #13 and Staff Work Room					

Asbestos-Containing Building Material	Location	Previous Condition	Present Condition	Change in Condition (Yes/No)	Estimated Damaged Quantity	Comments
Chalkboard, Tack Board & associated Adhesives	Classrooms 1 – 30, Classroom 32, Learning Center #2, Computer Lab, Media Center, Reading Room and Art Room					
Gray Sink Undercoating	Classrooms 1 – 33					
White Sink Undercoating	Staff Work Room and Media Center Office					
Black Sink Undercoating	Staff Room					
Light Gray Sink Undercoating	PPS					
Textured Suspended Ceiling Tile	Storage #5					
12" x 12' Fixed Ceiling Tile Glue Dots	Gym/All Purpose Room and Kitchen Exit Doorway					
2' x 2' Non-Textured Ceiling Tile	Kitchen					
2' x 2' Texture Suspended Ceiling Tile with Pinholes	Hallway #1, Nurse's Office and Bathroom, Office, Principal's Office, Custodian Closet and Staff Work Room					
2' x 2' Textured Suspended Ceiling Tile with Small Pinholes	Classroom 1 - 8, Classroom 10, 31 and 33, Custodian Closet, Accessible Bathroom, Boys and Girls Hallway #1 Bathroom, Media Storage Room, PPS, Teacher's Lounge, Computer Lab and Media Center					
2' x 4' Suspended Ceiling Tile with Pinholes	Classrooms 9, 11, 13, 15 – 20, 26, 27, 30 and Associated Bathrooms, Conference Room, Reading Room, Boys' Hallway #3 Bathroom, Staff Work Room					

Asbestos-Containing Building Material	Location	Previous Condition	Present Condition	Change in Condition (Yes/No)	Estimated Damaged Quantity	Comments
Cement Ceiling	Gym/All Purpose Room					
Tectum Ceiling Panels	Gym Back Entry Foyer					
Plaster Ceiling	Storage Room #2					
Pipe Fitting Insulation	Storage Rooms 8 and 9 (Suspected to exist in other locations within wall cavities associated with pipe system)					

Conditions: D = Damaged; F = Fair; G = Good; IA = Inaccessible; N/A = Not Applicable; SD = Significant Damage; SF = Square Feet

Surveillance conducted by: _____
(print name) (signature)

I, the LEA's Designated Person, have read and understood the findings noted above: _____

Date: _____

Appendix F

Preventive Measures

Preventive Measures for Various Asbestos-Containing Building Materials

A. Surfacing Materials

“Surfacing Materials” means materials in a school building that are applied by spray, trowel, or otherwise applied to surfaces. These include sprayed-applied fireproofing materials on structural members, ceiling and wall plasters, or other materials applied to surfaces for acoustical, fireproofing, or other purposes.

Surfacing Materials are generally considered friable and can release asbestos fibers if damaged by impact, air erosion, vibration, and/or water intrusion. When properly implemented, the following procedures will reduce the potential for fiber release:

1. Sprayed-Applied Fireproofing

- a) Identify the materials and post warning signs on the laid-in or glued-in ceiling tile. If the decking is not covered, place the sign on the wall.
- b) Maintain the materials in intact state and undamaged condition. During winter, pigeons, squirrels, and other rodents tend to roost in boiler/machine rooms and dislodge sprayed-applied fireproofing on the decking. Prevent such possibilities.
- c) Prevent water leakage. If the material is significantly damaged, removal is the best option. For minor damage, enclosure is a temporary solution. Encapsulation of damaged sprayed-on fireproofing material is not recommended.
- d) Train the custodial people who are responsible for care and maintenance of surfacing materials. Please note that the repair/removal can only be performed by a licensed abatement contractor.

2. Ceiling and Wall Plasters

- a) Identify the materials and post asbestos warning signs.
- b) Maintain the materials in intact state and undamaged condition. Avoid storing/stacking on/near the materials to reduce contact damage.
- c) Prevent water leakage. If the material is significantly damaged, removal is the best option. For minor damage, repair or enclosure is a temporary solution.
- d) Train the custodial people who are responsible for care and maintenance of surfacing materials.

B. Thermal System Insulation (TSI)

“Thermal System Insulation (TSI)” means insulating materials applied to pipes, pipe fittings, boilers, breechings, tanks, ducts, or other components to prevent process heat loss or gain, water condensation, or for other purposes (e.g., fire door insulation core).

TSI are generally considered friable ACBM. This means they can be easily damaged, increasing the potential for fiber release. When properly implemented, the following procedures will reduce the potential for fiber release:

1. Boiler and Breeching Insulation

- a) Identify the locations and label the boiler. Warning signs should be posted outside the boiler room.
- b) Reduce the likelihood of fiber release by ensuring that the insulation is not damaged. Avoid storing/stacking on/near the boiler to reduce contact damage.
- c) Maintain the insulation in an intact state and undamaged condition. Repair damaged areas as soon as possible to prevent further deterioration. If repair is not feasible due to extensive damage/deterioration, remove the material.
- d) Train the custodial people who are responsible for care and maintenance of TSI. Please note that the repair/removal can only be performed by a licensed abatement contractor.

2. Pipe, Pipe Fitting, Tank, Duct & Breeching Insulations

- a) Identify the locations and label the materials. Warning signs should be posted outside of rooms that have TSI materials.
- b) Reduce the likelihood of fiber release by ensuring that the materials are not damaged. Avoid storing/stacking near the materials to reduce contact damage.
- c) Maintain all TSI materials in intact state and undamaged condition. Inspect the protective jackets for damage. Repair damaged areas as soon as possible to prevent further deterioration. If repair is not feasible due to extensive damage/deterioration, remove the material.
- d) Train the custodial people who are responsible for care and maintenance of TSI. Please note that the repair/removal can only be performed by a licensed abatement contractor.

C. Miscellaneous Materials

“Miscellaneous Materials” are the other ACBM in a school building that are not categorized as Surfacing Materials or TSI. These include floor tiles, floor tile and carpet mastics, gypsum wallboard and joint compound, ceiling tiles, glue daubs, asbestos cement panels, cove base and associated glue, window/door caulking and glazing compounds, etc. The following maintenance procedures are recommended for these materials:

1. Vinyl Asbestos Floor Tiles (VAT)

Vinyl Asbestos Floor Tiles (VAT) are considered non-friable, however routine maintenance procedures such as spray-buffing, burnishing, wet scrubbing, and stripping can generate asbestos fibers. Following procedures, when properly implemented, will reduce the potential of fiber release:

- a) Do not sand, grind, or abrade the tiles. Stripping of VAT should be done as infrequently as possible. When stripping becomes necessary, follow the appropriate work practices. Never perform dry stripping.
- b) During spray-buffing or burnishing the floor, operate the machine at the lowest workable speed and use the least abrasive pad. Use a wet mop for routine cleaning whenever possible.
- c) Routinely check whether chair and desk glides are in good condition and replace when necessary. Worn glides can gouge the floor and cause fiber release.
- d) Place carpets/floor mats in all entrances to reduce abrasion of floor tiles by sand and pebbles. During winter, parking lots and walkways swept to the extent possible to avoid the tracking of salt and ice-melting compounds into the school by the students.

- e) Train the custodial people who are responsible for care and maintenance of VAT. Please note that the repair/removal can only be performed by a licensed abatement contractor.

2. Wallboard and Joint Compound Assembly

- a) Since a number of different homogeneous assemblies may exist in a building, sheetrock/joint compound must be assumed to be ACBM unless sample results prove otherwise. If any specific areas are going to be disturbed, samples of the material in that area should be collected and analyzed.
- b) Reduce the likelihood of fiber release by avoiding cutting or drilling holes through the sheetrock panels.

3. Ceiling Tile and Glue Daubs

- a) Reduce the likelihood of fiber release by limiting access to the space above the ceiling tiles. Maintain the ceiling tiles in undamaged condition. Replace any damaged or water-stained tile.
- b) If the ceiling tiles are non-asbestos, collect samples and analyze the glue daubs to identify asbestos-content before disturbing the tiles.

4. Asbestos Cement Panels, Window/Door Caulking and Glazing Compounds

- a) Maintain asbestos cement panels and window/door caulking and glazing compounds in undamaged condition.

5. Carpet Glue, Blackboard/Tack Board Glue, Floor Tile Mastic, Cove Base, and Mastic

- a) Reduce the likelihood of fiber release by leaving materials in place.
- b) Maintain materials in good condition. Collect samples and analyze to identify asbestos-content before disturbing.

Appendix G

Asbestos Inspector and Management Planner State Licenses and EPA Accreditations

1000418-00000422-00000001 of 0000001-C01-a1d00101-1284-00420

Dear SANDRA L GUZMAN,

Attached you will find your validated certificate for the coming year. Should you have any questions about your certificate renewal, please do not hesitate to write or call:

Department of Public Health
P.O. Box 340308
M.S.#12MQA
Hartford, CT 06134-0308

(860) 509-7603
oplc.dph@ct.gov
www.ct.gov/dph/license

Sincerely,



MANISHA JUTHANI, MD, COMMISSIONER
DEPARTMENT OF PUBLIC HEALTH

STATE OF CONNECTICUT
DEPARTMENT OF PUBLIC HEALTH

PURSUANT TO THE PROVISIONS OF THE GENERAL STATUTES OF CONNECTICUT

THE INDIVIDUAL NAMED BELOW IS CERTIFIED
BY THIS DEPARTMENT AS A

ASBESTOS CONSULTANT-INSP/MGMT PLANNER

SANDRA L GUZMAN

CERTIFICATE NO.
000335

CURRENT THROUGH
08/31/24

VALIDATION NO.
03-055356


SIGNATURE
COMMISSIONER

EMPLOYER'S COPY

STATE OF CONNECTICUT
DEPARTMENT OF PUBLIC HEALTH

NAME

SANDRA L GUZMAN

VALIDATION NO.
03-055356

CERTIFICATE NO.
000335

CURRENT THROUGH
08/31/24

PROFESSION

ASBESTOS CONSULTANT-INSP/MGMT PLANNER


SIGNATURE
COMMISSIONER

INSTRUCTIONS:

1. Detach and sign each of the cards on this form
2. Display the large card in a prominent place in your office or place of business.
3. The wallet card is for you to carry on your person. If you do not wish to carry the wallet card, place it in a secure place.
4. The employer's copy is for persons who must demonstrate current licensure/certification in order to retain employment or privileges. The employer's card is to be presented to the employer and kept by them as a part of your personnel file. Only one copy of this card can be supplied to you.

WALLET CARD

STATE OF CONNECTICUT
DEPARTMENT OF PUBLIC HEALTH

NAME

SANDRA L GUZMAN

VALIDATION NO.
03-055356

CERTIFICATE NO.
000335

CURRENT THROUGH
08/31/24

PROFESSION

ASBESTOS CONSULTANT-INSP/MGMT PLANNER


SIGNATURE
COMMISSIONER

1000218-0000222-0000001 of 0000001-C01-a1d00101-0564-00220

Dear EDUARDO M. MARQUES,

Attached you will find your validated certificate for the coming year. Should you have any questions about your certificate renewal, please do not hesitate to write or call:



Department of Public Health
P.O. Box 340308
M.S.#12MQA
Hartford, CT 06134-0308



(860) 509-7603
oplcdph@ct.gov
www.ct.gov/dph/license

Sincerely,





MANISHA JUTHANI, MD, COMMISSIONER
DEPARTMENT OF PUBLIC HEALTH

STATE OF CONNECTICUT DEPARTMENT OF PUBLIC HEALTH	
PURSUANT TO THE PROVISIONS OF THE GENERAL STATUTES OF CONNECTICUT	
THE INDIVIDUAL NAMED BELOW IS CERTIFIED BY THIS DEPARTMENT AS A	
ASBESTOS CONSULTANT-INSP/MGMT PLANNER	
EDUARDO M. MARQUES	CERTIFICATE NO. 000201
	CURRENT THROUGH 02/28/25
	VALIDATION NO. 03-083603
 SIGNATURE	 COMMISSIONER

EMPLOYER'S COPY STATE OF CONNECTICUT DEPARTMENT OF PUBLIC HEALTH		
NAME EDUARDO M. MARQUES		
VALIDATION NO. 03-083603	CERTIFICATE NO. 000201	CURRENT THROUGH 02/28/25
PROFESSION ASBESTOS CONSULTANT-INSP/MGMT PLANNER		
 SIGNATURE	 COMMISSIONER	

INSTRUCTIONS:

1. Detach and sign each of the cards on this form
2. Display the large card in a prominent place in your office or place of business.
3. The wallet card is for you to carry on your person. If you do not wish to carry the wallet card, place it in a secure place.
4. The employer's copy is for persons who must demonstrate current licensure/certification in order to retain employment or privileges. The employer's card is to be presented to the employer and kept by them as a part of your personnel file. Only one copy of this card can be supplied to you.

WALLET CARD STATE OF CONNECTICUT DEPARTMENT OF PUBLIC HEALTH		
NAME EDUARDO M. MARQUES		
VALIDATION NO. 03-083603	CERTIFICATE NO. 000201	CURRENT THROUGH 02/28/25
PROFESSION ASBESTOS CONSULTANT-INSP/MGMT PLANNER		
 SIGNATURE	 COMMISSIONER	



CERTIFICATE OF ACHIEVEMENT

This certifies that

Eduardo Miguel Marques

has successfully completed the
8 Hour Asbestos Site Inspector/Management Planner Refresher Training
Asbestos Accreditation Under TSCA Title II
40 CFR Part 763

Course training provided
via Live Webinar

Exam Score: 92%

conducted by:
ATLAS Technical Consultants, LLC
73 William Franks Drive
West Springfield, MA 01089
(413) 781-0070



A handwritten signature in dark ink, appearing to read "Thomas Dion".

Principal Instructor: Thomas Dion

May 23, 2024
Date of Course

May 23, 2025
Expiration Date

A handwritten signature in dark ink, appearing to read "Gregory J. Morsch".

Regional Training Director: Gregory Morsch

MPAR-3619
Certificate Number

May 23, 2024
Examination Date