



ROANOKE COUNTY PUBLIC SCHOOLS

Facilities and Operations

5937 Cove Road NW, Roanoke, VA 24019 ♦ (540) 562-3900 x 10154

Fax (540) 562-3994 ♦ www.rcs.k12.va.us

Document Title: RCPS2025-001 Addendum 1
 RFP#: RCPS2025-001
 RFP Title: Central Office Parking Lot Extension
 Date Addendum Issued: 7/10/24
 Date RFP Issued: 6/27/24
 Date Proposals are Due: 7/18/24, 2:00PM

This addendum provides additional background information in response to questions received from prospective proposers at the pre-bid meeting:

- Drainage away from the administration building is required.
- In lieu of additional grading to provide an exit path for run-off, a “CG6” curb and gutter system may be installed along the entire length of the parking lot on the opposite side from the building. If a gutter system is installed, it must include a concrete flume or similar at the exit.
- Conduit containing fiber optic cable runs under the area to be paved. It is assumed that this conduit is at least 24” deep and will not affect paving. However, RCPS is verifying the depth of the conduit and will post an addendum if it is determined the conduit will need to be relocated.
- Additional stone base that MAY be required if unsuitable soils are encountered should be priced as a per/ton addition.
- Concrete stop blocks should be priced as a per/block addition.

Note: A signed acknowledgment of this addendum must be received at the location indicated on the original solicitation either prior to the proposal due date or attached to your proposal. Signature on this addendum does not substitute for your signature on the original proposal/bid document. The original proposal/bid document must be signed.

Thank you,

Todd Kageals
 Phone: (540) 354-7492
 tkageals@rcps.us

Sign Name:

Print Name:

Name of Firm:

Date: