

Paragon Learning Center

Sample ID	Sample Date	Sample Time	Fixture Type	Cadmium (ppb)	Copper (ppb)	Iron (ppb)	Lead (ppb)	Zinc (ppb)	Location	Action
PRGN1	2/6/2018	5:58 AM	SC-1S	<1.00	15.3	<500	<1.00	5.97	Backflow Valve #1	No Action Taken
PRGN2	2/6/2018	6:02 AM	SC-1M	<1.00	10.4	<500	<1.00	3.16	Backflow Valve #2	No Action Taken
PRGN3-L	2/6/2018	6:05 AM	DFD	<1.00	175	<500	2.50	680	Main East Hallway Near Restrooms	No Action Taken
PRGN3-R	2/6/2018	6:06 AM	DFD	<1.00	13.0	<500	<1.00	10400	Main East Hallway Near Restrooms	No Action Taken
PRGN4-L	2/6/2018	6:10 AM	DFD	<1.00	554	<500	13.2	809	Classroom #4	Disabled
PRGN4-R	2/6/2018	6:10 AM	DFD	<1.00	359	<500	3.13	530	Classroom #4	Disabled
PRGN5	2/6/2018	6:11 AM	DFS	<1.00	963	<500	28.8	626	Classroom #4	Disabled
PRGN6	2/6/2018	6:11 AM	DFS	<1.00	539	<500	34.4	282	Classroom #4	Disabled
PRGN7	2/6/2018	6:15 AM	TL	1.51	310	<500	1.54	590	Teachers Lounge Sink	No Action Taken
PRGN8	2/6/2018	6:16 AM	FF	<1.00	945	<500	1.66	1390	Main Office	No Action Taken
PRGN9-L	2/6/2018	6:17 AM	DFD	<1.00	563	<500	8.35	479	West Hallway Near Gymnasium	No Action Taken
PRGN9-R	2/6/2018	6:17 AM	DFD	<1.00	594	<500	9.40	449	West Hallway Near Gymnasium	No Action Taken
PRGN10-L	2/6/2018	6:18 AM	DFD	<1.00	354	<500	10.2	1870	Cafeteria	No Action Taken
PRGN10-R	2/6/2018	6:18 AM	DFD	<1.00	529	<500	9.38	747	Cafeteria	No Action Taken
PRGN11	2/6/2018	6:19 AM	KSF	<1.00	218	<500	2.52	263	Kitchen	No Action Taken
SL 15SEC	2/6/2018	5:55 AM		<1.00	31.4	<500	1.01	15.3	Meter	No Action Taken
SL 45SEC	2/6/2018	5:55 AM		<1.00	20.3	<500	<1.00	13.0	Meter	No Action Taken

Fixture Type: DFS - Drinking Fountain with single faucet, DFD - Drinking Fountain with double faucet, *SC - Service Connection Tap; KS - Kitchen Sink; TL - Teachers Lounge Sink

* Service Connection Tap is not a point for consumption water