

## **RFP Contract #2144 – Rockville Center Sidewalk and ADA Upgrades Addendum No. 1 – Dated 8/8/2024**

This Addendum includes the following information **and** the ***Rockville Pedestrian Improvements\_CCGP Special Provisions.pdf*** as provided with the web site documents. Both shall be made part of this Project.

The date, time and place for the Bid Opening remain unchanged.

Bidders should include a notation to their submittal that they are aware of this Addendum being made part of the project.

The following questions were received and the **responses** are hereby made part of this project:

- Please note that the email link in the Legal Notice and Invitation to Bid is for [dryniewicz@vernon-ct.gov](mailto:dryniewicz@vernon-ct.gov) when clicked. **Project correspondence should be directed to David Smith, Town Engineer, at [dsmith@vernon-ct.gov](mailto:dsmith@vernon-ct.gov)**
- What is the anticipated start date / end date of the project? **September 15<sup>th</sup>, 2024 The contract duration as provided in the Special Provisions is 60 days.**
- Are there any liquidated damages for this project? **\$500/per calendar day, per the Special Provisions.**
- Are there time restrictions for working hours that would interfere with pedestrian / vehicle traffic? **No restricted hours other than hours of work posted in the RFP**
- Who is responsible for payment of the testing agency for material testing, compaction tests, concrete cylinders, the Owner or the Contractor? **The contractor shall engage approved 3<sup>rd</sup> party testing agency to supply reports of materials provided and installed for quality assurance.**
- Is there a list of approved Ready-mix suppliers available as noted in Specifications page 7 of 22 under Scope of Work additional requirements #6? **We would default to approved suppliers by the CTDOT.**

- There are numerous locations where the existing sidewalk is to be removed and replaced with 8" thick concrete sidewalk. Are the proposed ramps on either side of these areas proposed to be 5" or 8" thick? **8" deep only applies to the driveway apron, not the transition ramps**
- Index plan sheet C-001 shows Alternate #1 Trailhead Improvements. Confirm that this is not part of this project as we do not see a plan or item on bid form for this work. **The Trailhead improvements are not part of this Scope of Work.**
- Is it the intent to install granite curbing at all area where new sidewalk and ramps are to be installed? There is a construction legend showing double line as granite curb but no description notes on plan sheets depict curb as the "typical". **The intent is to install granite curbing ONLY where explicitly called out on the plans. All sidewalk ramps will be concrete curb cast with the ramp per the details (no separate payment for curbing). The double line in the legend should be considered as "curbing" with the specific type of curbing called out on the plans and/or shown in the ramp details.**
- Is there a contractor laydown available for this project? If so where? **There is no designated lay down area, the contractor shall independently provide if needed.**
- It appears that the only new proposed granite curbing to be installed will be on the North side of Brooklyn Street from +/- 75 lf from intersection of Vernon Ave running approximately 400 lf East as shown on plan sheet C-102. Is it the intent for all other curbing shown on plan sheets C-101 – C-201 to be new granite, precast, and/or cast in place curbing. Please clarify. **Granite curbing to be installed as described in the question (intersection of Vernon for 400 LF east on Brooklyn St), and other short segments as called out on the plans. The majority of the remaining curbing on the project is transition curbing cast with sidewalk ramps. This shall be constructed of concrete and is not paid separately (included in the unit price for sidewalk ramp). For concrete curbing, precast or cast-in-place is acceptable per CTDOT standards.**
- Plan sheets C-102 & C-103 have notes to "Remove & replace granite curbing" There is not an item for this work on the bid form. How will this work be paid for? **Paid under Item #0813021 6" Granite Stone Curbing**

- There is a note on the bottom half of plan sheet C-102 near the existing parking lot that states “Remove existing & replace with 5 ft wide concrete sidewalk (Granite curb to remain. Remove, reset, and/or replace curbing as directed by the Town”). How will this work be paid? **Sidewalk to be paid under Item 0921001A Concrete sidewalk item. If the Town decides in the field that the granite curbing should be replaced due to deteriorated condition, this shall be paid under item 0813021 6" Granite Curbing. The intent is to ONLY replace the sidewalk in this area, but additional curbing work may be added at the Town's discretion.**
- There are areas where existing pavement markings are to be eradicated. How will this work be paid? There isn't an item on the bid form. **Cost of this work shall be included in Item 1210105 and meet requirements of Form 818 Article 12.11.**
- Bid form has 9 Special “A” items (such as 0219011A, 0406005A, 0921001A, 0921002A, 0921005A, 0971001A, 0975004A, 0980001A, and 1208931A) which typically have specific specifications pertaining to each Special item. Please confirm if these are special items or standard DOT form 818 items. If they are “A” items please furnish the corresponding specifications. **Please see Special Provisions for additional specifications.**