SCI ENGINEERING, INC.
EARTH • SCIENCE • SOLUTIONS
GEOTECHNICAL
ENVIRONMENTAL
NATURAL RESOURCES
CULTURAL RESOURCES
CONSTRUCTION SERVICES

August 6, 2024

Kimberly Butts, CPSM
Director of Purchasing
Pattonville School District
11097 St. Charles Rock Road
St. Ann, Missouri 63074-1509

RE: Lead in Drinking Water Report
Print Shop
Harding Avenue
Maryland Heights, Missouri
SCI No. 2024-0848.2T

Dear Kimberly Butts:

INTRODUCTION

SCI Engineering, Inc. (SCI) is pleased to submit this report summarizing lead in drinking water sampling activities performed on July 10, 2024. The purpose of the sampling activities was to screen for elevated levels of lead in the drinking water at potable water sources throughout the above-referenced structure.

The drinking water survey is intended to satisfy the requirements for the "Get the Lead Out of School Drinking Water Act" (GTLOSDWA), Section 160.077 administered by the Missouri Department of Health and Senior Services. Potable water sources to be tested were identified by the school district prior to SCI's field activities.

LIMITATIONS

SCI's sampling activities were limited to locations identified by the school district, which can be found in the attached Water Sources List. SCI's sampling locations are detailed in the attached Field Sheets. Some water fixtures could not be sampled due to field conditions, faulty equipment, or the inability to locate fixtures in the field. If any additional potable water sources need testing, please contact SCI, and we will make arrangements for sampling these fixtures. Potable water sources that were not sampled will need a sign placed near each fixture informing students and faculty it is not to be used as a drinking water source.

DRINKING WATER SURVEY

SCI collected "first draw" samples which consisted of collecting a water sample from each fixture or sample location after it remained stagnant for at least eight hours. Prior to sampling, SCI first mobilized to the site to flush the identified potable water fixtures throughout the structure. Once each fixture was flushed, a sign was placed on the fixture indicating it should not be used. SCI then revisited the site, after a minimum of eight hours, to collect water samples from the fixtures.

SCI collected 3 drinking water samples (PS-1 through PS-3) from various water fixtures located throughout the structure and submitted them for analytical testing. The drinking water samples were analyzed for total lead by U.S. EPA Method 200.8. SCI collected a minimum of 250 milliliters of water from each location. Sampled water was containerized in laboratory-provided sample containers and shipped to the lab using standard chain-of-custody procedures.

The drinking water samples were analyzed for lead in accordance with the GTLOSDWA, Section 160.077, which establishes an action level (AL) of 5 parts per billion (ppb). The drinking water sample which exceeded the AL is identified in Table 1, below. A copy of the analytical test results and chain-of-custody for all samples is enclosed.

Table 1 – Lead in Drinking Water Results

Sample Number	Sample Location	Sample Description	Result (ppb)
PS-3	Kitchen	Drinking Fountain	26.7

CONCLUSION AND RECOMMENDATIONS

As can be seen in Table 1, above, 1 drinking water sample exceeded the AL. SCI recommends any fixture which exceeds the AL be taken out of service until remediated and follow up testing indicates results less than the AL. Alternatively, if a water fixture is determined not to be a potable drinking water source, signage may be installed indicating the purpose and/or restrictions of the fixture.

According to GTLOSDWA, any water fixtures which exceed the AL shall be remediated prior to August 1, 2024, or the first day on which students will be present in the building, whichever is later. Any replacement fixture shall be lead free, as defined in 40 CFR 143.12.

REPORTING

Within seven business days after receiving this report, the school district shall contact parents and staff via written notification which shall include the following:

- The test results and a summary that explains such results;
- A description of any remedial steps taken;
- A description of general health effects of lead contamination and community specific resources; and
- If there is not enough water to meet the drinking water needs of the students, teachers and staff, bottled water shall be provided.

Additionally, within two weeks of receiving this report, the results and any lead remediation plans must be made available on the school's website.

This report, and subsequent annual testing reports, must be submitted to the Missouri Department of Health and Senior Services, Healthy Drinking Water Unit, PO Box 570, Jefferson City, MO 65102-0570.

FUTURE TESTING

After the fixture identified in Table 1, above, have been remediated, the fixture must be sampled annually. Once the fixture has been tested and is below the action level, the school shall test the potable drinking water fixtures once every five years.

SCI appreciates the opportunity to be of service to you on this project, and we look forward to working with you in the future. Please contact us if you have any questions or comments regarding the information provided.

Respectfully,

SCI ENGINEERING, INC.

Brian L. Lieb
Project Scientist

Jessica B. Keeven, CHMM
Senior Scientist

BLL/JBK/bms

Enclosures
Water Sources List
SCI Field Sheets
Lead Testing Results

\\Scistcfps01\Projects\2024\2024-0848 Pattonville R-III School District Water Lead Testing\ES\Print Shop\Print Shop-Lead in Drinking Water Rpt.doc