Request for quotes

Surveillance camera purchase and installation

Craven County School System

No equipment substitutions are allowed for consideration

The Craven County School System is requesting quotes for the following surveillance camera work:

Havelock High School

101 Webb Boulevard

Havelock, NC 28532

- SCOPE OF WORK
  - Havelock High School
    - Salient VMS install with clean, point, focus and label all cameras properly. 51 existing cameras total, combination of IP and analogue. Would require decoders to convert analogue cameras to IP (site visit and evaluation needed).
    - Install a new Salient VMS server with RAID 5 storage. Server is built for 4MP resolution, 30 days retention, 15fps dual stream recording. with 25% growth factored in.
    - Once the new server is online, confirm camera locations to verify functionality, map out, clean, point, focus, and label cameras as needed for optimal viewing and to put the cameras in proper viewing order on the new server.
    - Will require a site visit.

New Bern High School

4200 Academic Drive

New Bern, NC 28562

- SCOPE OF WORK
  - New Bern High School
    - Salient VMS install with clean, point, focus and label all cameras properly. 67 existing cameras total, combination of IP and analogue. Would require decoders to convert analogue cameras to IP (site visit and evaluation needed).
    - Install a new Salient VMS server with RAID 5 storage. Server is built for 4MP resolution, 30 days retention, 15fps dual stream recording. with 25% growth factored in.
    - Once the new server is online, confirm camera locations to verify functionality, map out, clean, point, focus, and label cameras as needed for optimal viewing and to put the cameras in proper viewing order on the new server.
    - Will require a site visit.

West Craven High School

2600 Streets Ferry Road

Vanceboro, NC 28586

- SCOPE OF WORK
  - West Craven High School
    - Salient VMS install with clean, point, focus and label all cameras properly. 50 existing cameras total, combination of IP and analogue. Would require decoders to convert analogue cameras to IP (site visit and evaluation needed).
    - Install a new Salient VMS server with RAID 5 storage. Server built for 4MP resolution, 30 days retention, 15fps dual stream recording. with 25% growth factored in.
    - Once the new server is online, confirm camera locations to verify functionality, map out, clean, point, focus, and label cameras as needed for optimal viewing and to put the cameras in proper viewing order on the new server.
    - Will require a site visit.

West Craven Middle School

515 NW Craven Middle School Road

New Bern, NC 28562

- SCOPE OF WORK
  - West Craven Middle
    - Salient VMS install with clean, point, focus and label all cameras properly. 35 existing cameras total, combination of IP and analogue. Would require decoders to convert analogue cameras to IP (site visit and evaluation needed).

- Install a new Salient VMS server with RAID 5 storage. Server built for 4MP resolution, 30 days retention, 15fps dual stream recording. with 25% growth factored in. Once the new server is online, confirm camera locations to verify functionality, map out, clean, point, focus, and label cameras as needed for optimal viewing and to put the cameras in proper viewing order on the new server.
- Will require a site visit.

Please submit all quotes to:

Nick Lucas

Director of Security and

Emergency Management

Craven County Schools

Nick.lucas@cravenk12.org

Please put ***"Craven County Schools Camera Quote"*** in email header.

********Deadline for quote submission is 5:00 PM, October 15, 2024. ********