

LONGVIEW SCHOOL DISTRICT MARK MORRIS HIGH SCHOOL - CHILLER REPLACEMENT

NOVEMBER 01, 2024

**SECTION 000107
SEALS PAGE – MECHANICAL**

1.01 MECHANICAL ENGINEER

- A. Company Name: Windsor Engineers
 - 1. Address Line 1: 27300 NE 10th Ave
 - 2. City: Ridgefield
 - 3. State: Washington
 - 4. Zip Code: 98642
 - 5. Telephone: (360) 610-4931

1.02 SECTIONS INCLUDED UNDER THIS SEAL

- A. 230529 - Hangers and Supports for HVAC Piping and Equipment
- B. 230548 - Vibration and Seismic Controls for HVAC
- C. 230553 - Identification for HVAC Piping and Equipment
- D. 230593 - Testing, Adjusting, and Balancing for HVAC
- E. 230719 - HVAC Piping Insulation
- F. 230800 - Commissioning of HVAC
- G. 230913 - Instrumentation and Control Devices for HVAC
- H. 232113 - Hydronic Piping
- I. 232114 - Hydronic Specialties
- J. 232123 - Hydronic Pumps
- K. 233416 - Centrifugal HVAC Fans
- L. 236433 - Modular Water Chillers
- M. 238216 - Air Coils

1.03 SEAL



END OF SECTION

**SECTION 000107
SEALS PAGE – ELECTRICAL**

1.01 ELECTRICAL ENGINEER

- A. Company Name: Windsor Engineers
 - 1. Address Line 1: 27300 NE 10th Ave
 - 2. City: Ridgefield
 - 3. State: Washington
 - 4. Zip Code: 98642
 - 5. Telephone: (360) 610-4931

1.02 SECTIONS INCLUDED UNDER THIS SEAL

- A. 260505 - Selective Demolition for Electrical
- B. 260519 - Low-Voltage Electrical Power Conductors and Cables
- C. 260526 - Grounding and Bonding for Electrical Systems
- D. 260529 - Hangers and Supports for Electrical Systems
- E. 260533.13 - Conduit for Electrical Systems
- F. 260553 - Identification for Electrical Systems
- G. 262200 - Low-Voltage Transformers
- H. 262813 - Fuses
- I. 262816.16 - Enclosed Switches

1.03 SEAL



END OF SECTION

**SECTION 000110
TABLE OF CONTENTS**

PROCUREMENT AND CONTRACTING REQUIREMENTS

1.01 DIVISION 00 -- PROCUREMENT AND CONTRACTING REQUIREMENTS

- A. 000107 - Seals Page
- B. 000110 - Table of Contents
- C. Longview School District Notice to Bidders
- D. Advertisement for Bids
- E. Instructions to Bidders
- F. Bid Form
- G. Attestation Form
- H. Public Works Contract Agreement
- I. General Conditions

SPECIFICATIONS

2.01 DIVISION 01 -- GENERAL REQUIREMENTS

- A. 011000 - Summary
- B. 012000 - Price and Payment Procedures
- C. 012200 - Unit Prices
- D. 012500 - Substitution Procedures
- E. 013000 - Administrative Requirements
- F. 014000 - Quality Requirements
- G. 015000 - Temporary Facilities and Controls
- H. 016000 - Product Requirements
- I. 017000 - Execution and Closeout Requirements
- J. 017800 - Closeout Submittals

2.02 DIVISION 23 -- HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC)

- A. 230529 - Hangers and Supports for HVAC Piping and Equipment
- B. 230548 - Vibration and Seismic Controls for HVAC
- C. 230553 - Identification for HVAC Piping and Equipment
- D. 230593 - Testing, Adjusting, and Balancing for HVAC
- E. 230719 - HVAC Piping Insulation
- F. 230800 - Commissioning of HVAC
- G. 230913 - Instrumentation and Control Devices for HVAC
- H. 232113 - Hydronic Piping
- I. 232114 - Hydronic Specialties
- J. 232123 - Hydronic Pumps
- K. 233416 - Centrifugal HVAC Fans
- L. 236433 - Modular Water Chillers
- M. 238216 - Air Coils

2.03 DIVISION 26 -- ELECTRICAL

- A. 260505 - Selective Demolition for Electrical

- B. 260519 - Low-Voltage Electrical Power Conductors and Cables
- C. 260526 - Grounding and Bonding for Electrical Systems
- D. 260529 - Hangers and Supports for Electrical Systems
- E. 260533.13 - Conduit for Electrical Systems
- F. 260553 - Identification for Electrical Systems
- G. 262200 - Low-Voltage Transformers
- H. 262813 - Fuses
- I. 262816.16 - Enclosed Switches

2.04 DIVISION 32 – EXTERIOR IMPROVEMENTS

- A. 323113 – Chain Link Fences and Gates

END OF SECTION

LONGVIEW SCHOOL DISTRICT NO. 122

ALL THOSE PROVIDING BIDS – PLEASE READ THIS NOTICE

The Longview School District occasionally experiences problems with contractors who, after being awarded a bid, indicated they have made an error or have some other difficulty and do not intend to honor their bid. For this reason we want all contractors to be fully aware of the district's position with regard to the bidding process and the honoring of bids submitted.

State of Washington statutes require the Longview School District to go through a prescribed bidding process on all purchases over defined dollar limits. The district takes the bidding process seriously and its intent is to solicit bids that are accurate and that each contractor intends to honor. bidding contractor you are expected to submit bids that are accurate, complete, and contain all terms and conditions which you feel are necessary. If you find changes to your bid are necessary after you have submitted it to the district, the following guidelines will control.

- I. Bids may be changed in any way or withdrawn any time up to the time and date of bid submittal.
- II. AFTER THE TIME AND DATE OF THE BID SUBMITTAL, Bids cannot be changed. If accepted, the bid is considered to be a binding contract that you as the contractor will be expected to honor.
- III. A recap of the bids will be sent to all bidders after official acceptance by the School Board.

ADVERTISEMENT FOR BID

Bids will be accepted for the following project:

PROJECT NO.: 24052

TITLE: Longview School District
Chiller Replacement Project at Mark Morris High School

AGENCY: Longview School District No. 122

SUBMITTAL TIME/DATE/LOCATION: **Prior to 2:00 PM, Monday, December 2nd, 2024.**
Bids will be accepted at:
Longview School District MOTF Office
2080 38th Avenue
Longview, WA 98632

BY: Longview School District No. 122

PRE-PROPOSAL WALK-THROUGHS: **10:00 AM, Friday, November 15th, 2024.**
Walk-through location will be at Mark Morris High School,
1602 Mark Morris Ct, Longview, WA 98632. Meet near
the Dick Mealy Pool in the back parking lot.
Attendance at the Pre-Proposal Walk-through is
Mandatory for bidders.

The School District will make the plans available for contractors to view online without charge at:

<https://www.longviewschools.com/departments/business-services/bids-proposals>

Contact Information

If you have any questions throughout the process please contact the appropriate person at MOTF:

Bid Related Questions:

Barbara Howe
Maintenance Secretary
360-575-7852
Email - bhowe@longview.k12.wa.us

Project Related Questions:

Jason Reetz
Facilities Manager
360-575-7887
Email – jreetz@longview.k12.wa.us

ADVERTISEMENT FOR BID

Elegibility: This procurement is open to those individuals or organizations that satisfy the minimum qualifications stated herein and that are available and licensed for work in Washington State. This is a competitive bid public works project and will require a retainage (5%) and payment of prevailing wages.

Project Timeline: Commence project on or after December 03, 2024. Complete all work by August 22, 2025.

Estimated Project Schedule:

Pre-Proposal Walk-Through:	November 15, 2024
Bids Due:	December 02, 2024
Notice of Intent to Award:	December 03, 2024
Submittals for Chiller (provided by contractor for approval):	December 17, 2024
Engineers Submittal Response:	December 20, 2024
Procure Chiller:	December 30, 2024
Construction Start:	June 16, 2025
Construction Completion:	August 22, 2025

The District reserves the right to revise the above schedule.

No contractor may withdraw his bid after the hour and date set for the submittal thereof, or thereafter, before award of the Contract, unless award is delayed for a period exceeding thirty (30) days from the proposal submittal date.

The Owner reserves the right to accept or reject any or all proposals and to waive informalities.

INSTRUCTIONS TO BIDDERS

1.01 DEFINITIONS

- A. All definitions set forth in the General Conditions of the Contract for Construction or in other Contract Documents are applicable to the Bidding Documents.
- B. "**Addenda**" are written or graphic instruments issued by the Longview School District prior to the execution of the Contract which modify or interpret the Bidding Documents by additions, deletions, clarifications or corrections. The contents of Addenda are issued in no particular order and therefore should be carefully and completely reviewed. Addenda relating to administrative matters, such as, for example, the date or time of meetings or Bid receipt, may be issued in writing by fax, mail or other delivery.
- C. An "**Alternate Bid**" (or "**Alternate**") is an amount stated in the Bid to be added to or deducted from the amount of the Base Bid if the corresponding change in the Work, as described in the Bidding Documents, is accepted.
- D. "**Award**" means the formal decision by the Longview School District notifying a Bidder with the lowest Responsive Bid of the Longview School District's acceptance of the Bid and intent to enter into a contract with the Bidder.
- E. The "**Award Requirements**" include the following statutory requirements as a condition precedent to Award. The lowest Responsive Bidder shall:
- (1) have a certificate of registration in compliance with RCW 18.27;
 - (2) have a current state unified business identifier number;
 - (3) if applicable, have industrial insurance coverage for the Bidder's employees working in Washington as required in Title 51 RCW;
 - (4) have an employment security department number as required in Title 50 RCW;
 - (5) have a state excise tax registration number as required in Title 82 RCW;
 - (6) not be disqualified from bidding on any public works contract under RCW 39.06.010 (unregistered or unlicensed contractors) or RCW 39.12.065(3) (prevailing wage violations); and
 - (7) If bidding on a public works project subject to the apprenticeship utilization requirements in RCW 39.04.320, not have been found out of compliance by the Washington state apprenticeship and training council for working apprentices out of ratio, without appropriate supervision, or outside their approved work processes as outlined in their standards of apprenticeship under RCW 49.04 for the one-year period immediately preceding the date of the Bid solicitation.
- F. The "**Base Bid**" is the sum stated in the Bid for which the Bidder offers to perform the Work described in the Bidding Documents as the base to which work may be added or from which work may be deleted for sums stated in Alternate Bids.

- G. A "**Bid**" is a complete and properly signed proposal to do the Work or designated portion thereof, submitted in accordance with the Bidding Documents, for the sums therein stipulated and supported by any data called for by the Bidding Documents.
- H. A "**Bidder**" is a person or entity who submits a Bid for a prime contract with the Longview School District for the Work described in the proposed Contract Documents.
- I. The "**Bidding Documents**" include the Advertisement or Invitation to Bid, Instructions to Bidders, the Bid form, any other sample bidding and contract forms, the Bid Bond, and the proposed Contract Documents, including any Addenda issued prior to receipt of Bids.
- J. The "**Contract Documents**" proposed for the Work consist of the Agreement Between Owner and Contractor, the General Conditions of the Contract (as well as any Supplemental, Special or other Conditions included in the Project Manual), the Drawings, the Specifications, and all Addenda issued prior to, and all modifications issued after, execution of the Contract.
- K. To be considered "**Responsible**" or meet "**Responsibility**" requirements, a Bidder must meet the following supplemental criteria applicable to this Project to the satisfaction of the Longview School District:
- (1) The ability, capacity, and skill to perform the Contract;
 - (2) The character, integrity, reputation, judgment, experience, and efficiency of the Bidder;
 - (3) Whether the Bidder can perform the Contract within the time specified;
 - (4) The previous and existing compliance by the Bidder with laws relating to the Contract;
 - (5) The quality of performance of previous contracts, including demonstration of successful completion of similar projects in the last three (3) years;
 - (6) The designated Project Manager shall have a minimum of three (3) years of successful experience in project management and scheduling of projects of similar scope and complexity;
 - (7) The designated Superintendent shall have a minimum of five (5) years of successful supervision of projects of similar scope and complexity;
 - (8) Any other qualifications required by the Contract Documents or Bidding Documents; and
 - (9) Such other information as may be secured having a bearing on the decision to award the contract.
- L. A "**Sub-bidder**" is a person or entity who submits a bid to a Bidder for materials, equipment or labor for a portion of the Work.
- M. A "**Unit Price**" is an amount stated in the Bid as a price per unit of measurement for materials, equipment or services as described in the Bidding Documents or in the proposed Contract Documents. The Longview School District reserves the right to reject at any time, without impairing the balance of the proposal, any or all such predetermined unit prices.

1.2 BIDDER'S REPRESENTATIONS

By making its Bid, each Bidder represents that:

- A. BIDDING DOCUMENTS. The Bidder has read and understands the Bidding Documents, and its Bid is made in accordance with them.
- B. POSSIBLE SELF-PERFORMED WORK REQUIREMENT. The Bidder will perform *with its own forces* at least that percentage (if any) of the Work required by the Bidding Documents or the Contract Documents.
- C. PRE-BID MEETING. The Bidder has attended the pre-bid meeting(s) required by the Bidding Documents. The Project site is available for inspection for prospective bidders at a mandatory pre-bid site meeting and walk-through, as indicated in the Advertisement for Bids, and existing conditions should be examined. NOTE: THE INDIVIDUAL REPRESENTING THE GENERAL CONTRACTOR AT THE MANDATORY PRE-BID MEETING SHALL BE AN OFFICER OR OWNER OF THE COMPANY AND HAVE THE OFFICIAL CAPACITY TO BE A DULY AUTHORIZED REPRESENTATIVE OF THE COMPANY.
- D. BASIS. Its Bid is based upon the materials, systems, services, and equipment required by the Bidding Documents, without exception.
- E. EXAMINATION. The Bidder has carefully examined and understands the Bidding Documents, the Contract Documents (including, without limitation, any liquidated damages and insurance provisions), and the Project site, including any existing buildings, it has familiarized itself with the local conditions under which the Work is to be performed and has correlated its observations with the requirements of the proposed Contract Documents and it has satisfied itself as to the nature, location, character, quality and quantity of the Work, the labor, materials, equipment, goods, supplies, work, services and other items to be furnished, and all other requirements of the Contract Documents. The Bidder has also satisfied itself as to the conditions and other matters that may be encountered at the Project site or affect performance of the Work or the cost or difficulty thereof, including but not limited to those conditions and matters affecting: transportation, access, disposal, handling and storage of materials, equipment and other items; availability and quality of labor, water, electric power and utilities; availability and condition of roads; climatic conditions and seasons; physical conditions at the Project site and the surrounding locality; topography and ground surface conditions; and equipment and facilities needed preliminary to and at all times during the performance of the Work. The failure of the Bidder fully to acquaint itself with any applicable condition or matter shall not in any way relieve the Bidder from the responsibility for performing the Work in accordance with, and for the Contract Sum and within the Contract Time provided for in, the Contract Documents.
- F. PROJECT MANUAL. The Bidder has checked its copies of the Project Manual with the Table of Contents bound therein to ensure the Project Manual is complete.
- G. SEPARATE WORK. The Bidder has examined and coordinated all Drawings, Contract Documents, and Specifications for any other contracts to be awarded separately from, but in connection with, the Work being bid upon, so that the Bidder is fully informed as to conditions affecting the Work under the contract being bid upon.
- H. LICENSE REQUIREMENTS. Bidders and their proposed Subcontractors shall be registered and shall hold such licenses as may be required by the laws of Washington, including RCW 18.27, for the performance of the Work specified in the Contract Documents.

- I. NO EXCEPTIONS. Bids must be based upon the materials, systems and equipment described and required by the Bidding Documents, without exception.

1.3 BIDDING DOCUMENTS

A. COPIES

1. The School district will make the plans available for contractors to view online without charge at:
<https://longviewschools.comfbusiness-and-finance/bids-and-requests-for-proposal>.
2. **Sub-bidders.** Bidding Documents will not be issued directly to Sub-bidders or others unless specifically offered in the Advertisement or Invitation to Bid.
3. **Complete sets.** Bidders shall use complete sets of Bidding Documents in preparing Bids and are solely responsible for utilizing established plan holder identification processes to obtain updated bid information; the Longview School District does not assume any responsibility for errors or misinterpretations resulting from the use of incomplete and/or superseded sets of Bidding Documents. Printed copies of plans take precedence over any on-line images.
4. **Conditions.** The Longview School District makes copies of the Bidding Documents available on the above terms only for the purpose of obtaining Bids on the Work and do not confer a license or grant permission for any other use.
5. **Legible Documents.** To the extent any drawings, specifications, or other Bidding documents are not legible, it is the Bidder's responsibility to notify the Longview School District and to obtain legible documents from the plan center.

B. INTERPRETATION OR CORRECTION OF BIDDING DOCUMENTS

1. **Format.** The Contract Documents may be divided into parts, divisions, and sections for convenient organization and reference. Generally, there has been no attempt to divide the Specification sections into Work performed by the various building trades, any Work by separate contractors, or any Work required for separate facilities in or phases of the Project.
2. **Notify Owner.** Bidders and Sub-bidders shall promptly notify the Longview School District in writing of any ambiguity, inconsistency, or error that they may discover upon examination of the Bidding Documents or of the site and local conditions. All Bidders and Sub-bidders shall thoroughly familiarize themselves with specified products and installation procedures and submit to the Longview School District any objections (in writing) no later than seven (7) calendar days prior to the Bid Date. The submittal of the Bid constitutes acceptance of products and procedures specified as sufficient, adequate, and satisfactory for completion of the Contract.
3. **Written request.** Bidders and Sub-bidders requiring clarification or interpretation of the Bidding Documents shall make a written request which shall reach the Owner at least seven (7) calendar days prior to the date for receipt of Bids.

4. **Addenda.** Any interpretation, correction or change of the Bidding Documents will be made by written Addendum. Interpretations, corrections or changes of the Bidding Documents made in any other manner will not be binding, and Bidders shall not rely upon such interpretations, corrections and changes.
5. **Singular references.** Reference in the singular to an article, device, or piece of equipment shall include as many of such articles, devices, or pieces as are indicated in the Contract Documents or as are required to complete the installation.
6. **Utilities and runs.** The Bidder should assume that the exact locations of any underground or hidden utilities, underground fuel tanks, and any plumbing and electrical runs may be somewhat different from any location indicated in the surveys or Contract Documents.
7. **Division of Contract Documents.** The Contract Documents may be divided into parts, divisions, and sections for convenient organization and reference. Generally, there has been no attempt to divide the Specification sections into Work performed by the various building trades, any Work by separate contractors, or any Work required for separate facilities in of phases of the Project.

C. SUBSTITUTIONS

1. **Standard.** The materials, products, procedures and equipment described in the Bidding Documents establish a standard of required function, dimension, appearance, and quality that must be met by any proposed substitution.
2. **Substitution procedure.** No substitution will be considered prior to receipt of Bids unless the Owner receives a written request for approval on the Longview School District's Substitution Request form for the Project, with all data requested on the form completed, at least seven (7) days prior to the date for receipt of Bids. Each such request shall be submitted with a Request for Substitution form identical to or equivalent in content to the form found in the Project Manual, and shall include the name of the material or equipment proposed to be replaced and a complete description of the proposed substitute, including drawings, cuts, performance and test data, warranty information, and any other information necessary for an evaluation. A statement setting forth any changes in other materials, equipment or other Work that incorporation of the substitute would require shall be included. The proposer has the burden to prove the merit of the proposed substitute; by proposing the substitution, the Bidder represents that it has personally investigated the proposed material or product and determined that it is equal or better in all respects to that specified, that the same or better warranty will be provided for the substitution, that complete cost data, including all direct and indirect costs of any kind, has been presented, that the Contract Time will not be increased, and that it will coordinate the installation of the substitute if accepted and make all associated changes in the Work. The Owner's decision to approve or disapprove a proposed substitution shall be final. Written requests for approval shall constitute a guarantee by the Bidder that the articles or materials are in all respects, including warranty and installation, equal or superior to those specified, unless otherwise noted. To the extent the proposed substitution will require additional services by the Owner or its consultants after Bid award, the Bidder, if successful, will be required to pay the Owner or its consultants for these services at their customary hourly rates.
3. **Addendum.** If the Owner approves a proposed substitution prior to receipt of Bids, the approval will be set forth in a written Addendum. Bidders shall not rely upon approvals made in any other manner. Substitution request forms returned by the Owner are a courtesy only, and Bidders/Sub-bidders shall rely solely on substitution approvals listed in an Addenda.

4. **Post-Bid substitutions.** After the Contract has been executed, the Longview School District may consider a written request for the substitution of material or products in place of those specified in the Contract Documents only under exceptional circumstances as specified therein.

D. ADDENDA

1. **Written.** All Addenda will be written. They will be mailed, emailed, faxed, delivered, and/or posted electronically with notice to those the Owner knows to have received a complete set of Bidding Documents.
2. **Copies.** Copies of Addenda will be made available for inspection wherever Bidding Documents are on file for that purpose.
3. **Verification and acknowledgment of receipt.** Prior to bidding, each Bidder shall ascertain that it has received all Addenda issued. Each Bidder shall acknowledge its receipt of all Addenda in its Bid.

1.4 BIDDING PROCEDURE

A. FORM AND STYLE OF BIDS

1. **Form.** Bids (including any required attachments) shall be submitted on forms identical to the form included with the Bidding Documents. No oral, email, or telephonic responses or modifications will be considered to be Bids.
2. **Entries on the Bid form.** All blanks on the Bid form shall be filled in by typewriter or manually in ink.
3. **Words and figures.** Where so indicated by the makeup of the Bid form, sums shall be expressed in both words and figures; in case of discrepancy between the two, *the amount written in figures shall govern and the words shall be used to determine any ambiguities in the figures.* Portions of the Bid form may require the addition of component bids to a total or the identification of component amounts within a total. In case of discrepancy between component amounts listed and their sum(s), the component amounts listed shall govern.
4. **Initial changes.** Any interlineation, alteration or erasure must be initialed by an authorized representative of the Bidder.
5. **Alternates and Unit Prices.** All requested Alternates and unit prices should be bid. The Longview School District reserves the right, but is not obligated, to reject any Bid on which all requested Alternates or unit prices are not bid. If no change in the Base Bid is required for an Alternate, enter "*No Change.*" If there is no entry, it will be presumed that the Bidder has made no offer to accomplish this Alternate. If it is not otherwise clear from the Bid or nature of the Alternate, it will be presumed that the amount listed for an Alternate is an add rather than a deduct.
6. **No conditions.** The Bidder shall make no conditions or stipulations on the Bid form nor qualify its Bid in any other manner.
7. **Identity of Bidder.** The Bidder shall include in the specified location on the Bid form the legal name of the Bidder and, if requested, a description of the Bidder as a sole proprietor, a partnership, a joint venture, a corporation (including the state of incorporation), or another described form of legal entity. The Bid shall be signed by the person or persons legally

authorized to bind the Bidder to a contract. A Bid submitted by an agent shall have a current power of attorney attached certifying the agent's authority to bind the Bidder, and provide other information requested.

8. Bid amounts do not include sales tax. The Bid shall include in the sum stated all taxes imposed by law, EXCEPT STATE AND LOCAL SALES TAX ON THE CONTRACT SUM.
9. Bid breakdown. The Bid form may contain, for the Longview School District's accounting purposes only, a breakdown of some or all of the components included in the Base Bid.

B . POTENTIAL LISTING OF SUBCONTRACTORS

1. Procedure. On certain projects of the Longview School District, the Bid form includes a requirement that certain Subcontractors be listed, and the list must be submitted to the Longview School District. In these circumstances, the Bidder must name the Subcontractor with whom the Bidder, if awarded the Contract, will subcontract *directly* (i.e., not lower-tier Subcontractors) for performance of the work of:

- (a) HVAC (heating, ventilation and air conditioning),
- (b) plumbing as described in RCW 18.106,
- (c) electrical work as described in RCW 19.28, and
- (d) any other categories of Work listed on the Subcontractor listing form.

SELF-PERFORMANCE: If the Bidder intends to self-perform any of these categories of Work, it must name itself for each such category of Work.

IF NO SUBCONTRACTORS: If there is no work to be performed by a HVAC, plumbing, electrical, or other subcontractor category identified on the Bid form, the Bidder should insert "None" or "N/A" on the Bid form. If a category is left blank, that shall indicate that the Bidder believes that there is no work to be performed by that trade.

MULTIPLE ENTRIES: The Bidder shall not list more than one (1) entity for a particular category of Work identified, unless a Subcontractor varies with an Alternate Bid, in which case the Bidder shall identify the Subcontractor to be used for the Alternate and the affected portion of the Work and otherwise make its Bid clear as to which subcontractor shall be utilized depending upon the selection of alternates.

MULTIPLE SUBMITTAL TIMES. In the event the Bidding Documents call for a second submittal time for receipt of alternate bids, and no additional Subcontractors are listed with such alternate bids, the Longview School District will consider that there is no change in the Subcontractors from those listed with the base Bid.

2. Failure to Submit. In accordance with RCW 39.30.060, failure of a Bidder to submit as part of the Bid the names of such proposed heating, ventilation and air conditioning, plumbing, and electrical Subcontractors or to name itself to perform such Work or the naming of two or more Subcontractors to perform the same Work shall render the Bidder's Bid nonresponsive and, therefore, void.
3. Requirement to Subcontract. The Bidder, if awarded the Contract, will subcontract with the listed Subcontractor for performance of the portion of the Work designated on the Form

of Proposal, subject to the provisions of the Contract for Construction and RCW 39.30.060. The Bidder shall not substitute a listed Subcontractor in furtherance of bid shopping or bid peddling.

4. **Replacement.** If a listed Subcontractor is unable to comply with any bondability, qualification, or other requirements of the Contract or Bidding Documents (including without limitation a finding of Subcontractor non-Responsibility), the Longview School District may require the Bidder to replace the Subcontractor with a Subcontractor acceptable to the Longview School District at no change in the Contract Sum or Contract Time.
5. **Subcontractor Standards.** Subcontractors shall meet contractual and technical qualifications standards, and provide specialized certification, licensing, and/or payment and performance bonding where specified.

C. BID SECURITY

1. **Purpose and procedure.** Each Bid shall be accompanied by a bid security payable to the Longview School District in the form required in the Bidding Documents and equal to five percent (5%) of the Base Bid. The bid security constitutes a pledge that the Bidder will enter into the Contract with the Longview School District in the form provided, in a timely manner, and on the terms stated in its Bid and will furnish in a timely manner the payment and performance bonds, certificates of insurance, Contractor's Construction Schedule, and all other documents required in the Contract Documents. Should the Bidder fail or refuse to enter into the Contract or fail to furnish such documents, the amount of the bid security shall be forfeited to the Longview School District as liquidated damages, not as a penalty. By submitting its Bid and bid security, the Bidder agrees that any forfeiture is a reasonable prediction at the time of Bid submittal of future damages to the Longview School District.
2. **Form.** The bid security shall be in the form of a certified or bank cashier's check payable to the Longview School District or a bid bond executed by a bonding company acceptable to the Longview School District and licensed in the State of Washington on the form included with the Bidding Documents or on an acceptable and equivalent form. The Attorney-in-Fact who executes the bond on behalf of the surety shall be licensed to do business in the State of Washington and shall affix to the bond a certified and current copy of his/her Power of Attorney.
3. **Retaining Bid Security.** The Longview School District will have the right to retain the Bid Security of Bidders to whom an award is being considered until the earliest of either (a) the Contract has been executed, and payment and performance bonds have been furnished, or (b) the specified time has elapsed so that Bids may be withdrawn, or (c) all Bids have been rejected.
4. **Return of Bid Security.** Within forty-five (45) days after the Bid Date, the Longview School District will release or return Bid securities to Bidders whose Bids are not to be further considered in awarding the Contract. Bid securities of the three apparent low Bidders will be held until the Contract has been finally executed, after which all unforfeited Bid securities will be returned.

D. SUBMISSION OF BIDS

1. **Procedure.** The Bid, the Bid security, and any other documents required to be submitted with the Bid shall be enclosed in a sealed opaque envelope. The envelope shall be addressed to the party specified in the Advertisement or Invitation to Bidders and shall be identified with the Project name, the Bidder's name and address and, if applicable, the designated

portion of the Work for which the Bid is submitted. If the Bid is sent by mail the sealed envelope shall be enclosed in a separate mailing envelope with the notation "*SEALED BID ENCLOSED*" on the face thereof.

2. **Deposit.** Bids shall be deposited at the designated location prior to the time and date for receipt of Bids indicated in the Advertisement or Invitation to Bid, or any extension thereof made by Addendum. Bids received after the time and date for receipt of Bids may be returned unopened at the discretion of the Longview School District.
3. **Responsibility.** The Bidder assumes full responsibility for timely delivery at the location designated for receipt of Bids.
4. **Form.** Oral, fax, telephonic, email, electronic, or telegraphic Bids are invalid and will not be considered.

E. MODIFICATION OR WITHDRAWAL OF BID

1. **After receipt time.** A Bid may not be modified, withdrawn or canceled by the Bidder during a forty-five (45) day period following the time and date designated for the receipt of Bids, and each Bidder so agrees by virtue of submitting its Bid.
2. **Before receipt time.** Prior to the time and date designated for receipt of Bids, any Bid submitted may be modified or withdrawn only by notice to the party receiving Bids at the place designated for receipt of Bids. Such notice shall be in writing over the signature of the Bidder or by telegram or fax; if by telegram or fax, written confirmation over the signature of the Bidder shall be mailed and postmarked on or before the date and time set for receipt of Bids. The notice shall be worded so as not to reveal the amount of the original Bid. E-Mail notice will not be considered. It shall be the Bidder's sole responsibility to verify that the notice has been received by the Longview School District in time to be withdrawn before the Bid opening.
3. **Resubmittal.** Withdrawn Bids may be resubmitted up to the time designated for the receipt of Bids provided that they are then fully in conformance with these Instructions to Bidders.
4. **Bid security with resubmission.** Bid security shall be in an amount sufficient for the Bid as modified or resubmitted.

F. NOTICE

1. Notice or a request from a Bidder under these Instructions to Bidders must be in writing over the signature of the Bidder and delivered in person or by mail, express delivery, telegram or fax. If the notice is by telegram or fax, written confirmation over the signature of the Bidder must be mailed and postmarked on or before the date and time set for the notice.

1.5 CONSIDERATION OF BIDS

- A. OPENING OF BIDS: Unless stated otherwise in the Advertisement or Invitation to Bid or any Addendum, the properly identified Bids received on time will be opened publicly and will be read aloud. An abstract of the Base Bids and Alternate Bids, if any, will be made available to Bidders and other interested parties.

- B. **REJECTION OF BIDS:** The Longview School District shall have the right but not the obligation to reject any or all Bids for any reason or for no reason, to reject a Bid not accompanied by required Bid security or by other material or data required by the Bidding Documents, or to reject a Bid which is in any way incomplete or irregular.

C. **ACCEPTANCE OF BID (AWARD)**

1. **Owner.** The Longview School District intends (but is not bound) to award a Contract to the lowest Responsible and Responsive Bidder, provided the Bid has been submitted in accordance with the requirements of the Bidding Documents and does not exceed the funds available. The Longview School District has the right to waive any informality or irregularity in any Bid(s) received and to accept the Bid which, in its judgment, is in its own best interests.
2. **Alternates.** The Longview School District shall have the right to accept Alternates in any order or combination, unless otherwise specifically provided in the Contract Documents or Bidding Documents, and to determine the low Bidder on the basis of the sum of the Base Bid and the Alternates (if any) accepted. The Longview School District retains the right to accept Alternate Bid items at the price bid within 45 days after the Agreement is executed.
3. **Requirements for Award.** Before the Award, the lowest Responsive Bidder shall meet the Award Requirements.

D. **BID PROTEST PROCEDURES**

1. **Procedure.** A Bidder protesting for any reason the Bidding Documents, a bidding procedure, the Longview School District's objection to the Bidder or a person or entity proposed by the Bidder, including but not limited to a finding of non-Responsibility, the award of the Contract or any other aspect arising from or relating in any way to the bidding shall cause a written protest to be filed with the Longview School District within two (2) business days of the event giving rise to the protest and, in any event, no later than two (2) business days after the date upon which Bids are opened. (Intermediate Saturdays, Sundays, and legal holidays are not counted.) The written protest shall include the name of the protesting Bidder, a detailed description of the specific factual and legal grounds for the protest, copies of all supporting documents, and the specific relief requested. The written protest shall be delivered to:

Patti Bowen
Director of Business Services
Longview School District
2715 Lilac Street
Longview, WA 98632

2. **Consideration.** Upon receipt of the written protest, the Longview School District will consider the protest. The Longview School District may, within three (3) business days of the Longview School District's receipt of the protest, provide any other affected Bidder(s) the opportunity to respond in writing to the protest. If the protest is not resolved by mutual agreement of the protesting Bidder and the Longview School District, the Superintendent of the Longview School District or his or her designee will review the issues and promptly furnish a final and binding written decision to the protesting Bidder and any other affected Bidder(s) within six (6) business days of the Longview School District's receipt of the protest. (If more than one (1) protest is filed, the Longview School District's decision will be provided within six (6) business days of the Longview School District's receipt of the last protest.) If no reply is received from the Longview School District during the six (6) business-day period, the protest shall be deemed rejected.

3. **Waiver.** Failure to comply with these protest procedures will render a protest waived.
4. **Condition precedent.** Timely and proper compliance with and exhaustion of these protest procedures shall be a condition precedent to any otherwise permissible judicial consideration of a protest.

1.6 POSTBID INFORMATION

A. INFORMATION FROM APPARENT LOW BIDDER

1. **Submittal.** Within twenty-four (24) hours of the Owner's request, the apparent low Bidder and any other Bidders so requested shall submit to the Longview School District:
 - (a) submit additional information regarding the use of their own forces and the use of subcontractors and suppliers;
 - (b) a properly executed Contractor's Qualification Statement on the form provided (unless otherwise required to be submitted at the time of the Bid);
 - (c) a letter or form from the Bidder's insurance company stating that the insurance required by the Contract Documents will become effective upon execution of the Contract;
 - (d) a letter or form from the Bidder's surety stating that the bond(s) required by the Contract Documents will become effective upon execution of the Contract;
 - (e) if requested by the Longview School District, a detailed breakdown of the Bid in a form acceptable to the Longview School District;
 - (f) the names of the persons or entities (including a designation of the Work to be performed with the Contractor's own forces, and the names of those who are to furnish materials or equipment fabricated to a special design) proposed for each of the principal portions of the Work;
 - (g) the proprietary names and the suppliers of the principal items or systems of materials and equipment proposed for the Work; and
 - (h) a State Board of Education Form D-9, if requested.

Failure to provide any of the above information in a timely manner may constitute an event of breach permitting forfeiture of the Bid security.

2. **Responsibility.** The Bidder will be required to establish to the satisfaction of the Owner and the Longview School District the reliability and Responsibility of the persons or entities proposed to furnish and perform the Work described in the Bidding Documents as well as qualifications set forth in the Sections of the Project Manual pertaining to such proposed Subcontractor's respective trades. The Responsibility of the Bidder may be judged in part by the Responsibility of these proposed entities. The following will be considered:
 - The ability, capacity, and skill to perform the contract;
 - The character, integrity, reputation, judgment, experience, and efficiency of the Bidder;
 - Whether the Bidder can perform the contract within the time specified;
 - The quality of performance of previous contracts;

- The previous and existing compliance by the Bidder with laws relating to the contract; and
- Such other information as may be secured having a bearing on the decision to award the contract.

CONSIDERATION. In considering a Bidder's Responsibility, a Bidder shall be deemed to be unqualified to perform the Contract if, after review and verification of the representations included upon the Contractor's Qualification Statement submitted by the Bidder, conditions such as, but not limited to, the following appear:

(a) The Bidder does not have sufficient prior experience (or an acceptable substitute thereof, as described below) with projects of a similar nature in technical, managerial, and financial requirements to that in the present Contract being bid. In addition to such established contractors, a newly established contractor may be considered qualified if it has shown on the Contractor's Qualification Statement that it is staffed with sufficient technical, managerial, and financial personnel with prior experience in the nature of construction for which the Bids are invited.

(b) The Bidder does not have sufficient capability to undertake the obligations of the Contract. A determination will be made when the Longview School District's review of the probable cash flow needs of the Bidder for this Project (including payroll, cost of material and supplies, equipment rental costs, and any other direct or incidental costs of the Contract), concludes that the Bidder does not have sufficient financial resources to enable it to satisfy its financial obligations under the Contract.

(c) The Bidder has submitted unrealistic unit prices as determined by other Bidders' unit prices for this Project.

(d) The Bidder does not have sufficient staff, equipment, or plant available to perform the Contract. The Longview School District's determination in this matter will be based upon that represented by Bidder in the Contractor's Qualification Statement.

(e) The Bidder has a history of unsatisfactory performance of contracts of this or similar nature, regardless of whether such contracts existed between the Longview School District and the Bidder, or other parties and the Contractor.

- A determination of this nature will be made if the Longview School District, after review of the Bidder previous work experience, determines that the Bidder's unsatisfactory performance has resulted predominantly from the Bidder's failure rather than a failure to perform by another party. The School District will give the Contractor an opportunity to explain such nonperformance's before any final determination is reached.
- A determination of failure to perform will be made if the Longview School District is satisfied after review of the Bidder's prior experience, that the Bidder has repeatedly failed to satisfy its obligations under past contracts and the School District cannot safely assume satisfactory performance of the Contract by the Bidder.
- In reaching its determination, the Longview School District may consider statements of other parties to the prior unperformed contracts, as well as the representations of the Bidder on its Contractor's Qualification Statement.

3. **Subcontractors.** The Responsibility of the Bidder may be judged in part by the Responsibility of its Subcontractors. Bidders must verify Responsibility criteria for each first-tier Subcontractor. A Subcontractor of any tier that hires other Subcontractors must verify Responsibility criteria for each of its lower-tier Subcontractors. Verification shall include that each Subcontractor, at the time of subcontract execution, is Responsible and

possesses an electrical contractor license, if required by RCW 19.28, or an elevator contractor license, if required by RCW 70.87, and can obtain any payment and performance bonds required of the Bidding or Contract Documents.

4. **Request to Modify Criteria.** No later than ten (10) days prior to the Bid Date, a potential Bidder may request in writing that the Longview School District modify the Responsibility criteria listed in clause (2) above or elsewhere in the Contract Documents or the Bidding Documents. The Longview School District will evaluate the information submitted by the potential Bidder and respond before the Bid Date. If the evaluation results in a change of the criteria, the Longview School District will issue an Addendum identifying the new criteria.
 5. **Objection.** Prior to the Award of the Contract, the Owner will notify the Bidder in writing if either the Longview School District, after due investigation, has reasonable objection to the Bidder or a person or entity proposed by the Bidder, and the Longview School District will provide the reasons for the determination. The Bidder may appeal the determination within two (2) business days of its receipt of the objection by presenting additional information to the Longview School District, and the Longview School District will consider the additional information before issuing its final determination. The Bidder may, after the Longview School District's objection or determination, and at Bidder's option, (1) withdraw the Bid, (2) submit an acceptable substitute person or entity with no change in the Contract Time and no adjustment in the Base Bid or any Alternate Bid, even if there is a cost to the Bidder occasioned by the substitution, or (3) appeal by filing a protest in accordance with paragraph 5(D). In the event of withdrawal, Bid security will not be forfeited.
 6. **Change.** Persons and entities proposed by the Bidder and to whom the Longview School District has made no reasonable objection must be used on the Work for which they were proposed and shall not be changed except with the written consent of the Longview School District.
 7. **Right to Terminate.** The Bidder's representations concerning its qualifications will be construed as a covenant under the Contract. Should it appear that the Bidder has made a material misrepresentation on its Contractor's Qualification Statement, the Longview School District shall have the right to terminate the Contract for Contractor's breach, and the School District may then pursue such remedies as exist elsewhere under this Contract, or as otherwise are provided at law or equity.
- B. **INFORMATION FROM OTHER BIDDERS:** All other Bidders designated by the Owner as under consideration for award of a Contract shall also provide a properly executed Contractor's Qualification Statement, if so requested by the Longview School District.
- C. **BIDDING MISTAKES:** The Longview School District will not be obligated to consider notice of claimed bidding mistakes received more than three (3) business days after the Bid opening. In accordance with Washington law, a low Bidder that claims error and fails to enter into the Contract is prohibited from bidding on the Project if a subsequent call for Bids is made for the Project.
- 1.7 PERFORMANCE BOND AND LABOR AND MATERIAL PAYMENT BOND**
- A. **BOND REQUIREMENTS:** Within seven (7) days after the issuance of the Longview School District's notice of intent to award the Contract, and prior to the date of execution of the Contract, the Bidder shall furnish evidence satisfactory to the Longview School District of its ability to obtain statutory bonds pursuant to RCW 39.08 covering the faithful performance of the Contract

and the payment of all obligations arising thereunder in the form and amount prescribed in the Contract Documents. The cost of such bond shall be included in the Base Bid.

- B. SUBCONTRACTOR BONDS. The Longview School District reserves the right to require certain Subcontractors to furnish performance and labor and material payment bonds in form as set forth herein and as set forth under the Bidding Documents or Contract Documents. The School District shall not, however, be responsible for any costs for any Subcontractor bonds unless the Longview School District, prior to the execution of the Owner-Contractor Agreement, requires the Bidder, in writing, to furnish such bonds from designated Subcontractors. Should any bonds be furnished by subcontract bidders, or be required by any Bidder to be furnished by any subcontract bidder or Subcontractor, without the written request of the Longview School District prior to the execution of the Owner-Contractor Agreement, the costs for any such bonds shall be at the expense of the Bidder and shall not be added to the Contract Sum.
- C. TIME OF DELIVERY AND FORM OF BONDS. The Bidder shall deliver the bonds and other documents required by the Contract Documents to the Longview School District pursuant to the Contract Documents and in no event any later than seven (7) days after the date of execution of the Contract and prior to commencing operations at the site. The bonds shall be written in the form approved by the Longview School District for public work, as required by RCW 39.08. The bonds shall be written by a surety firm licensed to do business in the State of Washington, with an A.M. Best rating of at least A-/VIII. The Bidder shall require the Attorney-in-Fact who executes the required bonds on behalf of the surety to affix thereto a certified and current copy of his/her Power of Attorney.

1.08 FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

- A. FORM TO BE USED: The Agreement for the Work will be written on the form(s) contained in the Bidding Documents, including any General, Supplemental or Special Conditions, and the other Contract Documents included with the Project Manual. In the event no form is enclosed, an AIA Document A101-2007, "Standard Form of Agreement Between Owner and Contractor, where the basis of payment is a Stipulated Sum," along with the General Conditions (AIA Document A201-2007), as both are revised, modified and supplemented by the Longview School District, will be used.
- B. CONFLICTS: In case of conflict between the provisions of these Instructions and any other Bidding Document, these Instructions shall govern. In case of conflict between the provisions of the Bidding Documents and the Contract Documents, the Contract Documents shall govern.

1.09 CONTRACT DOCUMENTS

This paragraph contains descriptions of some but not all of the provisions of the Contract Documents.

- A. RETAINAGE: The Contract Documents specify the statutory retainage requirements of RCW 60.28 for this Project.
- B. CONTRACT TIME: The Contract Documents specify the Contract Time. Timely completion of this Project is essential to the Longview School District.
- C. PREVAILING WAGES: The Contract Documents contain requirements regarding the payment of prevailing wages pursuant to RCW 39.12.
- D. WRITTEN CLAIMS AND NOTICE: The Contract Documents contain a number of provisions that require the Contractor to provide notice of Claims and to make and support Claims, in

writing, within a specified time in order to maintain the Claim. The School District is under no obligation to consider Claims that fail, in any respect, to meet these requirements.

- E. CHANGES IN CONTRACT SUM: The Contract Documents contain provisions specifying requirements for and pricing of changes in the Contract Sum.
- F. DISPUTE RESOLUTION: The Contract Documents contain provisions replacing the arbitration provisions of the form General Conditions with an alternative dispute resolution procedure which, among other things, requires non-binding mediation of all disputes.
- G. CONTRACTOR REGISTRATION: Pursuant to RCW 39.06, the Bidder shall be registered or licensed as required by the laws of the State of Washington, including but not limited to, RCW 18.27.
- H. COMMISSIONING OF OPERATIONAL SYSTEMS: Certain systems may be designated in the Contract Documents as "Selected" or "Critical" or "Operational" Systems. If so, after the Contractor notifies the Longview School District as specified prior to the Date of Substantial Completion that the Systems are up and running and ready for normal operation, the Longview School District will schedule a pre-commissioning inspection of these Systems.
- I. TAXES. The Contractor shall include in its Bid and pay for all applicable taxes except State Sales Tax and Local Sales Tax, which shall be excluded in the preparation of its Bid. Such State and Local Sales Taxes shall be added to the Contract Sum, paid by the Longview School District to the Contractor, and then paid by the Contractor over the course of the Project. Refer to general, supplementary or other conditions regarding further information.
- J. OTHER PROVISIONS: The above paragraphs contain descriptions of some but not all of the provisions of the Contract Documents. Bidders should review in detail the Contract Documents themselves and not rely upon the above paragraphs in this article as complete or inclusive.

1.10 POSSIBLE TRENCH EXCAVATION SAFETY PROVISIONS

- A. To ensure that the Bidder agrees to comply with relevant trenching safety requirements of RCW 39.04.180 and RCW 49.17, the Base Bid must include the cost of any required trench safety provisions. The Bidder shall enter in the blank provided on the Bid form the dollar amount the Bidder has included in its Base Bid for any trench safety provisions for trenching that will exceed a depth of four feet. If trench excavation safety provisions do not pertain to the Project, the Bidder should enter "N.A." or "Not Applicable" in the blank on the Bid form.

END OF SECTION

**Longview School District No. 122
Chiller Replacement Project at Mark Morris High School
Project No. 24052**

BID FORM

To be submitted no later than 2:00 p.m. on the bid submittal date indicated in the Advertisement for Bids (as modified by any addenda).

TO: Barbara Howe
Maintenance Secretary
Longview School District No. 122
bhowe@longview.k12.wa.us

The undersigned Bidder submits the following bid:

BASE BID:

Pursuant to and in compliance with the Contract Documents, including the Advertisement for Bids and Instructions to Bidders, the Bidder hereby certifies that it has carefully examined the Contract Documents entitled:

Chiller Replacement Project at Mark Morris High School

Prepared by Windsor Engineers, Ridgefield, WA 98604

and the conditions affecting the Work, and being familiar with the site; and having made the necessary examinations, proposes to furnish all labor, materials, equipment, and services necessary to complete the Work in strict accordance with the Contract Documents for the above-named Project for the following sums:

Base Bid: Chiller Scope	
Total Bid	\$ _____

Bid Alternate No. 01: HV-08 Scope	
Total Bid	\$ _____

Initials of Bidder's Representative

SALES TAX:

None of the sums stated in the foregoing include Washington State Sales Tax, except as designated in Article 4 of the Instructions for Bidders.

TIME OF COMPLETION AND LIQUIDATED DAMAGES:

The undersigned Bidder agrees, if awarded the Contract, to complete the Work of the Contract within the number of calendar days specified in the Contract Documents and also agrees to the amounts specified for Liquidated Damages. It is further agreed that the time for completion of the Work described herein is a reasonable time considering the average climatic range and usual industrial conditions prevailing in the locality.

TRENCH EXCAVATION SAFETY PROVISIONS:

If the Contract Documents contain any work which requires trenching exceeding a depth of four feet, all costs for adequate trench safety systems shall be identified as a separate bid item in compliance with Chapter 39.04 RCW and WAC 296-155-650. The purpose of this provision is to ensure that the Bidder agrees to comply with all the relevant trench safety requirements of Chapter 49.17 RCW. This bid amount shall be considered as part of the Base Bid set forth above.

Bidder must include a lump sum dollar amount in blank below (even if the value is \$0.00) to be responsive.

Trench Excavation Safety Provisions Only: N/A

CONTRACT AND BONDS:

If the Owner awards a contract based on this bid within thirty (30) days of the bid submittal deadline, the Bidder agrees to execute a contract for the above work, for compensation computed from the above stated sums, on the Owner's contract form, and to furnish Payment and Performance Bonds and acceptable evidence of insurance as required by the Contract Documents.

PRE-BID MEETING:

Bidder certifies that its representative attended the mandatory pre-bid meeting on following date (initial next to each date):

☐ November 15th, 2024

Initials of Bidder's Representative

BID GUARANTEE:

Pursuant to the Instruction to Bidders, the Bidder hereby certifies that it has furnished a bid guarantee for no less than five (5) percent of the base bid, and that such guarantee accompanies this Bid Form.

The successful bidder shall submit an executed Contract, Payment and Performance Bonds, and acceptable evidence of insurance within seven (7) days after receipt of award notice and public works contract form from the Owner. If the successful bidder, upon award of a contract by the Owner, fails to execute the public works contract or submit the Payment and Performance Bonds and acceptable evidence of insurance as required within the time specified, Owner may revoke the award. Should the successful bidder fail to enter into a contract with Owner, the bid guarantee may be retained by Owner as liquidated damages, not as a penalty.

If a contract is not awarded within thirty (30) days after the bid submittal deadline, or if the bidder delivers a signed public works contract, Payment and Performance Bonds, and acceptable evidence of insurance, then the certified or cashier's check or cash submitted as the bid guarantee shall be returned to the bidder, or the Bid Bond shall become void.

CERTIFICATION:

By submitting this Bid Form, the Bidder agrees that it meets the responsibility criteria described in Section 1.01(K) of the Instructions to Bidders.

Initials of Bidder's Representative

Bidder's Business Name:		
Type of Business: ☐ Sole Proprietorship ☐ Partnership ☐ Corporation (State of Incorporation:____) ☐ Other		
Physical Business Address (Must not be a P.O. Box):		
City:	State:	Zip Code:
Business Telephone Number:	Business Fax Number:	Business E-mail Address:
State of Washington numbers for the following:		
Contractor Registration No.:	UBI No.:	Employment Security Dept. No.:
Receipt is hereby acknowledged of Addenda No(s).: _____ _____		
Bidder is in compliance with the responsible bidder criteria requirement of RCW 39.04.350(1)(g).		

OFFICIAL AUTHORIZED TO SIGN FOR BIDDER:

"I certify (or declare) under penalty of perjury under the laws of the State of Washington that the foregoing is true and correct":	
Signature:	Date:
Print Name and Title	Location or Place Executed: (City, State)

END OF BID FORM

Revised 6/14/2022

Initials of Bidder's Representative

Project Name:_____

The undersigned attests, under penalty of perjury, that the bidder has no final and binding citation or notice of assessment from Labor & Industries for:

- Minimum wage requirements and labor standards (RCW 49.46)
- Wages – payment – collection (RCW 49.48)
- And, only for contracts awarded between Sept. 1, 2010, and Dec. 31, 2013, not been found in violation of requirements to submit of information to L & I about certain “off-site, prefabricated, nonstandard, project specific items” (RCW 39.04.370)

Authorized Signature

Printed Name

Title

Date

**LONGVIEW SCHOOL DISTRICT NO. 122
PUBLIC WORKS CONTRACT**

Project Name: Chiller Replacement Project at Mark Morris High School

Project Number: 24052

Project Description: Replacement of chiller and associated equipment.

Project Location: Mark Morris High School, 1602 Mark Morris Ct, Longview, WA 98632

THIS PUBLIC WORKS CONTRACT ("Contract") is made and entered into by and between the Longview School District No. 122, a Washington quasi-municipal corporation ("Owner"), and CONTRACTOR NAME, a ENTITY DESCRIPTION ("Contractor"). Contractor and Owner may hereinafter be referred to as "Parties."

- A. Effective Date: This Contract shall be effective on the last date set forth on the signature page ("Effective Date").
- B. Contract Work: This Contract shall be the agreed basis of performing the Work identified and defined in the Contract Documents. The Contractor agrees to furnish all material, labor, tools, equipment, apparatus, facilities, etc. necessary to perform and complete in a workmanship like manner the Work called for in the Contract Documents for the Project noted above, according to the terms of this Contract and the Contract Documents, which documents are incorporated herein by reference, as if set forth herein in full.
- C. Enumeration of Contract Documents: The Contract Documents include the Advertisement for Bids, Instructions for Bidders, completed Bid Form, Payment and Performance Bonds, General Conditions, Supplemental Conditions to the General Conditions, other Special Forms, this Public Works Contract, and Addenda:
- D. Time for Completion: The Work to be performed under this Contract shall commence as soon as the Contractor has been officially notified to proceed and shall be substantially complete by August 22, 2025.
- E. Liquidated Damages: The Contractor further agrees that, from the compensation otherwise to be paid, the Owner may retain the cost of the rental chiller unit for each calendar day thereafter that the Work remains uncompleted, which sum is agreed upon as the liquidated damages, and the Parties agree this sum is not to be construed as in any sense a penalty.
- F. Apprenticeship Utilization: The Contractor acknowledges that apprenticeship utilization goals should be met, and that the Owner has determined monetary incentives for meeting the goals, and monetary penalties for not meeting the goals. The Contractor further agrees that, from the compensation otherwise to be paid, the Owner may retain the sum of \$0 as a monetary penalty for not meeting the apprenticeship utilization goals. The Contractor further agrees, that in addition to the compensation otherwise to be paid, the Owner will

pay by issuance of a Change Order \$0 as an incentive for meeting the apprenticeship utilization goals.

- G. Contract Award Amount: Owner hereby agrees to pay the Contractor the Contract Award Amount indicated below, not including State Sales Tax, as consideration for the agreements set forth above, including but not limited to, Contractor's completion of all Work, in strict accord with the Contract Documents, as follows:

Base Bid:

Alternates Awarded:

Alternate Bid No. ____

Alternate Bid No. ____

CONTRACT AWARD AMOUNT:

- H. Project Representatives: The parties designated the following persons to administer this Contract and receive notices pursuant to the Contract Documents.

1. The Owner's designated representative is as follows:

Patti Bowen

Director of Business Services

Longview School District

2715 Lilac St

Longview, WA 98632

pbowen@longview.k12.wa.us

360-575-7020

2. The Contractor's designated representative is as follows: NAME, TITLE, ADDRESS, EMAIL.

- I. Governing Law: This Contract shall be construed and governed by the laws and statutes of the State of Washington.

IN WITNESS WHEREOF, the Parties hereto have executed this Contract by having their authorized representatives affix their signatures below.

OWNER:
Longview School District No. 122

CONTRACTOR:
CONTRACTOR NAME

By: _____
Signature Date

By: _____
Signature Date

Name: _____

Name: _____

Title: _____

Title: _____

Washington Contractor's Registration No.: _____

Contractor's Federal Tax ID No.: _____

PART 1 – GENERAL PROVISIONS**1.01 DEFINITIONS**

- A. “Application for Payment” means a written request submitted by Contractor to the Owner (or A/E, if applicable) for payment of Work completed in accordance with the Contract Documents and approved Schedule of Values, supported by such substantiating data as Owner or A/E may require.
- B. “Architect,” “Engineer,” or “A/E” means a person or entity lawfully entitled to practice architecture or engineering, representing Owner within the limits of its delegated authority, if applicable to the Project. Owner may choose not to contract with an A/E for certain projects, in which event all references to the A/E shall be construed to reference the Owner.
- C. “Change Order” means a written instrument signed by Owner and Contractor stating their agreement upon all of the following: (1) a change in the Work; (2) the amount of the adjustment in the Contract Sum, if any, and (3) the extent of the adjustment in the Contract Time, if any.
- D. “Claim” means Contractor’s exclusive remedy for resolving disputes with Owner regarding the terms of a Change Order or a request for equitable adjustment, as more fully set forth in Part 8.
- E. “Contract Award Amount” is the sum of the Base Bid and any accepted Alternates.
- F. “Contract Documents” means the Advertisement for Bids, Instructions for Bidders, completed Bid Form, General Conditions, Supplemental Conditions, Public Works Contract, other Special Forms, Drawings, and Specifications, and all addenda and modifications thereof.
- G. “Contract Sum” is the total amount payable by Owner to Contractor, for performance of the Work in accordance with the Contract Documents, including all taxes imposed by law and properly chargeable to the Work, except Washington State sales tax.
- H. “Contract Time” is the number of calendar days allotted in the Contract Documents for achieving Substantial Completion of the Work.
- I. “Contractor” means the person or entity who has agreed with Owner to perform the Work in accordance with the Contract Documents.
- J. “Day” means a calendar day, unless otherwise specified.
- K. “Drawings” are the graphic and pictorial portions of the Contract Documents showing the design, location, and dimensions of the Work, and may include plans, elevations, sections, details, schedules, and diagrams.
- L. “Final Acceptance” means the written acceptance issued to Contractor by Owner after Contractor has completed the requirements of the Contract Documents, as more fully set forth in Section 6.09 B.
- M. “Final Completion” means that the Work is fully and finally complete in accordance with the Contract Documents, as more fully set forth in Section 6.09A.
- N. “Force Majeure” means those acts entitling Contractor to request an equitable adjustment in the Contract Time, as more fully set forth in Section 3.05A.

- O. "Notice" means a written notice which has been delivered in person to the individual or a member of the firm or entity or to an officer of the corporation for which it was intended or, if delivered or sent by registered or certified mail, to the last business address known to the party giving notice.
- P. "Notice to Proceed" means a notice from Owner to Contractor that defines the date on which the Contract Time begins to run.
- Q. "Owner" means the Longview School District or its authorized representative with the authority to enter into, administer, and/or terminate the Work in accordance with the Contract Documents and make related determinations and findings.
- R. "Person" means a corporation, partnership, business association of any kind, trust, company, or individual.
- S. "Prior Occupancy" means Owner's use of all or parts of the Project before Substantial Completion, as more fully set forth in Section 6.08A.
- T. "Progress Schedule" means a schedule of the Work, in a form satisfactory to Owner, as further set forth in Section 3.02.
- U. "Project" means the total construction of which the Work performed in accordance with the Contract Documents, which may be the whole or a part and which may include construction by Owner or by separate contractors.
- V. "Project Record" means the separate set of Drawings and Specifications as further set forth in Section 4.02A.
- W. "Schedule of Values" means a written breakdown allocating the total Contract Sum to each principal category of Work, in such detail as requested by Owner.
- X. "Specifications" are that portion of the Contract Documents consisting of the written requirements for materials, equipment, construction systems, standards, and workmanship for the Work, and performance of related services.
- Y. "Subcontract" means a contract entered into by Subcontractor for the purpose of obtaining supplies, materials, equipment, or services of any kind for or in connection with the Work.
- Z. "Subcontractor" means any person, other than Contractor, who agrees to furnish or furnishes any supplies, materials, equipment, or services of any kind in connection with the Work.
- AA. "Substantial Completion" means that stage in the progress of the Work when the construction is sufficiently complete, as more fully set forth in Section 6.07.
- AB. "Work" means the construction and services required by the Contract Documents, and includes, but is not limited to, labor, materials, supplies, equipment, services, permits, and the manufacture and fabrication of components, performed, furnished, or provided in accordance with the Contract Documents.

1.02 ORDER OF PRECEDENCE

Any conflict or inconsistency in the Contract Documents shall be resolved by giving the documents precedence in the following order:

- A. Signed Public Works Contract, including any Change Orders.

- B. Supplemental Conditions.
- C. General Conditions.
- D. Specifications.
- E. Drawings. In case of conflict within the Drawings, large-scale drawings shall take precedence over small-scale drawings.
- F. Signed and Completed Bid Form.
- G. Instructions to Bidders.
- H. Advertisement for Bids.

1.03 EXECUTION AND INTENT

Contractor makes the following representations to Owner:

- A. Contract Sum reasonable: The Contract Sum is reasonable compensation for the Work and the Contract Time is adequate for the performance of the Work, as represented by the Contract Documents;
- B. Contractor familiar with Project: Contractor has carefully reviewed the Contract Documents, visited and examined the Project site, become familiar with the local conditions in which the Work is to be performed, and satisfied itself as to the nature, location, character, quality, and quantity of the Work, the labor, materials, equipment, goods, supplies, work, services, and other items to be furnished and all other requirements of the Contract Documents, as well as the surface and subsurface conditions and other matters that may be encountered at the Project site or affect performance of the Work or the cost or difficulty thereof;
- C. Contractor financially capable: Contractor is financially solvent, able to pay its debts as they mature, and possesses sufficient working capital to complete the Work and perform Contractor's obligations required by the Contract Documents; and
- D. Contractor can complete Work: Contractor is able to furnish the plant, tools, materials, supplies, equipment, and labor required to complete the Work and perform the obligations required by the Contract Documents and has sufficient experience and competence to do so.

PART 2 – INSURANCE AND BONDS

2.01 CONTRACTOR'S LIABILITY INSURANCE

- A. Prior to commencement of the Work, the Contractor shall obtain all the insurance required by the Contract Documents and provide evidence satisfactory to Owner that such insurance has been procured. Review of the Contractor's insurance by Owner or the specification or approval of the insurance in this Contract or of its coverage or amount shall not relieve or decrease the liability of the Contractor under the Contract Documents or otherwise. The Contractor shall include in its bid the cost of all insurance and bonds required to complete the Base Bid Work and accepted alternates.

- B. The Contractor shall purchase and maintain in full force and effect the following insurance coverage without interruption from the date of commencement of the Work through the date of Final Acceptance and termination of any coverage required to be maintained after final payment, including, but not limited to, during the performance of any corrective Work required by Section 5.16. Completed Operations coverage shall remain in force for three (3) years after Final Acceptance. All coverages shall be written on an occurrence basis, reasonably acceptable to the Owner, and written for at least the minimum limits specified in this Section 2.01 or required by law, whichever coverage is greater.

1. Commercial General Liability (CGL):

- a. The Contractor shall procure an occurrence-based Commercial General Liability (CGL) insurance policy, written on an ISO-based occurrence form or its equivalent. Such insurance shall provide coverage for personal injury, bodily injury, and property damage liability arising from the Contractor's operations in connection with the Work, whether such operations are by the Contractor or Subcontractors and suppliers of any tier; owned, non-owned, and hired vehicles; work the Contractor may subcontract or sublet to others; and the indemnity provisions of this Contract. Without limiting the foregoing, such insurance shall protect the Contractor and additional insureds required by this Section 2.01 from claims set forth below that may arise out of or result from the Contractor's operations and completed operations under the Contract and for which the Contractor or the additional insureds may be legally liable, whether such operations are by the Contractor, a Subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts any of them may be liable:
- (1) Claims under workers' compensation (industrial insurance), disability benefit, and other similar employee benefit acts that are applicable to the Work to be performed in the form of Stop Gap Liability Insurance (Employer's Contingent Liability Insurance);
 - (2) Claims for damages because of bodily injury, occupational sickness or disease, or death of the Contractor's employees;
 - (3) Claims for damages because of bodily injury, sickness or disease, or death of any person other than the Contractor's employees;
 - (4) Claims for damages insured by usual personal injury liability coverage;
 - (5) Claims for damages, other than to the Work itself, because of injury to or destruction of tangible property, including loss of use resulting therefrom;
 - (6) Claims for bodily injury or property damage arising out of completed operations;
 - (7) Claims involving contractual liability insurance applicable to the Contractor's obligations under Section 5.22 ("Indemnification"); and
 - (8) Claims for bodily injury and property damage resulting from mold and fungus.

- b. Without limiting the foregoing, this CGL insurance shall be on a comprehensive basis and include all major divisions of coverage, including, but not limited to:
 - (1) Premises and Operations;
 - (2) Products and Completed Operations;
 - (3) Explosion, Collapse, and Underground (XCU);
 - (4) The Owners and Contractors Protective;
 - (5) Personal and Advertising Injury, with employment exclusion deleted;
 - (6) Blanket contractual, including specific provision for Contractor's obligation under the indemnity provisions of this Contract; and
 - (7) Broad Form Property Damage.
 2. Automobile Liability: Such insurance shall provide coverage for all owned, non-owned, and hired automobiles. It shall cover claims for damages because of bodily injury, death of a person, or property damage arising out of ownership, maintenance, or use of a motor vehicle (including loss of use thereof arising out of operation of automobiles), including Comprehensive Automobile Liability, Bodily Injury, and Property Damage Combined Single Limit.
 3. Umbrella Policy: For projects with a Contract Sum of \$1 million or more, the Contractor shall procure a true umbrella policy that provides excess limits over the primary layer.
 4. Employer's Liability: The Contractor shall provide an employer's liability policy providing coverage for liability to employees for work-related bodily injury or disease, other than liability imposed by workers' compensation law.
 5. Workers' Compensation: The Contractor shall provide, and require Subcontractors of any tier to provide, workers' compensation insurance as required by the industrial insurance laws of the State of Washington.
- C. The Contractor's insurance obtained under this Section 2.01 will:
1. Name the Owner, the Owner's consultants, as well as their directors, officers, employees, and agents, as additional insureds under CG 2010 and CG 2037 or their equivalent.
 2. Include a severability of interest (cross-liability clause) in favor of the Owner for Work performed under this Contract.
 3. Be designated and endorsed as primary coverage for both defense and indemnity, and any Owner's policies shall be excess and non-contributory.
 4. Provide a waiver of any rights of subrogation against the Owner.

5. Have per-project general aggregate provisions in accordance with the limits set forth in Section 2.01J, which provisions may be modified in the Special Conditions. The insurance shall be endorsed to have the general aggregate apply to this Project only.
 6. Without limiting the foregoing, the insurance described above shall include coverage for underground collapse and explosion exposures.
- D. Any company writing the insurance to be obtained pursuant to this Section 2.01 shall be authorized to do business in the State of Washington. Insurance carriers providing insurance in accordance with the Contract Documents must be acceptable to Owner and shall possess an A.B. Best's policyholder's rating of "A" or better and a financial rating of no less than "VIII."
- E. Losses up to the deductible amount of any insurance under this part shall be the responsibility of the Contractor.
- F. The Contract Sum includes an amount to pay the premium for insurance required under the Contract Documents and to name the Owner and others listed in the Contract Documents as additional insureds on all insurance policies required by Section 2.01.
- G. There shall be no self-insured retention without the prior written approval of the Owner.
- H. If the Owner is damaged by the failure of the Contractor to maintain any of the insurance in this Section 2.01 or to so notify the Owner, the Contractor shall bear all costs attributable thereto. The Owner may withhold payment pending receipt of all certificates of insurance. Failure to withhold payment shall not constitute a waiver.
- I. The Contractor shall comply with the Washington State Industrial Insurance Act and, if applicable, the Federal Longshoremen's and Harbor Workers' Act and the Jones Act.
- J. Coverage Limits: The minimum coverage limits for Contractor's liability insurance shall be as follows:
1. Commercial General Liability (CGL):
 - a. At least \$2,000,000 General Aggregate Limit (Other than Products-Completed Operations).
 - b. At least \$1,000,000 Each Occurrence Limit.
 - c. At least \$1,000,000 Products-Completed Operations Aggregate Limit.
 - d. At least \$1,000,000 Personal Injury and Advertising Liability Limit, each occurrence.
 2. Automobile Liability: At least \$1,000,000 Combined Single Limit for Automobile Bodily Injury and Property Damage Liability, each accident or loss.
 3. Umbrella Policy: Where applicable, the umbrella policy will have excess limits over the primary layer in an amount not less than \$2,000,000.
 4. Employer's Liability: At least \$1,000,000 each occurrence limit.

5. Workers' Compensation: The Contractor shall provide workers' compensation insurance in the amounts required by the industrial insurance laws of the State of Washington. For any employees not subject to the Washington State workers' compensation statute, the Contractor shall provide, and cause each Subcontractor to provide workers' compensation insurance with a private company in an amount equivalent to that provided by the workers' compensation statute, but no less than a \$1,000,000 limit of liability for the protection of its employees not otherwise protected. Stop Gap Liability Insurance (Employer's Contingent Liability Insurance) shall be at least \$1,000,000 Each Occurrence.

K. Proof of Insurance:

1. Prior to commencement of the Work, any presence on the site, or exposure to loss can occur, and in any event within seven (7) Days after the Owner has issued its Notice to Proceed, the Contractor shall furnish the Owner with the following:
 - a. Two (2) copies of Certificates of Insurance evidencing all insurance required by the Contract Documents;
 - b. A written statement of the actual costs (expressed as a percentage) of the Contractors' liability insurance under 2.01;
 - c. Endorsements for additional insureds as listed in Section 2.01C.1;
 - d. Two (2) copies of Department of Labor & Industries statements for state workers' compensation coverage.
2. All insurance policies and certificates must be signed copies. Edition dates of endorsements on policies obtained under this Section 2.01 shall be consistent.
3. All policies shall include the premium percentage to be paid by the Contractor for increases in the Contract Sum.
4. The Contractor shall furnish to the Owner copies of any subsequently issued endorsements amending, modifying, altering, or restricting coverage or limits.
5. Policies or certificates obtained under this part shall verify that the policy contains coverage for blanket contractual liability, including both oral and written contracts, and acknowledge the indemnification provisions and liability coverages called for by this Contract.
6. Upon written request, the Contractor shall provide a copy of its policies obtained under this part to the Owner within five (5) business days.
7. All insurance certificates obtained pursuant to this part will:
 - a. Name Owner's Project number and Project title.
 - b. State the insurance carrier's A.B. Best rating.
 - c. Evidence full compliance with the requirements of Section 2.01.

- d. Specifically require written notice by certified mail must be provided to the Owner at least forty-five (45) Days before the policies expire, are cancelled, or are reduced; the limits are decreased; or the additional insureds removed, except that thirty (30) Days' notice shall be required for surplus line insurance.
8. Notwithstanding anything herein to the contrary, the Contractor shall provide all bonding, insurance, and permit documentation as required by governmental entities for all portions of the Project.
9. The Contractor shall ensure and require that Subcontractors of any tier have insurance coverage to cover bodily injury and property damage on all operations and all vehicles owned or operated by Subcontractors of all tiers in the minimum amount of \$1,000,000 per occurrence with a \$2,000,000 general aggregate limit. Also, the Subcontractors shall name the Contractor and the Owner and cause the commercial liability coverage required by the Contract Documents to include (1) the Owner, as an additional insured for claims caused in whole or in part by the Subcontractor's negligent acts or omissions during the Subcontractor's operations; and (2) the Owner as an additional insured for claims caused in whole or in part by the Subcontractor's negligent acts or omissions during the Subcontractor's completed operations.
10. The Owner may withhold payment pending receipt of all certificates of insurance meeting the requirements of Section 2.01K. Failure to withhold payment shall not constitute a waiver of any provision of the Contract.

2.02 PAYMENT AND PERFORMANCE BONDS

- A. In accordance with Chapter 39.08 RCW ("Contractor's Bond"), the Contractor will furnish to the Owner bonds, with a surety company admitted and licensed in the State of Washington and acceptable to the Owner, conditioned that the Contractor will: (1) faithfully perform all provisions of this Contract (the "Performance Bond"); and (2) pay all laborers, mechanics, Subcontractors, and materialmen, and all persons who supply such person, persons, or Subcontractors, with provisions and supplies for carrying out the Project and pay the taxes, increases, and penalties incurred on the Project under state law (the "Payment Bond"). Each of the Performance Bond and Payment Bond will be in the full amount of the Contract Sum. Such surety company will possess an A.M. Best rating of "A" or better and a financial rating of no less than "IX."
- B. Bond forms must be deemed acceptable and approved by Owner. Owner shall deem acceptable and approve payment and performance bonds that use the Payment Bond and Performance Bond form published by and available from the American Institute of Architects (AIA) – form A312. Separate bonds for payment and performance must be provided to Owner. Provision of payment and performance bonds by Contractor to Owner is a condition precedent to performance by Owner.
- C. Prior to execution of a Change Order that, cumulatively with previous Change Orders, increases the Contract Award Amount by ten (10) percent or more, the Contractor shall provide either new payment and performance bonds for the revised Contract Sum, or riders to the existing payment and performance bonds increasing the amount of the bonds. The Contractor shall likewise provide additional bonds or riders when subsequent Change Orders increase the Contract Sum by ten (10) percent or more.

- D. No payment or performance bonds are required if the Contract Sum is \$150,000 or less and Owner and Contractor agree that Owner may, in lieu of the bond, retain 10 percent of the Contract Sum for the period allowed by RCW 39.08.010.
- E. All reinsurers that may be called upon to support or share in a surety's obligations specified in connection with the performance and payment bond obligations required of the Contractor by this Contract must also have an A.M. Best rating of "A" or better and financial rating of not less than "IX."
- F. Within seven (7) days of the issuance of Owner's Notice of Intent to Award the Contract, the Contractor will deliver evidence of its bondability to the Owner. Within seven (7) days after its execution of the Contract, the Contractor will deliver copies of the bonds to the Owner.
- G. THE OWNER MAY DECLINE TO ENTER INTO THE CONTRACT IF THE REQUESTED EVIDENCE OF BONDABILITY IS NOT RECEIVED. THE CONTRACTOR WILL NOT PROCEED WITH THE WORK UNTIL SUCH SURETY BOND IS RECEIVED. Evidence of bondability shall include the percentage to be paid by the Contractor for increases in the Contract Sum.
- H. Upon request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor will promptly furnish a copy of the bond(s) or will authorize a copy to be furnished.
- I. Additional Bond Security: The Contractor will promptly furnish additional security required to protect Owner and persons supplying labor or materials required by this Contract if: (1) Owner has a reasonable objection to the surety; or (2) any surety fails to furnish reports on its financial condition if required by Owner.
- J. Potential Subcontractors' Payment and Performance Bonds: Within ten (10) days after the issuance of the Notice to Proceed, any Subcontractors so required in the Bidding or Contract Documents or Special Conditions shall deliver evidence of their payment and performance bondability to the Owner through the Contractor. The evidence shall include a letter from the bonding company that includes the price of payment and performance bonds to be issued during the thirty (30) day period after the Notice to Proceed. The surety company must be acceptable to the Owner and admitted and licensed in the State of Washington, with an A.M. Best rating of "A" or better and a financial rating of no less than "VIII." The bonds shall be in an amount equal to the full contract sum of the Subcontract between the Subcontractor and the Contractor but shall not include sales tax. The bonds shall be conditioned that the Subcontractor shall faithfully perform all the provisions of its subcontract, payment of all obligations arising thereunder, and for one year's maintenance for correction of defective work. If the Owner elects to require payment and performance bonds from one or more of the Subcontractors, it will so notify the Contractor in writing within fourteen (14) days of receipt of the evidence of bondability from the respective Subcontractor, in which case the Contract Sum shall be increased by a Change Order in the amount specified in the letter, unless otherwise agreed by the parties. The Owner shall not be responsible for the costs of any Subcontractor bonds it requires until the Owner receives a copy of the bond. THE OWNER MAY DECLINE TO ENTER INTO THE CONTRACT OR MAY REQUIRE A CHANGE OF SUBCONTRACTOR AT NO INCREASE IN THE CONTRACT SUM OR CONTRACT TIME IF THIS EVIDENCE OF BONDABILITY IS NOT RECEIVED. THE OWNER MAY WITHHOLD PAYMENT TO THE CONTRACTOR UNTIL SUCH SURETY BONDS ARE RECEIVED. Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a

copy of the bonds or shall permit a copy to be made. The Subcontractors responsible to the Contractor for the work listed in the Instructions to Bidders must comply with this paragraph to the extent directed by the Owner.

- K. If the Owner is damaged by the failure of the Contractor to maintain any of the bonds or insurance in this Section 2.02 or elsewhere in the Contract Documents or to so notify the Owner, then the Contractor will bear all costs attributable thereto. The Owner may withhold payment pending receipt of all certificates of insurance and bonds. Failure to withhold payment will not constitute a waiver.

2.03 ALTERNATIVE SURETY

- A. When alternative surety required: Contractor shall promptly furnish payment and performance bonds from an alternative surety as required to protect Owner and persons supplying labor or materials required by the Contract Documents if:
1. Owner has a reasonable objection to the surety; or
 2. Any surety fails to furnish reports on its financial condition if required by Owner.

2.04 BUILDER'S RISK

- A. Contractor to buy Property Insurance: Contractor shall purchase and maintain property insurance in the amount of the Contract Sum, including all Change Orders for the Work, on a replacement-cost basis until Substantial Completion. For projects not involving New Building Construction, "Installation Floater" is an acceptable substitute for the Builder's Risk Insurance. The insurance shall cover the interest of Owner, Contractor, and any Subcontractors, as their interests may appear.
- B. Losses covered: Contractor property insurance shall be placed on an "all risk" basis and insure against the perils of fire and physical loss or damage including theft, vandalism, malicious mischief, collapse, false work, temporary buildings, and debris removal (including demolition occasioned by enforcement of any applicable legal requirements), and shall cover reasonable compensation for A/E's services and expenses required as a result of an insured loss.
- C. Waiver of subrogation rights: Owner and Contractor waive all subrogation rights against each other, any Subcontractors, A/E, A/E's subconsultants, separate contractors described herein, if any, and any of their subcontractors, for damages caused by fire or other perils to the extent covered by property insurance obtained pursuant to this section or other property insurance applicable to the Work, except such rights as they have to proceeds of such insurance held by Owner as fiduciary. The policies shall provide such waivers of subrogation by endorsement or otherwise. A waiver of subrogation shall be effective to a person or entity even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, did not pay the insurance premium directly or indirectly, and whether or not the person or entity had an insurable interest in the property damaged.

PART 3 – TIME AND SCHEDULE

3.01 PROGRESS AND COMPLETION

Contractor to meet schedule: Contractor shall diligently prosecute the Work, with adequate forces, achieve Substantial Completion within the Contract Time, and achieve Final Completion within a reasonable period thereafter.

3.02 CONSTRUCTION SCHEDULE

- A. Preliminary Progress Schedule: Contractor shall, within 14 Days after issuance of the Notice to Proceed, submit a preliminary Progress Schedule. The Progress Schedule shall show the sequence in which Contractor proposes to perform the Work and the dates on which Contractor plans to start and finish major portions of the Work, including dates for Shop Drawings and other submittals, and for acquiring materials and equipment.
- B. Form of Progress Schedule: The Progress Schedule shall be in the form of a bar chart, or a critical path method analysis, as specified by Owner. The preliminary Progress Schedule may be general, showing the major portions of the Work, with a more detailed Progress Schedule submitted as directed by Owner.
- C. Owner comments on Progress Schedule: Owner shall return comments on the preliminary Progress Schedule to Contractor within 14 Days of receipt. Review by Owner of Contractor's schedule does not constitute an approval or acceptance of Contractor's construction means, methods, or sequencing, or its ability to complete the Work within the Contract Time. Contractor shall revise and resubmit its schedule, as necessary. Owner may withhold a portion of progress payments until a Progress Schedule has been submitted which meets the requirements of this section.
- D. Monthly updates and compliance with Progress Schedule: Contractor shall utilize and comply with the Progress Schedule. On a monthly basis, or as otherwise directed by Owner, Contractor shall submit an updated Progress Schedule at its own expense to Owner indicating actual progress. If, in the opinion of Owner, Contractor is not in conformance with the Progress Schedule for reasons other than acts of Force Majeure as identified in Section 3.05, Contractor shall take such steps as are necessary to bring the actual completion dates of its work activities into conformance with the Progress Schedule, and if directed by Owner, Contractor shall submit a corrective action plan or revise the Progress Schedule to reconcile with the actual progress of the Work.
- E. Contractor to notify Owner of delays: Contractor shall promptly notify Owner in writing of any actual or anticipated event which is delaying or could delay achievement of any milestone or performance of any critical path activity of the Work. Contractor shall indicate the expected duration of the delay, the anticipated effect of the delay on the Progress Schedule, and the action being or to be taken to correct the problem. Provision of such notice does not relieve Contractor of its obligation to complete the Work within the Contract Time.

3.03 OWNER'S RIGHT TO SUSPEND THE WORK FOR CONVENIENCE

- A. Owner may suspend Work: Owner may, at its sole discretion, order Contractor, in writing, to suspend all or any part of the Work for up to 90 Days, or for such longer period as mutually agreed.
- B. Compliance with suspension; Owner's options: Upon receipt of a written notice suspending the Work, Contractor shall immediately comply with its terms and take all reasonable steps to minimize the incurrence of cost of performance directly attributable to such suspension. Within a period up to 90 Days after the notice is delivered to Contractor, or within any extension of that period to which the parties shall have agreed, Owner shall either:
 - 1. Cancel the written notice suspending the Work; or
 - 2. Terminate the Work covered by the notice as provided in the termination

provisions of Part 9.

- C. Resumption of Work: If a written notice suspending the Work is cancelled or the period of the notice or any extension thereof expires, Contractor shall resume Work.
- D. Equitable adjustment for suspensions: Contractor shall be entitled to an equitable adjustment in the Contract Time, or Contract Sum, or both, for increases in the time or cost of performance directly attributable to such suspension, provided Contractor complies with all requirements set forth in Part 7.

3.04 OWNER'S RIGHT TO STOP THE WORK FOR CAUSE

- A. Owner may stop Work for Contractor's failure to perform: If Contractor fails or refuses to perform its obligations in accordance with the Contract Documents, Owner may order Contractor, in writing, to stop the Work, or any portion thereof, until satisfactory corrective action has been taken.
- B. No equitable adjustment for Contractor's failure to perform: Contractor shall not be entitled to an equitable adjustment in the Contract Time or Contract Sum for any increased cost or time of performance attributable to Contractor's failure or refusal to perform or from any reasonable remedial action taken by Owner based upon such failure.

3.05 DELAY

- A. Force Majeure actions not a default; Force Majeure defined: Any delay in or failure of performance by Owner or Contractor, other than the payment of money, shall not constitute a default hereunder if and to the extent the cause for such delay or failure of performance was unforeseeable and beyond the control of the party ("Force Majeure"). Acts of Force Majeure include, but are not limited to:
 - 1. Acts of God or the public enemy;
 - 2. Acts or omissions of any government entity;
 - 3. Fire or other casualty for which Contractor is not responsible;
 - 4. Quarantine or epidemic;
 - 5. Strike or defensive lockout;
 - 6. Unusually severe weather conditions which could not have been reasonably anticipated; and
 - 7. Unusual delay in receipt of supplies or products which were ordered and expedited and for which no substitute reasonably acceptable to Owner was available. The pandemic of the disease COVID-19 and the consequences thereof do not constitute a Force Majeure Event.
- B. Contract Time adjustment for Force Majeure: Contractor shall be entitled to an equitable adjustment in the Contract Time for changes in the time of performance directly attributable to an act of Force Majeure, provided it makes a request for equitable adjustment according to Section 7.03. Contractor shall not be entitled to an adjustment in the Contract Sum resulting from an act of Force Majeure.
- C. Contract Time or Contract Sum adjustment if Owner at fault: Contractor shall be entitled to an equitable adjustment in Contract Time, and may be entitled to an equitable adjustment

in Contract Sum, if the cost or time of Contractor's performance is changed due to the fault or negligence of Owner, provided the Contractor makes a request according to Sections 7.02 and 7.03.

- D. No Contract Time or Contract Sum adjustment if Contractor at fault: Contractor shall not be entitled to an adjustment in Contract Time or in the Contract Sum for any delay or failure of performance to the extent such delay or failure was caused by Contractor or anyone for whose acts Contractor is responsible.
- E. Contract Time adjustment only for concurrent fault: To the extent any delay or failure of performance was concurrently caused by the Owner and Contractor, Contractor shall be entitled to an adjustment in the Contract Time for that portion of the delay or failure of performance that was concurrently caused, provided it makes a request for equitable adjustment according to Section 7.03, but shall not be entitled to an adjustment in Contract Sum.
- F. Contractor to mitigate delay impacts: Contractor shall make all reasonable efforts to prevent and mitigate the effects of any delay, whether occasioned by an act of Force Majeure or otherwise.

3.06 NOTICE TO OWNER OF LABOR DISPUTES

- A. Contractor to notify Owner of labor disputes: If Contractor has knowledge that any actual or potential labor dispute is delaying or threatens to delay timely performance in accordance with the Contract Documents, Contractor shall immediately give notice, including all relevant information, to Owner.
- B. Pass through notification provisions to Subcontractors: Contractor agrees to insert a provision in its Subcontracts and to require insertion in all sub-subcontracts, that in the event timely performance of any such contract is delayed or threatened by delay by any actual or potential labor dispute, the Subcontractor or Sub-subcontractor shall immediately notify the next higher tier Subcontractor or Contractor, as the case may be, of all relevant information concerning the dispute.

3.07 DAMAGES FOR FAILURE TO ACHIEVE TIMELY COMPLETION

- A. Liquidated Damages
 - 1. Reason for Liquidated Damages: Timely performance and completion of the Work is essential to Owner and time limits stated in the Contract Documents are of the essence. Owner will incur serious and substantial damages if Substantial Completion of the Work does not occur within the Contract Time. However, it would be difficult if not impossible to determine the exact amount of such damages. Consequently, provisions for liquidated damages are included in the Contract Documents.
 - 2. Calculation of Liquidated Damages amount: The liquidated damage amounts set forth in the Contract Documents will be assessed not as a penalty, but as liquidated damages for breach of the Contract Documents. This amount is fixed and agreed upon by and between the Contractor and Owner because of the impracticability and extreme difficulty of fixing and ascertaining the actual damages the Owner would in such event sustain. This amount shall be construed as the actual amount of damages sustained by the Owner, and may be retained by the Owner and deducted from periodic payments to the Contractor.

3. Contractor responsible even if Liquidated Damages assessed: Assessment of liquidated damages shall not release Contractor from any further obligations or liabilities pursuant to the Contract Documents.

B. Actual Damages

Calculation of Actual Damages: Actual damages will be assessed for failure to achieve Final Completion within the time provided. Actual damages will be calculated on the basis of direct architectural, administrative, and other related costs attributable to the Project from the date when Final Completion should have been achieved, based on the date Substantial Completion is actually achieved, to the date Final Completion is actually achieved. Owner may offset these costs against any payment due Contractor.

C. Waiver of Claims for Consequential Damages

The Contractor and Owner waive Claims against each other for consequential damages arising out of or relating to this Contract. This mutual waiver includes, without limitation:

1. Damages incurred by Owner for rental expenses, for income, profit, financing, business, and reputation, and for loss of management or employee productivity or of the services of such persons; and
2. Damages incurred by the Contractor for principal and home office overhead and expenses including, without limitation, the compensation of personnel stationed there, for losses of financing, business and reputation, for losses on other projects, for interest or financing costs, and for loss of profit, except as explicitly allowed under the Contract Documents.

PART 4 – SPECIFICATIONS, DRAWINGS, AND OTHER DOCUMENTS

4.01 DISCREPANCIES AND CONTRACT DOCUMENT REVIEW

- A. Specifications and Drawings are basis of the Work: The intent of the Specifications and Drawings is to describe a complete Project to be constructed in accordance with the Contract Documents. Contractor shall furnish all labor, materials, equipment, tools, transportation, permits, and supplies, and perform the Work required in accordance with the Drawings, Specifications, and other provisions of the Contract Documents.
- B. Parts of the Contract Documents are complementary: The Contract Documents are complementary. What is required by one part of the Contract Documents shall be binding as if required by all. Anything mentioned in the Specifications and not shown on the Drawings, or shown on the Drawings and not mentioned in the Specifications, shall be of like effect as if shown or mentioned in both.
- C. Contractor to report discrepancies in Contract Documents: Contractor shall carefully study and compare the Contract Documents with each other and with information furnished by Owner. If, during the performance of the Work, Contractor finds a conflict, error, inconsistency, or omission in the Contract Documents, it shall promptly and before proceeding with the Work affected thereby, report such conflict, error, inconsistency, or omission to the Owner (and A/E, if applicable) in writing.
- D. Contractor knowledge of discrepancy in documents – responsibility: Contractor shall do no Work without applicable Drawings, Specifications, or written modifications, or Shop Drawings where required, unless instructed to do so in writing by Owner. If Contractor performs any construction activity, and it knows or reasonably should have known that any

of the Contract Documents contain a conflict, error, inconsistency, or omission, Contractor shall be responsible for the performance and shall bear the cost for its correction.

- E. Contractor to perform Work implied by Contract Documents: Contractor shall provide any work or materials the provision of which is clearly implied and is within the scope of the Contract Documents even if the Contract Documents do not mention them specifically.
- F. Interpretation questions: Questions regarding interpretation of the requirements of the Contract Documents shall be referred to the Owner (and A/E, if applicable).

4.02 PROJECT RECORD

- A. Contractor to maintain Project Record Drawings and Specifications: Contractor shall legibly mark in ink on a separate set of the Drawings and Specifications all actual construction, including depths of foundations, horizontal and vertical locations of internal and underground utilities, and appurtenances referenced to permanent visible and accessible surface improvements, field changes of dimensions and details, actual suppliers, manufacturers and trade names, models of installed equipment, and Change Order Proposals (COP). This separate set of Drawings and Specifications shall be the "Project Record."
- B. Update Project Record weekly and keep on site: The Project Record shall be maintained on the project site throughout the construction and shall be clearly labeled "PROJECT RECORD." The Project Record shall be updated at least weekly noting all changes and shall be available to Owner at all times.
- C. Final Project Record before Final Acceptance: Contractor shall submit the completed and finalized Project Record to the Owner (and A/E, if applicable) prior to Final Acceptance.

4.03 SHOP DRAWINGS

- A. Definition of Shop Drawings: "Shop Drawings" means documents and other information required to be submitted to the Owner (or A/E, if applicable) by Contractor pursuant to the Contract Documents, showing in detail: the proposed fabrication and assembly of structural elements; and the installation (i.e., form, fit, and attachment details) of materials and equipment. Shop Drawings include, but are not limited to, drawings, diagrams, layouts, schematics, descriptive literature, illustrations, schedules, performance and test data, samples, and similar materials furnished by Contractor to explain in detail specific portions of the Work required by the Contract Documents. For materials and equipment to be incorporated into the Work, Contractor submittal shall include the name of the manufacturer, the model number, and other information concerning the performance, capacity, nature, and rating of the item. When directed, Contractor shall submit all samples at its own expense. Owner may duplicate, use, and disclose Shop Drawings provided in accordance with the Contract Documents.
- B. Approval of Shop Drawings: Contractor shall coordinate all Shop Drawings, and review them for accuracy, completeness, and compliance with the Contract Documents and shall indicate its approval thereon as evidence of such coordination and review. Where required by law, Shop Drawings shall be stamped by an appropriate professional licensed by the state of Washington. Shop Drawings submitted to the Owner (or A/E, if applicable) without evidence of Contractor's approval shall be returned for resubmission. Contractor shall review, approve, and submit Shop Drawings with reasonable promptness and in such sequence as to cause no delay in the Work or in the activities of Owner or separate contractors. Contractor's submittal schedule shall allow a reasonable time for the Owner

(or A/E, if applicable) to review. The Owner (or A/E, if applicable) will review, approve, or take other appropriate action on the Shop Drawings. Contractor shall perform no portion of the Work requiring submittal and review of Shop Drawings until the respective submittal has been reviewed and the A/E, if applicable, or Owner has approved or taken other appropriate action. The A/E and/or Owner, as applicable, shall respond to Shop Drawing submittals with reasonable promptness. Any Work by Contractor shall be in accordance with reviewed Shop Drawings. Submittals made by Contractor which are not required by the Contract Documents may be returned without action.

- C. Contractor not relieved of responsibility when Shop Drawings approved: Approval, or other appropriate action with regard to Shop Drawings, by Owner or A/E shall not relieve Contractor of responsibility for any errors or omissions in such Shop Drawings, nor from responsibility for compliance with the requirements of the Contract Documents. Unless specified in the Contract Documents, review by Owner or A/E shall not constitute an approval of the safety precautions employed by Contractor during construction, or constitute an approval of Contractor's means or methods of construction. If Contractor fails to obtain approval before installation and the item or work is subsequently rejected, Contractor shall be responsible for all costs of correction.
- D. Variations between Shop Drawings and Contract Documents: If Shop Drawings show variations from the requirements of the Contract Documents, Contractor shall describe such variations in writing, separate from the Shop Drawings, at the time it submits the Shop Drawings containing such variations. If the Owner (or A/E, if applicable) approves any such variation, an appropriate Change Order will be issued. If the variation is minor and does not involve an adjustment in the Contract Sum or Contract Time, a Change Order need not be issued; however, the modification shall be recorded upon the Project Record.
- E. Contractor to submit copies of Shop Drawings: Contractor shall submit to A/E and Owner for approval five (5) copies of all Shop Drawings. Unless otherwise indicated, three (3) sets of all Shop Drawings shall be retained by A/E, if applicable, or the Owner and two (2) sets shall be returned to Contractor.

4.04 ORGANIZATION OF SPECIFICATIONS

Specification organization by trade: Specifications may be prepared in sections which conform generally with trade practices. These sections are for Owner and Contractor convenience and shall not control Contractor in dividing the Work among the Subcontractors or in establishing the extent of the Work to be performed by any trade.

4.05 OWNERSHIP AND USE OF DRAWINGS, SPECIFICATIONS, AND OTHER DOCUMENTS

- A. A/E, not Contractor, owns Copyright of Drawings and Specifications: The Drawings, Specifications, and other documents prepared by A/E, if any, are instruments of A/E's service through which the Work to be executed by Contractor is described. Neither Contractor nor any Subcontractor shall own or claim a copyright in the Drawings, Specifications, and other documents prepared by A/E, if any, and A/E shall be deemed the author of them and will, along with any rights of Owner, retain all common law, statutory, and other reserved rights, in addition to the copyright. All copies of these documents, except Contractor's set, shall be returned or suitably accounted for to A/E, on request, upon completion of the Work.
- B. Drawings and Specifications to be used only for this Project: The Drawings, Specifications, and other documents prepared by the A/E, if any, and copies thereof furnished to

Contractor, are for use solely with respect to this Project. They are not to be used by Contractor or any Subcontractor on other projects or for additions to this Project outside the scope of the Work without the specific written consent of Owner (and A/E, if applicable). Contractor and Subcontractors are granted a limited license to use and reproduce applicable portions of the Drawings, Specifications, and other documents prepared by A/E, if any, appropriate to and for use in the execution of their Work.

- C. Shop Drawing license granted to Owner: Contractor and all Subcontractors grant a non-exclusive license to Owner, without additional cost or royalty, to use for its own purposes (including reproduction) all Shop Drawings, together with the information and diagrams contained therein, prepared by Contractor or any Subcontractor. In providing Shop Drawings, Contractor and all Subcontractors warrant that they have authority to grant to Owner a license to use the Shop Drawings, and that such license is not in violation of any copyright or other intellectual property right. Contractor agrees to defend and indemnify Owner pursuant to the indemnity provisions in Section 5.03 and 5.22 from any violations of copyright or other intellectual property rights arising out of Owner's use of the Shop Drawings hereunder, or to secure for Owner, at Contractor's own cost, licenses in conformity with this section.
- D. Shop Drawings to be used only for this Project: The Shop Drawings and other submittals prepared by Contractor, Subcontractors of any tier, or its or their equipment or material suppliers, and copies thereof furnished to Contractor, are for use solely with respect to this Project. They are not to be used by Contractor or any Subcontractor of any tier, or material or equipment supplier, on other projects or for additions to this Project outside the scope of the Work without the specific written consent of Owner. The Contractor, Subcontractors of any tier, and material or equipment suppliers are granted a limited license to use and reproduce applicable portions of the Shop Drawings and other submittals appropriate to and for use in the execution of their Work under the Contract Documents.

PART 5 – PERFORMANCE

5.01 CONTRACTOR CONTROL AND SUPERVISION

- A. Contractor responsible for means and methods of construction: Contractor shall supervise and direct the Work, using its best skill and attention, and shall perform the Work in a skillful manner. Contractor shall be solely responsible for and have control over construction means, methods, techniques, sequences, and procedures and for coordinating all portions of the Work, unless the Contract Documents give other specific instructions concerning these matters. Contractor shall disclose its means and methods of construction when requested by Owner.
- B. Compliance with laws: The Contractor shall abide by the provisions of all applicable Washington statutes and regulations and all those provisions of the county and city municipal codes that apply in the jurisdiction where the Project is located. Although a number of statutes are referenced in the Contract Documents, these references are not meant to be a complete list and should not be relied upon as such.
- C. WSSP compliance: The Parties acknowledge and agree that to the extent this Project receives Washington State funds for school construction, design and construction of the Project must meet at least the Washington Sustainable Schools Protocol (WSSP) requirements in accordance with Chapter 39.35D RCW. The Contractor will provide all services, including, but not limited to, labor and materials, required to construct the Project such that it fully meets all WSSP requirements in effect at the time the Project, or any portion thereof, is completed. The Contractor will fully participate in any and all activities

required by state law or regulations or the WSSP to achieve WSSP compliance and approval, including, but not limited to, providing all applications, documentation, and reports (annual or otherwise) requested by Owner or mandated by the WSSP. The Contractor will manage environmental issues and implement and document the Project's WSSP requirements, including but not limited to: monitoring the submittal process to ensure WSSP compliance, training Subcontractors in WSSP requirements, reviewing design changes during construction for WSSP impacts and informing the Owner of said impacts, ensuring installed products are WSSP compliant, and assembling, maintaining, and submitting all records to document WSSP compliance, including but not limited to annual reports.

- D. Competent superintendent required: Performance of the Work shall be directly supervised by a competent superintendent who has authority to act for Contractor. The superintendent must be satisfactory to the Owner and shall not be changed without the prior written consent of Owner. Owner may require Contractor to remove the superintendent from the Work or Project site, if Owner reasonably deems the superintendent incompetent, careless, or otherwise objectionable, provided Owner has first notified Contractor in writing and allowed a reasonable period for transition.
- E. Contractor responsible for acts and omissions of self and agents: Contractor shall be responsible to Owner for acts and omissions of Contractor, Subcontractors, and their employees and agents.
- F. Unemployment Compensation: Pursuant to Chapter 50.24 RCW ("Contributions by Employers") in general and RCW 50.24.130 in particular, the Contractor shall pay contributions for wages for personal services performed under this Contract or arrange for a bond acceptable to the Commissioner of the ESD.
- G. Contractor to employ competent and disciplined workforce: Contractor shall enforce strict discipline and good order among Contractor's employees and other persons carrying out the Work, including observance of badging, drug testing, and all smoking, tobacco, drug, alcohol, parking, safety, weapons, background checks, sexual harassment, and other rules governing the conduct of personnel at Owner's property and at the Project site.
 - 1. Copies of the Owner's policies and procedures applicable to the Project are available at <https://www.longviewschools.com/about/policies-procedures> .
 - 2. Contractor shall not permit employment of unfit persons or persons not properly skilled in tasks assigned to them.
 - 3. No employees of either Contractor or any of its Subcontractors of any tier shall harass, intimidate, have physical contact with, or engage in other verbal or physical conduct or communication of a sexual, intimidating, or harassing nature with students, parents, volunteers, or Owner's directors, officers, or employees, nor create an intimidating, hostile, or offensive environment.
 - 4. Without limiting the foregoing, Contractor shall remove from the Work and Project site any employee, agent, or other person who has violated Owner's policies and/or procedures or otherwise engaged in actions that Owner reasonably considers objectionable without change in the Contract Sum or Contract Time.
 - 5. Contractor shall also ensure by appropriate provisions in each subcontract agreement that Contractor may remove from the Work and Work site any Subcontractor or Subcontractor's employee who has violated District

policies/procedures or engaged in such action without change in the Contract Sum or Contract Time.

- G. Drug-Free Workplace: The Contractor and all Subcontractors of any tier shall fully comply with all applicable federal, state, and local laws and regulations regarding maintaining a drug-free workplace, including the Drug-Free Workplace Act of 1988. Any person not fit for duty for any reason, including the use of alcohol, controlled substances, or drugs, shall immediately be removed from the Work.
- H. Tobacco-Free Environment: Pursuant to RCW 28A.210.310, smoking or use of any kind of lighted pipe, cigar, cigarette, vaping device, or any other lighted smoking equipment, tobacco material, or smokeless tobacco product is prohibited on all District property.
- I. Weapons-Free Environment: The Contractor and its employees, agents, and Subcontractors of any tier shall not bring onto the Project site or onto any Owner property any firearm or any other type of weapon described in either RCW 9.41.280(1) or RCW 9.41.250. Any person violating this Section shall immediately be removed from the Work, and such a violation shall be grounds for termination of this Contract for cause at the Owner's discretion.
- J. Background checks: All employees of Contractor and Subcontractors of any tier who may have unsupervised access to students shall undergo a record check through the Washington State Patrol criminal investigation system under RCW 43.43.830-.834, RCW 10.97.030, and RCW 10.97.050, and through the Federal Bureau of Investigation, before working at the Project site. The record check will include a fingerprint check using a complete Washington State criminal identification fingerprint card. Contractor will provide the results of the record check to the subject of the records and to Owner. Contractor will pay all costs of the requirements set forth in this provision. When necessary, applicants may be employed on a conditional basis pending completion of the background check. In addition, any agreements between the Contractor and Subcontractors of any tier who will perform services for Owner will include this provision requiring the Subcontractor to comply with RCW 28A.400.303.
- K. Crimes Against Children: The Contractor will prohibit any employee of the Contractor from working at the Project site who has pleaded guilty to or been convicted of any crime enumerated in RCW 28A.400.322, as now or hereafter amended. Any failure to comply with this Section 5.01K will be grounds for the Owner to immediately terminate the Contract. In addition, any agreements between the Contractor and Subcontractors of any tier who will perform services for the Owner will include this provision requiring the Subcontractor to prohibit any employee of said Subcontractor from working at a public school or the Project site who has pleaded guilty to or been convicted of any crime enumerated in RCW 28A.400.322.
- L. Contractor to keep Project documents on site: Contractor shall keep on the Project site a copy of the Drawings, Specifications, addenda, reviewed Shop Drawings, and permits and permit drawings.
- M. Work during off hours: When work is to be performed during other than normal working hours or on Longview School District holidays, Contractor shall give Owner prior notice. Any construction activity between the hours of 10:00 p.m. to 6:00 a.m. is subject to approval of Owner.
- N. Without limiting Section 9.01, failure to comply with these requirements in Section 5.01 is grounds for immediate termination of the Contract for cause.

5.02 PERMITS, FEES, AND NOTICES

- A. Contractor to obtain and pay for permits: Unless otherwise provided in the Contract Documents, Contractor shall pay for and obtain all permits, licenses, and inspections necessary for proper execution and completion of the Work. Prior to Final Acceptance, the approved, signed permits shall be delivered to Owner.
- B. Allowances for permit fees: If allowances for permits or utility fees are called for in the Contract Documents and set forth in Contractor's bid, and the actual costs of those permits or fees differ from the allowances in the Contract Documents, the difference shall be adjusted by Change Order.
- C. Contractor to comply with all applicable laws: Contractor shall comply with and give notices required by all federal, state, and local laws, ordinances, rules, regulations, and lawful orders of public authorities applicable to performance of the Work.

5.03 PATENTS AND ROYALTIES

Payment, indemnification, and notice: Contractor is responsible for, and shall pay, all royalties and license fees. Contractor shall defend, indemnify, and hold Owner harmless from any costs, expenses, and liabilities arising out of the infringement by Contractor of any patent, copyright, or other intellectual property right used in the Work; however, provided that Contractor gives prompt notice, Contractor shall not be responsible for such defense or indemnity when a particular design, process, or product of a particular manufacturer or manufacturers is required by the Contract Documents. If Contractor has reason to believe that use of the required design, process, or product constitutes an infringement of a patent or copyright, it shall promptly notify Owner of such potential infringement.

5.04 PREVAILING WAGES

- A. Contractor to Pay Prevailing Wages: Contractor shall pay the prevailing rate of wages to all workers, laborers, or mechanics employed in the performance of any part of the Work in accordance with Chapter 39.12 RCW and the rules and regulations of the Department of Labor and Industries. The schedule of prevailing wage rates for the locality or localities of the Work, is determined by the Industrial Statistician of the Department of Labor and Industries. It is the Contractor's responsibility to verify the applicable prevailing wage rate.
- B. Statement of Intent to Pay Prevailing Wages: Before payment is made by the Owner to the Contractor for any work performed by the Contractor and Subcontractors whose work is included in the application for payment, the Contractor shall submit, or shall have previously submitted to the Owner for the Project, a Statement of Intent to Pay Prevailing Wages, approved by the Department of Labor and Industries, certifying the rate of hourly wage paid and to be paid each classification of laborers, workers, or mechanics employed upon the Work by Contractor and Subcontractors. Such rates of hourly wage shall not be less than the prevailing wage rate.
- C. Affidavit of Wages Paid: Prior to release of retainage, the Contractor shall submit to the Owner an Affidavit of Wages Paid, approved by the Department of Labor and Industries, for the Contractor and every Subcontractor, of any tier, that performed work on the Project.
- D. Disputes: Disputes regarding prevailing wage rates shall be referred for arbitration to the Director of the Department of Labor and Industries. The arbitration decision shall be final and conclusive and binding on all parties involved in the dispute as provided for by RCW

39.12.060.

- E. Statement with Pay Application; Post Statements of Intent at Jobsite: Each Application for Payment submitted by Contractor shall state that prevailing wages have been paid in accordance with the pre-filed statement(s) of intent, as approved. Copies of the approved intent statement(s) shall be posted on the job site with the address and telephone number of the Industrial Statistician of the Department of Labor and Industries where a complaint or inquiry concerning prevailing wages may be made.
- F. Contractor to Pay for Statements of Intent and Affidavits: In compliance with Chapter 296-127 WAC, Contractor shall pay to the Department of Labor and Industries the currently established fee(s) for each statement of intent and/or affidavit of wages paid submitted to the Department of Labor and Industries for certification.
- G. Certified Payrolls: Consistent with WAC 296-127-320, the Contractor and any Subcontractor shall submit a certified copy of payroll records if requested.

5.05 HOURS OF LABOR

- A. Overtime: Contractor shall comply with all applicable provisions of Chapter 49.28 RCW, which are incorporated herein by reference. Pursuant to that statute, no laborer, worker, or mechanic employed by Contractor, any Subcontractor, or any other person performing or contracting to do the whole or any part of the Work, shall be permitted or required to work more than eight (8) hours in any one calendar day, provided, that in cases of extraordinary emergency, such as danger to life or property, the hours of work may be extended, but in such cases the rate of pay for time employed in excess of eight (8) hours of each calendar day shall be not less than one and one-half (1.5) times the rate allowed for this same amount of time during eight (8) hours of service.
- B. 4-10 Agreements: Notwithstanding the preceding paragraph, Chapter 49.28 RCW permits the Contractor or a Subcontractor subject to those provisions to enter into an agreement with its employees in which the employees work up to ten (10) hours in a calendar day. No such agreement may provide that the employees work ten (10) hour days for more than four (4) calendar days a week. Any such agreement is subject to approval by the employees. The overtime provisions of Chapter 49.28 RCW shall not apply to the hours, up to forty (40) hours per week, worked pursuant to any such agreement.

5.06 NONDISCRIMINATION

- A. Discrimination prohibited by applicable laws: Discrimination in all phases of employment is prohibited by, among other laws and regulations, Title VII of the Civil Rights Act of 1964, the Vietnam Era Veterans Readjustment Act of 1974, Sections 503 and 504 of the Vocational Rehabilitation Act of 1973, the Equal Employment Act of 1972, the Age Discrimination Act of 1967, the Americans with Disabilities Act of 1990, the Civil Rights Act of 1991, Presidential Executive Order 11246, Executive Order 11375, the Washington State Law Against Discrimination, RCW 49.60, and Gubernatorial Executive Order 85-09. These laws and regulations establish minimum requirements for affirmative action and fair employment practices which Contractor must meet.
- B. During performance of the Work:
 - 1. Protected Classes: Contractor shall not discriminate against any employee or applicant for employment because of race, creed, color, national origin, sex, age, marital status, or the presence of any physical, sensory, or mental disability, Vietnam

era veteran status, ordisabled veteran status, nor commit any other unfair practices as defined in Chapter 49.60 RCW.

2. Advertisements to state nondiscrimination: Contractor shall, in all solicitations or advertisements for employees placed by or for it, state that all qualified applicants will be considered for employment, without regard to race, creed, color, national origin, sex, age, marital status, or the presence of any physical, sensory, or mental disability.
3. Contractor to notify unions and others of nondiscrimination: Contractor shall send to each labor union, employment agency, or representative of workers with which it has a collective bargaining agreement or other contract or understanding a notice advising the labor union, employment agency, or workers' representative of Contractor's obligations according to the Contract Documents and Chapter 49.60 RCW.
4. Owner and State access to Contractor records: Contractor shall permit access to its books, records, and accounts, and to its premises by Owner, and by the Washington State Human Rights Commission, for the purpose of investigation to ascertain compliance with this section of the Contract Documents.
5. Passthrough provisions to Subcontractors: Contractor shall include the provisions of this section in every Subcontract.

- C. Provisions for Aged and Handicapped Persons: The Contractor shall comply with applicable statutory provisions relating to public works of Chapter 70.92 RCW ("Provisions in Buildings for Aged and Handicapped Persons") and the federal Americans with Disabilities Act (ADA) and federal implementing regulations.

5.07 SAFETY PRECAUTIONS

- A. Contractor responsible for safety: Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Work. The Contractor shall comply with pertinent provisions of Chapter 49.17 RCW ("Washington Industrial Safety and Health Act") and Chapter 296-155 WAC ("Safety Standards for Construction Work").
- B. Contractor safety responsibilities: In carrying out its responsibilities according to the Contract Documents, Contractor shall protect the lives and health of employees performing the Work and other persons who may be affected by the Work; prevent damage to materials, supplies, and equipment whether on site or stored off-site; and prevent damage to other property at the site or adjacent thereto. Contractor shall comply with all applicable laws, ordinances, rules, regulations, and orders of any public body having jurisdiction for the safety of persons or property or to protect them from damage, injury, or loss; shall erect and maintain all necessary safeguards for such safety and protection; and shall notify owners of adjacent property and utilities when prosecution of the Work may affect them.
- C. Contractor to maintain safety records: Contractor shall maintain an accurate record of exposure data on all incidents relating to the Work resulting in death, traumatic injury, occupational disease, or damage to property, materials, supplies, or equipment. Contractor shall immediately report any such incident to Owner. Owner shall, at all times, have a right of access to all records of exposure.
- D. Contractor to provide HazMat training: Contractor shall provide all persons working on the

Project site with information and training on hazardous chemicals in their work at the time of their initial assignment, and whenever a new hazard is introduced into their work area.

1. Information. At a minimum, Contractor shall inform persons working on the Project site of:
 - a. WAC: The requirements of Chapter 296-62 WAC, General Occupational Health Standards;
 - b. Presence of hazardous chemicals: Any operations in their work area where hazardous chemicals are present; and
 - c. Hazard communications program: The location and availability of written hazard communication programs, including the required list(s) of hazardous chemicals and material safety data sheets required by Chapter 296-62 WAC.
 2. Training. At a minimum, Contractor shall provide training for persons working on the Project site which includes:
 - a. Detecting hazardous chemicals: Methods and observations that may be used to detect the presence or release of a hazardous chemical in the work area (such as monitoring conducted by the employer, continuous monitoring devices, visual appearance or odor of hazardous chemicals when being released, etc.);
 - b. Hazards of chemicals: The physical and health hazards of the chemicals in the work area;
 - c. Protection from hazards: The measures such persons can take to protect themselves from these hazards, including specific procedures Contractor, or its Subcontractors, or others have implemented to protect those on the Project site from exposure to hazardous chemicals, such as appropriate work practices, emergency procedures, and personal protective equipment to be used; and
 - d. Hazard communications program: The details of the hazard communications program developed by Contractor, or its Subcontractors, including an explanation of the labeling system and the material safety data sheet, and how employees can obtain and use the appropriate hazard information.
- E. Hazardous, toxic, or harmful substances: Contractor's responsibility for hazardous, toxic, or harmful substances shall include the following duties:
1. Illegal use of dangerous substances: Contractor shall not keep, use, dispose, transport, generate, or sell on or about the Project site, any substances now or hereafter designated as, or which are subject to regulation as, hazardous, toxic, dangerous, or harmful by any federal, state, or local law, regulation, statute or ordinance (hereinafter collectively referred to as "hazardous substances"), in violation of any such law, regulation, statute, or ordinance, but in no case shall any such hazardous substance be stored more than 90 Days on the Project site.
 2. Contractor notifications of spills, failures, inspections, and fines: Contractor shall promptly notify Owner of all spills or releases of any hazardous substances which are otherwise required to be reported to any regulatory agency and pay the cost of cleanup. Contractor shall promptly notify Owner of all failures to comply with any

federal, state, or local law, regulation, or ordinance; all inspections of the Project site by any regulatory entity concerning the same; all regulatory orders or fines; and all responses or interim cleanup actions taken by or proposed to be taken by any government entity or private party on the Project site.

- F. Public safety and traffic: All Work shall be performed with due regard for the safety of the public. Contractor shall perform the Work so as to cause a minimum of interruption of vehicular traffic or inconvenience to pedestrians. All arrangements to care for such traffic shall be Contractor's responsibilities. All expenses involved in the maintenance of traffic by way of detours shall be borne by Contractor.
- G. Contractor to act in an emergency: In an emergency affecting the safety of life, the Work, or adjoining property, Contractor is permitted to act, at its discretion, to prevent such threatened loss or injury, and Contractor shall so act if so authorized or instructed.
- H. No duty of safety by Owner or A/E: Nothing provided in this section shall be construed as imposing any duty upon Owner (or A/E if applicable) with regard to, or as constituting any express or implied assumption of control or responsibility over, Project site safety, or over any other safety conditions relating to employees or agents of Contractor or any of its Subcontractors, or the public.
- I. In order to receive a Notice to Proceed, the Contractor must submit the following to Owner:
 - 1. A copy of its company Safety Program. The Safety Program shall contain, at a minimum, the following:
 - a. Organization, including names of individuals who will perform safety duties, titles, work assignments, authority and reporting relationships.
 - b. Training Program. Who, how and when training is provided; method of employee training concerning safety rules and procedures; training in use of protective equipment.
 - c. Protective Equipment. List of personal protective equipment to be provided to employees.
 - d. Accident Prevention and Loss Control Plan. Work site inspection and hazard correction procedures; disciplinary procedures for safety infractions; accident response, investigation and reporting procedures.
 - e. Regular Safety Meetings. On-site weekly or other frequency as appropriate, safety meetings mandatory for all employees.
- J. Prior to commencing any Work onsite, Contractor shall submit an appropriate site specific safety plan for Owner's acceptance. The plan must be tailored to the needs of the particular project and to the types of hazards involved, and be in compliance with WISHA requirements. Contractor shall not begin any on-site Work until the site-specific safety plan has been accepted by Owner.
- K. COVID-19 Safety Compliance: Contractor shall comply with Owner's COVID-19 safety and mitigation protocols, as they may be revised from time to time and ensure that its owner(s) and employees, and those of its Subcontractors, comply with such mitigation protocols. Contractor shall also comply with and ensure its owner(s) and employees, and those of its Subcontractors, comply with Proclamation 21-14.1 *et seq.*

5.08 OPERATIONS, MATERIAL HANDLING, AND STORAGE AREAS

- A. Limited storage areas: Contractor shall confine all operations, including storage of materials, to Owner-approved areas.
- B. Temporary buildings and utilities at Contractor expense: Temporary buildings (e.g., storage sheds, shops, offices) and utilities may be provided by Contractor only with the consent of Owner and without expense to Owner. The temporary buildings and utilities shall be removed by Contractor at its expense upon completion of the Work.
- C. Roads and vehicle loads: Contractor shall use only established roadways or temporary roadways authorized by Owner. When materials are transported in prosecuting the Work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by federal, state, or local law or regulation.
- D. Ownership and reporting by Contractor of demolished materials: Ownership and control of all materials or facility components to be demolished or removed from the Project site by Contractor shall immediately vest in Contractor upon severance of the component from the facility or severance of the material from the Project site. Contractor shall be responsible for compliance with all laws governing the storage and ultimate disposal. Contractor shall provide Owner with a copy of all manifests and receipts evidencing proper disposal when required by Owner or applicable law.
- E. Contractor responsible for care of materials and equipment on-site: Contractor shall be responsible for the proper care and protection of its materials and equipment delivered to the Project site. Materials and equipment may be stored on the premises subject to approval of Owner. When Contractor uses any portion of the Project site as a shop, Contractor shall be responsible for any repairs, patching, or cleaning arising from such use.
- F. Contractor responsible for loss of materials and equipment: Contractor shall protect and be responsible for any damage or loss to the Work, or to the materials or equipment until the date of Substantial Completion, and shall repair or replace without cost to Owner any damage or loss that may occur, except damages or loss caused by the acts or omissions of Owner. Contractor shall also protect and be responsible for any damage or loss to the Work, or to the materials or equipment, after the date of Substantial Completion, and shall repair or replace without cost to Owner any such damage or loss that might occur, to the extent such damages or loss are caused by the acts or omissions of Contractor, or any Subcontractor.

5.09 PRIOR NOTICE OF EXCAVATION

- A. Excavation defined; Use of locator services: "Excavation" means an operation in which earth, rock, or other material on or below the ground is moved or otherwise displaced by any means, except the tilling of soil less than 12 inches in depth for agricultural purposes, or road ditch maintenance that does not change the original road grade or ditch flow line. Before commencing any excavation, Contractor shall provide notice of the scheduled commencement of excavation to all owners of underground facilities or utilities, through locator services.

5.10 UNFORESEEN PHYSICAL CONDITIONS

- A. Notice requirement for concealed or unknown conditions: If Contractor encounters conditions at the site which are subsurface or otherwise concealed physical conditions which differ materially from those indicated in the Contract Documents, or unknown physical

conditions of an unusual nature which differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents, then Contractor shall give written notice to Owner promptly and in no event later than seven (7) Days after the first observance of the conditions. Conditions shall not be disturbed prior to such notice.

- B. Adjustment in Contract Time and Contract Sum: If such conditions differ materially and cause a change in Contractor's cost of, or time required for, performance of any part of the Work, the Contractor may be entitled to an equitable adjustment in the Contract Time or Contract Sum, or both, provided it makes a request therefore as provided in Part 7.
- C. Mold: If Contractor encounters mold in the course of its work, it shall notify Owner to evaluate what action might be necessary. Contractor shall ensure that all building materials used during the work are dry prior to incorporation into the Work. If Contractor encounters water intrusion from any source it shall take immediate steps to ensure that any effected material is dry according to generally accepted industry standards

5.11 PROTECTION OF EXISTING STRUCTURES, EQUIPMENT, VEGETATION, UTILITIES AND IMPROVEMENTS

- A. Contractor to protect and repair property: Contractor shall protect from damage all existing structures, equipment, improvements, utilities, and vegetation: at or near the Project site; and on adjacent property of a third party, the locations of which are made known to or should be known by Contractor. Contractor shall repair any damage, including that to the property of a third party, resulting from failure to comply with the requirements of the Contract Documents or failure to exercise reasonable care in performing the Work. If Contractor fails or refuses to repair the damage promptly, Owner may have the necessary work performed and charge the cost to Contractor.
- B. Tree and vegetation protection: Contractor shall only remove trees when specifically authorized to do so, and shall protect vegetation that will remain in place.

5.12 LAYOUT OF WORK

- A. Advanced planning of the Work: Contractor shall plan and lay out the Work in advance of operations so as to coordinate all work without delay or revision.
- B. Layout responsibilities: Contractor shall lay out the Work from any Owner-established baselines and benchmarks indicated on the Drawings, and shall be responsible for all field measurements in connection with the layout. Contractor shall furnish, at its own expense, all stakes, templates, platforms, equipment, tools, materials, and labor required to lay out any part of the Work. Contractor shall be responsible for executing the Work to the lines and grades that may be established. Contractor shall be responsible for maintaining or restoring all stakes and other marks established.

5.13 MATERIAL AND EQUIPMENT

- A. Contractor to provide new and equivalent equipment and materials: All equipment, material, and articles incorporated into the Work shall be new and of the most suitable grade for the purpose intended, unless otherwise specifically provided in the Contract Documents. References in the Specifications to equipment, material, articles, or patented processes by tradename, make, or catalog number, shall be regarded as establishing a standard quality and shall not be construed as limiting competition. Contractor may, at its option, use any equipment, material, article, or process that, in the judgment of the Owner (or A/E if

applicable), is equal to that named in the specifications, unless otherwise specifically provided in the Contract Documents. Contractor shall ensure that all equipment, materials, and articles incorporated into the Work shall be free of asbestos.

- B. Contractor responsible for fitting parts together: Contractor shall do all cutting, fitting, or patching that may be required to make its several parts fit together properly, or receive or be received by work of others set forth in, or reasonably implied by, the Contract Documents. Contractor shall not endanger any work by cutting, excavating, or otherwise altering the Work and shall not cut or alter the work of any other contractor unless approved in advance by Owner.
- C. Owner may reject defective Work: Should any of the Work be found defective, or in any way not in accordance with the Contract Documents, this work, in whatever stage of completion, may be rejected by Owner.

5.14 AVAILABILITY AND USE OF UTILITY SERVICES

- A. Owner to provide and charge for utilities: Owner shall make all reasonable utilities available to Contractor from existing outlets and supplies, as specified in the Contract Documents. Unless otherwise provided in the Contract Documents, the utility service consumed shall be charged to or paid for by Contractor at prevailing rates charged to Owner or, where the utility is produced by Owner, at reasonable rates determined by Owner. Contractor will carefully conserve any utilities furnished.
- B. Contractor to install temporary connections and meters: Contractor shall, at its expense and in a skillful manner satisfactory to Owner, install and maintain all necessary temporary connections and distribution lines, together with appropriate protective devices, and all meters required to measure the amount of each utility used for the purpose of determining charges. Prior to the date of Final Acceptance, Contractor shall remove all temporary connections, distribution lines, meters, and associated equipment and materials.

5.15 TESTS AND INSPECTIONS

- A. Contractor to provide for all testing and inspection of Work: Contractor shall maintain an adequate testing and inspection program and perform such tests and inspections as are necessary or required to ensure that the Work conforms to the requirements of the Contract Documents. Contractor shall be responsible for inspection and quality surveillance of all its Work and all Work performed by any Subcontractor. Unless otherwise provided, Contractor shall make arrangements for such tests, inspections, and approvals with an independent testing laboratory or entity acceptable to Owner, or with the appropriate public authority, and shall bear all related costs of tests, inspections, and approvals. Contractor shall give Owner timely notice of when and where tests and inspections are to be made. Contractor shall maintain complete inspection records and make them available to Owner.
- B. Owner may conduct tests and inspections: Owner may, at any reasonable time, conduct such inspections and tests as it deems necessary to ensure that the Work is in accordance with the Contract Documents. Owner shall promptly notify Contractor if an inspection or test reveals that the Work is not in accordance with the Contract Documents. Unless the subject items are expressly accepted by Owner, such Owner inspection and tests are for the sole benefit of Owner and do not:
 - 1. Constitute or imply acceptance;
 - 2. Relieve Contractor of responsibility for providing adequate quality control measures;

3. Relieve Contractor of responsibility for risk of loss or damage to the Work, materials, or equipment;
 4. Relieve Contractor of its responsibility to comply with the requirements of the Contract Documents; or
 5. Impair Owner's right to reject defective or nonconforming items, or to avail itself of any other remedy to which it may be entitled.
- C. Inspections or inspectors do not modify Contract Documents: Neither observations by an inspector retained by Owner, the presence or absence of such inspector on the site, nor inspections, tests, or approvals by others, shall relieve Contractor from any requirement of the Contract Documents, nor is any such inspector authorized to change any term or condition of the Contract Documents.
- D. Contractor responsibilities on inspections: Contractor shall promptly furnish, without additional charge, all facilities, labor, material, and equipment reasonably needed for performing such safe and convenient inspections and tests as may be required by Owner. Owner may charge Contractor any additional cost of inspection or testing when Work is not ready at the time specified by Contractor for inspection or testing, or when prior rejection makes reinspection or retest necessary. Owner shall perform its inspections and tests in a manner that will cause no undue delay in the Work.

5.16 CORRECTION OF NONCONFORMING WORK

- A. Work covered by Contractor without inspection: If a portion of the Work is covered contrary to the requirements in the Contract Documents, it must, if required in writing by Owner, be uncovered for Owner's observation and be replaced at the Contractor's expense and without change in the Contract Time.
- B. Payment provisions for uncovering covered Work: If, at any time prior to Final Completion, Owner desires to examine the Work, or any portion of it, which has been covered, Owner may request to see such Work and it shall be uncovered by Contractor. If such Work is in accordance with the Contract Documents, the Contractor shall be entitled to an adjustment in the Contract Sum for the costs of uncovering and replacement, and, if completion of the Work is thereby delayed, an adjustment in the Contract Time, provided it makes such a request as provided in Part 7. If such Work is not in accordance with the Contract Documents, the Contractor shall pay the costs of examination and reconstruction.
- C. Contractor to correct and pay for non-conforming Work: Contractor shall promptly correct Work found by Owner not to conform to the requirements of the Contract Documents, whether observed before or after Substantial Completion and whether or not fabricated, installed, or completed. Contractor shall bear all costs of correcting such nonconforming Work, including additional testing and inspections.
- D. Contractor's compliance with warranty provisions: If, within one (1) year after the date of Substantial Completion of the Work or designated portion thereof, or within one year after the date for commencement of any system warranties established under Section 6.08, or within the terms of any applicable special warranty required by the Contract Documents, any of the Work is found by the Owner to be not in accordance with the requirements of the Contract Documents, Contractor shall correct it promptly after receipt of written notice from Owner to do so. Owner shall give such notice promptly after discovery of the condition. This period of one year shall be extended, with respect to portions of Work first performed after Substantial Completion, by the period of time between Substantial Completion and the

actual performance of the Work. Contractor's duty to correct with respect to Work repaired or replaced shall run for one year from the date of repair or replacement. Obligations under this paragraph shall survive Final Acceptance.

- E. Contractor to remove non-conforming Work: Contractor shall remove from the Project site portions of the Work which are not in accordance with the requirements of the Contract Documents and are neither corrected by Contractor nor accepted by Owner.
- F. Owner may charge Contractor for non-conforming Work: If Contractor fails to correct nonconforming Work within a reasonable time after written notice to do so, Owner may replace, correct, or remove the nonconforming Work and charge the cost thereof to the Contractor.
- G. Contractor to pay for damaged Work during correction: Contractor shall bear the cost of correcting destroyed or damaged Work, whether completed or partially completed, caused by Contractor's correction or removal of Work which is not in accordance with the requirements of the Contract Documents.
- H. No Period of limitation on other requirements: Nothing contained in this section shall be construed to establish a period of limitation with respect to other obligations which Contractor might have according to the Contract Documents. Establishment of the time period of one year as described in Section 5.16D relates only to the specific obligation of Contractor to correct the Work, and has no relationship to the time within which the Contractor's obligation to comply with the Contract Documents may be sought to be enforced, including the time within which such proceedings may be commenced.
- I. Owner may accept non-conforming Work and charge Contractor: If Owner prefers to accept Work which is not in accordance with the requirements of the Contract Documents, Owner may do so instead of requiring its removal and correction, in which case the Contract Sum may be reduced as appropriate and equitable.

5.17 CLEAN UP

Contractor to keep site clean and leave it clean: Contractor shall at all times keep the Project site, including hauling routes, infrastructures, utilities, and storage areas, free from accumulations of waste materials. Before completing the Work, Contractor shall remove from the premises its rubbish, tools, scaffolding, equipment, and materials. Upon completing the Work, Contractor shall leave the Project site in a clean, neat, and orderly condition satisfactory to Owner. If Contractor fails to clean up as provided herein, and after reasonable notice from Owner, Owner may do so and the cost thereof shall be charged to Contractor.

5.18 ACCESS TO WORK

Owner and A/E access to Work site: Contractor shall provide Owner (and A/E if applicable) access to the Work in progress wherever located.

5.19 OTHER CONTRACTS

Owner may award other contracts; Contractor to cooperate: Owner may undertake or award other contracts for additional work at or near the Project site. Contractor shall reasonably cooperate with the other contractors and with Owner's employees and shall carefully adapt scheduling and perform the Work in accordance with these Contract Documents to reasonably accommodate the other work.

5.20 SUBCONTRACTORS AND SUPPLIERS

- A. Subcontractor Responsibility: The Contractor shall include the language of this paragraph in each of its first-tier subcontracts and shall require each of its Subcontractors to include the same language of this section in each of their subcontracts, adjusting only as necessary the terms used for the contracting parties. Upon request of the Owner, the Contractor shall promptly provide documentation to the Owner demonstrating that the Subcontractor meets the subcontractor responsibility criteria below. The requirements of this paragraph apply to all Subcontractors regardless of tier. At the time of subcontract execution, the Contractor shall verify that each of its first-tier Subcontractors meets the following bidder responsibility criteria:
1. Have a current certificate of registration as a contractor in compliance with Chapter 18.27 RCW, which must have been in effect at the time of Subcontract bid submittal;
 2. Have a current Washington Unified Business Identifier (UBI) number;
 3. If applicable, have:
 - a. Industrial Insurance (workers' compensation) coverage for the Subcontractor's employees working in Washington, as required in Title 51 RCW;
 - b. A Washington Employment Security Department number, as required in Title 50 RCW;
 - c. A Washington Department of Revenue state excise tax registration number, as required in Title 82 RCW;
 - d. An electrical contractor license, if required by Chapter 19.28 RCW;
 - e. An elevator contractor license, if required by Chapter 70.87 RCW.
 4. Not be disqualified from bidding on any public works contract under RCW 39.06.010 or RCW 39.12.065(3).
 5. On a project subject to the apprenticeship utilization requirements in RCW 39.04.320, not have been found out of compliance by the Washington state apprenticeship and training council for working apprentices out of ratio, without appropriate supervision, or outside their approved work processes as outlined in their standards of apprenticeship under Chapter 49.04 RCW for the one-year period immediately preceding the date of the Owner's first advertisement of the project.
- B. Provide names of Subcontractors and use qualified firms: Before submitting the first Application for Payment, Contractor shall furnish in writing to Owner the names, addresses, and telephone numbers of all Subcontractors, as well as suppliers providing materials in excess of \$2,500. Contractor shall utilize Subcontractors and suppliers which are experienced and qualified and meet the requirements of the Contract Documents, if any. Contractor shall not utilize any Subcontractor or supplier to whom the Owner has a reasonable objection, and shall obtain Owner's written consent before making any substitutions or additions.
- C. Subcontracts in writing and passthrough provision: All Subcontracts must be in writing. By appropriate written agreement, Contractor shall require each Subcontractor, so far as applicable to the Work to be performed by the Subcontractor, to be bound to Contractor by terms of the Contract Documents, and to assume toward Contractor all the obligations and responsibilities which Contractor assumes toward Owner in accordance with the Contract

Documents. Each Subcontract shall preserve and protect the rights of Owner in accordance with the Contract Documents with respect to the Work to be performed by the Subcontractor so that subcontracting thereof will not prejudice such rights. Where appropriate, Contractor shall require each Subcontractor to enter into similar agreements with Sub-Subcontractors. However, nothing in this paragraph shall be construed to alter the contractual relations between Contractor and its Subcontractors with respect to insurance or bonds.

- D. Coordination of Subcontractors; Contractor responsible for Work: Contractor shall schedule, supervise, and coordinate the operations of all Subcontractors. No Subcontracting of any of the Work shall relieve Contractor from its responsibility for the performance of the Work in accordance with the Contract Documents or any other obligations of the Contract Documents.
- E. Automatic assignment of subcontracts: Each subcontract agreement for a portion of the Work is hereby assigned by Contractor to Owner provided that:
1. Effective only after termination and Owner approval: The assignment is effective only after termination by Owner for cause pursuant to Section 9.01 and only for those Subcontracts which Owner accepts by notifying the Subcontractor in writing; and
 2. Owner assumes Contractor's responsibilities: After the assignment is effective, Owner will assume all future duties and obligations toward the Subcontractor which Contractor assumed in the Subcontract.
 3. Impact of bond: The assignment is subject to the prior rights of the surety, if any, obligated under any bond provided in accordance with the Contract Documents.

5.21 WARRANTY OF CONSTRUCTION

- A. Contractor warranty of Work: In addition to any special warranties provided elsewhere in the Contract Documents, Contractor warrants that all Work conforms to the requirements of the Contract Documents and is free of any defect in equipment, material, or design furnished, or workmanship performed by Contractor.
- B. Contractor responsibilities: With respect to all warranties, express or implied, for Work performed or materials furnished according to the Contract Documents, Contractor shall:
1. Obtain warranties: Obtain all warranties that would be given in normal commercial practice;
 2. Warranties for benefit of Owner: Require all warranties to be executed, in writing, for the benefit of Owner;
 3. Enforcement of warranties: Enforce all warranties for the benefit of Owner, if directed by Owner; and
 4. Contractor responsibility for subcontractor warranties: Be responsible to enforce any subcontractor's, manufacturer's, or supplier's warranties should they extend beyond the period specified in the Contract Documents.
- C. Warranties beyond Final Acceptance: The obligations under this section shall survive Final Acceptance.

5.22 INDEMNIFICATION

- A. To the fullest extent permitted by law and subject to the conditions of this Section 5.22, the Contractor shall defend, indemnify, and hold harmless the Owner, its directors, officers, employees, consultants, project manager, students, and volunteers, the A/E, the A/E's consultants, agents and employees of any of them, and the successors and assigns of any of them ("Indemnified Parties") from and against all claims, damages, losses, and expenses, direct and indirect, or consequential, including but not limited to costs, design professional and consultant fees, and attorneys' fees incurred on such claims and in proving the right to indemnification ("Claims"), arising out of or resulting from performance of the Work, provided that such Claim is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), but only to the extent caused by the negligent acts or omissions of the Contractor, a Subcontractor of any tier, their agents, or anyone directly or indirectly employed by them, or anyone for whose acts they may be liable ("Indemnitor"), regardless of whether or not such Claim is caused in part by a party indemnified hereunder.
1. The Contractor shall fully defend, indemnify, and hold harmless the Indemnified Parties for the sole negligence of the Indemnitor.
 2. If such claims are caused by or are resulting from the sole negligence of the Indemnified Parties or their agents or employees, then the Contractor shall have no duty to defend, indemnify, and hold harmless the Indemnified Parties.
 3. If such claims are caused by or are resulting from the concurrent negligence of (a) the Indemnified Parties or the Indemnified Parties' agents or employees, and (b) the Contractor or the Contractor's agents or employees, then the Contractor shall be obligated to defend, indemnify, and hold harmless the Indemnified Parties only to the extent of the Indemnitor's negligence.
- B. The Contractor agrees to being added by the Owner as a party to any arbitration or litigation with third parties in which the Owner alleges indemnification or contribution from the Contractor, any of its Subcontractors of any tier, anyone directly or indirectly employed by any of them, or anyone for whose acts any of them may be liable. The Contractor agrees that all of its Subcontractors of any tier shall, in their subcontracts, similarly stipulate; in the event any does not, the Contractor shall be liable in place of such Subcontractor(s) of any tier.
- C. To the extent any portion of this 5.22 is stricken by a court of competent jurisdiction for any reason, all remaining provisions shall retain their vitality and effect.
- D. The obligations of the Contractor under this Section 5.22 shall not be construed to negate, abridge, or otherwise reduce any other right or obligations of indemnity which would otherwise exist as to any party or person described in this Section 5.22. To the extent the wording of this Section 5.22 would reduce or eliminate an available insurance coverage of the Contractor or the Owner, this Section 5.22 shall be considered modified to the extent that such insurance coverage is not affected.
- E. In claims against any person or entity indemnified under this Section 5.22 by an employee of the Contractor, a Subcontractor of any tier, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, the indemnification obligation under Section 5.22 shall not be limited by a limitation on amount or type of damages, compensation, or benefits payable by or for the Contractor or a Subcontractor of any tier under workers' compensation acts, disability benefit acts, or other employee benefit acts. After mutual negotiation of the parties, the Contractor waives immunity as to the Owner and its consultants only under Title 51 RCW ("Industrial Insurance)." IF THE CONTRACTOR DOES NOT AGREE WITH THIS WAIVER, IT MUST PROVIDE A WRITTEN NOTICE TO THE OWNER

PRIOR TO THE DATE FOR THE RECEIPT OF BIDS, OR THE CONTRACTOR WILL BE DEEMED TO HAVE NEGOTIATED AND WAIVED THIS IMMUNITY.

- F. Contractor will immediately report to the Owner any failure by the Contractor, a Subcontractor of any tier, or any third party observed by the Contractor to comply with applicable laws, regulations, or ordinances while performing the Work or upon the Project, including, but not limited to, those related to environmental compliance, spills, unauthorized fill in waters of the State (including wetlands), water quality standards, noise, and air quality.

PART 6 – PAYMENTS AND COMPLETION

6.01 CONTRACT SUM

Owner shall pay Contract Sum: Owner shall pay Contractor the Contract Sum plus state sales tax for performance of the Work, in accordance with the Contract Documents.

6.02 SCHEDULE OF VALUES

Contractor to submit Schedule of Values: Before submitting its first Application for Payment, Contractor shall submit to Owner for approval a breakdown allocating the total Contract Sum to each principal category of work, in such detail as requested by Owner ("Schedule of Values"). The approved Schedule of Values shall include appropriate amounts for demobilization, record drawings, O&M manuals, and any other requirements for Project closeout, and shall be used by Owner as the basis for progress payments. Payment for Work shall be made only for and in accordance with those items included in the Schedule of Values.

6.03 APPLICATION FOR PAYMENT

- A. Monthly Application for Payment with substantiation: At monthly intervals, unless determined otherwise by Owner, Contractor shall submit to Owner an itemized Application for Payment for Work completed in accordance with the Contract Documents and the approved Schedule of Values. Each application shall be supported by such substantiating data as Owner may require.
- B. Contractor certifies Subcontractors paid: By submitting an Application for Payment, Contractor is certifying that all Subcontractors have been paid, less earned retainage in accordance with RCW 60.28.011, as their interests appeared in the last preceding certificate of payment. By submitting an Application for Payment, Contractor is recertifying that the representations set forth in Section 1.03, are true and correct, to the best of Contractor's knowledge, as of the date of the Application for Payment.
- C. Reconciliation of Work with Progress Schedule: At the time it submits an Application for Payment, Contractor shall analyze and reconcile, to the satisfaction of Owner, the actual progress of the Work with the Progress Schedule.
- D. Payment for material delivered to site or stored off-site: If authorized by Owner, the Application for Payment may include request for payment for material delivered to the Project site and suitably stored, or for completed preparatory work. Payment may similarly be requested for material stored off the Project site, provided Contractor complies with or furnishes satisfactory evidence of the following:
1. Suitable facility or location: The material will be placed in a facility or location that is structurally sound, dry, lighted and suitable for the materials to be stored;
 2. Facility or location within 10 miles of Project: The facility or location is located within

a 10-mile radius of the Project. Other locations may be utilized, if approved in writing, by Owner;

3. Facility or location exclusive to Project's materials: Only materials for the Project are stored within the facility or location (or a secure portion of a facility or location set aside for the Project);
4. Insurance provided on materials in facility or location: Contractor furnishes Owner a certificate of insurance extending Contractor's insurance coverage for damage, fire, and theft to cover the full value of all materials stored, or in transit;
5. Facility or location locked and secure: The facility or location (or secure portion thereof) is continuously under lock and key, and only Contractor's authorized personnel shall have access;
6. Owner right of access to facility or location: Owner shall at all times have the right of access in company of Contractor;
7. Contractor assumes total responsibility for stored materials: Contractor and its surety assume total responsibility for the stored materials; and
8. Contractor provides documentation and Notice when materials moved to site: Contractor furnishes to Owner certified lists of materials stored, bills of lading, invoices, and other information as may be required, and shall also furnish Notice to Owner when materials are moved from storage to the Project site.

6.04 PROGRESS PAYMENTS

- A. Owner to pay within 30 Days: Owner shall make progress payments, in such amounts as Owner determines are properly due, within 30 Days after receipt of a properly executed Application for Payment. Owner shall notify Contractor in accordance with Chapter 39.76 RCW if the Application for Payment does not comply with the requirements of the Contract Documents.
- B. Withholding retainage; Options for retainage: Owner shall retain five (5) percent of the amount of each progress payment until forty-five (45) Days after Final Acceptance and receipt of all documents required by law or the Contract Documents, including, at Owner's request, consent of surety to release of the retainage. In accordance with Chapter 60.28 RCW, Contractor may request that monies reserved be retained in a fund by Owner, deposited by Owner in a bank or savings and loan, or placed in escrow with a bank or trust company to be converted into bonds and securities to be held in escrow with interest to be paid to Contractor. Owner may authorize in writing Contractor to provide an appropriate bond in lieu of the retained funds.
- C. Title passes to Owner upon payment: Title to all Work and materials covered by a progress payment shall pass to Owner at the time of such payment free and clear of all liens, claims, security interests, and encumbrances. Passage of title shall not, however, relieve Contractor from any of its duties and responsibilities for the Work or materials, or waive any rights of Owner to insist on full compliance by Contractor with the Contract Documents.
- D. Interest on unpaid balances: Payments due and unpaid in accordance with the Contract Documents shall bear interest as specified in Chapter 39.76 RCW.

6.05 PAYMENTS WITHHELD

- A. Owner's right to withhold payment: Owner may withhold or, on account of subsequently discovered evidence, nullify the whole or part of any payment to such extent as may be necessary to protect Owner from loss or damage for reasons including but not limited to:
1. Non-compliant Work: Work not in accordance with the Contract Documents;
 2. Remaining Work to cost more than unpaid balance: Reasonable evidence that the Work required by the Contract Documents cannot be completed for the unpaid balance of the Contract Sum;
 3. Owner correction or completion Work: Work by Owner to correct defective Work or complete the Work in accordance with Section 5.16;
 4. Contractor's failure to perform: Contractor's failure to perform in accordance with the Contract Documents; or
 5. Contractor's negligent acts or omissions: Cost or liability that may occur to Owner as the result of Contractor's fault or negligent acts or omissions.
- B. Owner to notify Contractor of withholding for unsatisfactory performance: In any case where part or all of a payment is going to be withheld for unsatisfactory performance, Owner shall notify Contractor in accordance with Chapter 39.76 RCW.

6.06 RETAINAGE AND BOND CLAIM RIGHTS

Chapters 39.08 RCW and 60.28 RCW incorporated by reference: Chapters 39.08 RCW and 60.28 RCW, concerning the rights and responsibilities of Contractor and Owner with regard to the performance and payment bonds and retainage, are made a part of the Contract Documents by reference as though fully set forth herein.

6.07 SUBSTANTIAL COMPLETION

Substantial Completion defined: Substantial Completion is the stage in the progress of the Work (or portion thereof designated and approved by Owner) when the construction is sufficiently complete, in accordance with the Contract Documents, so Owner has full and unrestricted use and benefit of the facilities (or portion thereof designated and approved by Owner) for the use for which it is intended. All Work other than incidental corrective and incidental punch list work shall be completed. Substantial Completion shall not have been achieved if all systems and parts are not functional, if utilities are not connected and operating normally, if all required occupancy permits have not been issued, or if the Work is not accessible by normal vehicular and pedestrian traffic routes. The date Substantial Completion is achieved shall be established in writing by Owner. Contractor may request an early date of Substantial Completion which must be approved by Change Order. Owner's occupancy of the Work or designated portion thereof does not necessarily indicate that Substantial Completion has been achieved.

6.08 PRIOR OCCUPANCY

- A. Prior Occupancy defined; Restrictions: Owner may, upon written notice thereof to Contractor, take possession of or use any completed or partially completed portion of the Work ("Prior Occupancy") at any time prior to Substantial Completion. Unless otherwise agreed in writing, Prior Occupancy shall not: be deemed an acceptance of any portion of the Work; accelerate the time for any payment to Contractor; prejudice any rights of Owner provided by any insurance, bond, guaranty, or the Contract Documents; relieve Contractor of the risk of loss or any of the obligations established by the Contract Documents; establish a date for termination or partial termination of the assessment of liquidated damages; or

constitute a waiver of claims.

- B. Damage; Duty to repair and warranties: Notwithstanding anything in the preceding paragraph, Owner shall be responsible for loss of or damage to the Work resulting from Prior Occupancy. Contractor's one (1) year duty to repair any system warranties shall begin on building systems activated and used by Owner as agreed in writing by Owner and Contractor.

6.09 FINAL COMPLETION, ACCEPTANCE, AND PAYMENT

- A. Final Completion defined: Final Completion shall be achieved when the Work is fully and finally complete in accordance with the Contract Documents. The date Final Completion is achieved shall be established by Owner in writing, but in no case shall Final Completion constitute Final Acceptance, which is a subsequent, separate, and distinct action.
- B. Final Acceptance defined: Final Acceptance shall be achieved when the Contractor has completed the requirements of the Contract Documents. The date Final Acceptance is achieved shall be established by Owner in writing. Prior to Final Acceptance, Contractor shall, in addition to all other requirements in the Contract Documents, submit to Owner a written notice of any outstanding disputes or claims between Contractor and any of its Subcontractors, including the amounts and other details thereof. Neither Final Acceptance, nor final payment, shall release Contractor or its sureties from any obligations of these Contract Documents or the payment and performance bonds, or constitute a waiver of any claims by Owner arising from Contractor's failure to perform the Work in accordance with the Contract Documents.
- C. Final payment waives Claim rights: Acceptance of final payment by Contractor, or any Subcontractor, shall constitute a waiver and release to Owner of all claims by Contractor, or any such Subcontractor, for an increase in the Contract Sum or the Contract Time, and for every actor omission of Owner relating to or arising out of the Work, except for those Claims made in accordance with the procedures, including the time limits, set forth in Part 8.

PART 7 – CHANGES

7.01 CHANGE IN THE WORK

- A. Changes in Work, Contract Sum, and Contract Time by Change Order: Owner may, at any time and without notice to Contractor's surety, order additions, deletions, revisions, or other changes in the Work. These changes in the Work shall be incorporated into the Contract Documents through the execution of Change Orders. If any change in the Work ordered by Owner causes an increase or decrease in the Contract Sum or the Contract Time, an equitable adjustment shall be made as provided in Section 7.02 or 7.03, respectively, and such adjustment(s) shall be incorporated into a Change Order.
- B. Owner may request COP from Contractor: If Owner desires to order a change in the Work, it may request a written Change Order Proposal (COP) from Contractor. Contractor shall submit a Change Order Proposal within fourteen (14) Days of the request from Owner, or within such other period as mutually agreed. Contractor's Change Order Proposal shall be full compensation for implementing the proposed change in the Work, including any adjustment in the Contract Sum or Contract Time, and including compensation for all delays in connection with such change in the Work and for any expense or inconvenience, disruption of schedule, or loss of efficiency or productivity occasioned by the change in the Work.

- C. COP negotiations: Upon receipt of the Change Order Proposal, or a request for equitable adjustment in the Contract Sum or Contract Time, or both, as provided in Sections 7.02 and 7.03, Owner may accept or reject the proposal, request further documentation, or negotiate acceptable terms with Contractor. Pending agreement on the terms of the Change Order, Owner may direct Contractor to proceed immediately with the Change Order Work. Contractor shall not proceed with any change in the Work until it has obtained Owner's approval. All Work done pursuant to any Owner-directed change in the Work shall be executed in accordance with the Contract Documents.
- D. Change Order as full payment and final settlement: If Owner and Contractor reach agreement on the terms of any change in the Work, including any adjustment in the Contract Sum or Contract Time, such agreement shall be incorporated in a Change Order. The Change Order shall constitute full payment and final settlement of all claims for time and for direct, indirect, and consequential costs, including costs of delays, inconvenience, disruption of schedule, or loss of efficiency or productivity, related to any Work either covered or affected by the Change Order, or related to the events giving rise to the request for equitable adjustment.
- E. Failure to agree upon terms of Change Order; Final offer and Claims: If Owner and Contractor are unable to reach agreement on the terms of any change in the Work, including any adjustment in the Contract Sum or Contract Time, Contractor may at any time in writing, request a final offer from Owner. Owner shall provide Contractor with its written response within thirty (30) Days of Contractor's request. Owner may also provide Contractor with a final offer at any time. If Contractor rejects Owner's final offer, or the parties are otherwise unable to reach agreement, Contractor's only remedy shall be to file a Claim as provided in Part 8.
- F. Field Authorizations: The Owner may direct the Contractor to proceed with a change in the work through a written Field Authorization (also referred to as a Field Order) when the time required to price and execute a Change Order would impact the Project.

The Field Authorization shall describe and include the following:

1. The scope of work;
2. An agreed upon maximum not-to-exceed amount;
3. Any estimated change to the Contract Time;
4. The method of final cost determination in accordance with the requirements of Part 7 of the General Conditions;
5. The supporting cost data to be submitted in accordance with the requirements of Part 7 of the General Conditions;

Upon satisfactory submittal by the Contractor and approval by the Owner of supporting cost data, a Change Order will be executed. The Owner will not make payment to the Contractor for Field Authorization work until that work has been incorporated into an executed Change Order.

7.02 CHANGE IN THE CONTRACT SUM

A. General Application

1. Contract Sum changes only by Change Order: The Contract Sum shall only be

changed by a Change Order. Contractor shall include any request for a change in the Contract Sum in its Change Order Proposal.

2. Owner fault or negligence as basis for change in Contract Sum: If the cost of Contractor's performance is changed due to the fault or negligence of Owner, or anyone for whose acts Owner is responsible, Contractor shall be entitled to make a request for an equitable adjustment in the Contract Sum in accordance with the following procedure. No change in the Contract Sum shall be allowed to the extent: Contractor's changed cost of performance is due to the fault or negligence of Contractor, or anyone for whose acts Contractor is responsible; the change is concurrently caused by Contractor and Owner; or the change is caused by an act of Force Majeure as defined in Section 3.05.
 - a. Notice and record keeping for equitable adjustment: A request for an equitable adjustment in the Contract Sum shall be based on written notice delivered to Owner within seven (7) Days of the occurrence of the event giving rise to the request. For purposes of this part, "occurrence" means when Contractor knew, or in its diligent prosecution of the Work should have known, of the event giving rise to the request. If Contractor believes it is entitled to an adjustment in the Contract Sum, Contractor shall immediately notify Owner and begin to keep and maintain complete, accurate, and specific daily records. Contractor shall give Owner access to any such records and, if requested shall promptly furnish copies of such records to Owner.
 - b. Content of notice for equitable adjustment; Failure to comply: Contractor shall not be entitled to any adjustment in the Contract Sum for any occurrence of events or costs that occurred more than seven (7) Days before Contractor's written notice to Owner. The written notice shall set forth, at a minimum, a description of: the event giving rise to the request for an equitable adjustment in the Contract Sum; the nature of the impacts to Contractor and its Subcontractors of any tier, if any; and to the extent possible the amount of the adjustment in Contract Sum requested. Failure to properly give such written notice shall, to the extent Owner's interests are prejudiced, constitute a waiver of Contractor's right to an equitable adjustment.
 - c. Contractor to provide supplemental information: Within thirty (30) Days of the occurrence of the event giving rise to the request, unless Owner agrees in writing to allow an additional period of time to ascertain more accurate data, Contractor shall supplement the written notice provided in accordance with Subsection (a), above, with additional supporting data. Such additional data shall include, at a minimum: the amount of compensation requested, itemized in accordance with the procedure set forth herein; specific facts, circumstances, and analysis that confirms not only that Contractor suffered the damages claimed, but that the damages claimed were actually a result of the act, event, or condition complained of and that the Contract Documents provide entitlement to an equitable adjustment to Contractor for such act, event, or condition; and documentation sufficiently detailed to permit an informed analysis of the request by Owner. When the request for compensation relates to a delay, or other change in Contract Time, Contractor shall demonstrate the impact on the critical path, in accordance with Section 7.03C. Failure to provide such additional information and

documentation within the time allowed or within the format required shall, to the extent Owner's interests are prejudiced, constitute a waiver of Contractor's right to an equitable adjustment.

- d. Contractor to proceed with Work as directed: Pending final resolution of any request made in accordance with this paragraph, unless otherwise agreed in writing, Contractor shall proceed diligently with performance of the Work.
 - e. Contractor to combine requests for same event together: Any requests by Contractor for an equitable adjustment in the Contract Sum and in the Contract Time that arise out of the same event(s) shall be submitted together.
3. Methods for calculating Change Order amount: The value of any Work covered by a Change Order, or of any request for an equitable adjustment in the Contract Sum, shall be determined by one of the following methods:
- a. Fixed Price: On the basis of a fixed price as determined in Section 7.02B.
 - b. Unit Prices: By application of unit prices to the quantities of the items involved as determined in Section 7.02C.
 - c. Time and Materials: On the basis of time and material as determined in Section 7.02D.
 - d. Fixed price method is default; Owner may direct otherwise: When Owner has requested Contractor to submit a Change Order Proposal, Owner may direct Contractor as to which method in the paragraph immediately above to use when submitting its proposal. Otherwise, Contractor shall determine the value of the Work, or of a request for an equitable adjustment, on the basis of the fixed price method.

B. Change Order Pricing – Fixed Price

Procedures: When the fixed price method is used to determine the value of any Work covered by a Change Order, or of a request for an equitable adjustment in the Contract Sum, the following procedures shall apply:

- 1. Breakdown and itemization of details on COP: Contractor's COP, or request for adjustment in the Contract Sum, shall be accompanied by a complete itemization of the costs, including labor, material, Subcontractor costs, and overhead and profit. The costs shall be itemized in the manner set forth below, and shall be submitted on breakdown sheets in a form approved by Owner.
- 2. Use of industry standards in calculating costs: All costs shall be calculated based upon appropriate industry standard methods of calculating labor, material quantities, and equipment costs.
- 3. Costs contingent on Owner's actions: If any of Contractor's pricing assumptions are contingent upon anticipated actions of Owner, Contractor shall clearly state them in the proposal or request for an equitable adjustment.
- 4. Markups on additive and deductive Work: The cost of any additive or deductive changes in the Work shall be calculated as set forth below, except that overhead and profit shall not be included on deductive changes in the Work. Where a change in the Work involves additive and deductive work by the same Contractor or

Subcontractor, small tools, overhead, profit, bond, and insurance markups will apply to the net difference.

5. Breakdown not required if change less than \$1,000: If the total cost of the change in the Work or request for equitable adjustment does not exceed \$1,000, Contractor shall not be required to submit a breakdown if the description of the change in the Work or request for equitable adjustment is sufficiently definitive for Owner to determine fair value.
6. Breakdown required if change between \$1,000 and \$2,500: If the total cost of the change in the Work or request for equitable adjustment is between \$1,000 and \$2,500, Contractor may submit a breakdown in the following level of detail if the description of the change in the Work or if the request for equitable adjustment is sufficiently definitive to permit the Owner to determine fair value:
 - a. Lump sum labor;
 - b. Lump sum material;
 - c. Lump sum equipment usage;
 - d. Overhead and profit as set forth below; and
 - e. Insurance and bond costs as set forth below.
7. Components of increased cost: Any request for adjustment of Contract Sum based upon the fixed price method shall include only the following items:
 - a. Craft labor costs: These are the labor costs determined by multiplying the estimated or actual additional number of craft hours needed to perform the change in the Work by the hourly labor costs. Craft hours should cover direct labor, as well as indirect labor due to trade inefficiencies. When estimating labor hours for electrical work, such hours shall be no greater than the Labor Units for specific items included in the "Normal" project conditions column of the NECA Manual of Labor Units, most recent edition. When estimating labor hours for mechanical work, such hours shall be no greater than 75% of the Labor Units for specific items included in the MCAA Web-Based Estimating Manual (WebLEM), subject to the assumptions and notes in the WebLEM, except that the Labor Units for "Hangers, Sleeves, & Inserts" shall be no greater than 50% of the WebLEM Labor Units. Special exceptions for electrical and mechanical work may be made for work having to be performed under extraordinary conditions. Such exceptions shall be identified and explained in any applicable pricing proposals and shall be subject to approval by Owner. The hourly costs shall be based on the following:
 - (1) Basic wages and benefits: Hourly rates and benefits as stated on the Department of Labor and Industries approved "statement of intent to pay prevailing wages" or a higher amount if approved by the Owner. Direct supervision shall be a reasonable percentage not to exceed fifteen (15) percent of the cost of direct labor. No supervision markup shall be allowed in a Change Order that contains direct labor costs for a working supervisor's hours (including any category of foreman).

- (2) Worker's insurance: Direct contributions to the State of Washington for industrial insurance; medical aid; and supplemental pension, by the class and rates established by the Department of Labor and Industries.
 - (3) Federal insurance: Direct contributions required by the Federal Insurance Compensation Act; Federal Unemployment Tax Act; and the State Unemployment Compensation Act.
 - (4) Travel allowance: Travel allowance and/or subsistence, if applicable, not exceeding those allowances established by regional labor union agreements, which are itemized and identified separately.
 - (5) Safety: Cost incurred due to the Washington Industrial Safety and Health Act, which shall be a reasonable percentage not to exceed two (2) of the sum of the amounts calculated in (1), (2), and (3) above.
- b. Material costs: This is an itemization of the quantity and cost of materials needed to perform the change in the Work. Material costs shall be developed first from actual known costs, including, but not limited to, Contractor's supplier(s)' actual cost(s) available from the standard industry pricing guide "Trade Service." If those are not available, material costs shall be developed second from supplier quotations. If those are not available, material costs shall be developed third from other standard industry pricing guides. Material costs shall include all available discounts. Freight costs, express charges, or special delivery charges shall be itemized.
- c. Equipment costs: This is an itemization of the type of equipment and the estimated or actual length of time the construction equipment appropriate for the Work is or will be used on the change in the Work. Costs will be allowed for construction equipment only if used solely for the changed Work, or for additional rental costs actually incurred by the Contractor. The Contractor's cost for utility vehicles and other items such as pickup trucks, vans, flatbed trucks, storage trailers, containers, etc., that are already in use or planned for use on the Project will not be compensated in Change Order work except for the time that, in the opinion of the Owner, such items: (1) are directly and necessarily used for the performance of the change work; and (2) the cost of using such items has not been included within the Contractor's total project overhead costs. Equipment charges shall be computed on the basis of actual invoice costs or if owned, from the current edition of one of the following sources:
- (1) Associated General Contractors Washington State Department of Transportation (AGC-WSDOT) Equipment Rental Agreement current edition, on the Contract execution date.
 - (2) The National Electrical Contractors Association for equipment used on electrical work. Equipment pricing shall be no greater than seventy-five (75) percent of NECA monthly rates.
 - (3) The Mechanical Contractors Association of America for equipment used on mechanical work.

The EquipmentWatch Rental Rate Blue Book shall be used as a basis for

establishing rental rates of equipment not listed in the above sources. The maximum rate for standby equipment shall not exceed that shown in the AGC-WSDOT Equipment Rental Agreement, current edition on the Contract execution date.

- d. Allowance for small tools, expendables & consumable supplies: Small tools consist of tools which cost \$1,000 or less and are normally furnished by the performing Contractor. The maximum rate for small tools shall not exceed the following:

- (1) For Contractor: three (3) percent of direct labor costs.
- (2) For Subcontractors: five (5) percent of direct labor costs.

Expendables and consumables supplies directly associated with the change in Work must be itemized.

- e. Subcontractor costs: This is defined as payments Contractor makes to Subcontractors for change Work performed by Subcontractors of any tier. The Subcontractors' cost of Work shall be calculated and itemized in the same manner as prescribed herein for Contractor.

- f. Allowance for overhead: This is defined as costs of any kind attributable to direct and indirect delay, acceleration, or impact, added to the total cost to Owner of any change in the Contract Sum. If the Contractor is compensated under Section 7.03D, the amount of such compensation shall be reduced by the amount Contractor is otherwise entitled to under this Subsection (f). This allowance shall compensate Contractor for all non-craft labor, temporary construction facilities, field engineering, schedule updating, as-built drawings, home office cost, B&O taxes, office engineering, estimating costs, additional overhead because of extended time, and any other cost incidental to the change in the Work. It shall be strictly limited in all cases to a reasonable amount, mutually acceptable, or if none can be agreed upon to an amount not to exceed the rates below:

- (1) Projects less than \$3 million: For projects where the Contract Award Amount is under \$3 million, the following shall apply:
 - (a) Contractor markup on Contractor Work: For Contractor, for any Work actually performed by Contractor's own forces, sixteen (16) percent of the first \$50,000 of the cost, and four (4) percent of the remaining cost, if any.
 - (b) Subcontractor markup for Subcontractor Work: For each Subcontractor (including lower-tier Subcontractors), for any Work actually performed by its own forces, sixteen (16) percent of the first \$50,000 of the cost, and four (4) percent of the remaining cost, if any.
 - (c) Contractor markup for Subcontractor Work: For Contractor, for any work performed by its Subcontractor(s), six (6) percent of the first \$50,000 of the amount due each Subcontractor, and four (4) percent of the remaining amount, if any.

- (d) Subcontractor markup for lower-tier Subcontractor Work: For each Subcontractor, for any Work performed by its Subcontractor(s) of any lower tier, four (4) percent of the first \$50,000 of the amount due the Sub-Subcontractor, and two (2) percent of the remaining amount, if any.
 - (e) Basis of cost applicable for markup: The cost to which overhead is to be applied shall be developed in accordance with Sections 7.02B.7.a-e.
- (2) Projects more than \$3 million: For projects where the Contract Award Amount is equal to or exceeds \$3 million, the following shall apply:
 - (f) Contractor markup on Contractor Work: For Contractor, for any Work actually performed by Contractor's own forces, twelve (12) percent of the first \$50,000 of the cost, and four (4) percent of the remaining cost, if any.
 - (g) Subcontractor markup for Subcontractor Work: For each Subcontractor (including lower-tier Subcontractors), for any Work actually performed by its own forces, twelve (12) percent of the first \$50,000 of the cost, and four (4) percent of the remaining cost, if any.
 - (h) Contractor markup for Subcontractor Work: For Contractor, for any Work performed by its Subcontractor(s), four (4) percent of the first \$50,000 of the amount due each Subcontractor, and two (2) percent of the remaining amount, if any.
 - (i) Subcontractor markup for lower tier Subcontractor Work: For each Subcontractor, for any Work performed by its Subcontractor(s) of any lower tier, four (4) percent of the first \$50,000 of the amount due the Sub-Subcontractor, and two (2) percent of the remaining amount, if any.
 - (j) Basis of cost applicable for markup: The cost to which overhead is to be applied shall be developed in accordance with Section 7.02B.7.a-e.
- g. Allowance for profit: Allowance for profit is an amount to be added to the cost of any change in Contract Sum, but not to the cost of change in Contract Time for which Contractor has been compensated pursuant to the conditions set forth in Section 7.03. It shall be limited to a reasonable amount, mutually acceptable, or if none can be agreed upon, to an amount not to exceed the rates below:
 - (1) Contractor / Subcontractor markup for self-performed Work: For Contractor or Subcontractor of any tier for work performed by their forces, six (6) percent of the cost developed in accordance with Sections 7.02B.7.a-e.
 - (2) Contractor / Subcontractor markup for Work performed at lower tier:

For Contractor or Subcontractor of any tier for work performed by a Subcontractor of a lower tier, four (4) percent of the subcontract cost developed in accordance with Section 7.02B.7.a-h.

- h. Insurance and bond premiums: Cost of change in insurance or bond premium: This is defined as:

(1) Contractor's liability insurance: The cost of any changes in Contractor's liability insurance arising directly from execution of the Change Order; and

(2) Payment and Performance Bond: The cost of the additional premium for Contractor's bond arising directly from the changed Work.

The cost of any change in insurance or bond premium shall be added after overhead and allowance for profit are calculated in accordance with Subsections f.-g, above.

C. Change Order Pricing – Unit Prices

1. Content of Owner authorization: Whenever Owner authorizes Contractor to perform Work on a unit-price basis, Owner's authorization shall clearly state:
 - a. Scope: Scope of work to be performed;
 - b. Reimbursement basis: Type of reimbursement including pre-agreed rates for material quantities; and
 - c. Reimbursement limit: Cost limit of reimbursement.
2. Contractor responsibilities: Contractor shall:
 - a. Cooperate with Owner and assist in monitoring the Work being performed. As requested by Owner, Contractor shall identify workers assigned to the Change Order Work and areas in which they are working;
 - b. Leave access as appropriate for quantity measurement; and
 - c. Not exceed any cost limit(s) without Owner's prior written approval.
3. Cost breakdown consistent with Fixed Price requirements: Contractor shall submit costs in accordance with Section 7.02B and satisfy the following requirements:
 - a. Unit prices must include overhead, profit, bond, and insurance premiums: Unit prices shall include reimbursement for all direct and indirect costs of the Work, including overhead, profit, bond, and insurance costs; and
 - b. Owner verification of quantities: Quantities must be supported by field measurement statements signed by Owner.

D. Change Order Pricing – Time-and-Material Prices

1. Content of Owner authorization: Whenever Owner authorizes Contractor to perform Work on a time-and-material basis, Owner's authorization shall clearly state:
 - a. Scope: Scope of Work to be performed;

- b. Reimbursement basis: Type of reimbursement, including pre-agreed rates, if any, for material quantities or labor; and
 - c. Reimbursement limit: Cost limit of reimbursement.
2. Contractor responsibilities: Contractor shall:
- a. Identify workers assigned: Cooperate with Owner and assist in monitoring the Work being performed. As requested by Owner, identify workers assigned to the Change Order Work and areas in which they are working;
 - b. Provide daily timesheets: Identify on daily time sheets all labor performed in accordance with this authorization. Submit copies of daily time sheets within two (2) working days for Owner's review.
 - c. Allow Owner to measure quantities: Leave access as appropriate for quantity measurement;
 - d. Perform Work efficiently: Perform all Work in accordance with this section as efficiently as possible; and
 - e. Not exceed Owner's cost limit: Not exceed any cost limit(s) without Owner's prior written approval.
3. Cost breakdown consistent with Fixed Price requirements: Contractor shall submit costs in accordance with Section 7.02B and additional verification supported by:
- a. Timesheets: Labor detailed on daily time sheets; and
 - b. Invoices: Invoices for material.

7.03 CHANGE IN THE CONTRACT TIME

- A. COP requests for Contract Time: The Contract Time shall only be changed by a Change Order. Contractor shall include any request for a change in the Contract Time in its Change Order Proposal.
- B. Time extension permitted if not Contractor's fault: If the time of Contractor's performance is changed due to an act of Force Majeure, or due to the fault or negligence of Owner or anyone for whose acts Owner is responsible, Contractor shall be entitled to make a request for an equitable adjustment in the Contract Time in accordance with the following procedure. No adjustment in the Contract Time shall be allowed to the extent Contractor's changed time of performance is due to the fault or negligence of Contractor, or anyone for whose acts Contractor is responsible.
- 1. Notice and record keeping for Contract Time request: A request for an equitable adjustment in the Contract Time shall be based on written notice delivered within seven (7) Days of the occurrence of the event giving rise to the request. If Contractor believes it is entitled to adjustment of Contract Time, Contractor shall immediately notify Owner and begin to keep and maintain complete, accurate, and specific daily records. Contractor shall give Owner access to any such record and if requested, shall promptly furnish copies of such record to Owner.
 - 2. Timing and content of Contractor's Notice: Contractor shall not be entitled to an adjustment in the Contract Time for any events that occurred more than seven (7)

Days before Contractor's written notice to Owner. The written notice shall set forth, at a minimum, a description of: the event giving rise to the request for an equitable adjustment in the Contract Time; the nature of the impacts to Contractor and its Subcontractors of any tier, if any; and to the extent possible the amount of the adjustment in Contract Time requested. Failure to properly give such written notice shall, to the extent Owner's interests are prejudiced, constitute a waiver of Contractor's right to an equitable adjustment.

3. Contractor to provide supplemental information: Within thirty (30) Days of the occurrence of the event giving rise to the request, unless Owner agrees in writing to allow an additional period of time to ascertain more accurate data, Contractor shall supplement the written notice provided in accordance with Section 7.03B.2 with additional supporting data. Such additional data shall include, at a minimum: the amount of delay claimed, itemized in accordance with the procedure set forth herein; specific facts, circumstances, and analysis that confirms not only that Contractor suffered the delay claimed, but that the delay claimed was actually a result of the act, event, or condition complained of, and that the Contract Documents provide entitlement to an equitable adjustment in Contract Time for such act, event, or condition; and supporting documentation sufficiently detailed to permit an informed analysis of the request by Owner. Failure to provide such additional information and documentation within the time allowed or within the format required shall, to the extent Owner's interests are prejudiced, constitute a waiver of Contractor's right to an equitable adjustment.
 4. Contractor to proceed with Work as directed: Pending final resolution of any request in accordance with this Section 7.03C unless otherwise agreed in writing, Contractor shall proceed diligently with performance of the Work.
- C. Contractor to demonstrate impact on critical path of schedule: Any change in the Contract Time covered by a Change Order, or based on a request for an equitable adjustment in the Contract Time, shall be limited to the change in the critical path of Contractor's schedule attributable to the change of Work or event(s) giving rise to the request for equitable adjustment. Any Change Order Proposal or request for an adjustment in the Contract Time shall demonstrate the impact on the critical path of the schedule. Contractor shall be responsible for showing clearly on the Progress Schedule that the change or event: had a specific impact on the critical path, and except in case of concurrent delay, was the sole cause of such impact; and could not have been avoided by resequencing of the Work or other reasonable alternatives.
- D. Cost of change in Contract Time: Contractor may request compensation for the cost of a change in Contract Time in accordance with this Section 7.03D, subject to the following conditions:
1. Must be solely fault of Owner or A/E: The change in Contract Time shall solely be caused by the fault or negligence of Owner (or A/E, if applicable);
 2. Procedures: Contractor shall follow the procedure set forth in Section 7.03B;
 3. Demonstrate impact on critical path: Contractor shall establish the extent of the change in Contract Time in accordance with Section 7.03C; and
 4. Limitations on daily costs: The daily cost of any change in Contract Time shall be limited to the items below, less the amount of any change in the Contract Sum the Contractor may otherwise be entitled to pursuant to Section 7.02B.7.f for any

change in the Work that contributed to this change in Contract Time:

- a. Non-productive supervision or labor: cost of nonproductive field supervision or labor extended because of delay;
- b. Weekly meetings and indirect activities: cost of weekly meetings or similar indirect activities extended because of the delay;
- c. Temporary facilities or equipment rental: cost of temporary facilities or equipment rental extended because of the delay;
- d. Insurance premiums: cost of insurance extended because of the delay;
- e. Overhead: general and administrative overhead in an amount to be agreed upon, but not to exceed three (3) percent of the Contract Award Amount divided by the originally specified Contract Time for each Day of the delay.

PART 8 – CLAIMS AND DISPUTE RESOLUTION

8.01 CLAIMS PROCEDURE

- A. Claim is Contractor's remedy: If the parties fail to reach agreement on the terms of any Change Order for Owner-directed Work as provided in Section 7.01, or on the resolution of any request for an equitable adjustment in the Contract Sum as provided in Section 7.02 or the Contract Time as provided in Section 7.03, Contractor's only remedy shall be to file a Claim with Owner as provided in this section.
- B. Claim filing deadline for Contractor: Contractor shall file its Claim within sixty (60) Days from Owner's final offer made in accordance with Section 7.01E, or by the date of Final Acceptance, whichever occurs first.
- C. Claim must cover all costs and be documented: The Claim shall be deemed to cover all changes in cost and time (including direct, indirect, impact, and consequential) to which Contractor may be entitled. It shall be fully substantiated and documented. At a minimum, the Claim shall contain the following information:
 1. Factual statement of Claim: A detailed factual statement of the Claim for additional compensation and time, if any, providing all necessary dates, locations, and items of Work affected by the Claim;
 2. Dates: The date on which facts arose which gave rise to the Claim;
 3. Owner and A/E employee's knowledgeable about Claim: The name of each employee of Owner (or A/E, if applicable) knowledgeable about the Claim;
 4. Support from Contract Documents: The specific provisions of the Contract Documents which support the Claim;
 5. Identification of other supporting information: The identification of any documents and the substance of any oral communications that support the Claim;
 6. Copies of supporting documentation: Copies of any identified documents, other than the Contract Documents, that support the Claim;
 7. Details on Claim for Contract Time: If an adjustment in the Contract Time is sought:

the specific days and dates for which it is sought; the specific reasons Contractor believes an extension in the Contract Time should be granted; and Contractor's analysis of its Progress Schedule to demonstrate the reason for the extension in Contract Time;

8. Details on Claim for adjustment of Contract Sum: If an adjustment in the Contract Sum is sought, the exact amount sought and a breakdown of that amount into the categories set forth in, and in the detail as required by Section 7.02; and
 9. Statement certifying Claim: A statement certifying, under penalty of perjury, that the Claim is made in good faith, that the supporting cost and pricing data are true and accurate to the best of Contractor's knowledge and belief, that the Claim is fully supported by the accompanying data, and that the amount requested accurately reflects the adjustment in the Contract Sum or Contract Time for which Contractor believes Owner is liable.
- D. Owner's response to Claim filed: After Contractor has submitted a fully documented Claim that complies with all applicable provisions of Parts 7 and 8, Owner shall respond, in writing, to Contractor as follows:
1. Response time for Claim less than \$50,000: If the Claim amount is less than \$50,000, with a decision within sixty (60) Days from the date the Claim is received; or
 2. Response time for Claim of \$50,000 or more: If the Claim amount is \$50,000 or more, with a decision within sixty (60) Days from the date the Claim is received, or with notice to Contractor of the date by which it will render its decision. Owner will then respond with a written decision in such additional time.
- E. Owner's review of Claim and finality of decision: To assist in the review of Contractor's Claim, Owner may visit the Project site, or request additional information, in order to fully evaluate the issues raised by the Claim. Contractor shall proceed with performance of the Work pending final resolution of any Claim. Owner's written decision as set forth above shall be final and conclusive as to all matters set forth in the Claim, unless Contractor follows the procedure set forth in Section 8.02.
- F. Continuing Contract performance: Pending final resolution of a Claim, and except as otherwise agreed in writing, Contractor shall proceed diligently with performance of the Contract and maintain Contractor's Construction Schedule, and the Owner shall continue to make payments in accordance with the Contract Documents.
- G. Waiver of Contractor rights for failure to comply with this Section: Any Claim of the Contractor against the Owner for damages, additional compensation, or additional time, shall be conclusively deemed to have been waived by the Contractor unless made in accordance with the requirements of this Section.

8.02 LITIGATION

- A. If Contractor disagrees with Owner's decision rendered in accordance with Section 8.01D, Contractor shall serve and file a lawsuit in an appropriate court within one-hundred and twenty (120) Days of Owner's decision. This requirement cannot be waived except by an explicit waiver signed by Owner. The failure to file a lawsuit within said one-hundred and twenty (120) Day period shall result in Owner's decision rendered in accordance with Section 8.01D being final and binding on Contractor and all of its Subcontractors.

- B. At any time, either before or after a lawsuit has been commenced by Contractor in accordance with Section 8.02A, Owner may require Contractor to participate in further mediation or arbitration, or both, in any forum or format as determined by Owner.
- C. Claims between Owner and Contractor, Contractor and its Subcontractors, Contractor (and A/E, if applicable), and Owner (and A/E, if applicable) shall, upon demand by Owner, be submitted in a single forum, or Owner may consolidate such Claims or join any of the above-named parties in the same forum.

8.03 **CLAIMS AUDITS**

- A. Owner may audit Claims: All Claims filed against Owner shall be subject to audit at any time following the filing of the Claim. Failure of Contractor, or Subcontractors of any tier, to maintain and retain sufficient records to allow Owner to verify all or a portion of the Claim or to permit Owner access to the books and records of Contractor, or Subcontractors of any tier, shall constitute a waiver of the Claim and shall bar any recovery.
- B. Contractor to make documents available: In support of Owner audit of any Claim, Contractor shall, upon request, promptly make available to Owner the following documents:
 - 1. Daily time sheets and supervisor's daily reports;
 - 2. Collective bargaining agreements;
 - 3. Insurance, welfare, and benefits records;
 - 4. Payroll registers;
 - 5. Earnings records;
 - 6. Payroll tax forms;
 - 7. Material invoices, requisitions, and delivery confirmations;
 - 8. Material cost distribution worksheet;
 - 9. Equipment records (list of company equipment, rates, etc.);
 - 10. Vendors', rental agencies', Subcontractors', and agents' invoices;
 - 11. Contracts between Contractor and each of its Subcontractors, and all lower-tier Subcontractor contracts and supplier contracts;
 - 12. Subcontractors' and agents' payment certificates;
 - 13. Cancelled checks (payroll and vendors);
 - 14. Job cost report, including monthly totals;
 - 15. Job payroll ledger;
 - 16. Planned resource loading schedules and summaries;
 - 17. General ledger;
 - 18. Cash disbursements journal;

19. Financial statements for all years reflecting the operations on the Work. In addition, the Owner may require, if it deems it appropriate, additional financial statements for three (3) years preceding execution of the Work;
 20. Depreciation records on all company equipment, whether these records are maintained by the company involved, its accountant, or others;
 21. If a source other than depreciation records is used to develop costs for Contractor's internal purposes in establishing the actual cost of owning and operating equipment, all such other source documents;
 22. All nonprivileged documents which relate to each and every Claim together with all documents which support the amount of any adjustment in Contract Sum or Contract Time sought by each Claim;
 23. Work sheets or software used to prepare the Claim establishing the cost components for items of the Claim including but not limited to labor, benefits and insurance, materials, equipment, Subcontractors, all documents that establish the time periods, individuals involved, the hours for the individuals, and the rates for the individuals; and
 24. Work sheets, software, and all other documents used by Contractor to prepare its bid.
- C. Contractor to provide facilities for audit and shall cooperate: The audit may be performed by employees of Owner or a representative of Owner. Contractor, and its Subcontractors, shall provide adequate facilities acceptable to Owner, for the audit during normal business hours. Contractor, and all Subcontractors, shall make a good faith effort to cooperate with Owner's auditors.

PART 9 – TERMINATION OF THE WORK

9.01 TERMINATION BY OWNER FOR CAUSE

- A. Notice to Terminate for Cause: Owner may, upon seven (7) Days' written notice to Contractor and to its surety, terminate (without prejudice to any right or remedy of Owner) the Work, or any part of it, for cause upon the occurrence of any one or more of the following events:
1. Contractor fails to prosecute Work: Contractor fails to prosecute the Work or any portion thereof with sufficient diligence to ensure Substantial Completion of the Work within the Contract Time;
 2. Contractor bankrupt: Contractor is adjudged bankrupt, makes a general assignment for the benefit of its creditors, or a receiver is appointed on account of its insolvency;
 3. Contractor fails to correct Work: Contractor fails in a material way to replace or correct Work not in conformance with the Contract Documents;
 4. Contractor fails to supply workers or materials: Contractor repeatedly fails to supply skilled workers or proper materials or equipment;
 5. Contractor failure to pay Subcontractors or labor: Contractor repeatedly fails to make prompt payment due to Subcontractors or for labor;
 6. Contractor violates laws: Contractor materially disregards or fails to comply with laws, ordinances, rules, regulations, or orders of any public authority having

jurisdiction; or

7. Contractor in material breach of Contract: Contractor is otherwise in material breach of any provision of the Contract Documents.
- B. Owner's actions upon termination: Upon termination, Owner may at its option:
1. Take possession of Project site: Take possession of the Project site and take possession of or use all materials, equipment, tools, and construction equipment and machinery thereon owned by Contractor to maintain the orderly progress of, and to finish, the Work;
 2. Accept assignment of Subcontracts: Accept assignment of subcontracts pursuant to Section 5.20; and
 3. Finish the Work: Finish the Work by whatever other reasonable method it deems expedient.
- C. Surety's role: Owner's rights and duties upon termination are subject to the prior rights and duties of the surety, if any, obligated under any bond provided in accordance with the Contract Documents.
- D. Contractor's required actions: When Owner terminates the Work in accordance with this section, Contractor shall take the actions set forth in Section 9.02B and shall not be entitled to receive further payment until the Work is accepted.
- E. Contractor to pay for unfinished Work: If the unpaid balance of the Contract Sum exceeds the cost of finishing the Work (including compensation for A/E's services, if applicable) and expenses made necessary thereby and any other extra costs or damages incurred by Owner in completing the Work, or as a result of Contractor's actions, such excess shall be paid to Contractor. If such costs exceed the unpaid balance, Contractor shall pay the difference to Owner. These obligations for payment shall survive termination.
- F. Contractor and Surety still responsible for Work performed: Termination of the Work in accordance with this section shall not relieve Contractor or its surety of any responsibilities for Work performed.
- G. Conversion of "Termination for Cause" to "Termination for Convenience": If Owner terminates Contractor for cause and it is later determined that none of the circumstances set forth in Section 9.01A exist, then such termination shall be deemed a termination for convenience pursuant to Section 9.02.

9.02 TERMINATION BY OWNER FOR CONVENIENCE

- A. Owner Notice of Termination for Convenience: Owner may, upon written notice, terminate (without prejudice to any right or remedy of Owner) the Work, or any part of it, for the convenience of Owner.
- B. Contractor response to termination Notice: Unless Owner directs otherwise, after receipt of a written notice of termination for either cause or convenience, Contractor shall promptly:
1. Cease Work: Stop performing Work on the date and as specified in the notice of termination;
 2. No further orders or Subcontracts: Place no further orders or Subcontracts for

materials, equipment, services or facilities, except as may be necessary for completion of such portion of the Work as is not terminated;

3. Cancel orders and Subcontracts: Cancel all orders and subcontracts, upon terms acceptable to Owner, to the extent that they relate to the performance of Work terminated;
 4. Assign orders and Subcontracts to Owner: Assign to Owner all of the right, title, and interest of Contractor in all orders and subcontracts;
 5. Take action to protect the Work: Take such action as may be necessary or as directed by Owner to preserve and protect the Work, Project site, and any other property related to this Project in the possession of Contractor in which Owner has an interest; and
 6. Continue performance not terminated: Continue performance only to the extent not terminated.
- C. Terms of adjustment in Contract Sum if Contract terminated: If Owner terminates the Work or any portion thereof for convenience, Contractor shall be entitled to make a request for an equitable adjustment for its reasonable direct costs incurred prior to the effective date of the termination, plus reasonable allowance for overhead and profit on Work performed prior to termination, plus the reasonable administrative costs of the termination, but shall not be entitled to any other costs or damages, whatsoever, provided however, the total sum payable upon termination shall not exceed the Contract Sum reduced by prior payments. Contractor shall be required to make its request in accordance with the provisions of Part 7.
- D. Owner to determine whether to adjust Contract Time: If Owner terminates the Work or any portion thereof for convenience, the Contract Time shall be adjusted as determined by Owner.

PART 10 – MISCELLANEOUS PROVISIONS

10.01 GOVERNING LAW

Applicable law and venue: The Contract Documents and the rights of the parties herein shall be governed by the laws of the State of Washington. Venue shall be in the county in which Owner's administrative office is located, unless otherwise specified.

10.02 SUCCESSORS AND ASSIGNS

Bound to successors; Assignment of Contract: Owner and Contractor respectively bind themselves, their partners, successors, assigns, and legal representatives to the other party hereto and to partners, successors, assigns, and legal representatives of such other party in respect to covenants, agreements, and obligations contained in the Contract Documents. Neither party shall assign the Work without written consent of the other, except that Contractor may assign the Work for security purposes, to a bank or lending institution authorized to do business in the State of Washington. If either party attempts to make such an assignment without such consent, that party shall nevertheless remain legally responsible for all obligations set forth in the Contract Documents.

10.03 MEANING OF WORDS

Meaning of words used in Specifications: Unless otherwise stated in the Contract Documents, words which have well-known technical or construction industry meanings are used in the Contract

Documents in accordance with such recognized meanings. Reference to standard specifications, manuals, or codes of any technical society, organization, or association, or to the code of any governmental authority, whether such reference be specific or by implication, shall be to the latest standard specification, manual, or code in effect on the date for submission of bids, except as may be otherwise specifically stated. Wherever in these Drawings and Specifications an article, device, or piece of equipment is referred to in the singular manner, such reference shall apply to as many such articles as are shown on the Drawings or required to complete the installation.

10.04 RIGHTS AND REMEDIES

No waiver of rights: No action or failure to act by Owner (or A/E, if applicable) shall constitute a waiver of a right or duty afforded them under the Contract Documents, nor shall action or failure to act constitute approval or an acquiescence in a breach therein, except as may be specifically agreed in writing.

10.05 CONTRACTOR REGISTRATION

Contractor must be registered or licensed: Pursuant to Chapter 39.06 RCW, Contractor shall be registered or licensed as required by the laws of the State of Washington, including but not limited to Chapter 18.27 RCW.

10.06 TIME COMPUTATIONS

Computing time: When computing any period of time, the day of the event from which the period of time begins shall not be counted. The last day is counted unless it falls on a weekend or legal holiday, in which event the period runs until the end of the next day that is not a weekend or holiday. When the period of time allowed is less than seven (7) days, intermediate Saturdays, Sundays, and legal holidays are excluded from the computation.

10.07 RECORDS RETENTION

Six-year records retention period: The wage, payroll, and cost records of Contractor, and its Subcontractors, and all records subject to audit in accordance with Section 8.03, shall be retained for a period of not less than six (6) years after the date of Final Acceptance.

10.08 THIRD-PARTY AGREEMENTS

No third-party relationships created: The Contract Documents shall not be construed to create a contractual relationship of any kind between any persons other than Owner and Contractor.

10.09 ANTITRUST ASSIGNMENT

Contractor assigns overcharge amounts to Owner: Owner and Contractor recognize that in actual economic practice, overcharges resulting from antitrust violations are in fact usually borne by the purchaser. Therefore, Contractor hereby assigns to Owner any and all claims for such overcharges as to goods, materials, and equipment purchased in connection with the Work performed in accordance with the Contract Documents, except as to overcharges which result from antitrust violations commencing after the Contract Sum is established and which are not passed on to Owner under a Change Order. Contractor shall put a similar clause in its Subcontracts, and require a similar clause in its Sub-Subcontracts, such that all claims for such overcharges on the Work are passed to Owner by Contractor.

10.10 WRITTEN NOTICE

Written notice shall be deemed to have been duly served if delivered in person to the designated

representative as identified in the Contract Documents, or to an officer of the corporation for which it was intended if the designated representative no longer works for that party; or if delivered at, or sent by facsimile, email, registered or certified mail, or courier service providing proof of delivery to, the last business address known to the party giving notice. The date of written notice shall be the earlier of the date of personal delivery, actual receipt by facsimile or email, or three (3) calendar days after the date of postmark.

10.11 PUBLIC RECORDS ACT COMPLIANCE

The Contractor understands that the Owner is bound by the Washington Public Records Act, Chapter 42.56 RCW. The Contractor agrees to fully cooperate with the Owner in responding to public records requests. The Contractor shall promptly provide such records to the Owner as requested by the Owner or required by law for the Owner to fulfill its obligations in responding to public records requests. Such records shall be provided at no cost to the Owner. The Contractor shall cause any subcontract to contain this provision. This section shall survive expiration or termination of this Contract for any reason.

10.12 SUBSTITUTION OF PERSONNEL

The Contractor and the Owner have no present intention to substitute personnel, and the parties shall endeavor to minimize substitutions and maintain continuity of personnel, but each reserves the right to substitute its personnel for the purpose of carrying out its responsibilities under this Contract. Such substitution by the Contractor shall be subject to the approval of the Owner, which approval shall not be unreasonably withheld. If the Contractor substitutes personnel, it shall not charge the Owner for any extra costs incurred thereby, including, without limitation, costs incurred to familiarize new personnel with the Project. If requested by the Owner, the Contractor shall remove from performing the Work, without cost to the Owner or delay to the Work, any person whose removal the Owner reasonably requests. Nothing in this provision shall be construed to alter the independent contractor status of the Contractor.

10.13 SEVERABILITY

If, for any reason, any part, term or provision of this Agreement is held by a court of competent jurisdiction to be illegal, void, or unenforceable, the validity of the remaining provisions shall not be affected, and the rights and obligations of the parties shall be construed and enforced as if the Agreement did not contain the particular provision held to be invalid; provided, however, that if it should appear that any provision of the Contract Documents is in conflict with any statutory provision of the State of Washington, the provision shall be deemed modified to conform to such statutory provision.»

10.14 HEADINGS AND CAPTIONS

Headings for convenience only: All headings and captions used in these General Conditions are only for convenience of reference, and shall not be used in any way in connection with the meaning, effect, interpretation, construction, or enforcement of the General Conditions, and do not define the limit or describe the scope or intent of any provision of these General Conditions.

- END OF GENERAL CONDITIONS -

Last Revised: April 8, 2022.

**SECTION 011000
SUMMARY**

PART 1 GENERAL

1.01 PROJECT

- A. Project Name: Chiller Replacement at Mark Morris High School..
- B. Owner's Name: Longview School District No. 122..
- C. Engineer's Name: Windsor Engineers.

1.02 CONTRACT DESCRIPTION

- A. Contract Type: A single prime contract based on a Stipulated Price as described in Contract Documents.

1.03 DESCRIPTION OF ALTERATIONS WORK

- A. Scope of demolition and removal work is indicated on drawings.
- B. Scope of alterations work is indicated on drawings.

1.04 OWNER OCCUPANCY

- A. Owner intends to continue to occupy portions of the existing building during the entire construction period.
- B. Owner intends to occupy the Project upon Substantial Completion.
- C. Cooperate with Owner to minimize conflict and to facilitate Owner's operations.
- D. Schedule the Work to accommodate Owner occupancy.

1.05 CONTRACTOR USE OF SITE AND PREMISES

- A. Construction Operations: Limited to areas noted on Drawings.
 - 1. Locate and conduct construction activities in ways that will limit disturbance to site.
- B. Arrange use of site and premises to allow:
 - 1. Owner occupancy.
 - 2. Work by Owner.
 - 3. Use of site and premises by the public.
- C. Provide access to and from site as required by law and by Owner:
 - 1. Emergency Building Exits During Construction: Keep all exits required by code open during construction period; provide temporary exit signs if exit routes are temporarily altered.
 - 2. Do not obstruct roadways, sidewalks, or other public ways without permit.
- D. Time Restrictions:
 - 1. Limit conduct of especially noisy exterior work to the hours of 7:30 a.m. to 6:00 p.m..
- E. Utility Outages and Shutdown:
 - 1. Limit disruption of utility services to hours the building is unoccupied.
 - 2. Prevent accidental disruption of utility services to other facilities.

END OF SECTION

**SECTION 012000
PRICE AND PAYMENT PROCEDURES**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Procedures for preparation and submittal of applications for progress payments.
- B. Documentation of changes in Contract Sum and Contract Time.
- C. Change procedures.
- D. Correlation of Contractor submittals based on changes.
- E. Procedures for preparation and submittal of application for final payment.

1.02 SCHEDULE OF VALUES

- A. Use Schedule of Values Form: AIA G703, edition stipulated in the Agreement.
- B. Electronic media printout including equivalent information will be considered in lieu of standard form specified; submit draft to Owner for approval.
- C. Forms filled out by hand will not be accepted.
- D. Include within each line item, a direct proportional amount of Contractor's overhead and profit.
- E. Revise schedule to list approved Change Orders, with each Application For Payment.

1.03 APPLICATIONS FOR PROGRESS PAYMENTS

- A. Payment Period: Submit at intervals stipulated in the Agreement.
- B. Use Form AIA G702 and Form AIA G703, edition stipulated in the Agreement.
- C. Electronic media printout including equivalent information will be considered in lieu of standard form specified; submit sample to Architect for approval.
- D. Forms filled out by hand will not be accepted.
- E. For each item, provide a column for listing each of the following:
 - 1. Item Number.
 - 2. Description of work.
 - 3. Scheduled Values.
 - 4. Previous Applications.
 - 5. Work in Place and Stored Materials under this Application.
 - 6. Authorized Change Orders.
 - 7. Total Completed and Stored to Date of Application.
 - 8. Percentage of Completion.
 - 9. Balance to Finish.
 - 10. Retainage.
- F. Execute certification by signature of authorized officer.
- G. Use data from approved Schedule of Values. Provide dollar value in each column for each line item for portion of work performed and for stored products.
- H. List each authorized Change Order as a separate line item, listing Change Order number and dollar amount as for an original item of work.
- I. Submit one electronic and three hard-copies of each Application for Payment.
- J. When Owner requires substantiating information, submit data justifying dollar amounts in question. Provide one copy of data with cover letter for each copy of submittal. Show application number and date, and line item by number and description.

1.04 MODIFICATION PROCEDURES

- A. For minor changes not involving an adjustment to the Contract Sum or Contract Time, Owner will issue instructions directly to Contractor.

- B. For other required changes, Engineer will issue a document signed by Owner instructing Contractor to proceed with the change, for subsequent inclusion in a Change Order.
 - 1. The document will describe the required changes and will designate method of determining any change in Contract Sum or Contract Time.
 - 2. Promptly execute the change.
- C. For changes for which advance pricing is desired, Engineer will issue a document that includes a detailed description of a proposed change with supplementary or revised drawings and specifications, a change in Contract Time for executing the change with a stipulation of any overtime work required and the period of time during which the requested price will be considered valid. Contractor shall prepare and submit a fixed price quotation within 2 days.
- D. Computation of Change in Contract Amount: As specified in the Agreement and Conditions of the Contract.
 - 1. For change requested by Owner for work falling under a fixed price contract, the amount will be based on Contractor's price quotation.
 - 2. For change requested by Contractor, the amount will be based on the Contractor's request for a Change Order as approved by Owner.
 - 3. For change ordered by Owner without a quotation from Contractor, the amount will be determined by Owner based on the Contractor's substantiation of costs as specified for Time and Material work.
- E. Substantiation of Costs: Provide full information required for evaluation.
 - 1. Provide the following data:
 - a. Quantities of products, labor, and equipment.
 - b. Taxes, insurance, and bonds.
 - c. Overhead and profit.
 - d. Justification for any change in Contract Time.
 - e. Credit for deletions from Contract, similarly documented.
 - 2. Support each claim for additional costs with additional information:
 - a. Origin and date of claim.
 - b. Dates and times work was performed, and by whom.
 - c. Time records and wage rates paid.
 - d. Invoices and receipts for products, equipment, and subcontracts, similarly documented.
 - 3. For Time and Material work, submit itemized account and supporting data after completion of change, within time limits indicated in the Conditions of the Contract.
- F. Execution of Change Orders: Owner will issue Change Orders for signatures of parties as provided in the Conditions of the Contract.
- G. After execution of Change Order, promptly revise Schedule of Values and Application for Payment forms to record each authorized Change Order as a separate line item and adjust the Contract Sum.

1.05 APPLICATION FOR FINAL PAYMENT

- A. Prepare Application for Final Payment as specified for progress payments, identifying total adjusted Contract Sum, previous payments, and sum remaining due.
- B. Application for Final Payment will not be considered until the following have been accomplished:
 - 1. All closeout procedures specified in Section 017000.
 - 2. Proper completion of all punchlist items..

END OF SECTION

**SECTION 012200
UNIT PRICES**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. List of unit prices, for use in preparing Bids.
- B. Measurement and payment criteria applicable to Work performed under a unit price payment method.

1.02 COSTS INCLUDED

- A. Unit Prices included on the Bid Form shall include full compensation for all required labor, products, tools, equipment, plant, transportation, services and incidentals; erection, application or installation of an item of the Work; overhead and profit.

1.03 UNIT QUANTITIES SPECIFIED

- A. Quantities indicated in the Bid Form are for bidding and contract purposes only. Quantities and measurements of actual Work will determine the payment amount.

1.04 PAYMENT

- A. Payment for Work governed by unit prices will be made on the basis of the actual measurements and quantities of Work that is incorporated in or made necessary by the Work and accepted by the Owner, multiplied by the unit price. Contract Sum will be adjust by Change Order.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

**SECTION 012500
SUBSTITUTION PROCEDURES**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Procedural requirements for proposed substitutions.

1.02 DEFINITIONS

- A. Substitutions: Changes from Contract Documents requirements proposed by Contractor to materials, products, assemblies, and equipment.
 - 1. Substitutions for Cause: Proposed due to changed Project circumstances beyond Contractor's control.
 - 2. Substitutions for Convenience: Proposed due to possibility of offering substantial advantage to the Project.

1.03 REFERENCE STANDARDS

- A. CSI/CSC Form 1.5C - Substitution Request (During the Bidding/Negotiating Stage); Current Edition.
- B. CSI/CSC Form 13.1A - Substitution Request (After the Bidding/Negotiating Phase); Current Edition.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 GENERAL REQUIREMENTS

- A. A Substitution Request for products, assemblies, materials, and equipment constitutes a representation that the submitter:
 - 1. Has investigated proposed product and determined that it meets or exceeds the quality level of the specified product, equipment, assembly, or system.
 - 2. Agrees to provide the same warranty for the substitution as for the specified product.
 - 3. Agrees to provide same or equivalent maintenance service and source of replacement parts, as applicable.
 - 4. Agrees to coordinate installation and make changes to other work that may be required for the work to be complete, with no additional cost to Owner.
 - 5. Waives claims for additional costs or time extension that may subsequently become apparent.
 - 6. Agrees to reimburse Owner for review or redesign services associated with re-approval by authorities.
- B. Document each request with complete data substantiating compliance of proposed substitution with Contract Documents. Burden of proof is on proposer.
 - 1. Note explicitly any non-compliant characteristics.
- C. Content: Include information necessary for tracking the status of each Substitution Request, and information necessary to provide an actionable response.
 - 1. Forms indicated in the Project Manual are adequate for this purpose, and must be used.
- D. Limit each request to a single proposed substitution item.
 - 1. Submit an electronic document, combining the request form with supporting data into single document.

3.02 SUBSTITUTION PROCEDURES DURING PROCUREMENT

- A. Submittal Time Restrictions:
 - 1. Owner will consider requests for substitutions only if submitted at least 10 days prior to the date for receipt of bids.
- B. Submittal Form (before award of contract):

1. Submit substitution requests by completing CSI/CSC Form 1.5C - Substitution Request. See this form for additional information and instructions. Use only this form; other forms of submission are unacceptable.

3.03 SUBSTITUTION PROCEDURES DURING CONSTRUCTION

- A. Submittal Form (after award of contract):
 1. Submit substitution requests by completing CSI/CSC Form 13.1A - Substitution Request (After Bidding/Negotiating). See this form for additional information and instructions. Use only this form; other forms of submission are unacceptable.
- B. Submit request for Substitution for Cause immediately upon discovery of need for substitution, but not later than 14 days prior to time required for review and approval by Engineer, in order to stay on approved project schedule.
- C. Submit request for Substitution for Convenience immediately upon discovery of its potential advantage to the project, but not later than 14 days prior to time required for review and approval by Engineer, in order to stay on approved project schedule.
 1. In addition to meeting general documentation requirements, document how the requested substitution benefits the Owner through cost savings, time savings, greater energy conservation, or in other specific ways.
 2. Document means of coordinating of substitution item with other portions of the work, including work by affected subcontractors.
 3. Bear the costs engendered by proposed substitution of:
 - a. Owner's compensation to the Engineer for any required redesign, time spent processing and evaluating the request.
 - b. Other construction by Owner.
 - c. Other unanticipated project considerations.
- D. Substitutions will not be considered under one or more of the following circumstances:
 1. When they are indicated or implied on shop drawing or product data submittals, without having received prior approval.
 2. Without a separate written request.
 3. When acceptance will require revisions to Contract Documents.

3.04 RESOLUTION

- A. Engineer may request additional information and documentation prior to rendering a decision. Provide this data in an expeditious manner.
- B. Engineer will notify Contractor in writing of decision to accept or reject request.

3.05 ACCEPTANCE

- A. Accepted substitutions change the work of the Project. They will be documented and incorporated into work of the project by Change Order, Construction Change Directive, Architectural Supplementary Instructions, or similar instruments provided for in the Conditions of the Contract.

3.06 CLOSEOUT ACTIVITIES

- A. See Section 017800 - Closeout Submittals, for closeout submittals.
- B. Include completed Substitution Request Forms as part of the Project record.

END OF SECTION

**SECTION 013000
ADMINISTRATIVE REQUIREMENTS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. General administrative requirements.
- B. Preconstruction meeting.
- C. Progress meetings.
- D. Construction progress schedule.
- E. Submittals for review, information, and project closeout.
- F. Number of copies of submittals.
- G. Requests for Interpretation (RFI) procedures.
- H. Submittal procedures.

1.02 RELATED REQUIREMENTS

- A. Section 016000 - Product Requirements: General product requirements.

1.03 GENERAL ADMINISTRATIVE REQUIREMENTS

- A. Comply with requirements of Section 017000 - Execution and Closeout Requirements for coordination of execution of administrative tasks with timing of construction activities.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PRECONSTRUCTION MEETING

- A. Owner will schedule a meeting after Notice of Award.
- B. Attendance Required:
 - 1. Owner.
 - 2. Engineer.
 - 3. Contractor.
- C. Agenda:
 - 1. Execution of Owner-Contractor Agreement.
 - 2. Submission of executed bonds and insurance certificates.
 - 3. Distribution of Contract Documents.
 - 4. Submission of list of subcontractors, list of products, schedule of values, and progress schedule.
 - 5. Designation of personnel representing the parties to Contract.
 - 6. Procedures and processing of field decisions, submittals, substitutions, applications for payments, proposal request, Change Orders, and Contract closeout procedures.
 - 7. Scheduling.
- D. Record minutes and distribute copies within two days after meeting to Engineer, Owner, participants, and those affected by decisions made.

3.02 PROGRESS MEETINGS

- A. Contractor to schedule and administer meetings throughout progress of the work at maximum bi-weekly intervals.
- B. Contractor to make arrangements for meetings, prepare agenda with copies for participants, preside at meetings.
- C. Attendance Required:
 - 1. Contractor.
 - 2. Owner.

3. Engineer.
 4. Contractor's superintendent.
 5. Major subcontractors.
- D. Agenda:
1. Review minutes of previous meetings.
 2. Review of work progress.
 3. Field observations, problems, and decisions.
 4. Identification of problems that impede, or will impede, planned progress.
 5. Review of submittals schedule and status of submittals.
 6. Review of RFIs log and status of responses.
 7. Maintenance of progress schedule.
 8. Corrective measures to regain projected schedules.
 9. Planned progress during succeeding work period.
 10. Maintenance of quality and work standards.
 11. Effect of proposed changes on progress schedule and coordination.
 12. Other business relating to work.
- E. Record minutes and distribute copies within two days after meeting to Engineer, Owner, participants, and those affected by decisions made.

3.03 CONSTRUCTION PROGRESS SCHEDULE

- A. Within 10 days after date of the Agreement, submit schedule for the work.
- B. If preliminary schedule requires revision after review, submit revised schedule within 10 days.
- C. Within 5 days after joint review, submit complete schedule.

3.04 REQUESTS FOR INFORMATION (RFI)

- A. Definition: A request seeking one of the following:
 1. An interpretation, amplification, or clarification of some requirement of Contract Documents arising from inability to determine from them the exact material, process, or system to be installed; or when the elements of construction are required to occupy the same space (interference); or when an item of work is described differently at more than one place in Contract Documents.
 2. A resolution to an issue which has arisen due to field conditions and affects design intent.
- B. Whenever possible, request clarifications at the next appropriate project progress meeting, with response entered into meeting minutes, rendering unnecessary the issuance of a formal RFI.
- C. Preparation: Prepare an RFI immediately upon discovery of a need for interpretation of Contract Documents. Failure to submit a RFI in a timely manner is not a legitimate cause for claiming additional costs or delays in execution of the work.
 1. Prepare a separate RFI for each specific item.
 - a. Review, coordinate, and comment on requests originating with subcontractors and/or materials suppliers.
 - b. Do not forward requests which solely require internal coordination between subcontractors.
 2. Prepare in a format and with content acceptable to Owner.
 3. Combine RFI and its attachments into a single electronic file. PDF format is preferred.
- D. Reason for the RFI: Prior to initiation of an RFI, carefully study all Contract Documents to confirm that information sufficient for their interpretation is definitely not included.
 1. Include in each request Contractor's signature attesting to good faith effort to determine from Contract Documents information requiring interpretation.
 2. Unacceptable Uses for RFIs: Do not use RFIs to request the following:
 - a. Approval of submittals (use procedures specified elsewhere in this section).
 - b. Approval of substitutions (see Section - 016000 - Product Requirements)

- c. Changes that entail change in Contract Time and Contract Sum (comply with provisions of the Conditions of the Contract).
 - d. Different methods of performing work than those indicated in the Contract Drawings and Specifications (comply with provisions of the Conditions of the Contract).
- 3. Improper RFIs: Requests not prepared in compliance with requirements of this section, and/or missing key information required to render an actionable response. They will be returned without a response, with an explanatory notation.
- E. Content: Include identifiers necessary for tracking the status of each RFI, and information necessary to provide an actionable response.
 - 1. Official Project name and number, and any additional required identifiers established in Contract Documents.
 - 2. Owner's, Engineer's, and Contractor's names.
 - 3. Discrete and consecutive RFI number, and descriptive subject/title.
 - 4. Reference to particular Contract Document(s) requiring additional information/interpretation. Identify pertinent drawing and detail number and/or specification section number, title, and paragraph(s).
 - 5. Annotations: Field dimensions and/or description of conditions which have engendered the request.
 - 6. Contractor's suggested resolution: A written and/or a graphic solution, to scale, is required in cases where clarification of coordination issues is involved, for example; routing, clearances, and/or specific locations of work shown diagrammatically in Contract Documents. If applicable, state the likely impact of the suggested resolution on Contract Time or the Contract Sum.
- F. Attachments: Include sketches, coordination drawings, descriptions, photos, submittals, and other information necessary to substantiate the reason for the request.
- G. RFI Log: Prepare and maintain a tabular log of RFIs for the duration of the project.
 - 1. Indicate current status of every RFI. Update log promptly and on a regular basis.
 - 2. Note dates of when each request is made, and when a response is received.
 - 3. Highlight items requiring priority or expedited response.
 - 4. Highlight items for which a timely response has not been received to date.
- H. Review Time: Engineer will respond and return RFIs to Contractor within ten calendar days of receipt.
- I. Responses: Content of answered RFIs will not constitute in any manner a directive or authorization to perform extra work or delay the project. If in Contractor's belief it is likely to lead to a change to Contract Sum or Contract Time, promptly issue a notice to this effect, and follow up with an appropriate Change Order request to Owner.

3.05 SUBMITTALS FOR REVIEW

- A. When the following are specified in individual sections, submit them for review:
 - 1. Product data.
 - 2. Shop drawings.
- B. Submit to Engineer for review for the limited purpose of checking for compliance with information given and the design concept expressed in Contract Documents.
- C. After review, provide copies and distribute in accordance with SUBMITTAL PROCEDURES article below and for record documents purposes described in Section 017800 - Closeout Submittals.

3.06 SUBMITTALS FOR INFORMATION

- A. When the following are specified in individual sections, submit them for information:
 - 1. Design data.
 - 2. Certificates.
 - 3. Test reports.

4. Inspection reports.
5. Manufacturer's instructions.
6. Manufacturer's field reports.
7. Other types indicated.

B. Submit for Engineer's knowledge as contract administrator or for Owner.

3.07 SUBMITTALS FOR PROJECT CLOSEOUT

- A. Submit Correction Punch List for Substantial Completion.
- B. Submit Final Correction Punch List for Substantial Completion.
- C. When the following are specified in individual sections, submit them at project closeout in compliance with requirements of Section 017800 - Closeout Submittals:
 1. Project record documents.
 2. Operation and maintenance data.
 3. Warranties.
 4. Bonds.
 5. Other types as indicated.
- D. Submit for Owner's benefit during and after project completion.

3.08 NUMBER OF COPIES OF SUBMITTALS

- A. Electronic Documents: Submit one electronic copy in PDF format; an electronically-marked up file will be returned. Create PDFs at native size and right-side up; illegible files will be rejected.

3.09 SUBMITTAL PROCEDURES

- A. General Requirements:
 1. Use a separate transmittal for each item.
 2. Submit separate packages of submittals for review and submittals for information, when included in the same specification section.
 3. Transmit using approved form.
 - a. Use Contractor's form, subject to prior approval by Engineer.
 4. Sequentially identify each item. For revised submittals use original number and a sequential numerical suffix.
 5. Identify: Project; Contractor; subcontractor or supplier; pertinent drawing and detail number; and specification section number and article/paragraph, as appropriate on each copy.
 6. Apply Contractor's stamp, signed or initialed certifying that review, approval, verification of products required, field dimensions, adjacent construction work, and coordination of information is in accordance with the requirements of the work and Contract Documents.
 - a. Submittals from sources other than the Contractor, or without Contractor's stamp will not be acknowledged, reviewed, or returned.
 7. Deliver each submittal on date noted in submittal schedule, unless an earlier date has been agreed to by all affected parties, and is of the benefit to the project.
 - a. Send submittals in electronic format via email to Owner.
 8. Schedule submittals to expedite the Project, and coordinate submission of related items.
 - a. For each submittal for review, allow 10 days excluding delivery time to and from the Contractor.
 9. Identify variations from Contract Documents and product or system limitations that may be detrimental to successful performance of the completed work.
 10. Provide space for Contractor and Engineer review stamps.
- B. Product Data Procedures:
 1. Submit only information required by individual specification sections.
 2. Collect required information into a single submittal.
 3. Do not submit (Material) Safety Data Sheets for materials or products.

- C. Shop Drawing Procedures:
 - 1. Prepare accurate, drawn-to-scale, original shop drawing documentation by interpreting Contract Documents and coordinating related work.
 - 2. Do not reproduce Contract Documents to create shop drawings.
 - 3. Generic, non-project-specific information submitted as shop drawings do not meet the requirements for shop drawings.
- D. Samples Procedures:
 - 1. Transmit related items together as single package.
 - 2. Identify each item to allow review for applicability in relation to shop drawings showing installation locations.

3.10 SUBMITTAL REVIEW

- A. Submittals for Review: Engineer will review each submittal, and approve, or take other appropriate action.
- B. Architect's actions will be reflected by marking each returned submittal using virtual stamp on electronic submittals.
 - 1. Notations may be made directly on submitted items and/or listed on appended Submittal Review cover sheet.

END OF SECTION

**SECTION 014000
QUALITY REQUIREMENTS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. References and standards.
- B. Testing and inspection agencies and services.
- C. Control of installation.
- D. Tolerances.
- E. Manufacturers' field services.
- F. Defect Assessment.

1.02 REFERENCES AND STANDARDS

- A. For products and workmanship specified by reference to a document or documents not included in the Project Manual, also referred to as reference standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. Comply with reference standard of date of issue current on date of Contract Documents, except where a specific date is established by applicable code.

PART 3 EXECUTION

2.01 CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce work of specified quality.
- B. Comply with manufacturers' instructions, including each step in sequence.
- C. Should manufacturers' instructions conflict with Contract Documents, request clarification from Engineer before proceeding.
- D. Comply with specified standards as minimum quality for the work except where more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- E. Have work performed by persons qualified to produce required and specified quality.
- F. Verify that field measurements are as indicated on shop drawings or as instructed by the manufacturer.
- G. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, and disfigurement.

2.02 TOLERANCES

- A. Monitor fabrication and installation tolerance control of products to produce acceptable Work. Do not permit tolerances to accumulate.
- B. Comply with manufacturers' tolerances. Should manufacturers' tolerances conflict with Contract Documents, request clarification from Engineer before proceeding.
- C. Adjust products to appropriate dimensions; position before securing products in place.

2.03 MANUFACTURERS' FIELD SERVICES

- A. When specified in individual specification sections, require material or product suppliers or manufacturers to provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, quality of workmanship, start-up of equipment, test, adjust, and balance equipment, and _____ as applicable, and to initiate instructions when necessary.
- B. Report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.

2.04 DEFECT ASSESSMENT

- A. Replace Work or portions of the Work not complying with specified requirements.

END OF SECTION

**SECTION 015000
TEMPORARY FACILITIES AND CONTROLS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Temporary sanitary facilities.
- B. Waste removal facilities and services.

1.02 TEMPORARY UTILITIES

- A. Owner will provide the following:
 - 1. Electrical power, consisting of connection to existing facilities.
 - 2. Water supply, consisting of connection to existing facilities.

1.03 TEMPORARY SANITARY FACILITIES

- A. Provide and maintain required facilities and enclosures. Provide at time of project mobilization.
- B. Maintain daily in clean and sanitary condition.

1.04 BARRIERS

- A. Provide barriers to prevent unauthorized entry to construction areas, to prevent access to areas that could be hazardous to workers or the public, to allow for owner's use of site and to protect existing facilities and adjacent properties from damage from construction operations and demolition.
- B. Protect non-owned vehicular traffic, stored materials, site, and structures from damage.

1.05 SECURITY - SEE SECTION 013553

- A. Provide security and facilities to protect Work, existing facilities, and Owner's operations from unauthorized entry, vandalism, or theft.

1.06 VEHICULAR ACCESS AND PARKING

- A. Coordinate access and haul routes with governing authorities and Owner.
- B. Provide and maintain access to fire hydrants, free of obstructions.
- C. Existing parking areas may be used for construction parking.

1.07 WASTE REMOVAL

- A. Provide waste removal facilities and services as required to maintain the site in clean and orderly condition.
- B. Provide containers with lids. Remove trash from site periodically.
- C. If materials to be recycled or re-used on the project must be stored on-site, provide suitable non-combustible containers; locate containers holding flammable material outside the structure unless otherwise approved by the authorities having jurisdiction.
- D. Open free-fall chutes are not permitted. Terminate closed chutes into appropriate containers with lids.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

**SECTION 016000
PRODUCT REQUIREMENTS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Re-use of existing products.
- B. Transportation, handling, storage and protection.
- C. Product option requirements.
- D. Substitution limitations.
- E. Maintenance materials, including extra materials, spare parts, tools, and software.

1.02 SUBMITTALS

- A. Product Data Submittals: Submit manufacturer's standard published data. Mark each copy to identify applicable products, models, options, and other data. Supplement manufacturers' standard data to provide information specific to this Project.
- B. Shop Drawing Submittals: Prepared specifically for this Project; indicate utility and electrical characteristics, utility connection requirements, and location of utility outlets for service for functional equipment and appliances.
- C. Sample Submittals: Illustrate functional and aesthetic characteristics of the product, with integral parts and attachment devices. Coordinate sample submittals for interfacing work.
 - 1. For selection from standard finishes, submit samples of the full range of the manufacturer's standard colors, textures, and patterns.

PART 2 PRODUCTS

2.01 EXISTING PRODUCTS

- A. Do not use materials and equipment removed from existing premises unless specifically required or permitted by Contract Documents.
- B. Unforeseen historic items encountered remain the property of the Owner; notify Owner promptly upon discovery; protect, remove, handle, and store as directed by Owner.
- C. Existing materials and equipment indicated to be removed, but not to be re-used, relocated, reinstalled, delivered to the Owner, or otherwise indicated as to remain the property of the Owner, become the property of the Contractor; remove from site.

2.02 NEW PRODUCTS

- A. Provide new products unless specifically required or permitted by Contract Documents.
- B. See Section 014000 - Quality Requirements, for additional source quality control requirements.

2.03 PRODUCT OPTIONS

- A. Products Specified by Reference Standards or by Description Only: Use any product meeting those standards or description.
- B. Products Specified by Naming One or More Manufacturers: Use a product of one of the manufacturers named and meeting specifications, no options or substitutions allowed.
- C. Products Specified by Naming One or More Manufacturers with a Provision for Substitutions: Submit a request for substitution for any manufacturer not named.

2.04 MAINTENANCE MATERIALS

- A. Furnish extra materials, spare parts, tools, and software of types and in quantities specified in individual specification sections.
- B. Deliver to Project site; obtain receipt prior to final payment.

PART 3 EXECUTION

3.01 SUBSTITUTION LIMITATIONS

- A. See Section 012500 - Substitution Procedures.

3.02 TRANSPORTATION AND HANDLING

- A. Package products for shipment in manner to prevent damage; for equipment, package to avoid loss of factory calibration.
- B. If special precautions are required, attach instructions prominently and legibly on outside of packaging.
- C. Coordinate schedule of product delivery to designated prepared areas in order to minimize site storage time and potential damage to stored materials.
- D. Transport and handle products in accordance with manufacturer's instructions.
- E. Transport materials in covered trucks to prevent contamination of product and littering of surrounding areas.
- F. Promptly inspect shipments to ensure that products comply with requirements, quantities are correct, and products are undamaged.
- G. Provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, or damage, and to minimize handling.
- H. Arrange for the return of packing materials, such as wood pallets, where economically feasible.

3.03 STORAGE AND PROTECTION

- A. Provide protection of stored materials and products against theft, casualty, or deterioration.
- B. Designate receiving/storage areas for incoming products so that they are delivered according to installation schedule and placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication. See Section 017419.
- C. Store and protect products in accordance with manufacturers' instructions.
- D. Store with seals and labels intact and legible.
- E. Store sensitive products in weathertight, climate-controlled enclosures in an environment favorable to product.
- F. For exterior storage of fabricated products, place on sloped supports above ground.
- G. Protect products from damage or deterioration due to construction operations, weather, precipitation, humidity, temperature, sunlight and ultraviolet light, dirt, dust, and other contaminants.
- H. Comply with manufacturer's warranty conditions, if any.
- I. Cover products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of products.
- J. Prevent contact with material that may cause corrosion, discoloration, or staining.
- K. Provide equipment and personnel to store products by methods to prevent soiling, disfigurement, or damage.
- L. Arrange storage of products to permit access for inspection. Periodically inspect to verify products are undamaged and are maintained in acceptable condition.

END OF SECTION

**SECTION 017000
EXECUTION AND CLOSEOUT REQUIREMENTS**

PART 1 GENERAL

PART 2 PRODUCTS

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that existing site conditions and substrate surfaces are acceptable for subsequent work. Start of work means acceptance of existing conditions.
- B. Verify that existing substrate is capable of structural support or attachment of new work being applied or attached.
- C. Examine and verify specific conditions described in individual specification sections.
- D. Take field measurements before confirming product orders or beginning fabrication, to minimize waste due to over-ordering or misfabrication.
- E. Verify that utility services are available, of the correct characteristics, and in the correct locations.
- F. Prior to Cutting: Examine existing conditions prior to commencing work, including elements subject to damage or movement during cutting and patching. After uncovering existing work, assess conditions affecting performance of work. Beginning of cutting or patching means acceptance of existing conditions.

3.02 PREPARATION

- A. Clean substrate surfaces prior to applying next material or substance.
- B. Seal cracks or openings of substrate prior to applying next material or substance.
- C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying any new material or substance in contact or bond.

3.03 GENERAL INSTALLATION REQUIREMENTS

- A. Install products as specified in individual sections, in accordance with manufacturer's instructions and recommendations, and so as to avoid waste due to necessity for replacement.
- B. Make vertical elements plumb and horizontal elements level, unless otherwise indicated.
- C. Install equipment and fittings plumb and level, neatly aligned with adjacent vertical and horizontal lines, unless otherwise indicated.
- D. Make consistent texture on surfaces, with seamless transitions, unless otherwise indicated.
- E. Make neat transitions between different surfaces, maintaining texture and appearance.

3.04 ALTERATIONS

- A. Drawings showing existing construction and utilities are based on casual field observation and existing record documents only.
 - 1. Verify that construction and utility arrangements are as indicated.
 - 2. Report discrepancies to Owner before disturbing existing installation.
 - 3. Beginning of alterations work constitutes acceptance of existing conditions.
- B. Maintain weatherproof exterior building enclosure except for interruptions required for replacement or modifications; take care to prevent water and humidity damage.
 - 1. Where openings in exterior enclosure exist, provide construction to make exterior enclosure weatherproof.
 - 2. Insulate existing ducts or pipes that are exposed to outdoor ambient temperatures by alterations work.
- C. Remove existing work as indicated and as required to accomplish new work.
 - 1. Remove items indicated on drawings.

2. Relocate items indicated on drawings.
 3. Where new surface finishes are to be applied to existing work, perform removals, patch, and prepare existing surfaces as required to receive new finish; remove existing finish if necessary for successful application of new finish.
 4. Where new surface finishes are not specified or indicated, patch holes and damaged surfaces to match adjacent finished surfaces as closely as possible.
- D. Services (Including but not limited to HVAC, Plumbing, Fire Protection, Electrical, and Telecommunications): Remove, relocate, and extend existing systems to accommodate new construction.
1. Maintain existing active systems that are to remain in operation; maintain access to equipment and operational components; if necessary, modify installation to allow access or provide access panel.
 2. Where existing systems or equipment are not active and Contract Documents require reactivation, put back into operational condition; repair supply, distribution, and equipment as required.
 3. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.
 - a. Disable existing systems only to make switchovers and connections; minimize duration of outages.
 - b. Provide temporary connections as required to maintain existing systems in service.
 4. Verify that abandoned services serve only abandoned facilities.
 5. Remove abandoned pipe, ducts, conduits, and equipment, including those above accessible ceilings; remove back to source of supply where possible, otherwise cap stub and tag with identification; patch holes left by removal using materials specified for new construction.
- E. Protect existing work to remain.
1. Prevent movement of structure; provide shoring and bracing if necessary.
 2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
 3. Repair adjacent construction and finishes damaged during removal work.
- F. Adapt existing work to fit new work: Make as neat and smooth transition as possible.
- G. Patching: Where the existing surface is not indicated to be refinished, patch to match the surface finish that existed prior to cutting. Where the surface is indicated to be refinished, patch so that the substrate is ready for the new finish.
- H. Refinish existing surfaces as indicated:
1. Where rooms or spaces are indicated to be refinished, refinish all visible existing surfaces to remain to the specified condition for each material, with a neat transition to adjacent finishes.
 2. If mechanical or electrical work is exposed accidentally during the work, re-cover and refinish to match.
- I. Clean existing systems and equipment.
- J. Remove demolition debris and abandoned items from alterations areas and dispose of off-site; do not burn or bury.
- K. Do not begin new construction in alterations areas before demolition is complete.
- L. Comply with all other applicable requirements of this section.

3.05 CUTTING AND PATCHING

- A. Whenever possible, execute the work by methods that avoid cutting or patching.
- B. See Alterations article above for additional requirements.
- C. Perform whatever cutting and patching is necessary to:
 1. Complete the work.

2. Fit products together to integrate with other work.
 3. Provide openings for penetration of mechanical, electrical, and other services.
 4. Match work that has been cut to adjacent work.
 5. Repair areas adjacent to cuts to required condition.
 6. Repair new work damaged by subsequent work.
 7. Remove samples of installed work for testing when requested.
 8. Remove and replace defective and non-complying work.
- D. Execute work by methods that avoid damage to other work and that will provide appropriate surfaces to receive patching and finishing. In existing work, minimize damage and restore to original condition.
- E. At penetrations of fire rated walls, partitions, ceiling, or floor construction, completely seal voids with fire rated material , to full thickness of the penetrated element.
- F. Patching:
1. Finish patched surfaces to match finish that existed prior to patching. On continuous surfaces, refinish to nearest intersection or natural break. For an assembly, refinish entire unit.
 2. Match color, texture, and appearance.
 3. Repair patched surfaces that are damaged, lifted, discolored, or showing other imperfections due to patching work. If defects are due to condition of substrate, repair substrate prior to repairing finish.

3.06 PROGRESS CLEANING

- A. Maintain areas free of waste materials, debris, and rubbish. Maintain site in a clean and orderly condition.
- B. Remove debris and rubbish from pipe chases, plenums, attics, crawl spaces, and other closed or remote spaces, prior to enclosing the space.
- C. Broom and vacuum clean interior areas prior to start of surface finishing, and continue cleaning to eliminate dust.
- D. Collect and remove waste materials, debris, and trash/rubbish from site periodically and dispose off-site; do not burn or bury.

3.07 PROTECTION OF INSTALLED WORK

- A. Protect installed work from damage by construction operations.
- B. Provide special protection where specified in individual specification sections.
- C. Provide temporary and removable protection for installed products. Control activity in immediate work area to prevent damage.

3.08 SYSTEM STARTUP

- A. Coordinate schedule for start-up of various equipment and systems.
- B. Verify that each piece of equipment or system has been checked for proper lubrication, drive rotation, belt tension, control sequence, and for conditions that may cause damage.
- C. Verify tests, meter readings, and specified electrical characteristics agree with those required by the equipment or system manufacturer.
- D. Verify that wiring and support components for equipment are complete and tested.
- E. Execute start-up under supervision of applicable Contractor personnel and manufacturer's representative in accordance with manufacturers' instructions.
- F. Submit a written report that equipment or system has been properly installed and is functioning correctly.

3.09 DEMONSTRATION AND INSTRUCTION

- A. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance, and shutdown of each item of equipment at scheduled time, at equipment location.
- B. For equipment or systems requiring seasonal operation, perform demonstration for other season within six months.
- C. Provide a qualified person who is knowledgeable about the Project to perform demonstration and instruction of Owner's personnel.

3.10 ADJUSTING

- A. Adjust operating products and equipment to ensure smooth and unhindered operation.
- B. Testing, adjusting, and balancing HVAC systems: See Section 230593 - Testing, Adjusting, and Balancing for HVAC.

3.11 FINAL CLEANING

- A. Use cleaning materials that are nonhazardous.
- B. Remove all labels that are not permanent. Do not paint or otherwise cover fire test labels or nameplates on mechanical and electrical equipment.
- C. Clean equipment and fixtures to a sanitary condition with cleaning materials appropriate to the surface and material being cleaned.
- D. Clean filters of operating equipment.
- E. Clean site; sweep paved areas, rake clean landscaped surfaces.
- F. Remove waste, surplus materials, trash/rubbish, and construction facilities from the site; dispose of in legal manner; do not burn or bury.

3.12 CLOSEOUT PROCEDURES

- A. Make submittals that are required by governing or other authorities.
 - 1. Provide copies to Engineer and Owner.
- B. Notify Engineer when work is considered ready for Engineer's Substantial Completion inspection.
- C. Submit written certification containing Contractor's Correction Punch List, that Contract Documents have been reviewed, work has been inspected, and that work is complete in accordance with Contract Documents and ready for Engineer's Substantial Completion inspection.
- D. Conduct Substantial Completion inspection and create Final Correction Punch List containing Engineer's and Contractor's comprehensive list of items identified to be completed or corrected and submit to Engineer.
- E. Correct items of work listed in Final Correction Punch List and comply with requirements for access to Owner-occupied areas.
- F. Notify Engineer when work is considered finally complete and ready for Engineer's Substantial Completion final inspection.
- G. Complete items of work determined by Engineer listed in executed Certificate of Substantial Completion.

END OF SECTION

**SECTION 017800
CLOSEOUT SUBMITTALS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Project Record Documents.
- B. Operation and Maintenance Data.
- C. Warranties and bonds.

1.02 RELATED REQUIREMENTS

- A. Section 013000 - Administrative Requirements: Submittals procedures, shop drawings, product data, and samples.
- B. Individual Product Sections: Specific requirements for operation and maintenance data.
- C. Individual Product Sections: Warranties required for specific products or Work.

1.03 SUBMITTALS

- A. Project Record Documents: Submit documents to Owner with claim for final Application for Payment.
- B. Operation and Maintenance Data:
 - 1. Submit two copies of preliminary draft or proposed formats and outlines of contents before start of Work. Owner will review draft and return one copy with comments.
 - 2. For equipment, or component parts of equipment put into service during construction and operated by Owner, submit completed documents within ten days after acceptance.
 - 3. Submit two sets of revised final documents in final form within 10 days after final inspection.
- C. Warranties and Bonds:
 - 1. For equipment or component parts of equipment put into service during construction with Owner's permission, submit documents within 10 days after acceptance.
 - 2. Make other submittals within 10 days after Date of Substantial Completion, prior to final Application for Payment.
 - 3. For items of Work for which acceptance is delayed beyond Date of Substantial Completion, submit within 10 days after acceptance, listing the date of acceptance as the beginning of the warranty period.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PROJECT RECORD DOCUMENTS

- A. Maintain on site one set of the following record documents; record actual revisions to the Work:
 - 1. Drawings.
 - 2. Specifications.
 - 3. Addenda.
 - 4. Change Orders and other modifications to the Contract.
 - 5. Reviewed shop drawings, product data, and samples.
 - 6. Manufacturer's instruction for assembly, installation, and adjusting.
- B. Ensure entries are complete and accurate, enabling future reference by Owner.
- C. Store record documents separate from documents used for construction.
- D. Record information concurrent with construction progress.
- E. Specifications: Legibly mark and record at each product section description of actual products installed, including the following:
 - 1. Product substitutions or alternates utilized.

2. Changes made by Addenda and modifications.
- F. Record Drawings and Shop Drawings: Legibly mark each item to record actual construction including:
 1. Field changes of dimension and detail.
 2. Details not on original Contract drawings.

3.02 OPERATION AND MAINTENANCE DATA

- A. Source Data: For each product or system, list names, addresses and telephone numbers of Subcontractors and suppliers, including local source of supplies and replacement parts.
- B. Product Data: Mark each sheet to clearly identify specific products and component parts, and data applicable to installation. Delete inapplicable information.
- C. Drawings: Supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.
- D. Typed Text: As required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions.

3.03 OPERATION AND MAINTENANCE DATA FOR EQUIPMENT AND SYSTEMS

- A. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.
- B. Maintenance Requirements: Include routine procedures and guide for preventative maintenance and trouble shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.

3.04 ASSEMBLY OF OPERATION AND MAINTENANCE MANUALS

- A. Where systems involve more than one specification section, provide separate tabbed divider for each system.
- B. Binders: Commercial quality, 8-1/2 by 11 inch three D side ring binders with durable plastic covers; 2 inch maximum ring size. When multiple binders are used, correlate data into related consistent groupings.
- C. Project Directory: Title and address of Project; names, addresses, and telephone numbers of Engineer, Consultants, Contractor and subcontractors, with names of responsible parties.
- D. Tables of Contents: List every item separated by a divider, using the same identification as on the divider tab; where multiple volumes are required, include all volumes Tables of Contents in each volume, with the current volume clearly identified.
- E. Dividers: Provide tabbed dividers for each separate product and system; identify the contents on the divider tab; immediately following the divider tab include a description of product and major component parts of equipment.
- F. Text: Manufacturer's printed data, or typewritten data on 20 pound paper.
- G. Drawings: Provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.

3.05 WARRANTIES AND BONDS

- A. Obtain warranties and bonds, executed in duplicate by responsible Subcontractors, suppliers, and manufacturers, within 10 days after completion of the applicable item of work. Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial completion is determined.
- B. Verify that documents are in proper form, contain full information, and are notarized.
- C. Co-execute submittals when required.
- D. Retain warranties and bonds until time specified for submittal.

- E. Manual: Bind in commercial quality 8-1/2 by 11 inch three D side ring binders with durable plastic covers.
- F. Cover: Identify each binder with typed or printed title WARRANTIES AND BONDS, with title of Project; name, address and telephone number of Contractor and equipment supplier; and name of responsible company principal.
- G. Table of Contents: Neatly typed, in the sequence of the Table of Contents of the Project Manual, with each item identified with the number and title of the specification section in which specified, and the name of product or work item.
- H. Separate each warranty or bond with index tab sheets keyed to the Table of Contents listing. Provide full information, using separate typed sheets as necessary. List Subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.

END OF SECTION

**SECTION 230529
HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Support and attachment components for equipment, piping, and other HVAC/hydronic work.

1.02 REFERENCE STANDARDS

- A. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- B. ASTM A153/A153M - Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2016a.
- C. ASTM A181/A181M - Standard Specification for Carbon Steel Forgings, for General - Purpose Piping; 2014 (Reapproved 2020).
- D. ASTM A36/A36M - Standard Specification for Carbon Structural Steel; 2019.
- E. ASTM B633 - Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel; 2015.
- F. ASTM E96/E96M - Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials; 2022a.
- G. MFMA-4 - Metal Framing Standards Publication; 2004.
- H. MSS SP-58 - Pipe Hangers and Supports - Materials, Design, Manufacture, Selection, Application, and Installation; 2018.

1.03 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate sizes and arrangement of supports and bases with the actual equipment and components to be installed.
 - 2. Coordinate the work with other trades to provide additional framing and materials required for installation.
 - 3. Coordinate compatibility of support and attachment components with mounting surfaces at the installed locations.
 - 4. Coordinate the arrangement of supports with ductwork, piping, equipment and other potential conflicts installed under other sections or by others.
 - 5. Notify Architect of any conflicts with or deviations from Contract Documents. Obtain direction before proceeding with work.
- B. Sequencing:
 - 1. Do not install products on or provide attachment to concrete surfaces until concrete has fully cured in accordance with Section 033000.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Shop Drawings of contractor fabricated support structures.
- C. Structural Details and Calculations: Submit structural details and calculations substantiating that building structure, anchorages, and fabricated steel braces can safely withstand maximum calculated loads.

1.05 QUALITY ASSURANCE

- A. Provide pipe and equipment hangers and supports in accordance with the following:
 - 1. In compliance with applicable building code.
 - 2. Seismic restraints and anchorages shall resist seismic forces as specified in the latest edition of the International Building Code for the seismic zone in which the project is constructed.

3. Seismic restraint shall not introduce excessive stresses in the piping caused by thermal expansion or contraction.
 4. Connections to structural framing shall not introduce twisting, torsion, or lateral bending in the framing members. Provide supplementary steel as required.
 5. Seismic restraints shall be in accordance with the latest edition of the SMACNA "Seismic Restraint Manual - Guidelines for Mechanical Systems" for the Seismic Hazard Level corresponding to the seismic zone in which the project is constructed.
- B. Engineered Support Systems: The following support systems shall be designed, detailed, and bear the seal of a professional engineer registered in the State having jurisdiction.
1. Supports and seismic restraints for suspended piping and equipment.
- C. Support frames such as pipe racks or stanchions for piping and equipment which provide support from below.
1. Equipment and piping support frame anchorage to supporting slab or structure.

PART 2 PRODUCTS

2.01 SUPPORT AND ATTACHMENT COMPONENTS

- A. General Requirements:
1. Comply with MSS SP-58.
 2. Provide all required hangers, supports, anchors, fasteners, fittings, accessories, and hardware as necessary for the complete installation of piping and HVAC work.
 3. Provide products listed, classified, and labeled as suitable for the purpose intended, where applicable.
 4. Where support and attachment component types and sizes are not indicated, select in accordance with manufacturer's application criteria as required for the load to be supported with a minimum safety factor of 2. Include consideration for vibration, equipment operation, and shock loads where applicable.
 5. Steel Components: Use corrosion resistant materials suitable for the environment where installed.
 - a. Zinc-Plated Steel: Electroplated in accordance with ASTM B633.
 - b. Galvanized Steel: Hot-dip galvanized after fabrication in accordance with ASTM A123/A123M or ASTM A153/A153M.
- B. Metal Channel (Strut) Framing Systems: Factory-fabricated continuous-slot metal channel (strut) and associated fittings, accessories, and hardware required for field-assembly of supports.
1. Manufacturers:
 - a. Cooper B-Line, a division of Eaton Corporation: www.cooperindustries.com.
 - b. Ferguson Enterprises Inc: www.fnw.com.
 - c. Thomas & Betts Corporation: www.tnb.com.
 - d. Unistrut, a brand of Atkore International Inc: www.unistrut.com.
 - e. Substitutions: See Section 016000 - Product Requirements.
 - f. Source Limitations: Furnish channels (struts) and associated fittings, accessories, and hardware produced by a single manufacturer.
 2. Provide factory-fabricated continuous-slot metal channel (strut) and associated fittings, accessories, and hardware required for field-assembly of supports.
 3. Comply with MFMA-4.
 4. Channel Material:
 - a. Indoor Dry Locations: Use painted steel, zinc-plated steel, or galvanized steel.
 - b. Outdoor and Damp or Wet Indoor Locations: Use galvanized steel.
- C. Hanger Rods: Threaded zinc-plated steel unless otherwise indicated.
1. Minimum Size, Unless Otherwise Indicated or Required:
 - a. Equipment Supports: 1/2 inch diameter.
 - b. Piping up to 1 inch (27 mm) nominal: 1/4 inch diameter.

- c. Piping larger than 1 inch (27 mm) nominal: 3/8 inch diameter.
 - d. Trapeze Support for Multiple Pipes: 3/8 inch diameter.
- D. Steel Cable:
 - 1. Manufacturers:
 - a. Ductmate Industries, Inc, a DMI Company; Clutcher Cable Hanging System: www.ductmate.com.
 - b. Substitutions: See Section 016000 - Product Requirements.
 - c. Source Limitations: Furnish associated fittings, accessories, and hardware produced by a single manufacturer.
- E. Thermal Insulated Pipe Supports:
 - 1. Manufacturers:
 - a. Aeroflex USA, Inc; Aerofix-U Pipe Supports: www.aeroflexusa.com.
 - b. KB Enterprises: www.snappitz.com.
 - c. Substitutions: See Section 016000 - Product Requirements.
 - 2. General Construction and Requirements:
 - a. Insulated pipe supports to be provided at hanger, support, and guide locations on pipe requiring insulation or additional support.
 - b. Surface Burning Characteristics: Flame spread index/smoke developed index of 5/30, maximum, when tested in accordance with ASTM E84 or UL 723.
 - c. Pipe supports to be provided for nominally sized, 1/2 inch to 30 inch iron pipes.
 - 3. PVC Jacket:
 - a. Pipe insulation protection shields to be provided with a ball bearing hinge and locking seam.
 - b. Minimum Service Temperature: Minus 40 degrees F.
 - c. Maximum Service Temperature: 180 degrees F.
 - d. Moisture Vapor Transmission: 0.0071 perm inch, when tested in accordance with ASTM E96/E96M.
 - e. Thickness: 60 mil.
 - f. Connections: Brush on welding adhesive.
- F. Pipe Supports:
 - 1. Liquid Temperatures Up To 122 degrees F:
 - a. Overhead Support: MSS SP-58 Types 1, 3 through 12.
 - b. Support From Below: MSS SP-58 Types 35 through 38.
- G. Beam Clamps: MSS SP-58 Types 19 through 23, 25 or 27 through 30 based on required load.
 - 1. Manufacturers:
 - a. Ferguson Enterprises Inc: www.fnw.com.
 - b. Substitutions: See Section 016000 - Product Requirements.
 - 2. Material: ASTM A36/A36M carbon steel or ASTM A181/A181M forged steel.
 - 3. Provide clamps with hardened steel cup-point set screws and lock-nuts for anchoring in place.
- H. Riser Clamps:
 - 1. Manufacturers:
 - a. Ferguson Enterprises Inc: www.fnw.com.
 - b. Substitutions: See Section 016000 - Product Requirements.
 - 2. Provide copper plated clamps for copper tubing support.
 - 3. For insulated pipe runs, provide two bolt-type clamps designed for installation under insulation.
- I. Offset Pipe Clamps: Double-leg design two-piece pipe clamp.
- J. Strut Clamps: Two-piece pipe clamp.
 - 1. Manufacturers:
 - a. Ferguson Enterprises Inc: www.fnw.com.

- b. Substitutions: See Section 016000 - Product Requirements.
 - c. Source Limitations: Furnish channels (struts) and associated fittings, accessories, and hardware produced by a single manufacturer.
- K. Insulation Clamps: Two bolt-type clamps designed for installation under insulation.
 - 1. Manufacturers:
 - a. Ferguson Enterprises Inc: www.fnw.com.
 - b. Substitutions: See Section 016000 - Product Requirements.
- L. Pipe Hangers: For a given pipe run use hangers of the same type and material.
 - 1. Manufacturers:
 - a. Ferguson Enterprises Inc: www.fnw.com.
 - b. Substitutions: See Section 016000 - Product Requirements.
 - 2. Provide coated or plated hangers to isolate steel hangers from dissimilar metal tube or pipe.
- M. Intermediate Pipe Guides: Use pipe clamps with oversize pipe sleeve that provides clearance around pipe.
 - 1. Pipe Diameter 6 inches and Smaller: Provide minimum clearance of 0.16 inch.
 - 2. Pipe Diameter 8 inches: Provide U-bolts with double nuts providing minimum clearance of 0.28 inch.
 - 3. Pipe Diameter 8 inches: 0.625 inch U-bolt.
- N. Dielectric Barriers: Provide between metallic supports and metallic piping and associated items of dissimilar type; acceptable dielectric barriers include rubber or plastic sheets or coatings attached securely to pipe or item.
- O. Non-Penetrating Rooftop Supports for Low-Slope Roofs:
 - 1. Manufacturers:
 - a. Cooper B-Line, a division of Eaton Corporation: www.cooperindustries.com.
 - b. Erico International Corporation, a brand of Pentair: www.erico.com.
 - c. Ferguson Enterprises Inc: www.fnw.com.
 - d. PHP Systems/Design: www.phpsd.com/#sle.
 - e. Unistrut, a brand of Atkore International Inc: www.unistrut.com.
 - f. Substitutions: See Section 016000 - Product Requirements.
 - 2. Provide steel pedestals with thermoplastic or rubber base that rest on top of roofing membrane, not requiring any attachment to the roof structure and not penetrating the roofing assembly, with support fixtures as specified.
 - 3. Base Sizes: As required to distribute load sufficiently to prevent indentation of roofing assembly.
 - 4. Attachment/Support Fixtures: As recommended by manufacturer, same type as indicated for equivalent indoor hangers and supports.
 - 5. Mounting Height: Provide minimum clearance of 6 inches under supported component to top of roofing.
- P. Anchors and Fasteners:
 - 1. Manufacturers - Mechanical Anchors:
 - a. Hilti, Inc: www.us.hilti.com.
 - b. ITW Red Head, a division of Illinois Tool Works, Inc: www.itwredhead.com.
 - c. Powers Fasteners, Inc: www.powers.com.
 - d. Simpson Strong-Tie Company Inc: www.strongtie.com.
 - e. Substitutions: See Section 016000 - Product Requirements.
 - 2. Manufacturers - Powder-Actuated Fastening Systems:
 - a. Hilti, Inc: www.us.hilti.com.
 - b. ITW Ramset, a division of Illinois Tool Works, Inc: www.ramset.com.
 - c. Powers Fasteners, Inc: www.powers.com/#.
 - d. Simpson Strong-Tie Company Inc: www.strongtie.com.

- e. Substitutions: See Section 016000 - Product Requirements.
- 3. Unless otherwise indicated and where not otherwise restricted, use the anchor and fastener types indicated for the specified applications.
- 4. Concrete: Use preset concrete inserts, expansion anchors, or screw anchors.
- 5. Solid or Grout-Filled Masonry: Use expansion anchors or screw anchors.
- 6. Hollow Masonry: Use toggle bolts.
- 7. Hollow Stud Walls: Use toggle bolts.
- 8. Steel: Use beam clamps, machine bolts, or welded threaded studs.
- 9. Sheet Metal: Use sheet metal screws.
- 10. Wood: Use wood screws.
- 11. Plastic and lead anchors are not permitted.
- 12. Hammer-driven anchors and fasteners are not permitted.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that mounting surfaces are ready to receive support and attachment components.
- C. Verify that conditions are satisfactory for installation prior to starting work.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install anchors and fasteners in accordance with ICC Evaluation Services, LLC (ICC-ES) evaluation report conditions of use where applicable.
- C. Provide independent support from building structure. Do not provide support from piping, ductwork, conduit, or other systems.
- D. Unless specifically indicated or approved by Architect, do not provide support from suspended ceiling support system or ceiling grid.
- E. Unless specifically indicated or approved by Architect, do not provide support from roof deck.
- F. Do not penetrate or otherwise notch or cut structural members without approval of Structural Engineer.
- G. Provide thermal insulated pipe supports complete with hangers and accessories. Install thermal insulated pipe supports during the installation of the piping system.
- H. Equipment Support and Attachment:
 - 1. Use metal fabricated supports or supports assembled from metal channel (strut) to support equipment as required.
 - 2. Use metal channel (strut) secured to studs to support equipment surface-mounted on hollow stud walls when wall strength is not sufficient to resist pull-out.
 - 3. Use metal channel (strut) to support surface-mounted equipment in wet or damp locations to provide space between equipment and mounting surface.
 - 4. Securely fasten floor-mounted equipment. Do not install equipment such that it relies on its own weight for support.
- I. Secure fasteners according to manufacturer's recommended torque settings.
- J. Remove temporary supports.

3.03 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect support and attachment components for damage and defects.
- C. Repair cuts and abrasions in galvanized finishes using zinc-rich paint recommended by manufacturer. Replace components that exhibit signs of corrosion.
- D. Correct deficiencies and replace damaged or defective support and attachment components.

LONGVIEW SCHOOL DISTRICT
MMHS CHILLER REPLACEMENT
November 01, 2024

230529
Hangers and Supports for HVAC Piping and
Equipment

END OF SECTION

SECTION 230548
VIBRATION AND SEISMIC CONTROLS FOR HVAC

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Vibration isolation requirements.
- B. Seismic control requirements.
- C. Vibration-isolated equipment support bases.
- D. Vibration isolators.
- E. External seismic snubber assemblies.
- F. Seismic restraint systems.

1.02 RELATED REQUIREMENTS

- A. Section 014533 - Code-Required Special Inspections and Procedures.
- B. Section 033000 - Cast-in-Place Concrete.

1.03 DEFINITIONS

- A. HVAC Component: Where referenced in this section in regards to seismic controls, applies to any portion of the HVAC system subject to seismic evaluation in accordance with applicable codes, including distributed systems (e.g. ductwork, piping).
- B. Seismic Restraint: Structural members or assemblies of members or manufactured elements specifically designed and applied for transmitting seismic forces between components and the seismic force-resisting system of the structure.

1.04 REFERENCE STANDARDS

- A. ASCE 7 - Minimum Design Loads and Associated Criteria for Buildings and Other Structures; Most Recent Edition Cited by Referring Code or Reference Standard.
- B. ASCE 19 - Structural Applications of Steel Cables for Buildings; 2016.
- C. ASHRAE (HVAC) - ASHRAE Handbook - HVAC Applications; Most Recent Edition Cited by Referring Code or Reference Standard.
- D. FEMA 412 - Installing Seismic Restraints for Mechanical Equipment; 2002.
- E. FEMA 413 - Installing Seismic Restraints for Electrical Equipment; 2004.
- F. FEMA 414 - Installing Seismic Restraints for Duct and Pipe; 2004.
- G. FEMA E-74 - Reducing the Risks of Nonstructural Earthquake Damage; 2012.
- H. SMACNA (SRM) - Seismic Restraint Manual Guidelines for Mechanical Systems; 2008.

1.05 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate selection and arrangement of vibration isolation and/or seismic control components with the actual equipment to be installed.
 - 2. Coordinate the work with other trades to provide additional framing and materials required for installation.
 - 3. Coordinate compatibility of support and attachment components with mounting surfaces at the installed locations.
 - 4. Seismic Controls:
 - a. Coordinate the arrangement of seismic restraints with piping, conduit, equipment, and other potential conflicts installed under other sections or by others.
 - 5. Notify Architect of any conflicts with or deviations from Contract Documents. Obtain direction before proceeding with work.
- B. Sequencing:

1. Do not install products on or provide attachment to concrete surfaces until concrete has fully cured in accordance with Section 033000.

1.06 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Design Documents: Prepare and submit all information required for plan review and permitting by authorities having jurisdiction, including but not limited to floor plans, details, and calculations.
- C. Product Data: Provide manufacturer's standard catalog pages and data sheets for products, including materials, fabrication details, dimensions, and finishes.
 1. Vibration Isolators: Include rated load capacities and deflections; include information on color coding or other identification method for spring element load capacities.
 2. Seismic Controls: Include seismic load capacities.
- D. Shop Drawings - Vibration Isolation Systems:
 1. Include dimensioned plan views and sections indicating proposed arrangement of vibration isolators; indicate equipment weights and static deflections.
 2. Vibration-Isolated Equipment Support Bases: Include base weights, including concrete fill where applicable; indicate equipment mounting provisions.
- E. Shop Drawings - Seismic Controls:
 1. Include dimensioned plan views and sections indicating proposed HVAC component locations and distributed system routing, with locations and details of gravity supports and seismic restraints and associated attachments.
 2. Identify mounting conditions required for equipment seismic qualification.
 3. Identify anchor manufacturer, type, minimum embedment, minimum spacing, minimum member thickness, and minimum edge distance requirements.
 4. Indicate proposed arrangement of distributed system trapeze support groupings.
 5. Indicate proposed locations for distributed system flexible fittings and/or connections.
 6. Indicate locations of seismic separations where applicable.
 7. Include point load drawings indicating design loads transmitted to structure at each attachment location.
- F. Seismic Design Data:
 1. Compile information on project-specific characteristics of actual installed HVAC components necessary for determining seismic design forces required to design appropriate seismic controls, including but not limited to the following.
 - a. Component importance factor (I_p).
 - b. For distributed systems, component materials and connection methods.
 - c. Component amplification factor (a_p) and component response modification factor (R_p), determined in accordance with ASCE 7 tables.
 - d. Applicability of overstrength factor (for certain anchorage in concrete and masonry).
- G. Certification for seismically qualified equipment; identify basis for certification.
- H. Evaluation Reports: For products specified as requiring evaluation and recognition by a qualified evaluation service, provide current evaluation reports.
- I. Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
- J. Evidence of qualifications for seismic controls designer.
- K. Evidence of qualifications for manufacturer.

1.07 QUALITY ASSURANCE

- A. Comply with applicable building code.

- B. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.01 VIBRATION ISOLATION REQUIREMENTS

- A. Design and provide vibration isolation systems to reduce vibration transmission to supporting structure from vibration-producing HVAC equipment and/or HVAC connections to vibration-isolated equipment.
- B. Comply with applicable general recommendations of ASHRAE (HVACA), where not in conflict with other specified requirements:
- C. General Requirements:
 - 1. Select vibration isolators to provide required static deflection.
 - 2. Select vibration isolators for uniform deflection based on distributed operating weight of actual installed equipment.
 - 3. Select vibration isolators for outdoor equipment to comply with wind design requirements.
- D. Piping Isolation:
 - 1. Provide vibration isolators for piping supports:
 - a. Located in equipment rooms.
 - b. Located within 50 feet of connected vibration-isolated equipment and pressure-regulating valve (PRV) stations.
 - 2. Minimum Static Deflection:
 - a. First Three Supports Closest to Isolated Equipment: Same as static deflection of equipment; maximum of 2 inch deflection required.
 - b. Remainder of Supports: 0.75 inch deflection unless otherwise indicated.
 - 3. Suspended Piping, Non-Seismic Applications: Use resilient material isolator hangers, spring isolator hangers, or combination resilient material/spring isolator hangers.
 - 4. Suspended Piping, Seismic Applications: Use seismic type resilient material isolator hangers, seismic type spring isolator hangers, or seismic type combination resilient material/spring isolator hangers.
 - 5. Floor-Mounted Piping, Non-Seismic Applications: Use open (unhoused) spring isolators.
 - 6. Floor-Mounted Piping, Seismic Applications: Use seismic type restrained spring isolators.
 - 7. Use modular seal or approved resilient material where vibration-isolated piping penetrates building elements (e.g. walls, floors) arranged to prevent vibration transmission to structure.
- E. Thrust Restraint Applications:
 - 1. Use thrust restraints to resist horizontal motion due to thrust for fan heads, suspended fans, and base-mounted and suspended air handling equipment operating at 2.0 inches wg or greater total static pressure.
 - 2. Minimum Static Deflection: Same as static deflection of equipment.
 - 3. Limit lateral movement to 0.25 inch or less unless otherwise indicated.

2.02 SEISMIC CONTROL REQUIREMENTS

- A. Design and provide HVAC component restraints, supports, and attachments suitable for seismic loads determined in accordance with applicable codes, as well as gravity and operating loads and other structural design considerations of the installed location. Consider wind loads for outdoor HVAC components.
- B. Seismic Restraints:
 - 1. Provide seismic restraints for HVAC components except where exempt according to applicable codes and specified seismic design criteria, as approved by authorities having jurisdiction.

2. Comply with applicable general recommendations of the following, where not in conflict with applicable codes, seismic design criteria, or other specified requirements:
 - a. ASHRAE (HVACA).
 - b. FEMA 412.
 - c. FEMA 413.
 - d. FEMA 414.
 - e. FEMA E-74.
 - f. SMACNA (SRM).
3. External Seismic Snubber Assemblies:
 - a. Provide quantity and arrangement of external seismic snubber assemblies as required to restrain equipment in all directions (both lateral and vertical).
 - b. Do not use external seismic snubber assemblies that restrain equipment only in one or more lateral directions (but not vertical) except where uplift forces are zero or are addressed by other restraints.
4. Seismic Restraint Systems:
 - a. Except where otherwise restricted, use of either cable or rigid restraints is permitted.
 - b. Use only cable restraints to restrain vibration-isolated HVAC components, including distributed systems.
 - c. Size restraint elements, including anchorage, to resist seismic loads as necessary to restrain HVAC component in all lateral directions; consider bracket geometry in anchor load calculations.
 - d. Use rod stiffener clips to attach bracing to hanger rods as required to prevent rod buckling from vertical (upward) compressive load introduced by cable or rigid restraints loaded in tension, in excess of downward tensile load due to supported HVAC component weight.
 - e. Select hanger rods and associated anchorage as required to accommodate vertical (downward) tensile load introduced by rigid restraints loaded in compression, in addition to downward tensile load due to supported HVAC component weight.
 - f. Clevis hangers may only be used for attachment of transverse restraints; do not use for attachment of longitudinal restraints.
 - g. Where seismic restraints are attached to clevis hangers, provide clevis bolt reinforcement accessory to prevent clevis hanger deformation.
 - h. Do not introduce lateral loads on open bar joist chords or the weak axis of beams, or loads in any direction at other than panel points unless approved by project Structural Engineer of Record.
- C. Seismic Attachments:
 1. Attachments to be bolted, welded, or otherwise positively fastened without consideration of frictional resistance produced by the effects of gravity.
 2. Post-Installed Concrete and Masonry Anchors: Evaluated and recognized by ICC Evaluation Service, LLC (ICC-ES) or qualified evaluation service acceptable to authorities having jurisdiction for compliance with applicable building code, and qualified for seismic applications; concrete anchors to be qualified for installation in both cracked and uncracked concrete.
 3. Do not use power-actuated fasteners.
 4. Do not use friction clips (devices that rely on mechanically applied friction to resist loads). Beam clamps may be used for supporting sustained loads where provided with restraining straps.
 5. Comply with anchor minimum embedment, minimum spacing, minimum member thickness, and minimum edge distance requirements.
 6. Concrete Housekeeping Pads:
 - a. Increase size of pad as required to comply with anchor requirements.
 - b. Provide pad reinforcement and doweling to ensure integrity of pad and connection and to provide adequate load path from pad to supporting structure.

- D. Seismic Interactions:
 - 1. Include provisions to prevent seismic impact between HVAC components and other structural or nonstructural components.
 - 2. Include provisions such that failure of a component, either essential or nonessential, does not cause the failure of an essential component.
- E. Seismic Relative Displacement Provisions:
 - 1. Use suitable fittings or flexible connections to accommodate:
 - a. Relative displacements between component supports attached to dissimilar parts of structure that may move differently during an earthquake.
 - b. Design displacements at seismic separations.
 - c. Anticipated drifts between floors.

2.03 VIBRATION-ISOLATED EQUIPMENT SUPPORT BASES

- A. Manufacturers:
 - 1. Vibration-Isolated Equipment Support Bases:
 - a. Kinetics Noise Control, Inc: www.kineticsnoise.com.
 - b. Mason Industries: www.mason-ind.com.
 - c. Vibration Eliminator Company, Inc: www.veco-nyc.com/.
 - d. Substitutions: See Section 016000 - Product Requirements.
 - 2. Source Limitations: Furnish vibration-isolated equipment support bases and associated components and accessories produced by the same manufacturer as the vibration isolators and obtained from a single supplier.
- B. Vibration-Isolated Concrete Inertia Bases:
 - 1. Description: Concrete-filled engineered steel forms with integral mounting provisions for vibration isolators, sized and configured for mounting of equipment.
 - 2. Minimum Base Depth: 6 inches.
 - 3. Minimum Base Mass (Including Concrete): 1.5 times weight of supported equipment.
 - 4. Concrete Reinforcement: Welded or tied reinforcing bars running both ways in a single layer.
 - 5. Concrete: Filled on site with minimum 3000 psi concrete in accordance with Section 033000.

2.04 VIBRATION ISOLATORS

- A. Manufacturers:
 - 1. Vibration Isolators:
 - a. Kinetics Noise Control, Inc: www.kineticsnoise.com.
 - b. Mason Industries: www.mason-ind.com.
 - c. Vibration Eliminator Company, Inc: www.veco-nyc.com.
 - d. Substitutions: See Section 016000 - Product Requirements.
- B. General Requirements:
 - 1. Resilient Materials for Vibration Isolators: Oil, ozone, and oxidant resistant.
 - 2. Spring Elements for Spring Isolators:
 - a. Color code or otherwise identify springs to indicate load capacity.
 - b. Lateral Stability: Minimum lateral stiffness to vertical stiffness ratio of 0.8.
 - c. Designed to operate in the linear portion of their load versus deflection curve over deflection range of not less than 50 percent above specified deflection.
 - d. Designed to provide additional travel to solid of not less than 50 percent of rated deflection at rated load.
 - e. Selected to provide designed deflection of not less than 75 percent of specified deflection.
 - f. Selected to function without undue stress or overloading.
 - 3. Seismic Snubbing Elements for Seismic Isolators:
 - a. Air Gap: Between 0.125 inches and 0.25 inches unless otherwise indicated.

- b. Points of Contact: Cushioned with resilient material, minimum 0.25 inch thick; capable of being visually inspected for damage and replaced.

2.05 EXTERNAL SEISMIC SNUBBER ASSEMBLIES

- A. Manufacturers:
 - 1. External Seismic Snubber Assemblies:
 - a. Kinetics Noise Control, Inc: www.kineticsnoise.com.
 - b. Mason Industries: www.mason-ind.com.
 - c. Vibration Eliminator Company, Inc: www.veco-nyc.com.
 - d. Substitutions: See Section 016000 - Product Requirements.
 - 2. Source Limitations: Furnish external seismic snubber assemblies and associated accessories produced by the same manufacturer as the vibration isolators and obtained from a single supplier.
- B. Description: Steel snubbing assemblies designed for external attachment to both equipment and supporting structure that, as part of a complete system, restrain equipment motion in all directions during a seismic event while maintaining vibration isolation during normal operation.
- C. Seismic Snubbing Elements:
 - 1. Air Gap: Between 0.125 inches and 0.25 inches unless otherwise indicated.
 - 2. Points of Contact: Cushioned with resilient material, minimum 0.25 inch thick; capable of being visually inspected for damage and replaced.

2.06 SEISMIC RESTRAINT SYSTEMS

- A. Manufacturers:
 - 1. Seismic Restraint Systems:
 - a. Eaton Corporation: www.eaton.com.
 - b. Kinetics Noise Control, Inc: www.kineticsnoise.com.
 - c. Mason Industries: www.mason-ind.com.
 - d. Substitutions: See Section 016000 - Product Requirements.
- B. Description: System components and accessories specifically designed for field assembly and attachment of seismic restraints.
- C. Cable Restraints:
 - 1. Comply with ASCE 19.
 - 2. Cables: Pre-stretched, galvanized steel wire rope with certified break strength.
 - 3. Cable Connections: Use only swaged end fittings. Cable clips and wedge type end fittings are not permitted in accordance with ASCE 19.
 - 4. Use protective thimbles for cable loops where potential for cable damage exists.
- D. Rigid Restraints: Use MFMA-4 steel channel (strut), steel angle, or steel pipe for structural element; suitable for both compressive and tensile design loads.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as shown on the drawings.
- B. Verify that mounting surfaces are ready to receive vibration isolation and/or seismic control components and associated attachments.
- C. Verify that conditions are satisfactory for installation prior to starting work.

3.02 CODE-REQUIRED SPECIAL INSPECTIONS

- A. Arrange work to accommodate tests and/or inspections performed by Special Inspection Agency employed by Owner or Architect in accordance with Section 014533 and statement of special inspections as required by applicable building code.
- B. Frequency of Special Inspections: Where special inspections are designated as continuous or periodic, arrange work accordingly.

1. Continuous Special Inspections: Special Inspection Agency to be present in the area where the work is being performed and observe the work at all times the work is in progress.
 2. Periodic Special Inspections: Special Inspection Agency to be present in the area where work is being performed and observe the work part-time or intermittently and at the completion of the work.
- C. Seismic special inspections include, but are not limited to:
1. Seismically Qualified Equipment: Verification that label, anchorage and mounting comply with the certificate of compliance.
 2. Installation and anchorage of piping systems designed to carry hazardous materials and their associated mechanical units for Seismic Design Categories C, D, E, and F; periodic inspection.
 3. Installation and anchorage of ductwork designed to carry hazardous materials for Seismic Design Categories C, D, E and F; periodic inspection.
 4. Installation and anchorage of vibration isolation systems for Seismic Design Categories C, D, E, and F where the approved Contract Documents require a nominal clearance of 1/4 inch or less between equipment support frame and seismic restraint; periodic inspection.
 5. Verification of required clearances between HVAC equipment, distribution systems, and associated supports and fire protection sprinkler system drops and sprigs for Seismic Design Categories C, D, E, and F; periodic inspection.
- D. Seismic special inspections include, but are not limited to:
1. Seismically Qualified Equipment: Verification that label, anchorage and mounting comply with the certificate of compliance.
 2. Installation and anchorage of piping systems designed to carry hazardous materials and their associated mechanical units for Seismic Design Categories C, D, E, and F; periodic inspection.
 3. Installation and anchorage of ductwork designed to carry hazardous materials for Seismic Design Categories C, D, E and F; periodic inspection.
 4. Installation and anchorage of vibration isolation systems for Seismic Design Categories C, D, E, and F where the approved Contract Documents require a nominal clearance of 1/4 inch or less between equipment support frame and seismic restraint; periodic inspection.
- E. Prior to starting work, Contractor to submit written statement of responsibility to authorities having jurisdiction and to Owner acknowledging awareness of special requirements contained in the statement of special inspections.
- F. Special Inspection Agency services do not relieve Contractor from performing inspections and testing specified elsewhere.

3.03 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install anchors and fasteners in accordance with ICC Evaluation Services, LLC (ICC-ES) evaluation report conditions of use where applicable.
- C. Secure fasteners according to manufacturer's recommended torque settings.
- D. Install flexible piping connections to provide sufficient slack for vibration isolation and/or seismic relative displacements as indicated or as required.
- E. Vibration Isolation Systems:
 1. Vibration-Isolated Equipment Support Bases:
 - a. Provide specified minimum clearance beneath base.
 2. Spring Isolators:
 - a. Position equipment at operating height; provide temporary blocking as required.
 - b. Lift equipment free of isolators prior to lateral repositioning to avoid damage to isolators.

- c. Level equipment by adjusting isolators gradually in sequence to raise equipment uniformly such that excessive weight or stress is not placed on any single isolator.
 3. Isolator Hangers:
 - a. Use precompressed isolator hangers where required to facilitate installation and prevent damage to equipment utility connection provisions.
 - b. Locate isolator hangers at top of hanger rods in accordance with manufacturer's instructions.
 4. Thrust Restraints:
 - a. Adjust restraint movement under normal operating static pressure.
 5. Clean debris from beneath vibration-isolated equipment that could cause short circuiting of isolation.
 6. Use elastomeric grommets for attachments where required to prevent short circuiting of isolation.
 7. Adjust isolators to be free of isolation short circuits during normal operation.
 8. Do not overtighten fasteners such that resilient material isolator pads are compressed beyond manufacturer's maximum recommended deflection.
- F. Seismic Controls:
 1. Provide specified snubbing element air gap; remove any factory-installed spacers, debris, or other obstructions.
 2. Use only specified components, anchorage, and hardware evaluated by seismic design. Comply with conditions of seismic certification where applicable.
 3. Where mounting hole diameter exceeds bolt diameter by more than 0.125 inch, use epoxy grout, elastomeric grommet, or welded washer to reduce clearance to 0.125 inch or less.
 4. Equipment with Sheet Metal Housings:
 - a. Use Belleville washers to distribute stress over a larger surface area of the sheet metal connection interface as approved by manufacturer.
 - b. Attach additional steel as approved by manufacturer where required to transfer loads to structure.
 - c. Where mounting surface is irregular, do not shim housing; reinforce housing with additional steel as approved by manufacturer.
 5. Concrete Housekeeping Pads:
 - a. Size in accordance with seismic design to meet anchor requirements.
 - b. Install pad reinforcement and doweling in accordance with seismic design to ensure integrity of pad and associated connection to slab.
 6. Seismic Restraint Systems:
 - a. Do not attach seismic restraints and gravity supports to dissimilar parts of structure that may move differently during an earthquake.
 - b. Install restraints within permissible angles in accordance with seismic design.
 - c. Install cable restraints straight between component/run and structural attachment; do not bend around other nonstructural components or structural elements.
 - d. Install hanger rod stiffeners where indicated using only specified clamps; do not weld stiffeners to hanger rod.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect vibration isolation and/or seismic control components for damage and defects.
- C. Vibration Isolation Systems:
 1. Verify isolator static deflections.
 2. Verify vibration isolation performance during normal operation; investigate sources of isolation short circuits.
- D. Seismic Controls:
 1. Verify snubbing element air gaps.

- E. Correct deficiencies and replace damaged or defective vibration isolation and/or seismic control components.

END OF SECTION

SECTION 230553
IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Nameplates.
- B. Tags.
- C. Pipe markers.
- D. Ceiling tacks.

1.02 REFERENCE STANDARDS

1.03 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Chart and Schedule: Submit valve chart and schedule, including valve tag number, location, function, and valve manufacturer's name and model number.

PART 2 PRODUCTS

2.01 IDENTIFICATION APPLICATIONS

- A. Air Handling Units: Nameplates.
- B. Piping: Tags.
- C. Pumps: Nameplates.
- D. Small-sized Equipment: Tags.
- E. Tanks: Nameplates.
- F. Thermostats: Nameplates.
- G. Valves: Tags and ceiling tacks where located above lay-in ceiling.

2.02 NAMEPLATES

- A. Manufacturers:
 - 1. Advanced Graphic Engraving, LLC: www.advancedgraphicengraving.com.
 - 2. Brimar Industries, Inc: www.pipemarker.com.
 - 3. Craftmark Pipe Markers: www.craftmarkid.com.
 - 4. Kolbi Pipe Marker Co: www.kolbipipemarkers.com.
 - 5. Seton Identification Products, a Tricor Direct Company: www.seton.com.
 - 6. Substitutions: See Section 016000 - Product Requirements.
- B. Letter Color: White.
- C. Letter Height: 1/4 inch.
- D. Background Color: Black.

2.03 TAGS

- A. Manufacturers:
 - 1. Advanced Graphic Engraving: www.advancedgraphicengraving.com.
 - 2. Brady Corporation: www.bradycorp.com.
 - 3. Brimar Industries, Inc: www.pipemarker.com.
 - 4. Craftmark Pipe Markers: www.craftmarkid.com.
 - 5. Kolbi Pipe Marker Co: www.kolbipipemarkers.com.
 - 6. Seton Identification Products, a Tricor Company: www.seton.com.
 - 7. Substitutions: See Section 016000 - Product Requirements.
- B. Plastic Tags: Laminated three-layer plastic with engraved black letters on light contrasting background color. Tag size minimum 1-1/2 inch diameter.

- C. Metal Tags: Brass with stamped letters; tag size minimum 1-1/2 inch diameter with smooth edges.
- D. Valve Tag Chart: Typewritten letter size list in anodized aluminum frame.

2.04 PIPE MARKERS

- A. Manufacturers:
 - 1. Brady Corporation: www.bradycorp.com.
 - 2. Brimar Industries, Inc: www.pipemarker.com.
 - 3. Craftmark Pipe Markers: www.craftmarkid.com.
 - 4. Kolbi Pipe Marker Co: www.kolbipipemarkers.com.
 - 5. Seton Identification Products, a Tricor Company: www.seton.com.
 - 6. Substitutions: See Section 016000 - Product Requirements.
- B. Color: Comply with ASME A13.1.
- C. Plastic Pipe Markers: Factory fabricated, flexible, semi- rigid plastic, preformed to fit around pipe or pipe covering; minimum information indicating flow direction arrow and identification of fluid being conveyed.
- D. Plastic Tape Pipe Markers: Flexible, vinyl film tape with pressure sensitive adhesive backing and printed markings.
- E. Underground Plastic Pipe Markers: Bright colored continuously printed plastic ribbon tape, minimum 6 inches wide by 4 mil thick, manufactured for direct burial service.
- F. Color code as follows:
 - 1. Heating, Cooling, and Boiler Feedwater: Green with white letters.
 - 2. Toxic and Corrosive Fluids: Orange with black letters.
 - 3. Compressed Air: Blue with white letters.

2.05 CEILING TACKS

- A. Manufacturers:
 - 1. Craftmark Pipe Marker: www.craftmarkid.com.
 - 2. Substitutions: See Section 016000 - Product Requirements.
- B. Description: Steel with 3/4 inch diameter color coded head.
- C. Color code as follows:
 - 1. HVAC Equipment: Yellow.
 - 2. Fire Dampers and Smoke Dampers: Red.
 - 3. Heating/Cooling Valves: Blue.

PART 3 EXECUTION

3.01 PREPARATION

- A. Degrease and clean surfaces to receive adhesive for identification materials.

3.02 INSTALLATION

- A. Install nameplates with corrosive-resistant mechanical fasteners, or adhesive. Apply with sufficient adhesive to ensure permanent adhesion and seal with clear lacquer.
- B. Install tags with corrosion resistant chain.
- C. Install plastic pipe markers in accordance with manufacturer's instructions.
- D. Install plastic tape pipe markers complete around pipe in accordance with manufacturer's instructions.
- E. Use tags on piping 3/4 inch diameter and smaller.
 - 1. Identify service, flow direction, and pressure.
 - 2. Install in clear view and align with axis of piping.

3. Locate identification not to exceed 20 feet on straight runs including risers and drops, adjacent to each valve and Tee, at each side of penetration of structure or enclosure, and at each obstruction.
- F. Locate ceiling tacks to locate valves or dampers above lay-in panel ceilings. Locate in corner of panel closest to equipment.

END OF SECTION

SECTION 230593
TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Testing, adjustment, and balancing of air systems.
- B. Testing, adjustment, and balancing of hydronic and refrigerating systems.
- C. Measurement of final operating condition of HVAC systems.
- D. Sound measurement of equipment operating conditions.
- E. Commissioning activities.

1.02 RELATED REQUIREMENTS

- A. Section 019113 - General Commissioning Requirements: Commissioning requirements that apply to all types of work.
- B. Section 230800 - Commissioning of HVAC.

1.03 REFERENCE STANDARDS

- A. AABC (NSTSB) - AABC National Standards for Total System Balance, 7th Edition; 2016.
- B. ASHRAE Std 111 - Measurement, Testing, Adjusting, and Balancing of Building HVAC Systems; 2008, with Errata (2019).

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. TAB Plan: Submit a written plan indicating the testing, adjusting, and balancing standard to be followed and the specific approach for each system and component.
 - 1. Include at least the following in the plan:
 - a. List of all air flow, water flow, sound level, system capacity and efficiency measurements to be performed and a description of specific test procedures, parameters, formulas to be used.
 - b. Copy of field checkout sheets and logs to be used, listing each piece of equipment to be tested, adjusted and balanced with the data cells to be gathered for each.
 - c. Discussion of what notations and markings will be made on the duct and piping drawings during the process.
 - d. Final test report forms to be used.
 - e. Detailed step-by-step procedures for TAB work for each system and issue, including:
 - 1) Terminal flow calibration (for each terminal type).
 - 2) Branch/submain proportioning.
 - 3) Total flow calculations.
 - 4) Rechecking.
 - 5) Diversity issues.
 - f. Confirmation of understanding of the outside air ventilation criteria under all conditions.
 - g. Method of checking building static and exhaust fan and/or relief damper capacity.
 - h. Procedures for formal deficiency reports, including scope, frequency and distribution.
- C. Control System Coordination Reports: Communicate in writing to the controls installer all setpoint and parameter changes made or problems and discrepancies identified during TAB that affect, or could affect, the control system setup and operation.
- D. Final Report: Indicate deficiencies in systems that would prevent proper testing, adjusting, and balancing of systems and equipment to achieve specified performance.
 - 1. Revise TAB plan to reflect actual procedures and submit as part of final report.

2. Submit draft copies of report for review prior to final acceptance of Project. Provide final copies for Architect and for inclusion in operating and maintenance manuals.
3. Include actual instrument list, with manufacturer name, serial number, and date of calibration.
4. Form of Test Reports: Where the TAB standard being followed recommends a report format use that; otherwise, follow ASHRAE Std 111.
5. Units of Measure: Report data in I-P (inch-pound) units only.
6. Include the following on the title page of each report:
 - a. Name of Testing, Adjusting, and Balancing Agency.
 - b. Address of Testing, Adjusting, and Balancing Agency.
 - c. Telephone number of Testing, Adjusting, and Balancing Agency.
 - d. Project name.
 - e. Project location.
 - f. Report date.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 GENERAL REQUIREMENTS

- A. Perform total system balance in accordance with one of the following:
 1. AABC (NSTSB), AABC National Standards for Total System Balance.
- B. Begin work after completion of systems to be tested, adjusted, or balanced and complete work prior to Substantial Completion of the project.
- C. Where HVAC systems and/or components interface with life safety systems, including fire and smoke detection, alarm, and control, coordinate scheduling and testing and inspection procedures with the authorities having jurisdiction.
- D. TAB Agency Qualifications:
 1. Company specializing in the testing, adjusting, and balancing of systems specified in this section.
 2. Having minimum of three years documented experience.
 3. Certified by one of the following:
 - a. AABC, Associated Air Balance Council: www.aabc.com/#sle; upon completion submit AABC National Performance Guaranty.
- E. TAB Supervisor and Technician Qualifications: Certified by same organization as TAB agency.

3.02 EXAMINATION

- A. Verify that systems are complete and operable before commencing work. Ensure the following conditions:
 1. Systems are started and operating in a safe and normal condition.
 2. Temperature control systems are installed complete and operable.
 3. Proper thermal overload protection is in place for electrical equipment.
 4. Final filters are clean and in place. If required, install temporary media in addition to final filters.
 5. Duct systems are clean of debris.
 6. Fans are rotating correctly.
 7. Fire and volume dampers are in place and open.
 8. Air coil fins are cleaned and combed.
 9. Access doors are closed and duct end caps are in place.
 10. Air outlets are installed and connected.
 11. Duct system leakage is minimized.
 12. Hydronic systems are flushed, filled, and vented.
 13. Pumps are rotating correctly.
 14. Proper strainer baskets are clean and in place.

- 15. Service and balance valves are open.
- B. Submit field reports. Report defects and deficiencies that will or could prevent proper system balance.
- C. Beginning of work means acceptance of existing conditions.

3.03 PREPARATION

- A. Provide instruments required for testing, adjusting, and balancing operations. Make instruments available to Architect to facilitate spot checks during testing.
- B. Provide additional balancing devices as required.

3.04 ADJUSTMENT TOLERANCES

- A. Air Handling Systems: Adjust to within plus or minus 5 percent of design for supply systems and plus or minus 10 percent of design for return and exhaust systems.
- B. Air Outlets and Inlets: Adjust total to within plus 10 percent and minus 5 percent of design to space. Adjust outlets and inlets in space to within plus or minus 10 percent of design.
- C. Hydronic Systems: Adjust to within plus or minus 10 percent of design.

3.05 RECORDING AND ADJUSTING

- A. Field Logs: Maintain written logs including:
 - 1. Running log of events and issues.
 - 2. Discrepancies, deficient or uncompleted work by others.
 - 3. Contract interpretation requests.
 - 4. Lists of completed tests.
- B. Ensure recorded data represents actual measured or observed conditions.
- C. Permanently mark settings of valves, dampers, and other adjustment devices allowing settings to be restored. Set and lock memory stops.
- D. Mark on drawings the locations where traverse and other critical measurements were taken and cross reference the location in the final report.
- E. After adjustment, take measurements to verify balance has not been disrupted or that such disruption has been rectified.
- F. Leave systems in proper working order, replacing belt guards, closing access doors, closing doors to electrical switch boxes, and restoring thermostats to specified settings.

3.06 AIR SYSTEM PROCEDURE

- A. Adjust air handling and distribution systems to provide required or design supply, return, and exhaust air quantities at site altitude.
- B. Make air quantity measurements in ducts by Pitot tube traverse of entire cross sectional area of duct.
- C. Measure air quantities at air inlets and outlets.
- D. Use volume control devices to regulate air quantities only to extend that adjustments do not create objectionable air motion or sound levels. Effect volume control by duct internal devices such as dampers and splitters.
- E. Vary total system air quantities by adjustment of fan speeds. Provide drive changes required. Vary branch air quantities by damper regulation.
- F. Provide system schematic with required and actual air quantities recorded at each outlet or inlet.
- G. Adjust outside air automatic dampers, outside air, return air, and exhaust dampers for design conditions.
- H. Measure temperature conditions across outside air, return air, and exhaust dampers to check leakage.

- I. Where modulating dampers are provided, take measurements and balance at extreme conditions. Balance variable volume systems at maximum air flow rate, full cooling, and at minimum air flow rate, full heating.
- J. Check multi-zone units for motorized damper leakage. Adjust air quantities with mixing dampers set first for cooling, then heating, then modulating.
- K. For variable air volume system powered units set volume controller to air flow setting indicated. Confirm connections properly made and confirm proper operation for automatic variable air volume temperature control.

3.07 WATER SYSTEM PROCEDURE

- A. Adjust water systems to provide required or design quantities.
- B. Use calibrated Venturi tubes, orifices, or other metered fittings and pressure gages to determine flow rates for system balance. Where flow metering devices are not installed, base flow balance on temperature difference across various heat transfer elements in the system.
- C. Adjust systems to provide specified pressure drops and flows through heat transfer elements prior to thermal testing. Perform balancing by measurement of temperature differential in conjunction with air balancing.
- D. Effect system balance with automatic control valves fully open to heat transfer elements.
- E. Effect adjustment of water distribution systems by means of balancing cocks, valves, and fittings. Do not use service or shut-off valves for balancing unless indexed for balance point.
- F. Where available pump capacity is less than total flow requirements or individual system parts, full flow in one part may be simulated by temporary restriction of flow to other parts.

3.08 COMMISSIONING

- A. See Sections 019113 - General Commissioning Requirements and 230800 for additional requirements.
- B. Perform prerequisites prior to starting commissioning activities.
- C. Fill out Prefunctional Checklists for:
 - 1. Air side systems.
 - 2. Water side systems.
- D. Furnish to the Commissioning Authority, upon request, any data gathered but not shown in the final TAB report.
- E. Re-check minimum outdoor air intake flows and maximum and intermediate total airflow rates for 50 percent of the air handlers plus a random sample equivalent to 25 percent of the final TAB report data as directed by Commissioning Authority.
 - 1. Original TAB agency shall execute the re-checks, witnessed by the Commissioning Authority.
 - 2. Use the same test instruments as used in the original TAB work.
 - 3. Failure of more than 10 percent of the re-checked items of a given system shall result in the rejection of the system TAB report; rebalance the system, provide a new system TAB report, and repeat random re-checks.
 - 4. For purposes of re-check, failure is defined as follows:
 - a. Air Flow of Supply and Return: Deviation of more than 10 percent of instrument reading.
 - b. Minimum Outside Air Flow: Deviation of more than 20 percent of instrument reading; for inlet vane or VFD OSA compensation system using linear proportional control, deviation of more than 30 percent at intermediate supply flow.
 - c. Temperatures: Deviation of more than one degree F.
 - d. Air and Water Pressures: Deviation of more than 10 percent of full scale of test instrument reading.

- e. Sound Pressures: Deviation of more than 3 decibels, with consideration for variations in background noise.
- 5. For purposes of re-check, a whole system is defined as one in which inaccuracies will have little or no impact on connected systems; for example, the air distribution system served by one air handler or the hydronic chilled water supply system served by a chiller or the condenser water system.
- F. In the presence of the Commissioning Authority, verify that:
 - 1. Final settings of all valves, splitters, dampers and other adjustment devices have been permanently marked.
 - 2. The air system is being controlled to the lowest possible static pressure while still meeting design loads, less diversity; this shall include a review of TAB methods, established control setpoints, and physical verification of at least one leg from fan to diffuser having all balancing dampers wide open and that during full cooling of all terminal units taking off downstream of the static pressure sensor, the terminal unit on the critical leg has its damper 90 percent or more open.
 - 3. The water system is being controlled to the lowest possible pressure while still meeting design loads, less diversity; this shall include a review of TAB methods, established control setpoints, and physical verification of at least one leg from the pump to the coil having all balancing valves wide open and that during full cooling the cooling coil valve of that leg is 90 percent or more open.

3.09 SCOPE

- A. Test, adjust, and balance the following:
 - 1. HVAC Pumps.
 - 2. Air Cooled Water Chillers.
 - 3. Air Coils.
 - 4. Fans.
 - 5. Air Filters.

3.10 MINIMUM DATA TO BE REPORTED

- A. Electric Motors:
 - 1. Manufacturer.
 - 2. Model/Frame.
 - 3. HP/BHP.
 - 4. Phase, voltage, amperage; nameplate, actual, no load.
 - 5. RPM.
- B. Pumps:
 - 1. Identification/number.
 - 2. Manufacturer.
 - 3. Size/model.
 - 4. Design flow rate, pressure drop, BHP.
 - 5. Actual flow rate, pressure drop, BHP.
 - 6. Discharge pressure.
 - 7. Suction pressure.
 - 8. Total operating head pressure.
 - 9. Shut off, discharge and suction pressures.
 - 10. Shut off, total head pressure.
- C. Chillers:
 - 1. Identification/number.
 - 2. Manufacturer.
 - 3. Capacity.
 - 4. Model number.
 - 5. Serial number.

6. Evaporator entering water temperature, design and actual.
 7. Evaporator leaving water temperature, design and actual.
 8. Evaporator pressure drop, design and actual.
 9. Evaporator water flow rate, design and actual.
 10. Condenser entering water temperature, design and actual.
 11. Condenser pressure drop, design and actual.
 12. Condenser water flow rate, design and actual.
- D. Cooling Coils:
1. Identification/number.
 2. Location.
 3. Service.
 4. Manufacturer.
 5. Air flow, design and actual.
 6. Entering air DB temperature, design and actual.
 7. Leaving air DB temperature, design and actual.
 8. Water flow, design and actual.
 9. Water pressure drop, design and actual.
- E. Air Moving Equipment:
1. Location.
 2. Manufacturer.
 3. Model number.
 4. Serial number.
 5. Arrangement/Class/Discharge.
 6. Air flow, specified and actual.
 7. Return air flow, specified and actual.
 8. Outside air flow, specified and actual.
 9. Total static pressure (total external), specified and actual.
 10. Inlet pressure.
 11. Discharge pressure.
 12. Fan RPM.
- F. Sound Level Reports:
1. Location.
 2. Octave bands - equipment off.
 3. Octave bands - equipment on.

END OF SECTION

**SECTION 230719
HVAC PIPING INSULATION**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Piping insulation.
- B. Flexible removable and reusable blanket insulation.
- C. Jackets and accessories.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.

1.03 REFERENCE STANDARDS

- A. ASTM A666 - Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar; 2015.
- B. ASTM B209 - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2014.
- C. ASTM B209M - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric); 2014.
- D. ASTM C177 - Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus; 2019.
- E. ASTM C534/C534M - Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form; 2020a.
- F. ASTM C547 - Standard Specification for Mineral Fiber Pipe Insulation; 2022a.
- G. ASTM E96/E96M - Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials; 2022a.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service, and locations.
- C. Manufacturer's Instructions: Indicate installation procedures that ensure acceptable workmanship and installation standards will be achieved.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with not less than three years of documented experience.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Accept materials on site, labeled with manufacturer's identification, product density, and thickness.
- B. Inspect for damage prior to acceptance.

1.07 FIELD CONDITIONS

- A. Maintain ambient conditions required by manufacturers of each product.
- B. Maintain temperature before, during, and after installation for minimum of 24 hours.

PART 2 PRODUCTS

2.01 REGULATORY REQUIREMENTS

- A. Surface Burning Characteristics: Flame spread index/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E84 or UL 723.

2.02 GLASS FIBER, RIGID

- A. Manufacturers:
 - 1. CertainTeed Corporation.
 - 2. Johns Manville Corporation.
 - 3. Knauf Insulation.
 - 4. Owens Corning Corporation.
 - 5. Substitutions: See Section 016000 - Product Requirements.
- B. Insulation: ASTM C547 and ASTM C795; rigid molded, noncombustible.
 - 1. K Value: ASTM C177, 0.24 at 75 degrees F.
 - 2. Maximum Service Temperature: 850 degrees F.
 - 3. Maximum Moisture Absorption: 0.2 percent by volume.
- C. Insulation: ASTM C547 and ASTM C795; rigid molded, noncombustible, with wicking material to transport condensed water to the outside of the system for evaporation to the atmosphere.
 - 1. K Value: ASTM C177, 0.23 at 75 degrees F.
 - 2. Maximum Service Temperature: 220 degrees F.
 - 3. Maximum Moisture Absorption: 0.2 percent by volume.
- D. Insulation: ASTM C547 and ASTM C795; semi-rigid, noncombustible, end grain adhered to jacket.
 - 1. Maximum Service Temperature: 650 degrees F.
 - 2. Maximum Moisture Absorption: 0.2 percent by volume.
- E. Vapor Barrier Jacket: White kraft paper with glass fiber yarn, bonded to aluminized film; moisture vapor transmission when tested in accordance with ASTM E96/E96M of 0.02 perm-inches.
- F. Vapor Barrier Lap Adhesive: Compatible with insulation.

2.03 FLEXIBLE ELASTOMERIC CELLULAR INSULATION

- A. Insulation: Preformed flexible elastomeric cellular rubber insulation complying with ASTM C534/C534M Grade 1; use molded tubular material wherever possible.
 - 1. Minimum Service Temperature: Minus 40 degrees F.
 - 2. Maximum Service Temperature: 220 degrees F.
 - 3. Connection: Waterproof vapor barrier adhesive.

2.04 JACKETS

- A. Aluminum Jacket: ASTM B209 (ASTM B209M) formed aluminum sheet.
 - 1. Thickness: 0.016 inch sheet.
 - 2. Finish: Smooth.
 - 3. Joining: Longitudinal slip joints and 2 inch laps.
 - 4. Fittings: 0.016 inch thick die shaped fitting covers with factory attached protective liner.
- B. Stainless Steel Jacket: ASTM A666, Type 304 stainless steel.
 - 1. Thickness: 0.010 inch.
 - 2. Finish: Smooth.
 - 3. Metal Jacket Bands: 3/8 inch wide; 0.010 inch thick stainless steel.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that piping has been tested and inspected before applying insulation materials.
- B. Verify that surfaces are clean and dry, with foreign material removed.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install in accordance with NAIMA National Insulation Standards.
- C. Exposed Piping: Locate insulation and cover seams in least visible locations.

- D. Insulated pipes conveying fluids below ambient temperature; insulate entire system including fittings, valves, unions, flanges, strainers, flexible connections, pump bodies, and expansion joints.
- E. Glass fiber insulated pipes conveying fluids below ambient temperature:
 - 1. Provide vapor barrier jackets, factory-applied or field-applied; secure with self-sealing longitudinal laps and butt strips with pressure sensitive adhesive. Secure with outward clinch expanding staples and vapor barrier mastic.
 - 2. Insulate fittings, joints, and valves with molded insulation of like material and thickness as adjacent pipe. Finish with glass cloth and vapor barrier adhesive or PVC fitting covers.
- F. Glass fiber insulated pipes conveying fluids above ambient temperature.
 - 1. Provide standard jackets, with or without vapor barrier, factory-applied or field-applied. Secure with self-sealing longitudinal laps and butt strips with pressure sensitive adhesive. Secure with outward clinch expanding staples.
 - 2. Insulate fittings, joints, and valves with insulation of like material and thickness as adjoining pipe. Finish with glass cloth and adhesive or PVC fitting covers.
- G. Continue insulation through walls, sleeves, pipe hangers, and other pipe penetrations. Finish at supports, protrusions, and interruptions. At fire separations, refer to Section 078400.
- H. Pipe Exposed in Mechanical Equipment Rooms or Finished Spaces (less than 10 feet above finished floor): Finish with PVC jacket and fitting covers.
- I. Exterior Applications: Provide vapor barrier jacket. Insulate fittings, joints, and valves with insulation of like material and thickness as adjoining pipe, and finish with glass mesh reinforced vapor barrier cement. Cover with aluminum jacket with seams located on bottom side of horizontal piping. Provide two coats of UV resistant finish for flexible elastomeric cellular insulation without jacketing.
- J. Buried Piping: Provide pre-manufactured continuous pre-insulated piping for underground piping. R-values shall match values scheduled. No piping joints shall be installed underground.
- K. Heat Traced Piping: Insulate fittings, joints, and valves with insulation of like material, thickness, and finish as adjoining pipe. Size large enough to enclose pipe and heat tracer. Cover with aluminum jacket with seams located on bottom side of horizontal piping.

3.03 SCHEDULE

- A. Cooling Systems:
 - 1. Chilled Water (Greater than 40 degrees F): 1 inch Insulation
 - 2. Cold Condensate Drains : 1/2 inch Insulation
 - 3. Condensate Drains from Cooling Coils: 1/2 inch Insulation

END OF SECTION

**SECTION 230800
COMMISSIONING OF HVAC**

PART 1 GENERAL

1.01 SUMMARY

- A. See Section 019113 - General Commissioning Requirements for overall objectives; comply with the requirements of Section 019113.
- B. This section covers the Contractor's responsibilities for commissioning; each subcontractor or installer responsible for the installation of a particular system or equipment item to be commissioned is responsible for the commissioning activities relating to that system or equipment item.
- C. The Commissioning Authority (CA) directs and coordinates all commissioning activities and provides Prefunctional Checklists and Functional Test Procedures for Contractor's use.
- D. The entire HVAC system is to be commissioned, including commissioning activities for the following specific items:
 - 1. Other equipment and systems explicitly identified elsewhere in Contract Documents as requiring commissioning.
- E. The Prefunctional Checklist and Functional Test requirements specified in this section are in addition to, not a substitute for, inspection or testing specified in other sections.

1.02 REFERENCE STANDARDS

- A. ASHRAE Guideline 1.1 - HVAC&R Technical Requirements for the Commissioning Process; 2007, with Errata (2012).

1.03 SUBMITTALS

- A. Updated Submittals: Keep the Commissioning Authority informed of all changes to control system documentation made during programming and setup; revise and resubmit when substantial changes are made.
- B. Startup Reports, Prefunctional Checklists, and Trend Logs: Submit for approval of Commissioning Authority.
- C. HVAC Control System O&M Manual Requirements. In addition to documentation specified elsewhere, compile and organize at minimum the following data on the control system:
 - 1. Specific step-by-step instructions on how to perform and apply all functions, features, modes, etc. mentioned in the controls training sections of this specification and other features of this system. Provide an index and clear table of contents. Include the detailed technical manual for programming and customizing control loops and algorithms.
 - 2. Full as-built set of control drawings.
 - 3. Full as-built sequence of operations for each piece of equipment.
 - 4. Full points list; in addition to the information on the original points list submittal, include a listing of all rooms with the following information for each room:
 - a. Floor.
 - b. Room number.
 - c. Room name.
 - d. Air handler unit ID.
 - e. Reference drawing number.
 - f. Air terminal unit tag ID.
 - g. Heating and/or cooling valve tag ID.
 - h. Minimum air flow rate.
 - i. Maximum air flow rate.
 - 5. Full print out of all schedules and set points after testing and acceptance of the system.
 - 6. Full as-built print out of software program.
 - 7. Electronic copy on disk of the entire program for this facility.

8. Marking of all system sensors and thermostats on the as-built floor plan and HVAC drawings with their control system designations.
9. Maintenance instructions, including sensor calibration requirements and methods by sensor type, etc.
10. Control equipment component submittals, parts lists, etc.
11. Warranty requirements.
12. Copies of all checkout tests and calibrations performed by the Contractor (not commissioning tests).
13. Organize and subdivide the manual with permanently labeled tabs for each of the following data in the given order:
 - a. Sequences of operation.
 - b. Control drawings.
 - c. Points lists.
 - d. Controller and/or module data.
 - e. Thermostats and timers.
 - f. Sensors and DP switches.
 - g. Valves and valve actuators.
 - h. Dampers and damper actuators.
 - i. Program setups (software program printouts).
- D. Project Record Documents: See Section 017800 for additional requirements.
 1. Submit updated version of control system documentation, for inclusion with operation and maintenance data.
 2. Show actual locations of all static and differential pressure sensors (air, water and building pressure) and air-flow stations on project record drawings.
- E. Draft Training Plan: In addition to requirements specified in Section 017900, include:
 1. Follow the recommendations of ASHRAE Guideline 1.1.
 2. Control system manufacturer's recommended training.
 3. Demonstration and instruction on function and overrides of any local packaged controls not controlled by the HVAC control system.
- F. Training Manuals: See Section 017900 for additional requirements.
 1. Provide three extra copies of the controls training manuals in a separate manual from the O&M manuals.

PART 2 PRODUCTS

2.01 TEST EQUIPMENT

- A. Provide all standard testing equipment required to perform startup and initial checkout and required functional performance testing; unless otherwise noted such testing equipment will NOT become the property of Owner.
- B. Equipment-Specific Tools: Where special testing equipment, tools and instruments are specific to a piece of equipment, are only available from the vendor, and are required in order to accomplish startup or Functional Testing, provide such equipment, tools, and instruments as part of the work at no extra cost to Owner; such equipment, tools, and instruments are to become the property of Owner.

PART 3 EXECUTION

3.01 PREPARATION

- A. Cooperate with the Commissioning Authority in development of the Prefunctional Checklists and Functional Test Procedures.
- B. Furnish additional information requested by the Commissioning Authority.
- C. Prepare a preliminary schedule for HVAC pipe and duct system testing, flushing and cleaning, equipment start-up and testing, adjusting, and balancing start and completion for use by the Commissioning Authority; update the schedule as appropriate.

- D. Notify the Commissioning Authority when pipe and duct system testing, flushing, cleaning, startup of each piece of equipment and testing, adjusting, and balancing will occur; when commissioning activities not yet performed or not yet scheduled will delay construction notify ahead of time and be proactive in seeing that the Commissioning Authority has the scheduling information needed to efficiently execute the commissioning process.
- E. Put all HVAC equipment and systems into operation and continue operation during each working day of testing, adjusting, and balancing and commissioning, as required.
- F. Provide test holes in ducts and plenums where directed to allow air measurements and air balancing; close with an approved plug.
- G. Provide temperature and pressure taps in accordance with Contract Documents.

3.02 INSPECTING AND TESTING - GENERAL

- A. Submit startup plans, startup reports, and Prefunctional Checklists for each item of equipment or other assembly to be commissioned.
- B. Perform the Functional Tests directed by the Commissioning Authority for each item of equipment or other assembly to be commissioned.
- C. Provide two-way radios for use during the testing.
- D. Valve/Damper Stroke Setup and Check:
 - 1. For all valve/damper actuator positions checked, verify the actual position against the control system readout.
 - 2. Set pump/fan to normal operating mode.
 - 3. Command valve/damper closed; visually verify that valve/damper is closed and adjust output zero signal as required.
 - 4. Command valve/damper open; verify position is full open and adjust output signal as required.
 - 5. Command valve/damper to a few intermediate positions.
 - 6. If actual valve/damper position does not reasonably correspond, replace actuator or add pilot positioner (for pneumatics).
- E. Isolation Valve or System Valve Leak Check: For valves not by coils.
 - 1. With full pressure in the system, command valve closed.
 - 2. Use an ultra-sonic flow meter to detect flow or leakage.
- F. Deficiencies: Correct deficiencies and re-inspect or re-test, as applicable, at no extra cost to Owner.

3.03 TAB COORDINATION

- A. TAB: Testing, adjusting, and balancing of HVAC.
- B. Coordinate commissioning schedule with TAB schedule.
- C. Review the TAB plan to determine the capabilities of the control system toward completing TAB.
- D. Provide all necessary unique instruments and instruct the TAB technicians in their use; such as handheld control system interface for setting terminal unit boxes, etc.
- E. Have all required Prefunctional Checklists, calibrations, startup and component Functional Tests of the system completed and approved by the Commissioning Authority prior to starting TAB.
- F. Provide a qualified control system technician to operate the controls to assist the TAB technicians or provide sufficient training for the TAB technicians to operate the system without assistance.

3.04 CONTROL SYSTEM FUNCTIONAL TESTING

- A. Prefunctional Checklists for control system components will require a signed and dated certification that all system programming is complete as required to accomplish the

requirements of Contract Documents and the detailed Sequences of Operation documentation submittal.

- B. Do not start Functional Testing until all controlled components have themselves been successfully Functionally Tested in accordance with Contract Documents.
- C. Using a skilled technician who is familiar with this building, execute the Functional Testing of the control system as required by the Commissioning Authority.
- D. Functional Testing of the control system constitutes demonstration and trend logging of control points monitored by the control system.
 - 1. The scope of trend logging is partially specified; trend log up to 50 percent more points than specified at no extra cost to Owner.
 - 2. Perform all trend logging specified in Prefunctional Checklists and Functional Test procedures.
- E. Functionally Test integral or stand-alone controls in conjunction with the Functional Tests of the equipment they are attached to, including any interlocks with other equipment or systems; further testing during control system Functional Test is not required unless specifically indicated below.
- F. Demonstrate the following to the Commissioning Authority during testing of controlled equipment; coordinate with commissioning of equipment.
 - 1. Setpoint changing features and functions.
 - 2. Sensor calibrations.
- G. Demonstrate to the Commissioning Authority:
 - 1. That all specified functions and features are set up, debugged and fully operable.
 - 2. That scheduling features are fully functional and setup, including holidays.
 - 3. That all graphic screens and value readouts are completed.
 - 4. Correct date and time setting in central computer.
 - 5. That field panels read the same time as the central computer; sample 10 percent of field panels; if any of those fail, sample another 10 percent; if any of those fail test all remaining units at no extra cost to Owner.
 - 6. Functionality of field panels using local operator keypads and local ports (plug-ins) using portable computer/keypad; demonstrate 100 percent of panels and 10 percent of ports; if any ports fail, sample another 10 percent; if any of those fail, test all remaining units at no extra cost to Owner.
 - 7. Power failure and battery backup and power-up restart functions.
 - 8. Global commands features.
 - 9. Security and access codes.
 - 10. Occupant over-rides (manual, telephone, key, keypad, etc.).
 - 11. O&M schedules and alarms.
 - 12. Occupancy sensors and controls.
 - 13. All control strategies and sequences not tested during controlled equipment testing.
- H. If the control system, integral control components, or related equipment do not respond to changing conditions and parameters appropriately as expected, as specified and according to acceptable operating practice, under any of the conditions, sequences, or modes tested, correct all systems, equipment, components, and software required at no additional cost to Owner.

3.05 OPERATION AND MAINTENANCE MANUALS

- A. See Section 017800 for additional requirements.
- B. Add design intent documentation furnished by Architect to manuals prior to submission to Owner.
- C. Submit manuals related to items that were commissioned to Commissioning Authority for review; make changes recommended by Commissioning Authority.

- D. Commissioning Authority will add commissioning records to manuals after submission to Owner.

3.06 DEMONSTRATION AND TRAINING

- A. See Section 017900 for additional requirements.
- B. Demonstrate operation and maintenance of HVAC system to Owner' personnel; if during any demonstration, the system fails to perform in accordance with the information included in the O&M manual, stop demonstration, repair or adjust, and repeat demonstration. Demonstrations may be combined with training sessions if appropriate.
- C. These demonstrations are in addition to, and not a substitute for, Prefunctional Checklists and demonstrations to the Commissioning Authority during Functional Testing.
- D. TAB Review: Instruct Owner's personnel for minimum ____ hours, after completion of TAB, on the following:
 - 1. Review final TAB report, explaining the layout and meanings of each data type.
 - 2. Discuss any outstanding deficient items in control, ducting or design that may affect the proper delivery of air or water.
 - 3. Identify and discuss any terminal units, duct runs, diffusers, coils, fans and pumps that are close to or are not meeting their design capacity.
 - 4. Discuss any temporary settings and steps to finalize them for any areas that are not finished.
 - 5. Other salient information that may be useful for facility operations, relative to TAB.
- E. HVAC Control System Training: Perform training in at least three phases:
 - 1. Phase 1 - Basic Control System: Provide minimum of 4 hours of actual training on the control system itself. Upon completion of training, each attendee, using appropriate documentation, should be able to perform elementary operations and describe general hardware architecture and functionality of the system.
 - a. This training may be held on-site or at the manufacturer's facility.
 - b. If held off-site, the training may occur prior to final completion of the system installation.
 - c. For off-site training, Contractor shall pay expenses of up to two attendees.
 - 2. Phase 2 - Integrating with HVAC Systems: Provide minimum of 4 hours of on-site, hands-on training after completion of Functional Testing. Include instruction on:
 - a. The specific hardware configuration of installed systems in this facility and specific instruction for operating the installed system, including interfaces with other systems, if any.
 - b. Security levels, alarms, system start-up, shut-down, power outage and restart routines, changing setpoints and alarms and other typical changed parameters, overrides, freeze protection, manual operation of equipment, optional control strategies that can be considered, energy savings strategies and set points that if changed will adversely affect energy consumption, energy accounting, procedures for obtaining vendor assistance, etc.
 - c. Trend logging and monitoring features (values, change of state, totalization, etc.), including setting up, executing, downloading, viewing both tabular and graphically and printing trends; provide practice in setting up trend logging and monitoring during training session.
 - d. Every display screen, allowing time for questions.
 - e. Point database entry and modifications.
- F. Provide the services of manufacturer representatives to assist instructors where necessary.
- G. Provide the services of the HVAC controls instructor at other training sessions, when requested, to discuss the interaction of the controls system as it relates to the equipment being discussed.

END OF SECTION

SECTION 230913
INSTRUMENTATION AND CONTROL DEVICES FOR HVAC

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Air Supply System:
 - 1. Pressure relief valves.
- B. Control panels.
- C. Control Valves:
 - 1. Globe pattern.
 - 2. Butterfly pattern.
 - 3. Electronic operators.
- D. Dampers.
- E. Damper Operators:
 - 1. Electric operators.
 - 2. Inlet vane operators.
- F. Humidistats:
 - 1. Room humidistats.
 - 2. Limit duct humidistats.
- G. Input/Output Sensors:
 - 1. Temperature sensors.
 - 2. Humidity sensors.
 - 3. Static pressure (air pressure) sensors.
 - 4. Equipment operation (current) sensors.
 - 5. Damper position indicators.
- H. Thermostats:
 - 1. Airstream thermostats.
- I. Time clocks.
- J. Transmitters:
 - 1. Building static pressure transmitters.
 - 2. Pressure transmitters.
 - 3. Temperature transmitters.
- K. Flow Sensors:
 - 1. Flow nozzles.
 - 2. Venturi tubes.
 - 3. Airflow measurement array (AFMA).
 - 4. Ultrasonic flow meters.
 - 5. Insertion turbine meters.
 - 6. Insertion magnetic flow meters.
 - 7. Flow switches.

1.02 REFERENCE STANDARDS

- A. AMCA 500-D - Laboratory Methods of Testing Dampers for Rating; 2018.
- B. ANSI C12.1 - Electric Meters - Code for Electricity Metering; 2016.
- C. ANSI C12.10 - Physical Aspects of Watthour Meters - Safety Standard; 2011.
- D. ANSI C12.20 - American National Standard for Electricity Meters - 0.2 and 0.5 Accuracy Classes; 2015.

1.03 ADMINISTRATIVE REQUIREMENTS

- A. Preinstallation Meeting: Conduct a preinstallation meeting one week before starting work of this section; require attendance by all affected installers.
- B. Sequencing: Ensure that utility connections are achieved in an orderly and expeditious manner.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Product Data: Provide description and engineering data for each control system component. Include sizing as requested. Provide data for each system component and software module.
- C. Shop Drawings: Indicate complete operating data, system drawings, wiring diagrams, and written detailed operational description of sequences. Submit schedule of valves indicating size, flow, and pressure drop for each valve. For automatic dampers indicate arrangement, velocities, and static pressure drops for each system.
- D. Manufacturer's Instructions: Provide for all manufactured components.
- E. Project Record Documents: Record actual locations of control components, including panels, thermostats, and sensors. Accurately record actual location of control components, including panels, thermostats, and sensors.
 - 1. Revise shop drawings to reflect actual installation and operating sequences.

1.05 QUALITY ASSURANCE

- A. Designer Qualifications: Design system under direct supervision of a Professional Engineer experienced in design of this work and licensed in the State in which the Project is located.
- B. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
- C. Installer Qualifications: Company specializing in performing the work of this section with minimum 3 years experience approved by manufacturer.
- D. Products Requiring Electrical Connection: Listed and classified by Underwriters Laboratories Inc., as suitable for the purpose specified and indicated.

1.06 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.

PART 2 PRODUCTS

2.01 EQUIPMENT - GENERAL

- A. Products Requiring Electrical Connection: Listed and classified by Underwriters Laboratories Inc., as suitable for the purpose specified and indicated.

2.02 AIR SUPPLY SYSTEM

- A. Pressure Relief Valves:
 - 1. ASME Code Rated and labeled for high pressure side and sized for installed capacity of pressure regulators at low pressure. Set at maximum 20 percent above low pressure.

2.03 CONTROL PANELS

- A. Unitized cabinet type for each system under automatic control with relays and controls mounted in cabinet and temperature indicators, pressure gauges, pilot lights, push buttons and switches flush on cabinet panel face.

2.04 CONTROL VALVES

- A. Globe Pattern:
 - 1. Up to 2 inches: Bronze body, bronze trim, rising stem, renewable composition disc, screwed ends with backseating capacity repackable under pressure.
 - 2. Over 2 inches: Iron body, bronze trim, rising stem, plug-type disc, flanged ends, renewable seat and disc.

3. Hydronic Systems:
 - a. Rate for service pressure of 125 psig at 250 degrees F.
 - b. Replaceable plugs and seats of stainless steel.
 - c. Size for 3 psig maximum pressure drop at design flow rate.
 - d. Two-way valves shall have equal percentage characteristics, three way valves linear characteristics. Size two-way valve operators to close valves against pump shut off head.
- B. Butterfly Pattern:
 1. Iron body, bronze disc, resilient replaceable seat for service to 180 degrees F wafer or lug ends, extended neck.
 2. Hydronic Systems:
 - a. Rate for service pressure of 125 psig at 250 degrees F.
 - b. Size for 1 psig maximum pressure drop at design flow rate.
- C. Electronic Operators:
 1. Valves shall spring return to normal position as indicated on freeze, fire, or temperature protection.
 2. Select operator for full shut off at maximum pump differential pressure.

2.05 INPUT/OUTPUT SENSORS

- A. Temperature Sensors:
 1. Use thermistor or RTD type temperature sensing elements with characteristics resistant to moisture, vibration, and other conditions consistent with the application without affecting accuracy and life expectancy.
 2. Construct RTD of nickel or platinum with base resistance of 1000 ohms at 70 degrees F.
 3. 100 ohm platinum RTD is acceptable if used with project DDC controllers.
 4. Temperature Sensing Device: Compatible with project DDC controllers.
 5. Performance Characteristics:
 - a. RTD:
 - 1) Room Sensor Accuracy: Plus/minus 0.50 degrees F minimum.
 - 2) Duct Averaging Accuracy: Plus/minus 0.50 degrees F minimum.
 - 3) Chilled Water Accuracy: Plus/minus 0.50 degrees F minimum.
 - 4) All Other Accuracy: Plus/minus 0.75 degrees F minimum.
 - 5) Range: Minus 40 degrees F through 220 degrees F minimum.
 - b. Thermistor:
 - 1) Accuracy (All): Plus/minus 0.36 degrees F minimum.
 - 2) Range: Minus 25 degrees F through 122 degrees F minimum.
 - 3) Heat Dissipation Constant: 2.7 mW per degree C.
 - c. Temperature Transmitter:
 - 1) Accuracy: 0.10 degree F minimum or plus/minus 0.20 percent of span.
 - 2) Output: 4 to 20 mA.
 - d. Sensing Range:
 - 1) Provide limited range sensors if required to sense the range expected for a respective point.
 - 2) Use RTD type sensors for extended ranges beyond minus 30 degrees F to 230 degrees F.
 - 3) Use temperature transmitters in conjunction with RTD's when RTD's are incompatible with DDC controller direct temperature input.
 - e. Room Sensors: Locking cover.
 - f. Outside Air Sensors: Watertight inlet fitting shielded from direct rays of the sun.
 - g. Ceiling and Recessed Mount Temperature Sensors: Ceiling-mounted sensor in a low-profile housing.
 - h. Room Temperature Sensors with Integral Digital Display:
 - 1) Provide a keypad with the following capabilities:

- (a) Setpoint adjustment to accommodate room setpoint and DDC Input/Output Points List.
 - (b) Display and control fan operation status.
 - (c) Manual occupancy override and indication of occupancy status.
 - (d) Controller mode status.
- B. Static Pressure (Air Pressure) Sensors:
 - 1. Unidirectional with ranges not exceeding 150 percent of maximum expected input.
 - 2. Temperature compensate with typical thermal error or 0.06 percent of full scale in temperature range of 40 to 100 degrees F.
 - 3. Accuracy: One percent of full scale with repeatability 0.3 percent.
 - 4. Output: 0 to 5 vdc with power at 12 to 28 vdc.
- C. Equipment Operation (Current) Sensors:
 - 1. Status Inputs for Fans: Differential pressure switch with adjustable range of 0 to 5 inches wg.
 - 2. Status Inputs for Pumps: Differential pressure switch piped across pump with adjustable pressure differential range of 8 to 60 psi.
 - 3. Status Inputs for Electric Motors: Current sensing relay with current transformers, adjustable and set to 175 percent of rated motor current.
- D. Damper Position Indicators: Potentiometer mounted in enclosure with adjustable crank arm assembly connected to damper to transmit 0 to 100 percent damper travel.

2.06 FLOW SENSORS

- A. Flow Nozzles:
 - 1. Fabricate flow nozzle from austenitic stainless steel with an accuracy of plus/minus 1 percent of full flow.
 - 2. Inlet Nozzle: Elliptical with the nozzle throat to be the quadrant of an ellipse.
 - 3. Thickness of the nozzle wall and flange to be such that distortion of the nozzle throat from strains caused by the pipeline pressure and temperature, flange bolting, or other methods of installing the nozzle in the pipeline must not cause the accuracy to degrade beyond the specified limit.
 - 4. Outside Diameter of the Nozzle Flange or Design of the Flange Facing: Nozzle throat to be centered accurately in the pipe.
- B. Venturi Tubes:
 - 1. Fabricate the venturi tube from cast iron with an accuracy of plus/minus 1 percent of full flow.
 - 2. Line the throat section with austenitic stainless steel.
 - 3. Machine the surface of the throat to plus/minus 50 micro-inches including the short curvature leading from the converging entrance section into the throat.
- C. Airflow Measurement Array (AFMA):
 - 1. Airflow Straighteners:
 - a. Provide AFMA's with an airflow straightener if required by the AFMA manufacturer's published installation instructions.
 - b. In the absence of published documentation, provide airflow straighteners if there is any duct obstruction within 5 duct diameters upstream of the AFMA.
 - c. Straightener: Contained inside a flanged sheet metal casing, with the AFMA located as specified according to the published recommendations of the AFMA manufacturer.
 - d. Construction to consist of 0.125 inch aluminum honeycomb with the straightener depth not less than 1.5 inches.
 - 2. Outdoor Air Temperature: In outside air measurement or in low-temperature air delivery applications, provide an AFMA certified by the manufacturer to be accurate as specified over a temperature range of minus 20 degrees F to 120 degrees F.
 - 3. Airflow Resistance:

- a. Resistance to Airflow Through the AFMA and the Airflow Straightener: Not to exceed 0.085 inches at an airflow velocity of 2000 fpm.
 - b. AFMA Construction: Suitable for operation at air flows of up to 5000 fpm over a temperature range of 40 degrees F to 120 degrees F.
 4. Pitot Tube:
 - a. Furnish each pitot tube AFMA with an array of velocity sensing elements.
 - b. Distribute the sensing elements across the duct section in the pattern and quantity specified or as recommended by the installation instructions of the AFMA manufacturer.
 - 1) Pitot Tube AFMA's in Air Flows Over 600 fpm: Accuracy of plus/minus 5 percent over a range of 500 fpm to 2500 fpm.
 - 2) Pitot Tube AFMA's in Air Flows Under 600 fpm: Accuracy of plus/minus 5 percent over a range of 125 fpm to 2500 fpm.
 5. Electronic:
 - a. Each electronic AFMA to consist of an array of velocity sensing elements of the resistance temperature detector (RTD) or thermistor type.
 - b. Sensing Elements: Distributed across the duct cross section in the quantity and pattern specified or recommended by the published application data of the manufacturer.
 - c. Fan Inlet Measurement Devices: Refer to drawings and/or equipment schedules.
- D. Ultrasonic Flow Meters:
 1. Optimize ultrasonic transducers for the specific pipe and process conditions for the application.
 2. Flow Meter Accuracy: Plus/minus 1 percent of rate from 0.98 fps to 40 fps.
 3. Include dry contact outputs, 4 to 20 mA, 0 to 10 VDC.
- E. Insertion Turbine Flow Meters:
 1. Furnish dual axial turbine flowmeter with all installation hardware required to enable insertion and removal of the meter without system shutdown.
 2. All Parts: Meet or exceed the pressure classification of the piping system installed in.
 3. Accuracy for the Insertion Turbine Flow Meter: Plus/minus 0.5 percent of the rate at calibrated velocity, within plus/minus of the rate over a 10 to 1 turn down and within plus/minus 2 percent of the rate over a 50 to 1 turn down.
 4. Repeatability: Plus/minus 0.25 percent of reading.
 5. The meter flow sensing element to operate over a range suitable for the installed location with a pressure loss limited to 1 percent of operating pressure at maximum flow rate.
 6. Include dry contact outputs, 4 to 20 mA, 0 to 10 VDC.
 7. Fabricate the turbine rotor assembly of Series 300 stainless steel and use Teflon seats.
- F. Insertion Magnetic Flow Meters:
 1. Provide insertion type magnetic flow meters with all installation hardware necessary to enable the insertion and removal of the meter without system shutdown.
 2. All Parts: Meet or exceed the pressure classification of the piping system installed in.
 3. Accuracy: No greater than 1 percent of the rate from 2 fps to 20 fps.
 4. Fabricate wetted material parts from 300 series stainless steel.
 5. Include 4 to 20 mA dry contact pulse outputs, 0 to 10 VDC.
- G. Flow Switches:
 1. Repetitive Accuracy: Plus/minus 10 percent of actual flow setting.
 2. Switch Actuation: Adjustable over the operating range and sized for the application, such that the setpoint is between 25 and 75 percent of the full range.
 3. Provide Form C snap-action contacts, rated for the application.
 4. Furnish non-flexible paddle with magnetically actuated contacts, rated for service at a pressure greater than the installed conditions.

5. Flow Switch for Use in Sewage Systems: Rated for use in corrosive environments encountered.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that systems are ready to receive work.
- C. Beginning of installation means installer accepts existing conditions.
- D. Sequence work to ensure installation of components is complementary to installation of similar components in other systems.
- E. Coordinate installation of system components with installation of mechanical systems equipment such as air handling units and air terminal units.
- F. Ensure installation of components is complementary to installation of similar components.
- G. Coordinate installation of system components with installation of mechanical systems equipment such as air handling units and air terminal units.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Provide conduit and electrical wiring in accordance with Section 260583. Electrical material and installation shall be in accordance with appropriate requirements of Division 26.

3.03 MAINTENANCE

- A. Provide service and maintenance of control system for one year from Date of Substantial Completion.
- B. Provide complete service of controls systems, including call backs, and submit written report of each service call.
- C. In addition to normal service calls, make minimum of 2 complete normal inspections of approximately 2 hours duration to inspect, calibrate, and adjust controls.

END OF SECTION

**SECTION 232113
HYDRONIC PIPING**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Hydronic system requirements.
- B. Chilled water piping, above grade.
- C. Condenser water piping, above grade.
- D. Pipe hangers and supports.
- E. Unions, flanges, mechanical couplings, and dielectric connections.
- F. Valves:
 - 1. Ball valves.
 - 2. Butterfly valves.
 - 3. Check valves.
 - 4. Pressure independent temperature control valves and balancing valves.
- G. Flow controls.

1.02 REFERENCE STANDARDS

- A. ASME B16.3 - Malleable Iron Threaded Fittings: Classes 150 and 300; 2016.
- B. ASME B16.18 - Cast Copper Alloy Solder Joint Pressure Fittings; 2018.
- C. ASME B16.22 - Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings; 2018.
- D. ASME B31.9 - Building Services Piping; 2020.
- E. ASTM A53/A53M - Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2020.
- F. ASTM A234/A234M - Standard Specification for Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and High Temperature Service; 2019.
- G. ASTM B32 - Standard Specification for Solder Metal; 2020.
- H. ASTM B88 - Standard Specification for Seamless Copper Water Tube; 2020.
- I. ASTM B88M - Standard Specification for Seamless Copper Water Tube (Metric); 2020.
- J. ASTM F1476 - Standard Specification for Performance of Gasketed Mechanical Couplings for Use in Piping Applications; 2007 (Reapproved 2019).
- K. AWS A5.8M/A5.8 - Specification for Filler Metals for Brazing and Braze Welding; 2019.
- L. AWS D1.1/D1.1M - Structural Welding Code - Steel; 2020, with Errata (2021).
- M. AWWA C606 - Grooved and Shouldered Joints; 2015.
- N. MSS SP-58 - Pipe Hangers and Supports - Materials, Design, Manufacture, Selection, Application, and Installation; 2018.

1.03 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Product Data:
 - 1. Include data on pipe materials, pipe fittings, valves, and accessories.
 - 2. Provide manufacturers catalog information.

PART 2 PRODUCTS

2.01 HYDRONIC SYSTEM REQUIREMENTS

- A. Comply with ASME B31.9 and applicable federal, state, and local regulations.
- B. Piping: Provide piping, fittings, hangers, and supports as required, as indicated, and as follows:

1. Where more than one piping system material is specified, provide joining fittings that are compatible with piping materials and ensure that the integrity of the system is not jeopardized.
 2. Use non-conducting dielectric connections whenever jointing dissimilar metals.
 3. Grooved mechanical joints may be used in accessible locations only.
 - a. Accessible locations include those exposed on interior of building, in pipe chases, and in mechanical rooms, aboveground outdoors, and as approved by Architect.
 - b. Use rigid joints unless otherwise indicated.
 4. Provide pipe hangers and supports in accordance with ASME B31.9 or MSS SP-58 unless indicated otherwise.
- C. Pipe-to-Valve and Pipe-to-Equipment Connections: Use flanges, unions, or grooved couplings to allow disconnection of components for servicing; do not use direct welded, soldered, or threaded connections.
- D. Valves: Provide valves where indicated:

2.02 CHILLED WATER PIPING, ABOVE GRADE

- A. Steel Pipe: ASTM A53/A53M, Schedule 40, black; using one of the following joint types:
1. Welded Joints: ASTM A234/A234M, wrought steel welding type fittings; AWS D1.1/D1.1M welded.
 2. Threaded Joints: ASME B16.3, malleable iron fittings.
 3. Grooved Joints: AWWA C606 grooved pipe, fittings of same material, and mechanical couplings.
- B. Copper Tube: ASTM B88 (ASTM B88M), Type K (A), hard drawn; using one of the following joint types:
1. Solder Joints: ASME B16.18 cast brass/bronze or ASME B16.22, solder wrought copper fittings.
 - a. Solder: ASTM B32 lead-free solder, HB alloy (95-5 tin-antimony) or tin and silver.
 - b. Braze: AWS A5.8M/A5.8 BCuP copper/silver alloy.
 2. Grooved Joints: AWWA C606 grooved tube, fittings of same material, and copper-tube-dimension mechanical couplings.
 3. Tee Connections: Mechanically extracted collars with notched and dimpled branch tube.

2.03 CONDENSER WATER PIPING, ABOVE GRADE

- A. Copper Tube: ASTM B88 (ASTM B88M), Type K (A), drawn; using one of the following joint types:
1. Solder Joints: ASME B16.18 cast brass/bronze or ASME B16.22 solder wrought copper fittings.
 - a. Solder: ASTM B32 lead-free solder, HB alloy (95-5 tin-antimony) or tin and silver.
 2. Grooved Joints: AWWA C606 grooved tube, fittings of same material, and copper-tube-dimension mechanical couplings.
 3. Tee Connections: Mechanically extracted collars with notched and dimpled branch tube.

2.04 PIPE HANGERS AND SUPPORTS

- A. Provide hangers and supports that comply with MSS SP-58.
1. If type of hanger or support for a particular situation is not indicated, select appropriate type using MSS SP-58 recommendations.
- B. In grooved installations, use rigid couplings with offsetting angle-pattern bolt pads or with wedge-shaped grooves in header piping to permit support and hanging in accordance with ASME B31.9.

2.05 UNIONS, FLANGES, MECHANICAL COUPLINGS, AND DIELECTRIC CONNECTIONS

- A. Mechanical Couplings for Grooved and Shouldered Joints: Two or more curved housing segments with continuous key to engage pipe groove, circular C-profile gasket, and bolts to secure and compress gasket.

1. Dimensions and Testing: In accordance with AWWA C606.
2. Mechanical Couplings: Comply with ASTM F1476.
3. Bolts and Nuts: Hot dipped galvanized or zinc-electroplated steel.
4. When pipe is field grooved, provide coupling manufacturer's grooving tools.

2.06 BALL VALVES

- A. Manufacturers:
 1. Anvil International: www.anvilintl.com.
 2. Apollo Valves: www.apollovalves.com.
 3. Grinnell Products: www.grinnell.com.
 4. Shurjoint Piping Products, Inc: www.shurjoint.com.
 5. Victaulic Company: www.victaulic.com.
 6. Viega LLC: www.viega.us.
- B. Up To and Including 2 Inches:
 1. Bronze one piece body, chrome plated brass ball, teflon seats and stuffing box ring, lever handle with balancing stops, solder ends with union.
- C. Over 2 Inches:
 1. Ductile iron body, chrome plated stainless steel ball, teflon, Virgin TFE, or _____ seat and stuffing box seals, lever handle, gear operated, or _____, flanged ends, rated to 800 psi.

2.07 BUTTERFLY VALVES

- A. Manufacturers:
 1. Anvil International: www.anvilintl.com.
 2. Apollo Valves: www.apollovalves.com.
 3. Grinnell Products: www.grinnell.com.
 4. Victaulic Company: www.victaulic.com.
- B. Body: Cast or ductile iron with resilient replaceable EPDM seat, wafer, lug, grooved, or _____ ends, extended neck.
- C. Disc: Construct of aluminum bronze, chrome plated ductile iron, stainless steel, ductile iron with EPDM encapsulation, Buna-N encapsulation, or _____.
- D. Operator: 10 position lever handle.

2.08 SWING CHECK VALVES

- A. Manufacturers:
 1. Anvil International: www.anvilintl.com.
 2. Grinnell Products: www.grinnell.com/#sle.
 3. Shurjoint Piping Products, Inc: www.shurjoint.com/#sle.
 4. Victaulic Company: www.victaulic.com.
- B. Up To and Including 2 Inches:
 1. Bronze body, bronze trim, bronze rotating swing disc, with composition disc, solder ends.
- C. Over 2 Inches:
 1. Iron body, bronze or _____ trim, stainless steel, bronze, bronze faced rotating, or _____ swing disc, renewable disc and seat, flanged, grooved, or _____ ends.

2.09 PRESSURE INDEPENDENT TEMPERATURE CONTROL VALVES AND BALANCING VALVES

- A. Manufacturers:
 1. Danfoss; AB-QM Valve: www.danfoss.com/#sle.

2.10 FLOW CONTROLS

- A. Manufacturers:
 1. Anvil International: www.anvilintl.com.

2. Griswold Controls: www.griswoldcontrols.com.
 3. Hays Fluid Controls: www.haysfluidcontrols.com.
 4. ITT Bell & Gossett: www.bellgossett.com.
 5. Shurjoint Piping Products, Inc: www.shurjoint.com.
 6. Taco, Inc: www.taco-hvac.com.
 7. Victaulic Company; _____: www.victaulic.com.
- B. Construction: Class 125, Brass or bronze body with union on inlet and outlet, temperature and pressure test plug on inlet and outlet, blowdown/backflush drain.
- C. Calibration: Control flow within 10 percent of selected rating, over operating pressure range of 10 times minimum pressure required for control, minimum pressure 2 psi.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Route piping in orderly manner, parallel to building structure, and maintain gradient.
- C. Install piping to conserve building space and to avoid interference with use of space.
- D. Group piping whenever practical at common elevations.
- E. Slope piping and arrange to drain at low points.

END OF SECTION

**SECTION 232114
HYDRONIC SPECIALTIES**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Buffer tanks.
- B. Expansion tanks.
- C. Air vents.
- D. Strainers.
- E. Suction diffusers.
- F. Pump connectors.
- G. Combination pump discharge valves.
- H. Pressure-temperature test plugs.
- I. Balancing valves.

1.02 REFERENCE STANDARDS

- A. ASME BPVC-VIII-1 - Boiler and Pressure Vessel Code, Section VIII, Division 1: Rules for Construction of Pressure Vessels; 2019.

1.03 SUBMITTALS

- A. Product Data: Provide product data for manufactured products and assemblies required for this project. Include component sizes, rough-in requirements, service sizes, and finishes. Include product description and model.
- B. Manufacturer's Installation Instructions: Indicate hanging and support methods, joining procedures.
- C. Project Record Documents: Record actual locations of flow controls.
- D. Maintenance Data: Include installation instructions, assembly views, lubrication instructions, and replacement parts list.

1.04 DELIVERY, STORAGE, AND HANDLING

- A. Accept valves on site in shipping containers with labeling in place. Inspect for damage.
- B. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.
- C. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed system.

PART 2 PRODUCTS

2.01 BUFFER TANKS

- A. Manufacturers:
 - 1. Amtrol Inc
 - 2. Bell & Gossett, a brand of Xylem, Inc
 - 3. Taco, Inc
- B. Construction: Closed, welded steel, tested, and stamped in accordance with ASME BPVC-VIII-1; cleaned, prime coated, and supplied with steel support saddles; with tappings for installation of accessories.

2.02 EXPANSION TANKS

- A. Manufacturers:
 - 1. Amtrol Inc
 - 2. Bell & Gossett, a brand of Xylem, Inc

3. Taco, Inc
- B. Construction: Welded steel, tested and stamped in accordance with ASME BPVC-VIII-1; supplied with National Board Form U-1, adjustable flexible EPDM diaphragm or bladder seal factory precharged to 12 psi, and steel support stand.
- C. Automatic Cold Water Fill Assembly: Pressure reducing valve, reduced pressure double check backflow preventer, test cocks, strainer, vacuum breaker, and valved by-pass.
- D. Accessories: Provide air-charging fitting, bulls eye sight glass, pressure gauge, and tank drain ball valve.

2.03 AIR VENTS

- A. Manufacturers:
 1. Armstrong International, Inc
 2. Bell & Gossett, a brand of Xylem, Inc
 3. Taco, Inc
- B. Float Type:
 1. Brass or semi-steel body, copper, polypropylene, or solid non-metallic float, stainless steel valve and valve seat; suitable for system operating temperature and pressure; with isolating valve.

2.04 STRAINERS

- A. Manufacturers:
 1. American Wheatley, a company of Global Flow Products, LLC
 2. Armstrong International, Inc
 3. Grinnell Products
 4. The Metraflex Company
- B. Y-Type, Size 2 inch and Smaller:
 1. Threaded body with 1/32 inch stainless steel perforated screen and blow-off plug for minimum working pressure of 175 psi.
 2. Body Material by Fluid Service:
 - a. Cast Iron or Brass:
 - 1) Steam: Up to 250 psi at 450 degrees F.
 - 2) Liquids: Up to 400 psi at 150 degrees F.
- C. Y-Type, Size 4 to 30 inch:
 1. Flanged steel or iron body with 1/8 inch stainless steel perforated screen.
 2. Body Material by Fluid Service:
 - a. Cast Iron:
 - 1) Steam: Up to 125 psi at 350 degrees F.
 - 2) Liquids: Up to 200 psi at 150 degrees F.

2.05 SUCTION DIFFUSERS

- A. Manufacturers:
 1. Anvil International; _____
 2. Bell & Gossett, a brand of Xylem, Inc
 3. Grinnell Products
 4. Taco.
- B. Fitting: Angle pattern, cast-iron body, threaded for 2 inch and smaller, flanged for 2-1/2 inch and larger, rated for 175 psi working pressure, with inlet vanes, cylinder strainer with 3/16 inch diameter openings, disposable 5/32 inch mesh strainer to fit over cylinder strainer, 20 mesh startup screen, and permanent magnet located in flow stream and removable for cleaning.
- C. Class 150, Size 1-1/2 to 4 inch:
 1. Angle-pattern flanged carbon steel fitted with integral vanes, removable strainer, and magnetic drain plugs for particle removal without disassembly.

2. Maximum Operating Service:
 - a. Class 150: 150 psi at 450 degrees F.

2.06 PUMP CONNECTORS

- A. Manufacturers:
 1. Anvil International
 2. Ferguson Enterprises Inc
 3. The Metraflex Company
- B. Flexible Connectors: Flanged, braided type with wetted components of stainless steel, sized to match piping.
 1. Maximum Operating Service: 150 psi at 120 degrees F.
 2. End Connections: Same as specified for pipe jointing.
 3. Provide pump connector with integral vanes to reduce turbulent flow.
 4. Provide necessary accessories including, but not limited to, swivel joints.

2.07 COMBINATION PUMP DISCHARGE VALVES

- A. Manufacturers:
 1. Anvil International
 2. Crane Co.
 3. Taco, Inc
- B. Triple-Duty Globe Type: Grooved cast-iron angle pattern body with bolt-on bonnet, position indicator, non-slam check valve with spring-loaded bronze disc and seat, stainless steel stem, metering connectors, flow shutoff mechanism, and adjustable flow handle.

2.08 PRESSURE-TEMPERATURE TEST PLUGS

- A. Construction: Brass body designed to receive temperature or pressure probe with removable protective cap, and Neoprene rated for minimum 200 degrees F.
- B. Application: Use extended length plugs to clear insulated piping.

2.09 BALANCING VALVES

- A. Manufacturers:
 1. Bell & Gossett, a brand of Xylem, Inc
 2. Ferguson Enterprises Inc
 3. Taco, Inc
- B. Size 2 inch and Smaller:
 1. Provide ball or globe style with flow balancing, flow measurement, and shut-off capabilities, memory stops, minimum of two metering ports and threaded or soldered connections.
 2. Metal construction materials consist of bronze or brass.
- C. Size 2.5 inch and Larger:
 1. Provide ball, globe, or butterfly style with flow balancing, flow measurement, and shut-off capabilities, memory stops, minimum of two metering ports and flanged, grooved, or _____ connections.
 2. Valve body construction materials consist of cast iron or carbon steel.
 3. Internal components construction materials consist of brass, aluminum bronze, bronze, Teflon, or EPDM

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install specialties in accordance with manufacturer's instructions.
- B. Provide manual air vents at system high points and as indicated.
- C. Provide valved drain and hose connection on strainer blowdown connection.

- D. Provide pump suction fitting on suction side of base-mounted centrifugal pumps where indicated. Remove temporary strainers after cleaning systems.
- E. Provide combination pump discharge valve on discharge side of base mounted centrifugal pumps where indicated.
- F. Support pump fittings with floor-mounted pipe and flange supports.
- G. Provide relief valves on pressure tanks, low-pressure side of reducing valves, heat exchangers, and expansion tanks.
- H. Pipe relief valve outlet to nearest floor drain.

END OF SECTION

**SECTION 232123
HYDRONIC PUMPS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Base-mounted pumps.

1.02 REFERENCE STANDARDS

- A. UL 778 - Standard for Motor-Operated Water Pumps; Current Edition, Including All Revisions.

1.03 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Product Data: Provide certified pump curves showing performance characteristics with pump and system operating point plotted. Include NPSH curve when applicable. Include electrical characteristics and connection requirements.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Taco, <https://www.tacomfort.com>
- B. Bell & Gossett, a Xylem Inc. brand: www.bellgossett.com
- C. Substitutions: See Section 016000 - Product Requirements.

2.02 HVAC PUMPS - GENERAL

- A. Provide pumps that operate at specified system fluid temperatures without vapor binding and cavitation, are non-overloading in parallel or individual operation, and operate within 25 percent of midpoint of published maximum efficiency curve.
- B. Minimum Quality Standard: UL 778.
- C. Base Mounted Pumps: Aligned by qualified millwright.
- D. Products Requiring Electrical Connection: Listed and classified by UL or testing agency acceptable to Authority Having Jurisdiction as suitable for the purpose specified and indicated.

2.03 BASE-MOUNTED PUMPS

- A. Type: Horizontal shaft, single stage, direct connected, radially or horizontally split casing, for 125 psi maximum working pressure.
- B. Casing: Cast iron, or ductile iron with suction and discharge gauge ports, renewable bronze casing wearing rings, seal flush connection, drain plug, flanged suction and discharge.
- C. Impeller: Bronze, fully enclosed, keyed to shaft.
- D. Bearings: Oil lubricated roller or ball bearings.
- E. Shaft: Alloy steel with copper, bronze, or stainless steel shaft sleeve.
- F. Seal: Mechanical seal, 225 degrees F maximum continuous operating temperature.
- G. Seal: Packing gland with minimum four rings graphite impregnated packing and bronze lantern rings, 250 degrees F maximum continuous operating temperature.

PART 3 EXECUTION

3.01 PREPARATION

- A. Verify that electric power is available and of the correct characteristics.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Provide access space around pumps for service. Provide no less than minimum space recommended by manufacturer.

- C. Decrease from line size with long radius reducing elbows or reducers. Support piping adjacent to pump such that no weight is carried on pump casings. For close-coupled or base-mounted pumps, provide supports under elbows on pump suction and discharge line sizes 4 inches and over.
- D. Provide line sized shut-off valve and strainer on pump suction, and line sized soft seat check valve and balancing valve on pump discharge.
- E. Provide air cock and drain connection on horizontal pump casings.
- F. Provide drains for bases and seals, piped to and discharging into floor drains.
- G. Check, align, and certify alignment of base-mounted pumps prior to start-up.
- H. Install close-coupled and base-mounted pumps on concrete housekeeping base, with anchor bolts, set and level, and grout in place. See Section 033000.
- I. Lubricate pumps before start-up.

END OF SECTION

**SECTION 233416
CENTRIFUGAL HVAC FANS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Backward inclined centrifugal fans / Fan array.

1.02 REFERENCE STANDARDS

- A. AMCA (DIR) - (Directory of) Products Licensed Under AMCA International Certified Ratings Program; 2015.
- B. AMCA 210 - Laboratory Methods of Testing Fans for Certified Aerodynamic Performance Rating; 2016.
- C. AMCA 300 - Reverberant Room Method for Sound Testing of Fans; 2014.
- D. AMCA 301 - Methods for Calculating Fan Sound Ratings from Laboratory Test Data; 2014.

1.03 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittal procedures.
- B. Product Data: Provide data on centrifugal fans and accessories including fan curves with specified operating point plotted, power, rpm, sound power levels for both fan inlet and outlet at rated capacity, and electrical characteristics and connection requirements.
- C. Manufacturer's Instructions: Include complete installation instructions.

1.04 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.
- B. Products Requiring Electrical Connection: Listed and classified by Underwriters Laboratories Inc. as suitable for the purpose specified and indicated.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Protect motors, shafts, and bearings from weather and construction dust.

PART 2 PRODUCTS

2.01 MANUFACTURERS BY FAN TYPE

- A. Backward-Inclined Centrifugal Fans / Fan Array:
 - 1. Loren Cook Company
 - 2. Ziehl-Abegg
 - 3. Twin City Fan & Blowe
 - 4. Q-PAC

2.02 PERFORMANCE REQUIREMENTS

- A. The fan array will be arranged with high performance direct drive, single inlet, plenum fans with backwards inclined, high efficiency welded-aluminum or high performance composite impeller with galvanized or aluminum support frame. Manual blank-off plates shall be provided to block fan airflow, one plate to be provided per array.
- B. The fans are driven by long-life, low-temperature brushless DC electronically commutated motor (EC-Motor) with external rotor and integrated maintenance-free electronic circuitry and electronics. The motor is manufactured with maintenance-free, permanently lubricated ball bearings and shall be statically and dynamically balanced in accordance with ISO 1940 part 1. The motor shall be closed, protection level IP 54, thermal class 155. Motor efficiency class shall comply with IE4. Fan characteristic curves indicate measurements on a chamber test in accordance with ISO5801. The three phase external rotor motor integrated into the fan hub meets the requirements for circulating electric machines set forth in DIN EN 60 034-1 (VDE 0530 Part 1).

- C. Fan Array shall be listed per UL 1995.
- D. Fan assemblies shall be prewired with wire whips and plug connectors.
- E. Fan system manufacturer must stock replacement parts in North America. The fan bulkhead wall shall be constructed in a manner for easy field assembly, constructed of 14 gauge G90 formed sheet metal. The bend profile at each panel's seam shall provide vertical structural support for the bulkhead wall. Structural support along the bulkhead perimeter to be provided by others.
- F. The factory mounted and wired single point power panel shall include an external disconnect. The panel shall be UL or ETL listed. Controller shall be configurable for fan speed control via 0-10 VDC input, 4-20 mA input, constant airflow, or duct static pressure (static pressure sensor to be field provided and mounted). Control panel shall be equipped with relays for locking between other electrically driven components.
- G. 5KAIC SCCR disconnect shall be provided.
- H. Performance Ratings: Determined in accordance with AMCA.
- I. Sound Ratings: Tested to AMCA standards.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with manufacturer's instructions.

END OF SECTION

**SECTION 236433
MODULAR WATER CHILLERS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Packaged air-cooled water chiller.

1.02 REFERENCE STANDARDS

- A. AHRI 550/590 (I-P) - Performance Rating of Water-chilling and Heat Pump Water-heating Packages Using the Vapor Compression Cycle; 2020.
- B. AHRI 575 - Method of Measuring Machinery Sound Within an Equipment Space; 2008.
- C. ASHRAE Std 15 - Safety Standard for Refrigeration Systems and Designation and Classification of Refrigerants; 2019, with Errata (2020).
- D. ASHRAE Std 90.1 I-P - Energy Standard for Buildings Except Low-Rise Residential Buildings; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- E. ASME BPVC-VIII-1 - Boiler and Pressure Vessel Code, Section VIII, Division 1: Rules for Construction of Pressure Vessels; 2019.
- F. ASTM B117 - Standard Practice for Operating Salt Spray (Fog) Apparatus; 2019.
- G. UL 1995 - Heating and Cooling Equipment; Current Edition, Including All Revisions.

1.03 SUBMITTALS

- A. Product Data: Provide rated capacities, weights, specialties and accessories, electrical requirements and wiring diagrams.
- B. Shop Drawings: Indicate components, assembly, dimensions, weights and loadings, required clearances, and location and size of field connections. Indicate equipment, piping and connections, valves, strainers, and thermostatic valves required for complete system.
- C. Warranty: Submit manufacturer's warranty and ensure forms have been filled out in Owner's name and registered with manufacturer.

1.04 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum five years of documented experience.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Comply with manufacturer's written installation instructions for rigging, unloading, and transporting units.
- B. Deliver units to the job site completely assembled and charged with refrigerant and oil by manufacturer.

1.06 WARRANTY

- A. Manufacturer's Warranty: Provide minimum five year warranty to include coverage for materials and labor for compressor.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. SMARDT; www.smardt.com

2.02 AIR-COOLED MODULAR WATER CHILLER CONSTRUCTION REQUIREMENTS

- A. Factory assembled and tested package-module consisting of compressor(s), compressor motor(s), evaporator, condenser, enclosure, refrigeration circuits(s) and specialties, interconnecting piping, water circuit isolation valves, starters, and microprocessor-based controls.

1. Rating: AHRI 550/590 (I-P).
 2. Safety: UL 1995 and ASHRAE Std 15.
 3. Machinery Sound Testing: AHRI 575.
 4. Construction & Testing: ASME BPVC-VIII-1 if applicable for construction type.
 5. Energy Efficiency: ASHRAE Std 90.1.
 6. Enclosures:
 - a. Frame: Heavy gauge steel with factory painted finish.
 - b. Perform 500-hour minimum salt spray test in accordance with ASTM B117 for units exposed to outdoor conditions.
- B. Evaporator Side:
1. Brazed plate made of 316 stainless steel.
 2. Working Pressure Rating, Refrigerant Side: 650 psi minimum.
 3. Working Pressure Rating, Water Side: 285 psi minimum.
 4. End Connections: Provide with flanged end connections.
- C. Cold Surface Insulation:
1. Insulation is factory or field installed on evaporator, connections, and suction piping.
 2. 0.75 inches minimum thick, closed cell, expanded polyvinyl chloride, polyurethane, or Armaflex II insulation with a maximum K factor of 0.28.
- D. Provide factory installed vents and water drain connections on evaporator or piping.
- E. Provide factory-installed manual isolation valves in supply and return piping with modulating valve for variable primary flow operation.
- F. Air-Cooled Finned-Tube Condenser:
1. Mechanically bonded aluminum fins to copper tubing and protect with corrosion resistant materials or coatings.
 2. Clean and leak test at minimum pressure of 650 psi.
 3. Coil Guards: Provide corrosion proof, heavy gauge wire panels, factory installed. Protect condenser coil by enclosing with heavy plastic to prevent damage during shipping or rigging.
 4. Fans and Motors:
 - a. Vertical-Discharge Fans: Dynamically balance propeller, shrouded-axial, or airfoil type fans of reinforced polymer or glass fiber reinforced composite corrosion resistant construction equipped with sealed, permanently lubricated ball bearings.
 - b. Discharge Fan Guards: Corrosion resistant, heavy gauge steel wire.
 - c. Motors: Direct drive, totally enclosed for outdoor use with current overload protection.
- G. Refrigeration Circuits:
1. Provide two independent refrigeration circuits with one compressor per circuit.
 2. Provide liquid line shut-off valve, filter-drier, thermal expansion valve, refrigerant relief device, and compressor discharge check valve for each independent circuit.
- H. Controls Package:
1. Prewire, assemble, factory mount, and test operating and safety control system consisting of a digital display or gauges, on-auto-off switch, motor starting contactors, disconnect switches, power and control wiring. Provide controls, monitoring, programmable setpoints, alarms, and BAS as defined below:
 - a. Automatic Adjustable Operating Controls:
 - 1) Temperature of chilled water leaving chiller.
 - 2) Number of compressor circuits required to operate based on setpoints and system load.
 - 3) Compressor short-cycling prevention.
 - 4) Lead/lag operation for compressors. New lead compressor selected every 24 hours to equalize run time.

- 5) Automatic reset on power source failure.
- 6) Load limiting.
- b. Normal Operation Monitoring and Open Coverless Displays:
 - 1) Hours of operation.
 - 2) Suction and discharge refrigerant pressures.
 - 3) Automatic diagnostics.
 - 4) Number of starts.
 - 5) On/off compressor status.
 - 6) Entering and leaving chilled water temperatures.
 - 7) Status of operation.
 - 8) Compressor winding temperature.
 - 9) Suction temperature.
 - 10) Oil pressure.
- c. Setpoints:
 - 1) Leaving chilled water temperature.
 - 2) Date/time.
- d. Automatic Chiller Shut-Down Safety Controls and Alarm:
 - 1) Automatic Reset:
 - (a) Chilled water flow interlock.
 - (b) Voltage protection (over/under).
 - (c) Phase reversal protection.
 - 2) Manual Reset:
 - (a) Low suction pressure.
 - (b) High motor winding temperature.
 - (c) Low chilled water temperature.
 - (d) Low chilled water flow.
 - (e) High condenser refrigerant discharge pressure.
 - (f) Motor current overload and phase loss.
 - (g) Low oil flow.
 - 3) Remote Alarm: Activate remote, audible bell upon safety shutdown of chiller.
 - 4) Minimum Data Transmission to BAS:
 - (a) All system operating conditions.
 - (b) Capacity control information.
 - (c) Safety shutdown conditions.
 - 5) Minimum Operating Commands from BAS:
 - (a) Remote unit start/stop.
 - (b) Remote chilled water reset.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Align chiller package on steel or concrete foundations.
- C. Install units on vibration isolators, see Section 230548.
- D. Connect to electrical service.
- E. Connect to chilled water piping.
- F. Arrange piping for easy dismantling to permit tube cleaning and removal.
- G. Coordinate BAS, BMS, or Integrated Automation linking between unit controller(s) and remote front end interface.

3.02 MANUFACTURER'S FIELD SERVICES

- A. Perform factory startup of the chiller by factory trained and authorized servicing technicians confirming equipment has been correctly installed prior to equipment becoming operational and covered under the manufacturer's warranty.
- B. Supply initial charge of refrigerant and oil if not completely factory charged.
- C. Demonstrate system operations and verify specified performance.

END OF SECTION

**SECTION 238216
AIR COILS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Water cooling coils.

1.02 RELATED REQUIREMENTS

- A. Section 220719 - Plumbing Piping Insulation.

1.03 REFERENCE STANDARDS

- A. SMACNA (DCS) - HVAC Duct Construction Standards Metal and Flexible; 2005 (Revised 2009).

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide coil and frame configurations, dimensions, materials, rows, connections, and rough-in dimensions.
- C. Shop Drawings: Indicate coil and frame configurations, dimensions, materials, rows, connections, and rough-in dimensions.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Protect coil fins from crushing and bending by leaving in shipping cases until installation, and by storing indoors.
- B. Protect coils from entry of dirt and debris with pipe caps or plugs.

1.07 WARRANTY

- A. Provide five year manufacturer warranty.

PART 2 PRODUCTS

2.01 WATER COOLING COILS

- A. Manufacturers:
 - 1. REA Cooperation; www.rae-coils.com
 - 2. Aerofin Corporation; _____: www.aerofin.com
 - 3. Substitutions: See Section 016000 - Product Requirements.
- B. Tubes: 5/8 inch OD seamless copper or brass arranged in parallel or staggered pattern, expanded into fins, silver brazed joints.
- C. Fins: Aluminum or copper continuous plate type with full fin collars. Solder coat copper fin coils.
- D. Casing: Die formed channel frame of 16 gauge, 0.0598 inch galvanized steel with 3/8 inch mounting holes on 3 inch centers. Provide tube supports for coils longer than 36 inches.
- E. Headers: Cast iron with tubes expanded into header.
- F. Testing: Air test under water to 200 psi for working pressure of 200 psi and 220 degrees F.
- G. Configuration: Drainable, with threaded plugs in headers for drain and vent; threaded plugs in return bends and in headers opposite each tube.
- H. Fin Spacing: 8 fins per inch.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with manufacturer's written instructions.
- B. Install in ducts and casings in accordance with SMACNA (DCS).
 - 1. Support coil sections independent of piping on steel channel or double angle frames and secure to casings.
 - 2. Arrange supports to avoid piercing drain pans.
 - 3. Provide airtight seal between coil and duct or casing.
- C. Protect coils to prevent damage to fins and flanges. Comb out bent fins.
- D. Install coils level. Install cleanable tube coils with 1:50 pitch.
- E. Make connections to coils with unions and flanges.
- F. Hydronic Coils:
 - 1. Hydronic Coils: Connect water supply to leaving air side of coil (counterflow arrangement).
 - 2. Ensure water coils are drainable and provide drain connection at low points.
- G. Cooling Coils:
 - 1. Provide three break moisture eliminators of 24 gauge, 0.0239 inch galvanized steel, where air velocity exceeds 500 ft/min.
 - 2. Provide drain pan and drain connection; fabricate from 20 gauge, 0.0359 inch galvanized steel, extend 3 inches from face of entering air side, 6 inches from face of leaving air side, and 4 inches from face of eliminators. Pipe drain pans individually to floor drain with water seal trap.
- H. Insulate headers located outside air flow as specified for piping. Refer to Section 220719.

END OF SECTION

**SECTION 260505
SELECTIVE DEMOLITION FOR ELECTRICAL**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Electrical demolition.

1.02 RELATED REQUIREMENTS

- A. Section 017000 - Execution and Closeout Requirements: Additional requirements for alterations work.

PART 2 PRODUCTS

2.01 MATERIALS AND EQUIPMENT

- A. Materials and equipment for patching and extending work: As specified in individual sections.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that abandoned wiring and equipment serve only abandoned facilities.
- B. Demolition drawings are based on casual field observation and existing record documents.
- C. Report discrepancies to Engineer before disturbing existing installation.
- D. Beginning of demolition means installer accepts existing conditions.

3.02 PREPARATION

- A. Disconnect electrical systems in walls, floors, and ceilings to be removed.
- B. Coordinate utility service outages with utility company.
- C. Provide temporary wiring and connections to maintain existing systems in service during construction. When work must be performed on energized equipment or circuits, use personnel experienced in such operations.

3.03 DEMOLITION AND EXTENSION OF EXISTING ELECTRICAL WORK

- A. Perform work for removal and disposal of equipment and materials containing toxic substances regulated under the Federal Toxic Substances Control Act (TSCA) in accordance with applicable federal, state, and local regulations. Applicable equipment and materials include, but are not limited to:
 - 1. PCB-containing electrical equipment, including transformers, capacitors, and switches.
- B. Remove, relocate, and extend existing installations to accommodate new construction.
- C. Remove abandoned wiring to source of supply.
- D. Remove exposed abandoned conduit, including abandoned conduit above accessible ceiling finishes. Cut conduit flush with walls and floors, and patch surfaces.
- E. Disconnect abandoned outlets and remove devices. Remove abandoned outlets if conduit servicing them is abandoned and removed. Provide blank cover for abandoned outlets that are not removed.
- F. Disconnect and remove abandoned panelboards and distribution equipment.
- G. Disconnect and remove electrical devices and equipment serving utilization equipment that has been removed.
- H. Maintain access to existing electrical installations that remain active. Modify installation or provide access panel as appropriate.
- I. Extend existing installations using materials and methods compatible with existing electrical installations, or as specified.

3.04 CLEANING AND REPAIR

- A. Clean and repair existing materials and equipment that remain or that are to be reused.

END OF SECTION

SECTION 260519
LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Single conductor building wire.
- B. Metal-clad cable.
- C. Wiring connectors.
- D. Electrical tape.
- E. Oxide inhibiting compound.
- F. Wire pulling lubricant.
- G. Cable ties.

1.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.

1.03 REFERENCE STANDARDS

- A. ASTM B3 - Standard Specification for Soft or Annealed Copper Wire; 2013 (Reapproved 2018).
- B. ASTM B8 - Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft; 2011 (Reapproved 2017).
- C. ASTM B33 - Standard Specification for Tin-Coated Soft or Annealed Copper Wire for Electrical Purposes; 2010 (Reapproved 2014).
- D. ASTM B787/B787M - Standard Specification for 19 Wire Combination Unilay-Stranded Copper Conductors for Subsequent Insulation; 2004 (Reapproved 2014).
- E. ASTM B800 - Standard Specification for 8000 Series Aluminum Alloy Wire for Electrical Purposes - Annealed and Intermediate Tempers; 2005 (Reapproved 2015).
- F. ASTM B801 - Standard Specification for Concentric-Lay-Stranded Conductors of 8000 Series Aluminum Alloy Wire for Subsequent Covering of Insulation; 2016.
- G. ASTM D3005 - Standard Specification for Low-Temperature Resistant Vinyl Chloride Plastic Pressure-Sensitive Electrical Insulating Tape; 2017.
- H. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- I. NECA 104 - Recommended Practice for Installing Aluminum Building Wire and Cable; 2012.
- J. NECA 120 - Standard for Installing Armored Cable (AC) and Metal-Clad Cable (MC); 2012.
- K. NEMA WC 70 - Power Cables Rated 2000 Volts or Less for the Distribution of Electrical Energy; 2009.
- L. NETA ATS - Acceptance Testing Specifications for Electrical Power Equipment and Systems; 2017.
- M. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- N. UL 44 - Thermoset-Insulated Wires and Cables; Current Edition, Including All Revisions.
- O. UL 83 - Thermoplastic-Insulated Wires and Cables; Current Edition, Including All Revisions.
- P. UL 486A-486B - Wire Connectors; Current Edition, Including All Revisions.
- Q. UL 486C - Splicing Wire Connectors; Current Edition, Including All Revisions.
- R. UL 486D - Sealed Wire Connector Systems; Current Edition, Including All Revisions.
- S. UL 510 - Polyvinyl Chloride, Polyethylene, and Rubber Insulating Tape; Current Edition, Including All Revisions.

- T. UL 1569 - Metal-Clad Cables; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
1. Coordinate sizes of raceways, boxes, and equipment enclosures installed under other sections with the actual conductors to be installed, including adjustments for conductor sizes increased for voltage drop.
 2. Coordinate with electrical equipment installed under other sections to provide terminations suitable for use with the conductors to be installed.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for conductors and cables, including detailed information on materials, construction, ratings, listings, and available sizes, configurations, and stranding.

1.06 QUALITY ASSURANCE

- A. Comply with requirements of NFPA 70.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Receive, inspect, handle, and store conductors and cables in accordance with manufacturer's instructions.

1.08 FIELD CONDITIONS

- A. Do not install or otherwise handle thermoplastic-insulated conductors at temperatures lower than 14 degrees F, unless otherwise permitted by manufacturer's instructions. When installation below this temperature is unavoidable, notify Architect and obtain direction before proceeding with work.

PART 2 PRODUCTS

2.01 CONDUCTOR AND CABLE APPLICATIONS

- A. Do not use conductors and cables for applications other than as permitted by NFPA 70 and product listing.
- B. Provide single conductor building wire installed in suitable raceway unless otherwise indicated, permitted, or required.
- C. Metal-clad cable is permitted only as follows:
1. Where not otherwise restricted, may be used:
 - a. Where concealed above accessible ceilings for final connections from junction boxes to luminaires.
 - 1) Maximum Length: 6 feet.
 - b. Where concealed in hollow stud walls, above accessible ceilings, and under raised floors for branch circuits up to 20 A.
 - 1) Exception: Provide single conductor building wire in raceway for circuit homerun from first outlet to panelboard.
 2. In addition to other applicable restrictions, may not be used:
 - a. Where exposed to damage.
 - b. For damp, wet, or corrosive locations, unless provided with a PVC jacket listed as suitable for those locations.

2.02 CONDUCTOR AND CABLE GENERAL REQUIREMENTS

- A. Provide products that comply with requirements of NFPA 70.
- B. Provide products listed, classified, and labeled as suitable for the purpose intended.
- C. Unless specifically indicated to be excluded, provide all required conduit, boxes, wiring, connectors, etc. as required for a complete operating system.

- D. Comply with NEMA WC 70.
- E. Thermoplastic-Insulated Conductors and Cables: Listed and labeled as complying with UL 83.
- F. Thermoset-Insulated Conductors and Cables: Listed and labeled as complying with UL 44.
- G. Conductors and Cables Installed Exposed in Spaces Used for Environmental Air (only where specifically permitted): Plenum rated, listed and labeled as suitable for use in return air plenums.
- H. Conductor Material:
 - 1. Provide copper conductors except where aluminum conductors are specifically indicated or permitted for substitution. Conductor sizes indicated are based on copper unless specifically indicated as aluminum. Conductors designated with the abbreviation "AL" indicate aluminum.
 - a. Substitution of aluminum conductors for copper is permitted, when approved by Owner and authority having jurisdiction, only for the following:
 - 1) Services: Copper conductors size 1/0 AWG and larger.
 - 2) Feeders: Copper conductors size 1/0 AWG and larger.
 - b. Where aluminum conductors are substituted for copper, comply with the following:
 - 1) Size aluminum conductors to provide, when compared to copper sizes indicated, equivalent or greater ampacity and equivalent or less voltage drop.
 - 2) Increase size of raceways, boxes, wiring gutters, enclosures, etc. as required to accommodate aluminum conductors.
 - 2. Copper Conductors: Soft drawn annealed, 98 percent conductivity, uncoated copper conductors complying with ASTM B3, ASTM B8, or ASTM B787/B787M unless otherwise indicated.
 - 3. Tinned Copper Conductors: Comply with ASTM B33.
 - 4. Aluminum Conductors (only where specifically indicated or permitted for substitution): AA-8000 series aluminum alloy conductors recognized by ASTM B800 and compact stranded in accordance with ASTM B801 unless otherwise indicated.
- I. Minimum Conductor Size:
 - 1. Branch Circuits: 12 AWG.
 - a. Exceptions:
 - 1) 20 A, 120 V circuits longer than 100 feet: 10 AWG, for voltage drop.
 - 2) 20 A, 120 V circuits longer than 150 feet: 8 AWG, for voltage drop.
 - 3) 20 A, 277 V circuits longer than 250 feet: 10 AWG, for voltage drop.
 - 2. Control Circuits: 14 AWG.
- J. Where conductor size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.
- K. Conductor Color Coding:
 - 1. Color code conductors as indicated unless otherwise required by the authority having jurisdiction. Maintain consistent color coding throughout project.
 - 2. Color Coding Method: Integrally colored insulation.
 - a. Conductors size 4 AWG and larger may have black insulation color coded using vinyl color coding electrical tape.
 - 3. Color Code:
 - a. 480Y/277 V, 3 Phase, 4 Wire System:
 - 1) Phase A: Brown.
 - 2) Phase B: Orange.
 - 3) Phase C: Yellow.
 - 4) Neutral/Grounded: Gray.
 - b. 208Y/120 V, 3 Phase, 4 Wire System:
 - 1) Phase A: Black.
 - 2) Phase B: Red.

- 3) Phase C: Blue.
- 4) Neutral/Grounded: White.
- c. Equipment Ground, All Systems: Green.

2.03 SINGLE CONDUCTOR BUILDING WIRE

- A. Manufacturers:
 - 1. Copper Building Wire:
 - a. Cerro Wire LLC: www.cerrowire.com/#sle.
 - b. Encore Wire Corporation: www.encorewire.com/#sle.
 - c. General Cable Technologies Corporation: www.generalcable.com/#sle.
 - d. Southwire Company: www.southwire.com/#sle.
 - 2. Aluminum Building Wire (only where specifically indicated or permitted for substitution):
 - a. Encore Wire Corporation: www.encorewire.com/#sle.
 - b. Southwire Company: www.southwire.com/#sle.
 - c. Stabiloy, a brand of General Cable Technologies Corporation: www.stabiloy.com/#sle.
- B. Description: Single conductor insulated wire.
- C. Conductor Stranding:
 - 1. Feeders and Branch Circuits:
 - a. Size 10 AWG and Smaller: Solid or stranded.
 - b. Size 8 AWG and Larger: Stranded.
 - 2. Control Circuits: Stranded.
- D. Insulation Voltage Rating: 600 V.
- E. Insulation:
 - 1. Copper Building Wire: Type THHN/THWN or THHN/THWN-2, except as indicated below.
 - a. Size 4 AWG and Larger: Type XHHW-2.
 - b. Installed Underground: Type XHHW-2.
 - 2. Aluminum Building Wire (only where specifically indicated or permitted for substitution): Type XHHW-2.

2.04 METAL-CLAD CABLE

- A. Manufacturers:
 - 1. AFC Cable Systems Inc: www.afcweb.com/#sle.
 - 2. Encore Wire Corporation: www.encorewire.com/#sle.
 - 3. Southwire Company: www.southwire.com/#sle.
- B. Description: NFPA 70, Type MC cable listed and labeled as complying with UL 1569, and listed for use in classified firestop systems to be used.
- C. Conductor Stranding:
 - 1. Size 10 AWG and Smaller: Solid or stranded.
 - 2. Size 8 AWG and Larger: Stranded.
- D. Insulation Voltage Rating: 600 V.
- E. Insulation: Type THHN, THHN/THWN, or THHN/THWN-2.
- F. Grounding: Full-size integral equipment grounding conductor.
- G. Armor: Steel, interlocked tape.
- H. Provide PVC jacket applied over cable armor where indicated or required for environment of installed location.

2.05 WIRING CONNECTORS

- A. Description: Wiring connectors appropriate for the application, suitable for use with the conductors to be connected, and listed as complying with UL 486A-486B or UL 486C as applicable.

- B. Wiring Connectors for Splices and Taps:
 - 1. Copper Conductors Size 8 AWG and Smaller: Use twist-on insulated spring connectors.
 - 2. Copper Conductors Size 6 AWG and Larger: Use mechanical connectors or compression connectors.
 - 3. Connectors for Aluminum Conductors: Use compression connectors or mechanical connectors.
- C. Wiring Connectors for Terminations:
 - 1. Provide terminal lugs for connecting conductors to equipment furnished with terminations designed for terminal lugs.
 - 2. Provide compression adapters for connecting conductors to equipment furnished with mechanical lugs when only compression connectors are specified.
 - 3. Where over-sized conductors are larger than the equipment terminations can accommodate, provide connectors suitable for reducing to appropriate size, but not less than required for the rating of the overcurrent protective device.
 - 4. Copper Conductors Size 8 AWG and Larger: Use mechanical connectors or compression connectors where connectors are required.
 - 5. Aluminum Conductors: Use compression connectors or mechanical connectors for all connections.
 - 6. Stranded Conductors Size 10 AWG and Smaller: Use crimped terminals for connections to terminal screws.
- D. Do not use insulation-piercing or insulation-displacement connectors designed for use with conductors without stripping insulation.
- E. Twist-on Insulated Spring Connectors: Rated 600 V, 221 degrees F for standard applications and 302 degrees F for high temperature applications; pre-filled with sealant and listed as complying with UL 486D for damp and wet locations.
 - 1. Manufacturers:
 - a. 3M: www.3m.com/#sle.
 - b. Ideal Industries, Inc: www.idealindustries.com/#sle.
 - c. NSI Industries LLC: www.nsiindustries.com/#sle.
- F. Mechanical Connectors: Provide bolted type or set-screw type.
 - 1. Manufacturers:
 - a. Burndy LLC: www.burndy.com/#sle.
 - b. IlSCO: www.ilsco.com/#sle.
 - c. Thomas & Betts Corporation: www.tnb.com/#sle.
- G. Compression Connectors: Provide circumferential type or hex type crimp configuration.
 - 1. Manufacturers:
 - a. Burndy LLC: www.burndy.com/#sle.
 - b. IlSCO: www.ilsco.com/#sle.
 - c. Thomas & Betts Corporation: www.tnb.com/#sle.
- H. Crimped Terminals: Nylon-insulated, with insulation grip and terminal configuration suitable for connection to be made.
 - 1. Manufacturers:
 - a. Burndy LLC: www.burndy.com/#sle.
 - b. IlSCO: www.ilsco.com/#sle.
 - c. Thomas & Betts Corporation: www.tnb.com/#sle.

2.06 ACCESSORIES

- A. Electrical Tape:
 - 1. Vinyl Color Coding Electrical Tape: Integrally colored to match color code indicated; listed as complying with UL 510; minimum thickness of 7 mil; resistant to abrasion, corrosion, and sunlight; suitable for continuous temperature environment up to 221 degrees F.

2. Vinyl Insulating Electrical Tape: Complying with ASTM D3005 and listed as complying with UL 510; minimum thickness of 7 mil; resistant to abrasion, corrosion, and sunlight; conformable for application down to 0 degrees F and suitable for continuous temperature environment up to 221 degrees F.
- B. Oxide Inhibiting Compound: Listed; suitable for use with the conductors or cables to be installed.
- C. Wire Pulling Lubricant: Listed; suitable for use with the conductors or cables to be installed and suitable for use at the installation temperature.
- D. Cable Ties: Material and tensile strength rating suitable for application.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that interior of building has been protected from weather.
- B. Verify that work likely to damage wire and cable has been completed.
- C. Verify that raceways, boxes, and equipment enclosures are installed and are properly sized to accommodate conductors and cables in accordance with NFPA 70.
- D. Verify that field measurements are as indicated.
- E. Verify that conditions are satisfactory for installation prior to starting work.

3.02 INSTALLATION

- A. Circuiting Requirements:
 1. Unless dimensioned, circuit routing indicated is diagrammatic.
 2. When circuit destination is indicated without specific routing, determine exact routing required.
 3. Arrange circuiting to minimize splices.
 4. Maintain separation of wiring for emergency systems in accordance with NFPA 70.
 5. Common Neutrals: Unless otherwise indicated, sharing of neutral/grounded conductors among up to three single phase branch circuits of different phases installed in the same raceway is not permitted. Provide dedicated neutral/grounded conductor for each individual branch circuit.
- B. Install products in accordance with manufacturer's instructions.
- C. Perform work in accordance with NECA 1 (general workmanship).
- D. Install aluminum conductors in accordance with NECA 104.
- E. Install metal-clad cable (Type MC) in accordance with NECA 120.
- F. Installation in Raceway:
 1. Tape ends of conductors and cables to prevent infiltration of moisture and other contaminants.
 2. Pull all conductors and cables together into raceway at same time.
 3. Do not damage conductors and cables or exceed manufacturer's recommended maximum pulling tension and sidewall pressure.
 4. Use suitable wire pulling lubricant where necessary, except when lubricant is not recommended by the manufacturer.
- G. Paralleled Conductors: Install conductors of the same length and terminate in the same manner.
- H. Secure and support conductors and cables in accordance with NFPA 70 using suitable supports and methods approved by the authority having jurisdiction. Provide independent support from building structure. Do not provide support from raceways, piping, ductwork, or other systems.
 1. Installation Above Suspended Ceilings: Do not provide support from ceiling support system. Do not provide support from ceiling grid or allow conductors and cables to lay on

- ceiling tiles.
- 2. Installation in Vertical Raceways: Provide supports where vertical rise exceeds permissible limits.
- I. Terminate cables using suitable fittings.
 - 1. Metal-Clad Cable (Type MC):
 - a. Use listed fittings.
 - b. Cut cable armor only using specialized tools to prevent damaging conductors or insulation. Do not use hacksaw or wire cutters to cut armor.
- J. Install conductors with a minimum of 12 inches of slack at each outlet.
- K. Neatly train and bundle conductors inside boxes, wireways, panelboards and other equipment enclosures.
- L. Group or otherwise identify neutral/grounded conductors with associated ungrounded conductors inside enclosures in accordance with NFPA 70.
- M. Make wiring connections using specified wiring connectors.
 - 1. Make splices and taps only in accessible boxes. Do not pull splices into raceways or make splices in conduit bodies.
 - 2. Remove appropriate amount of conductor insulation for making connections without cutting, nicking or damaging conductors.
 - 3. Do not remove conductor strands to facilitate insertion into connector.
 - 4. Clean contact surfaces on conductors and connectors to suitable remove corrosion, oxides, and other contaminants. Do not use wire brush on plated connector surfaces.
 - 5. Connections for Aluminum Conductors: Fill connectors with oxide inhibiting compound where not pre-filled by manufacturer.
 - 6. Mechanical Connectors: Secure connections according to manufacturer's recommended torque settings.
 - 7. Compression Connectors: Secure connections using manufacturer's recommended tools and dies.
- N. Insulate splices and taps that are made with uninsulated connectors using methods suitable for the application, with insulation and mechanical strength at least equivalent to unspliced conductors.
- O. Insulate ends of spare conductors using vinyl insulating electrical tape.
- P. Field-Applied Color Coding: Where vinyl color coding electrical tape is used in lieu of integrally colored insulation as permitted in Part 2 under "Color Coding", apply half overlapping turns of tape at each termination and at each location conductors are accessible.
- Q. Install firestopping to preserve fire resistance rating of partitions and other elements, using materials and methods specified in Section 078400.
- R. Unless specifically indicated to be excluded, provide final connections to all equipment and devices, including those furnished by others, as required for a complete operating system.

3.03 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect and test in accordance with NETA ATS, except Section 4.
- C. Perform inspections and tests listed in NETA ATS, Section 7.3.2. The insulation resistance test is required for all conductors. The resistance test for parallel conductors listed as optional is not required.
 - 1. Disconnect surge protective devices (SPDs) prior to performing any high potential testing. Replace SPDs damaged by performing high potential testing with SPDs connected.
- D. Correct deficiencies and replace damaged or defective conductors and cables.

END OF SECTION

**SECTION 260526
GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Grounding and bonding requirements.
- B. Conductors for grounding and bonding.
- C. Connectors for grounding and bonding.

1.02 RELATED REQUIREMENTS

- A. Section 260519 - Low-Voltage Electrical Power Conductors and Cables: Additional requirements for conductors for grounding and bonding, including conductor color coding.
- B. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

1.03 REFERENCE STANDARDS

- A. IEEE 81 - IEEE Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Grounding System; 2012.
- B. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- C. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- D. UL 467 - Grounding and Bonding Equipment; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Verify exact locations of underground metal water service pipe entrances to building.
 - 2. Coordinate the work with other trades to provide steel reinforcement complying with specified requirements for concrete-encased electrode.

1.05 QUALITY ASSURANCE

- A. Comply with requirements of NFPA 70.

PART 2 PRODUCTS

2.01 GROUNDING AND BONDING REQUIREMENTS

- A. Existing Work: Where existing grounding and bonding system components are indicated to be reused, they may be reused only where they are free from corrosion, integrity and continuity are verified, and where acceptable to the authority having jurisdiction.
- B. Do not use products for applications other than as permitted by NFPA 70 and product listing.
- C. Unless specifically indicated to be excluded, provide all required components, conductors, connectors, conduit, boxes, fittings, supports, accessories, etc. as necessary for a complete grounding and bonding system.
- D. Where conductor size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.
- E. Grounding System Resistance:
 - 1. Achieve specified grounding system resistance under normally dry conditions unless otherwise approved by Engineer. Precipitation within the previous 48 hours does not constitute normally dry conditions.
 - 2. Grounding Electrode System: Not greater than 5 ohms to ground, when tested according to IEEE 81 using "fall-of-potential" method.
- F. Grounding Electrode System:
 - 1. Provide connection to required and supplemental grounding electrodes indicated to form grounding electrode system.

- a. Provide continuous grounding electrode conductors without splice or joint.
 - b. Install grounding electrode conductors in raceway where exposed to physical damage. Bond grounding electrode conductor to metallic raceways at each end with bonding jumper.
 2. Provide additional ground electrode(s) as required to achieve specified grounding electrode system resistance.
- G. Bonding and Equipment Grounding:
 1. Provide bonding for equipment grounding conductors, equipment ground busses, metallic equipment enclosures, metallic raceways and boxes, device grounding terminals, and other normally non-current-carrying conductive materials enclosing electrical conductors/equipment or likely to become energized as indicated and in accordance with NFPA 70.
 2. Provide insulated equipment grounding conductor in each feeder and branch circuit raceway. Do not use raceways as sole equipment grounding conductor.
 3. Where circuit conductor sizes are increased for voltage drop, increase size of equipment grounding conductor proportionally in accordance with NFPA 70.
 4. Unless otherwise indicated, connect wiring device grounding terminal to branch circuit equipment grounding conductor and to outlet box with bonding jumper.
 5. Terminate branch circuit equipment grounding conductors on solidly bonded equipment ground bus only. Do not terminate on neutral (grounded) or isolated/insulated ground bus.
 6. Provide bonding jumper across expansion or expansion/deflection fittings provided to accommodate conduit movement.

2.02 GROUNDING AND BONDING COMPONENTS

- A. General Requirements:
 1. Provide products listed, classified, and labeled as suitable for the purpose intended.
 2. Provide products listed and labeled as complying with UL 467 where applicable.
- B. Conductors for Grounding and Bonding, in Addition to Requirements of Section 260526:
 1. Use insulated copper conductors unless otherwise indicated.
 - a. Exceptions:
 - 1) Use bare copper conductors where installed underground in direct contact with earth.
 - 2) Use bare copper conductors where directly encased in concrete (not in raceway).
- C. Connectors for Grounding and Bonding:
 1. Description: Connectors appropriate for the application and suitable for the conductors and items to be connected; listed and labeled as complying with UL 467.
 2. Unless otherwise indicated, use exothermic welded connections for underground, concealed and other inaccessible connections.
 3. Unless otherwise indicated, use mechanical connectors, compression connectors, or exothermic welded connections for accessible connections.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Perform work in accordance with NECA 1 (general workmanship).
- C. Make grounding and bonding connections using specified connectors.
 1. Remove appropriate amount of conductor insulation for making connections without cutting, nicking or damaging conductors. Do not remove conductor strands to facilitate insertion into connector.
 2. Remove nonconductive paint, enamel, or similar coating at threads, contact points, and contact surfaces.

3. Exothermic Welds: Make connections using molds and weld material suitable for the items to be connected in accordance with manufacturer's recommendations.
 4. Mechanical Connectors: Secure connections according to manufacturer's recommended torque settings.
 5. Compression Connectors: Secure connections using manufacturer's recommended tools and dies.
- D. Identify grounding and bonding system components in accordance with Section 260553.

END OF SECTION

SECTION 260529
HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Support and attachment requirements and components for equipment, conduit, cable, boxes, and other electrical work.

1.02 REFERENCE STANDARDS

- A. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- B. ASTM A153/A153M - Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2016a.
- C. ASTM B633 - Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel; 2015.
- D. MFMA-4 - Metal Framing Standards Publication; 2004.
- E. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- F. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- G. UL 5B - Strut-Type Channel Raceways and Fittings; Current Edition, Including All Revisions.

1.03 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate sizes and arrangement of supports and bases with the actual equipment and components to be installed.
 - 2. Coordinate the work with other trades to provide additional framing and materials required for installation.
 - 3. Coordinate compatibility of support and attachment components with mounting surfaces at the installed locations.
 - 4. Coordinate the arrangement of supports with ductwork, piping, equipment and other potential conflicts installed under other sections or by others.
- B. Sequencing:
 - 1. Do not install products on or provide attachment to concrete surfaces until concrete has fully cured in accordance with Section 033000.

1.04 QUALITY ASSURANCE

- A. Comply with NFPA 70.
- B. Comply with applicable building code.

PART 2 PRODUCTS

2.01 SUPPORT AND ATTACHMENT COMPONENTS

- A. General Requirements:
 - 1. Provide all required hangers, supports, anchors, fasteners, fittings, accessories, and hardware as necessary for the complete installation of electrical work.
 - 2. Provide products listed, classified, and labeled as suitable for the purpose intended, where applicable.
 - 3. Where support and attachment component types and sizes are not indicated, select in accordance with manufacturer's application criteria as required for the load to be supported with a minimum safety factor of 4. Include consideration for vibration, equipment operation, and shock loads where applicable.
 - 4. Do not use products for applications other than as permitted by NFPA 70 and product listing.

5. Steel Components: Use corrosion resistant materials suitable for the environment where installed.
 - a. Indoor Dry Locations: Use zinc-plated steel or approved equivalent unless otherwise indicated.
 - b. Outdoor and Damp or Wet Indoor Locations: Use galvanized steel, stainless steel, or approved equivalent unless otherwise indicated.
 - c. Zinc-Plated Steel: Electroplated in accordance with ASTM B633.
 - d. Galvanized Steel: Hot-dip galvanized after fabrication in accordance with ASTM A123/A123M or ASTM A153/A153M.
- B. Conduit and Cable Supports: Straps, clamps, etc. suitable for the conduit or cable to be supported.
 1. Conduit Straps: One-hole or two-hole type; steel or malleable iron.
 2. Conduit Clamps: Bolted type unless otherwise indicated.
 3. Manufacturers:
 - a. Cooper Crouse-Hinds, a division of Eaton Corporation: www.cooperindustries.com/#sle.
 - b. Erico International Corporation: www.erico.com/#sle.
 - c. O-Z/Gedney, a brand of Emerson Electric Co: www.emerson.com/#sle.
 - d. Thomas & Betts Corporation: www.tnb.com/#sle.
- C. Outlet Box Supports: Hangers, brackets, etc. suitable for the boxes to be supported.
 1. Manufacturers:
 - a. Cooper Crouse-Hinds, a division of Eaton Corporation: www.cooperindustries.com/#sle.
 - b. Erico International Corporation: www.erico.com/#sle.
 - c. O-Z/Gedney, a brand of Emerson Electric Co: www.emerson.com/#sle.
 - d. Thomas & Betts Corporation: www.tnb.com/#sle.
- D. Metal Channel (Strut) Framing Systems: Factory-fabricated continuous-slot metal channel (strut) and associated fittings, accessories, and hardware required for field-assembly of supports.
 1. Comply with MFMA-4.
 2. Channel (Strut) Used as Raceway (only where specifically indicated): Listed and labeled as complying with UL 5B.
 3. Channel Material:
 4. Minimum Channel Thickness: Steel sheet, 12 gage, 0.1046 inch.
 5. Minimum Channel Dimensions: 1-5/8 inch width by 13/16 inch height.
 6. Manufacturers:
 - a. Cooper B-Line, a division of Eaton Corporation: www.cooperindustries.com/#sle.
 - b. Thomas & Betts Corporation: www.tnb.com/#sle.
 - c. Unistrut, a brand of Atkore International Inc: www.unistrut.com/#sle.
 - d. Substitutions: See Section 016000 - Product Requirements.
- E. Hanger Rods: Threaded zinc-plated steel unless otherwise indicated.
- F. Anchors and Fasteners:
 1. Unless otherwise indicated and where not otherwise restricted, use the anchor and fastener types indicated for the specified applications.
 2. Concrete: Use preset concrete inserts, expansion anchors, or screw anchors.
 3. Steel: Use beam clamps, machine bolts, or welded threaded studs.
 4. Sheet Metal: Use sheet metal screws.
 5. Preset Concrete Inserts: Continuous metal channel (strut) and spot inserts specifically designed to be cast in concrete ceilings, walls, and floors.
 - a. Comply with MFMA-4.
 - b. Channel Material: Use galvanized steel.

- c. Manufacturer: Same as manufacturer of metal channel (strut) framing system.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Perform work in accordance with NECA 1 (general workmanship).
- C. Provide independent support from building structure. Do not provide support from piping, ductwork, or other systems.
- D. Unless specifically indicated or approved by Engineer, do not provide support from suspended ceiling support system or ceiling grid.
- E. Unless specifically indicated or approved by Engineer, do not provide support from roof deck.
- F. Do not penetrate or otherwise notch or cut structural members without approval of Structural Engineer.
- G. Provide required vibration isolation and/or seismic controls in accordance with Section 260548.
- H. Equipment Support and Attachment:
 - 1. Use metal fabricated supports or supports assembled from metal channel (strut) to support equipment as required.
 - 2. Use metal channel (strut) secured to studs to support equipment surface-mounted on hollow stud walls when wall strength is not sufficient to resist pull-out.
 - 3. Use metal channel (strut) to support surface-mounted equipment in wet or damp locations to provide space between equipment and mounting surface.
 - 4. Unless otherwise indicated, mount floor-mounted equipment on properly sized 3 inch high concrete pad constructed in accordance with Section 033000.
 - 5. Securely fasten floor-mounted equipment. Do not install equipment such that it relies on its own weight for support.
- I. Preset Concrete Inserts: Use manufacturer provided closure strips to inhibit concrete seepage during concrete pour.
- J. Secure fasteners according to manufacturer's recommended torque settings.
- K. Remove temporary supports.

3.02 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Inspect support and attachment components for damage and defects.
- C. Repair cuts and abrasions in galvanized finishes using zinc-rich paint recommended by manufacturer. Replace components that exhibit signs of corrosion.
- D. Correct deficiencies and replace damaged or defective support and attachment components.

END OF SECTION

**SECTION 260533.13
CONDUIT FOR ELECTRICAL SYSTEMS**

PART 1 GENERAL

4.01 SECTION INCLUDES

- A. Galvanized steel rigid metal conduit (RMC).
- B. Flexible metal conduit (FMC).
- C. Liquidtight flexible metal conduit (LFMC).
- D. Electrical metallic tubing (EMT).
- E. Rigid polyvinyl chloride (PVC) conduit.
- F. Liquidtight flexible nonmetallic conduit (LFNC).
- G. Conduit fittings.
- H. Accessories.

4.02 RELATED REQUIREMENTS

- A. Section 078400 - Firestopping.
- B. Section 260526 - Grounding and Bonding for Electrical Systems.
- C. Section 260529 - Hangers and Supports for Electrical Systems.

4.03 REFERENCE STANDARDS

- A. ANSI C80.1 - American National Standard for Electrical Rigid Steel Conduit (ERSC); 2015.
- B. ANSI C80.3 - American National Standard for Electrical Metallic Tubing -- Steel (EMT-S); 2015.
- C. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- D. NECA 101 - Standard for Installing Steel Conduits (Rigid, IMC, EMT); 2013.
- E. NECA 111 - Standard for Installing Nonmetallic Raceways (RNC, ENT, LFNC); 2003.
- F. NEMA FB 1 - Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit, Electrical Metallic Tubing, and Cable; 2014.
- G. NEMA TC 2 - Electrical Polyvinyl Chloride (PVC) Conduit; 2013.
- H. NEMA TC 3 - Polyvinyl Chloride (PVC) Fittings for Use with Rigid PVC Conduit and Tubing; 2016.
- I. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- J. UL 1 - Flexible Metal Conduit; Current Edition, Including All Revisions.
- K. UL 6 - Electrical Rigid Metal Conduit-Steel; Current Edition, Including All Revisions.
- L. UL 360 - Liquid-Tight Flexible Steel Conduit; Current Edition, Including All Revisions.
- M. UL 514B - Conduit, Tubing, and Cable Fittings; Current Edition, Including All Revisions.
- N. UL 651 - Schedule 40, 80, Type EB and A Rigid PVC Conduit and Fittings; Current Edition, Including All Revisions.
- O. UL 797 - Electrical Metallic Tubing-Steel; Current Edition, Including All Revisions.
- P. UL 1203 - Explosion-Proof and Dust-Ignition-Proof Electrical Equipment for Use in Hazardous (Classified) Locations; Current Edition, Including All Revisions.
- Q. UL 1660 - Liquid-Tight Flexible Nonmetallic Conduit; Current Edition, Including All Revisions.

4.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:

1. Coordinate minimum sizes of conduits with the actual conductors to be installed, including adjustments for conductor sizes increased for voltage drop.
 2. Coordinate the arrangement of conduits with structural members, ductwork, piping, equipment and other potential conflicts installed under other sections or by others.
 3. Verify exact conduit termination locations required for boxes, enclosures, and equipment installed under other sections or by others.
 4. Coordinate the work with other trades to provide roof penetrations that preserve the integrity of the roofing system and do not void the roof warranty.
- B. Sequencing:
1. Do not begin installation of conductors and cables until installation of conduit is complete between outlet, junction and splicing points.

4.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements for submittals procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for conduits and fittings.
- C. Project Record Documents: Record actual routing for conduits installed underground, conduits embedded within concrete slabs, and conduits 2 inch (53 mm) trade size and larger.

4.06 QUALITY ASSURANCE

- A. Comply with requirements of NFPA 70.

PART 2 PRODUCTS

5.01 CONDUIT APPLICATIONS

- A. Do not use conduit and associated fittings for applications other than as permitted by NFPA 70 and product listing.
- B. Unless otherwise indicated and where not otherwise restricted, use the conduit types indicated for the specified applications. Where more than one listed application applies, comply with the most restrictive requirements. Where conduit type for a particular application is not specified, use galvanized steel rigid metal conduit.
- C. Underground:
 1. Under Slab on Grade: Use galvanized steel rigid metal conduit or rigid PVC conduit.
 2. Exterior, Direct-Buried: Use galvanized steel rigid metal conduit or rigid PVC conduit.
 3. Where rigid polyvinyl (PVC) conduit is provided, transition to galvanized steel rigid metal conduit where emerging from underground.
- D. Concealed Above Accessible Ceilings: Use galvanized steel rigid metal conduit or electrical metallic tubing (EMT).
- E. Interior, Damp or Wet Locations: Use galvanized steel rigid metal conduit.
- F. Exposed, Interior, Not Subject to Physical Damage: Use galvanized steel rigid metal conduit or electrical metallic tubing (EMT).
- G. Exposed, Interior, Subject to Physical Damage: Use galvanized steel rigid metal conduit.
- H. Exposed, Exterior: Use galvanized steel rigid metal conduit or electrical metallic tubing (EMT)..
- I. Connections to Vibrating Equipment:
 1. Dry Locations: Use flexible metal conduit.
 2. Damp, Wet, or Corrosive Locations: Use liquidtight flexible metal conduit.
 3. Maximum Length: 6 feet unless otherwise indicated.
 4. Vibrating equipment includes, but is not limited to:
 - a. Transformers.
 - b. Motors.

5.02 CONDUIT REQUIREMENTS

- A. Existing Work: Where existing conduits are indicated to be reused, they may be reused only where they comply with specified requirements, are free from corrosion, and integrity is verified by pulling a mandrel through them.
- B. Provide all conduit, fittings, supports, and accessories required for a complete raceway system.
- C. Provide products listed, classified, and labeled as suitable for the purpose intended.
- D. Minimum Conduit Size, Unless Otherwise Indicated:
 - 1. Branch Circuits: 1/2 inch (16 mm) trade size.
 - 2. Branch Circuit Homeruns: 3/4 inch (21 mm) trade size.
 - 3. Underground, Interior: 3/4 inch (21 mm) trade size.
 - 4. Underground, Exterior: 1 inch (27 mm) trade size.
- E. Where conduit size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.

5.03 GALVANIZED STEEL RIGID METAL CONDUIT (RMC)

- A. Manufacturers:
 - 1. Allied Tube & Conduit: www.alliedeg.com/#sle.
 - 2. Republic Conduit: www.republic-conduit.com/#sle.
 - 3. Wheatland Tube, a Division of Zekelman Industries: www.wheatland.com/#sle.
- B. Description: NFPA 70, Type RMC galvanized steel rigid metal conduit complying with ANSI C80.1 and listed and labeled as complying with UL 6.
- C. Fittings:
 - 1. Manufacturers:
 - a. Bridgeport Fittings Inc: www.bptfittings.com/#sle.
 - b. O-Z/Gedney, a brand of Emerson Electric Co: www.emerson.com/#sle.
 - c. Thomas & Betts Corporation: www.tnb.com/#sle.
 - 2. Non-Hazardous Locations: Use fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
 - 3. Hazardous (Classified) Locations: Use fittings listed and labeled as complying with UL 1203 for the classification of the installed location.
 - 4. Material: Use steel or malleable iron.
 - 5. Connectors and Couplings: Use threaded type fittings only. Threadless set screw and compression (gland) type fittings are not permitted.

5.04 FLEXIBLE METAL CONDUIT (FMC)

- A. Manufacturers:
 - 1. AFC Cable Systems, Inc: www.afcweb.com/#sle.
 - 2. Electri-Flex Company: www.electriflex.com/#sle.
 - 3. International Metal Hose: www.metalhose.com/#sle.
- B. Description: NFPA 70, Type FMC standard wall steel flexible metal conduit listed and labeled as complying with UL 1, and listed for use in classified firestop systems to be used.
- C. Fittings:
 - 1. Manufacturers:
 - a. Bridgeport Fittings Inc: www.bptfittings.com/#sle.
 - b. O-Z/Gedney, a brand of Emerson Electric Co: www.emerson.com/#sle.
 - c. Thomas & Betts Corporation: www.tnb.com/#sle.
 - 2. Description: Fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
 - 3. Material: Use steel or malleable iron.

5.05 LIQUIDTIGHT FLEXIBLE METAL CONDUIT (LFMC)

- A. Manufacturers:

1. AFC Cable Systems, Inc: www.afcweb.com/#sle.
 2. Electri-Flex Company: www.electriflex.com/#sle.
 3. International Metal Hose: www.metalhose.com/#sle.
- B. Description: NFPA 70, Type LFMC polyvinyl chloride (PVC) jacketed steel flexible metal conduit listed and labeled as complying with UL 360.
- C. Fittings:
1. Manufacturers:
 - a. Bridgeport Fittings Inc: www.bptfittings.com/#sle.
 - b. O-Z/Gedney, a brand of Emerson Electric Co: www.emerson.com/#sle.
 - c. Thomas & Betts Corporation: www.tnb.com/#sle.
 2. Description: Fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
 3. Material: Use steel or malleable iron.

5.06 ELECTRICAL METALLIC TUBING (EMT)

- A. Manufacturers:
1. Allied Tube & Conduit: www.alliedeg.com/#sle.
 2. Republic Conduit: www.republic-conduit.com/#sle.
 3. Wheatland Tube, a Division of Zekelman Industries: www.wheatland.com/#sle.
- B. Description: NFPA 70, Type EMT steel electrical metallic tubing complying with ANSI C80.3 and listed and labeled as complying with UL 797.
- C. Fittings:
1. Manufacturers:
 - a. Bridgeport Fittings Inc: www.bptfittings.com/#sle.
 - b. O-Z/Gedney, a brand of Emerson Electric Co: www.emerson.com/#sle.
 - c. Thomas & Betts Corporation: www.tnb.com/#sle.
 2. Description: Fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
 3. Material: Use steel or malleable iron.
 4. Connectors and Couplings: Use compression (gland) or set-screw type.
 - a. Do not use indenter type connectors and couplings.
 5. Damp or Wet Locations (where permitted): Use fittings listed for use in wet locations.

5.07 RIGID POLYVINYL CHLORIDE (PVC) CONDUIT

- A. Manufacturers:
1. Cantex Inc: www.cantexinc.com/#sle.
 2. Carlon, a brand of Thomas & Betts Corporation: www.carlon.com/#sle.
 3. JM Eagle: www.jmeagle.com/#sle.
- B. Description: NFPA 70, Type PVC rigid polyvinyl chloride conduit complying with NEMA TC 2 and listed and labeled as complying with UL 651; Schedule 40 unless otherwise indicated, Schedule 80 where subject to physical damage; rated for use with conductors rated 90 degrees C.
- C. Fittings:
1. Manufacturer: Same as manufacturer of conduit to be connected.
 2. Description: Fittings complying with NEMA TC 3 and listed and labeled as complying with UL 651; material to match conduit.

5.08 LIQUIDTIGHT FLEXIBLE NONMETALLIC CONDUIT (LFNC)

- A. Description: NFPA 70, Type LFNC liquidtight flexible nonmetallic conduit listed and labeled as complying with UL 1660.
- B. Fittings:
1. Manufacturer: Same as manufacturer of conduit to be connected.

2. Description: Fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B; suitable for the type of conduit to be connected.

5.09 ACCESSORIES

- A. Conduit Joint Compound: Corrosion-resistant, electrically conductive; suitable for use with the conduit to be installed.
- B. Solvent Cement for PVC Conduit and Fittings: As recommended by manufacturer of conduit and fittings to be installed.
- C. Firestop Sleeves: Listed; provide as required to preserve fire resistance rating of building elements.

PART 3 EXECUTION

6.01 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Perform work in accordance with NECA 1 (general workmanship).
- C. Install galvanized steel rigid metal conduit (RMC) in accordance with NECA 101.
- D. Install rigid polyvinyl chloride (PVC) conduit in accordance with NECA 111.
- E. Install liquidtight flexible nonmetallic conduit (LFNC) in accordance with NECA 111.
- F. Conduit Routing:
 1. Conduits in the following areas may be exposed, unless otherwise indicated:
 - a. Electrical rooms.
 - b. Mechanical equipment rooms.
 - c. Within joists in areas with no ceiling.
 2. Unless otherwise approved, do not route conduits exposed:
 - a. Across floors.
 - b. Across building exterior surfaces.
 3. Conduits installed underground or embedded in concrete may be routed in the shortest possible manner unless otherwise indicated. Route all other conduits parallel or perpendicular to building structure and surfaces, following surface contours where practical.
 4. Arrange conduit to maintain adequate headroom, clearances, and access.
 5. Arrange conduit to provide no more than the equivalent of four 90 degree bends between pull points.
 6. Group parallel conduits in the same area together on a common rack.
- G. Conduit Support:
 1. Secure and support conduits in accordance with NFPA 70 and Section 260529 using suitable supports and methods approved by the authority having jurisdiction.
 2. Provide independent support from building structure. Do not provide support from piping, ductwork, or other systems.
- H. Connections and Terminations:
 1. Use approved zinc-rich paint or conduit joint compound on field-cut threads of galvanized steel conduits prior to making connections.
 2. Where two threaded conduits must be joined and neither can be rotated, use three-piece couplings or split couplings. Do not use running threads.
 3. Use suitable adapters where required to transition from one type of conduit to another.
 4. Provide drip loops for liquidtight flexible conduit connections to prevent drainage of liquid into connectors.
 5. Terminate threaded conduits in boxes and enclosures using threaded hubs or double lock nuts for dry locations and raintight hubs for wet locations.
 6. Provide insulating bushings or insulated throats at all conduit terminations to protect conductors.

7. Secure joints and connections to provide maximum mechanical strength and electrical continuity.
- I. Penetrations:
 1. Do not penetrate or otherwise notch or cut structural members, including footings and grade beams, without approval of Structural Engineer.
 2. Make penetrations perpendicular to surfaces unless otherwise indicated.
 3. Provide sleeves for penetrations as indicated or as required to facilitate installation. Set sleeves flush with exposed surfaces unless otherwise indicated or required.
 4. Conceal bends for conduit risers emerging above ground.
 5. Seal interior of conduits entering the building from underground at first accessible point to prevent entry of moisture and gases.
 6. Where conduits penetrate waterproof membrane, seal as required to maintain integrity of membrane.
 7. Make penetrations for roof-mounted equipment within associated equipment openings and curbs where possible to minimize roofing system penetrations. Where penetrations are necessary, seal as indicated or as required to preserve integrity of roofing system and maintain roof warranty. Include proposed locations of penetrations and methods for sealing with submittals.
 8. Install firestopping to preserve fire resistance rating of partitions and other elements, using materials and methods specified in Section 078400.
- J. Conduit Movement Provisions: Where conduits are subject to movement, provide expansion and expansion/deflection fittings to prevent damage to enclosed conductors or connected equipment. This includes, but is not limited to:
 1. Where conduits cross structural joints intended for expansion, contraction, or deflection.
 2. Where calculated in accordance with NFPA 70 for rigid polyvinyl chloride (PVC) conduit installed above ground to compensate for thermal expansion and contraction.
 3. Where conduits are subject to earth movement by settlement or frost.
- K. Condensation Prevention: Where conduits cross barriers between areas of potential substantial temperature differential, provide sealing fitting or approved sealing compound at an accessible point near the penetration to prevent condensation. This includes, but is not limited to:
 1. Where conduits pass from outdoors into conditioned interior spaces.
 2. Where conduits pass from unconditioned interior spaces into conditioned interior spaces.
 3. Where conduits penetrate coolers or freezers.
- L. Provide grounding and bonding in accordance with Section 260526.

6.02 FIELD QUALITY CONTROL

- A. See Section 014000 - Quality Requirements, for additional requirements.
- B. Repair cuts and abrasions in galvanized finishes using zinc-rich paint recommended by manufacturer. Replace components that exhibit signs of corrosion.
- C. Correct deficiencies and replace damaged or defective conduits.

END OF SECTION

SECTION 260553
IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

7.01 SECTION INCLUDES

- A. Electrical identification requirements.
- B. Identification nameplates and labels.
- C. Wire and cable markers.

7.02 RELATED REQUIREMENTS

- A. Section 260519 - Low-Voltage Electrical Power Conductors and Cables: Color coding for power conductors and cables 600 V and less; vinyl color coding electrical tape.

PART 2 PRODUCTS

8.01 IDENTIFICATION REQUIREMENTS

- A. Identification for Equipment:
 - 1. Use identification nameplate to identify each piece of electrical distribution and control equipment and associated sections, compartments, and components.
 - a. Transformers:
 - 1) Identify kVA rating.
 - 2) Identify voltage and phase for primary and secondary.
 - 3) Identify power source and circuit number. Include location when not within sight of equipment.
 - 4) Identify load(s) served..
 - 2. Use identification label on inside of door at each fused switch to identify required NEMA fuse class and size.
- B. Identification for Conductors and Cables:
 - 1. Color Coding for Power Conductors 600 V and Less: Comply with Section 260519.
 - 2. Use identification nameplate or identification label to identify color code for ungrounded and grounded power conductors inside door or enclosure at each piece of feeder or branch-circuit distribution equipment when premises has feeders or branch circuits served by more than one nominal voltage system.
 - 3. Use wire and cable markers to identify circuit number or other designation indicated for power, control, and instrumentation conductors and cables at the following locations:

8.02 IDENTIFICATION NAMEPLATES AND LABELS

- A. Identification Nameplates:
 - 1. Manufacturers:
 - a. Brimar Industries, Inc: www.brimar.com/#sle.
 - b. Kolbi Pipe Marker Co: www.kolbipipemarkers.com/#sle.
 - c. Seton Identification Products: www.seton.com/#sle.
 - 2. Materials:
 - a. Indoor Clean, Dry Locations: Use plastic nameplates.
 - b. Outdoor Locations: Use plastic, stainless steel, or aluminum nameplates suitable for exterior use.
 - 3. Plastic Nameplates: Two-layer or three-layer laminated acrylic or electrically non-conductive phenolic with beveled edges; minimum thickness of 1/16 inch; engraved text.
 - 4. Stainless Steel Nameplates: Minimum thickness of 1/32 inch; engraved or laser-etched text.
 - 5. Aluminum Nameplates: Anodized; minimum thickness of 1/32 inch; engraved or laser-etched text.
 - 6. Mounting Holes for Mechanical Fasteners: Two, centered on sides for sizes up to 1 inch high; Four, located at corners for larger sizes.

- B. Identification Labels:
 - 1. Materials: Use self-adhesive laminated plastic labels; UV, chemical, water, heat, and abrasion resistant.
 - 2. Text: Use factory pre-printed or machine-printed text. Do not use handwritten text unless otherwise indicated.

8.03 WIRE AND CABLE MARKERS

- A. Manufacturers:
 - 1. Brady Corporation: www.bradyid.com/#sle.
 - 2. HellermannTyton: www.hellermannityton.com/#sle.
 - 3. Panduit Corp: www.panduit.com/#sle.
- B. Markers for Conductors and Cables: Use wrap-around self-adhesive vinyl cloth, wrap-around self-adhesive vinyl self-laminating, heat-shrink sleeve, plastic sleeve, plastic clip-on, or vinyl split sleeve type markers suitable for the conductor or cable to be identified.
- C. Markers for Conductor and Cable Bundles: Use plastic marker tags secured by nylon cable ties.
- D. Legend: Power source and circuit number or other designation indicated.
- E. Text: Use factory pre-printed or machine-printed text, all capitalized unless otherwise indicated.
- F. Minimum Text Height: 1/8 inch.
- G. Color: Black text on white background unless otherwise indicated.

PART 3 EXECUTION

9.01 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Install identification products to be plainly visible for examination, adjustment, servicing, and maintenance. Unless otherwise indicated, locate products as follows:
 - 1. Surface-Mounted Equipment: Enclosure front.
 - 2. Flush-Mounted Equipment: Inside of equipment door.
 - 3. Free-Standing Equipment: Enclosure front; also enclosure rear for equipment with rear access.
 - 4. Elevated Equipment: Legible from the floor or working platform.
 - 5. Interior Components: Legible from the point of access.
 - 6. Conductors and Cables: Legible from the point of access.
- C. Install identification products centered, level, and parallel with lines of item being identified.
- D. Secure nameplates to exterior surfaces of enclosures using stainless steel screws and to interior surfaces using self-adhesive backing or epoxy cement.
- E. Install self-adhesive labels and markers to achieve maximum adhesion, with no bubbles or wrinkles and edges properly sealed.

END OF SECTION

**SECTION 262200
LOW-VOLTAGE TRANSFORMERS**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. General purpose transformers.

1.02 RELATED REQUIREMENTS

- A. Section 033000 - Cast-in-Place Concrete: Concrete equipment pads.
- B. Section 260526 - Grounding and Bonding for Electrical Systems.
- C. Section 260529 - Hangers and Supports for Electrical Systems.
- D. Section 260533.13 - Conduit for Electrical Systems: Flexible conduit connections.
- E. Section 260548 - Vibration and Seismic Controls for Electrical Systems.
 - 1. Includes requirements for the seismic qualification of equipment specified in this section.
- F. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

1.03 REFERENCE STANDARDS

- A. 10 CFR 431, Subpart K - Energy Efficiency Program for Certain Commercial and Industrial Equipment - Distribution Transformers; Current Edition.
- B. IEEE C57.94 - IEEE Recommended Practice for Installation, Application, Operation, and Maintenance of Dry-Type Distribution and Power Transformers; 2015.
- C. IEEE C57.96 - IEEE Standard Guide for Loading Dry-Type Distribution and Power Transformers; 2013.
- D. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- E. NECA 409 - Standard for Installing and Maintaining Dry-Type Transformers; 2015.
- F. NEMA ST 20 - Dry-Type Transformers for General Applications; 2014.
- G. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2020.
- H. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- I. UL 506 - Standard for Specialty Transformers; Current Edition, Including All Revisions.
- J. UL 1561 - Standard for Dry-Type General Purpose and Power Transformers; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Include voltage, kVA, impedance, tap configurations, insulation system class and rated temperature rise, efficiency, sound level, enclosure ratings, outline and support point dimensions, weight, required clearances, service condition requirements, and installed features.
- C. Shop Drawings: Provide dimensioned plan and elevation views of transformers and adjacent equipment with all required clearances indicated.
 - 1. Identify mounting conditions required for equipment seismic qualification.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Basis of design: Schneider Electric; Square D Products[<>]: www.schneider-electric.us/#sle.
- B. ABB/GE: www.geindustrial.com/#sle.
- C. Eaton Corporation: www.eaton.com/#sle.

- D. Siemens Industry, Inc: www.usa.siemens.com/#sle.
- E. Substitutions: See Section 016000 - Product Requirements.

2.02 TRANSFORMERS - GENERAL REQUIREMENTS

- A. Description: Factory-assembled, dry type transformers for 60 Hz operation designed and manufactured in accordance with NEMA ST 20 and listed, classified, and labeled as suitable for the purpose intended.
- B. Seismic Qualification: Provide transformers suitable for application under seismic design criteria in accordance with Section 260548 where required. Include certification of compliance with submittals.
- C. Unless noted otherwise, transformer ratings indicated are for continuous loading according to IEEE C57.96 under the following service conditions:
 - 1. Altitude: Less than 3,300 feet.
 - 2. Ambient Temperature:
 - a. Greater than 10 kVA: Not exceeding 104 degrees F.
 - b. Less than 10 kVA: Not exceeding 77 degrees F.
- D. Core: High grade, non-aging silicon steel with high magnetic permeability and low hysteresis and eddy current losses. Keep magnetic flux densities substantially below saturation point, even at 10 percent primary overvoltage. Tightly clamp core laminations to prevent plate movement and maintain consistent pressure throughout core length.
- E. Impregnate core and coil assembly with non-hydroscopic thermo-setting varnish to effectively seal out moisture and other contaminants.
- F. Basic Impulse Level: 10 kV.
- G. Ground core and coil assembly to enclosure by means of a visible flexible copper grounding strap.
- H. Isolate core and coil from enclosure using vibration-absorbing mounts.
- I. Nameplate: Include transformer connection data, ratings, wiring diagrams, and overload capacity based on rated winding temperature rise.

2.03 GENERAL PURPOSE TRANSFORMERS

- A. Description: Self-cooled, two winding transformers listed and labeled as complying with UL 506 or UL 1561; ratings as indicated on the drawings.
- B. Insulation System and Allowable Average Winding Temperature Rise:
 - 1. 15 kVA and Larger: Class 220 degrees C insulation system with 150 degrees C average winding temperature rise.
- C. Coil Conductors: Continuous copper or aluminum windings with terminations brazed or welded.
- D. Winding Taps:
 - 1. 500 kVA and Larger: Two 2.5 percent full capacity primary taps above and two 2.5 percent full capacity primary taps below rated voltage.
- E. Energy Efficiency: Comply with 10 CFR 431, Subpart K.
- F. Sound Levels: Standard sound levels complying with NEMA ST 20
- G. Mounting Provisions:
 - 1. Larger than 75 kVA: Suitable for floor mounting.
- H. Transformer Enclosure: Comply with NEMA ST 20.
 - 1. Environment Type per NEMA 250: Unless otherwise indicated, as specified for the following installation locations:
 - a. Outdoor locations: Type 3R.
 - 2. Construction: Steel.
 - a. 15 kVA and Larger: Ventilated.

3. Finish: Manufacturer's standard grey, suitable for outdoor installations.
4. Provide lifting eyes or brackets.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Perform work in accordance with NECA 1 (general workmanship).
- B. Install products in accordance with manufacturer's instructions.
- C. Install transformers in accordance with NECA 409 and IEEE C57.94.
- D. Use flexible conduit, under the provisions of Section 260533.13, 2 feet minimum length, for connections to transformer case. Make conduit connections to side panel of enclosure.
- E. Arrange equipment to provide minimum clearances as specified on transformer nameplate and in accordance with manufacturer's instructions and NFPA 70.
- F. Install transformers plumb and level.
- G. Transformer Support:
 1. Provide required support and attachment in accordance with Section 260529, where not furnished by transformer manufacturer.
 2. Use integral transformer flanges, accessory brackets furnished by manufacturer, or field-fabricated supports to support wall-mounted transformers.
 3. Unless otherwise indicated, mount floor-mounted transformers on properly sized 3 inch high concrete pad constructed in accordance with Section 033000.
- H. Provide grounding and bonding in accordance with Section 260526.
- I. Remove shipping braces and adjust bolts that attach the core and coil mounting bracket to the enclosure according to manufacturer's recommendations in order to reduce audible noise transmission.
- J. Where not factory-installed, install lugs sized as required for termination of conductors as indicated.

3.02 ADJUSTING

- A. Measure primary and secondary voltages and make appropriate tap adjustments.
- B. Adjust tightness of mechanical and electrical connections to manufacturer's recommended torque settings.

END OF SECTION

**SECTION 262813
FUSES**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Fuses.

1.02 RELATED REQUIREMENTS

- A. Section 262816.16 - Enclosed Switches: Fusible switches.

1.03 REFERENCE STANDARDS

- A. NEMA FU 1 - Low Voltage Cartridge Fuses; 2012.
- B. UL 248-1 - Low-Voltage Fuses - Part 1: General Requirements; Current Edition, Including All Revisions.
- C. UL 248-10 - Low-Voltage Fuses - Part 10: Class L Fuses; Current Edition, Including All Revisions.
- D. UL 248-12 - Low-Voltage Fuses - Part 12: Class R Fuses; Current Edition, Including All Revisions.

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordination:
 - 1. Coordinate fuse clips furnished in equipment provided under other sections for compatibility with indicated fuses.
 - a. Fusible Enclosed Switches: See Section 262816.16.
 - 2. Coordinate fuse requirements according to manufacturer's recommendations and nameplate data for actual equipment to be installed.
 - 3. Notify Engineer of any conflicts with or deviations from Contract Documents. Obtain direction before proceeding with work.

1.05 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's standard data sheets including voltage and current ratings, interrupting ratings, time-current curves, and current limitation curves.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Bussmann, a division of Eaton Corporation: www.cooperindustries.com/#sle.
- B. Littelfuse, Inc: www.littelfuse.com/#sle.
- C. Mersen: ep-us.mersen.com/#sle.
- D. Substitutions: See Section 016000 - Product Requirements.

2.02 APPLICATIONS

- A. Feeders:
 - 1. Fusible Switches up to 600 Amperes: Class RK1, time-delay.
 - 2. Fusible Switches Larger Than 600 Amperes: Class L, time-delay.
- B. General Purpose Branch Circuits: Class RK1, time-delay.

2.03 FUSES

- A. Provide products listed, classified, and labeled as suitable for the purpose intended.
- B. Unless specifically indicated to be excluded, provide fuses for all fusible equipment as required for a complete operating system.
- C. Provide fuses of the same type, rating, and manufacturer within the same switch.

- D. Comply with UL 248-1.
- E. Unless otherwise indicated, provide cartridge type fuses complying with NEMA FU 1, Class and ratings as indicated.
- F. Voltage Rating: Suitable for circuit voltage.
- G. Class R Fuses: Comply with UL 248-12.
- H. Class L Fuses: Comply with UL 248-10.
- I. Selectivity: Where the requirement for selectivity is indicated, furnish products as required to achieve selective coordination.
- J. Provide the following accessories where indicated or where required to complete installation:
 - 1. Fuseholders: Compatible with indicated fuses.
 - 2. Fuse Reducers: For adapting indicated fuses to permit installation in switch designed for fuses with larger ampere ratings.

2.04 SPARE FUSES:

- A. Provide one complete set of spare fuses to the owner of each type and size installed on the project.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Do not install fuses until circuits are ready to be energized.
- B. Install fuses with label oriented such that manufacturer, type, and size are easily read.

END OF SECTION

**SECTION 262816.16
ENCLOSED SWITCHES**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Enclosed safety switches.

1.02 RELATED REQUIREMENTS

- A. Section 260526 - Grounding and Bonding for Electrical Systems.
- B. Section 260529 - Hangers and Supports for Electrical Systems.
- C. Section 260548 - Vibration and Seismic Controls for Electrical Systems.
- D. Section 260553 - Identification for Electrical Systems: Identification products and requirements.
- E. Section 262813 - Fuses.

1.03 REFERENCE STANDARDS

- A. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2015.
- B. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2020.
- C. NEMA KS 1 - Heavy Duty Enclosed and Dead-Front Switches (600 Volts Maximum); 2013.
- D. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- E. UL 50 - Enclosures for Electrical Equipment, Non-Environmental Considerations; Current Edition, Including All Revisions.
- F. UL 50E - Enclosures for Electrical Equipment, Environmental Considerations; Current Edition, Including All Revisions.
- G. UL 98 - Enclosed and Dead-Front Switches; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide manufacturer's standard catalog pages and data sheets for enclosed switches and other installed components and accessories.
- C. Manufacturer's equipment seismic qualification certification.
- D. Project Record Documents: Record actual locations of enclosed switches.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. ABB/GE: www.geindustrial.com/#sle.
- B. Eaton Corporation: www.eaton.com/#sle.
- C. Schneider Electric; Square D Products: www.schneider-electric.us/#sle.
- D. Siemens Industry, Inc: www.usa.siemens.com/#sle.
- E. Substitutions: See Section 016000 - Product Requirements.

2.02 ENCLOSED SAFETY SWITCHES

- A. Description: Quick-make, quick-break enclosed safety switches listed and labeled as complying with UL 98; heavy or general duty as indicated; ratings, configurations, and features as indicated on the drawings.
- B. Provide products listed, classified, and labeled as suitable for the purpose intended.
- C. Seismic Qualification: Provide enclosed safety switches suitable for application under the seismic design criteria specified in Section 260548 where required. Include certification of compliance with submittals.

- D. Unless otherwise indicated, provide products suitable for continuous operation under the following service conditions:
 - 1. Altitude: Less than 6,600 feet.
 - 2. Ambient Temperature: Between -22 degrees F and 104 degrees F.
- E. Horsepower Rating: Suitable for connected load.
- F. Voltage Rating: Suitable for circuit voltage.
- G. Short Circuit Current Rating:
 - 1. Provide enclosed safety switches, when protected by the fuses or supply side overcurrent protective devices to be installed, with listed short circuit current rating not less than the existing rating of the electrical system.
- H. Provide with switch blade contact position that is visible when the cover is open.
- I. Fuse Clips for Fusible Switches: As required to accept fuses indicated.
- J. Conductor Terminations: Suitable for use with the conductors to be installed.
- K. Provide solidly bonded equipment ground bus in each enclosed safety switch, with a suitable lug for terminating each equipment grounding conductor.
- L. Enclosures: Comply with NEMA 250, and list and label as complying with UL 50 and UL 50E.
 - 1. Environment Type per NEMA 250: Unless otherwise indicated, as specified for the following installation locations:
 - a. Indoor Clean, Dry Locations: Type 1.
 - b. Outdoor Locations: Type 3R.
 - 2. Finish for Painted Steel Enclosures: Manufacturer's standard, factory applied grey unless otherwise indicated.
- M. Provide safety interlock to prevent opening the cover with the switch in the ON position with capability of overriding interlock for testing purposes.
- N. Heavy Duty Switches:
 - 1. Comply with NEMA KS 1.
 - 2. Conductor Terminations:
 - a. Provide mechanical lugs unless otherwise indicated.
 - b. Provide compression lugs where indicated.
 - c. Lug Material: Aluminum, suitable for terminating aluminum or copper conductors.
 - 3. Provide externally operable handle with means for locking in the OFF position, capable of accepting three padlocks.
- O. General Duty Switches:
 - 1. Conductor Terminations:
 - a. Provide mechanical lugs.
 - b. Lug Material: Aluminum, suitable for terminating aluminum or copper conductors.
 - 2. Provide externally operable handle with means for locking in the OFF position, capable of accepting two padlocks.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field measurements are as indicated.
- B. Verify that the ratings of the enclosed switches are consistent with the indicated requirements.
- C. Verify that mounting surfaces are ready to receive enclosed safety switches.
- D. Verify that conditions are satisfactory for installation prior to starting work.

3.02 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Perform work in accordance with NECA 1 (general workmanship).

- C. Arrange equipment to provide minimum clearances in accordance with manufacturer's instructions and NFPA 70.
- D. Provide required support and attachment in accordance with Section 260529.
- E. Install enclosed switches plumb.
- F. Except where indicated to be mounted adjacent to the equipment they supply, mount enclosed switches such that the highest position of the operating handle does not exceed 79 inches above the floor or working platform.
- G. Provide grounding and bonding in accordance with Section 260526.
- H. Provide fuses complying with Section 262813 for fusible switches as indicated or as required by equipment manufacturer's recommendations.
- I. Identify enclosed switches in accordance with Section 260553.

3.03 ADJUSTING

- A. Adjust tightness of mechanical and electrical connections to manufacturer's recommended torque settings.

3.04 CLEANING

- A. Clean dirt and debris from switch enclosures and components according to manufacturer's instructions.
- B. Repair scratched or marred exterior surfaces to match original factory finish.

END OF SECTION

**SECTION 323113
CHAIN LINK FENCES AND GATES**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Chain link fence design and installation, including all components necessary for installation.

1.02 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on fabric, posts, accessories, fittings and hardware.
- C. Shop Drawings: Indicate plan layout, spacing of components, post foundation dimensions, hardware anchorage, and schedule of components. See CLFMI CLF-SFR0111 for planning and design recommendations.

1.03 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section, with not less than three years of documented experience.
- B. Fence Installer: Company with demonstrated successful experience installing similar projects and products, with not less than five years of documented experience.

1.04 WARRANTY

- A. See Section 017800 - Closeout Submittals, for additional warranty requirements.

PART 2 PRODUCTS

2.01 COMPONENTS

- A. Contractor shall provide a complete and operable chain link fence enclosure with gates. See drawing S001 for additional general notes and requirements. See drawing S401 for fence layout and concrete footing locations. See drawings S501 and S502 for fence details. All components and hardware necessary for a complete installation may not be shown on the "S" drawing sheets. Contractor shall provide complete shop drawings showing all components and hardware necessary for a complete installation of the fence and gates. Notes on the "S" drawings related to the fence scope that say "by others" are not to be construed as scope outside of the contract, but are to be construed as scope to be designed and provided by the fence contractor.
- B. Fabric: 1 inch diamond mesh interwoven wire, 6 gauge, 0.1920 inch thick, top selvage knuckle end closed, bottom selvage twisted tight.

END OF SECTION