

SECTION 02 41 00

DEMOLITION

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Removal of designated construction.
- B. Identification of utilities.
- C. Demolition requirements.

1.2 RELATED SECTIONS

- A. General Conditions Sections, as applicable.

1.3 PROJECT RECORD DOCUMENTS

- A. Submit under provisions of General Conditions.
- B. Accurately record actual locations of capped utilities and subsurface obstructions.

1.4 REGULATORY REQUIREMENTS

- A. Perform work of this Section under provisions of CBC Chapter 33, CFC Chapter 33, and NFPA 241 for demolition work, safety of structure, dust control and safety of occupants.
- B. Obtain required permits from authorities.
- C. Do not close or obstruct egress width to exits.
- D. Do not disable or disrupt building fire or life safety systems without three-day prior written notice to Owner.
- E. Conform to procedures applicable when discovering hazardous or contaminated materials.

1.5 SCHEDULING

- A. Schedule work under the provisions of Division 01.
- B. Describe demolition removal procedures and schedule.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 PREPARATION

- A. Provide, erect and maintain temporary barriers as required.
- B. Erect and maintain temporary partitions to prevent spread of dust, odors, and noise to adjoining facilities.
- C. Protect existing materials and finishes that are not scheduled or otherwise required to be demolished.
- D. Mark location of utilities.

3.2 DEMOLITION REQUIREMENTS

- A. Conduct demolition to minimize interference with adjacent and occupied buildings.
- B. Maintain protected egress and access to the Work.

3.3 DEMOLITION

- A. Disconnect, remove, cap and identify designated utilities within demolition areas.
- B. Demolish in an orderly and careful manner. Protect existing supporting structural members and materials.
- C. Except where noted otherwise, remove demolished materials from site. Do not bury or burn materials on site.
- D. Remove demolished materials from site as Work progresses. Upon completion of Work, leave areas in clean condition.
- E. Remove temporary Work.

END OF SECTION