SPECIFICATIONS

PROJECT:

Serving Line Replacements

PURPOSE:

Beaumont ISD is requesting proposals for a turnkey installation of serving line equipment at the following location:

Odom Academy 2550 W. Virginia Street Beaumont, TX 77705

SCOPE NOTES:

- Contractor required to perform site visit to verify all measurements and utilities are correct.
- Contractor to consult Child Nutrition Director before ordering all equipment/materials.
- Contractor to provide and install all equipment.
- Disconnect existing utilities to serving line.
- Remove and dispose of existing serving line off site.
- Electrical modifications to accommodate new serving line load center and heated cabinet.
- Contractor to include any possible plumbing reworking or upgrading.
- Start up and functional test new serving line, refrigeration, heated cabinet and milk coolers.
- Provide operator training on all equipment.
- 3D renderings included in the specifications are for layout purposes only. Equipment is to be per spec and verified by vendor/contractor.

VENDOR QUALIFICATIONS:

- Proposer to provide all necessary tools, ladders, and lifts.
- Proposer must have adequate personnel on their staff to perform the required tasks as outlined in this RFP.
- Proposer must have job supervisor present on-site, at all times during this project.
- Proposer to provide proof of Liability Insurance – if awarded the project.

CONTRACTOR RESPONSIBILITIES:

- Contractor to communicate with Child Nutrition Director the daily inspection and project plans.
- Contractor to check in with the District personnel upon arrival at facility.
- Contractor shall wear identifying apparel and badge.

SPECIFICATIONS

Cafeteria Serving Line Replacements		Odom Academy 2550 W. Virginia, Beaumont, TX 77705
Item	Qty	Specifications
Serving Line #1	**1**	**Custom Serving Counter; CounterCraft; Model SCSL-306 (or the like)**
		Fully enclosed base counter
		Stainless steel top with 2” turn down at all free sides, 4” splash at wall where applicable
		Provide one (1) full size hotel pan for utensils at the cashier counter. Hotel pan to be custom built into countertop
		Provide one (1) countertop to ceiling, 1-5/8" round chase tubing for data cable. Location near cashier section, refer to drawings
		Solid surface tray slide (similar to Corian) without button or rivets
		Decorative and removable, laminate front panels
		One (1) load center compartments.
		All electrical to be interconnected to load center. Electrical to be located in electrical conduit pipe, flex conduit to be kept to a minimum. Exposed flex conduit will not be accepted. All wiring to be numbered at all junctions, per circuit. Wiring diagram to be provided at each load center door. All receptacles, mounted in the counter, to be recess mounted and labeled
		One (1) lot CounterCraft (or the like) Food guards with LED lights throughout and heat lamps over hot food wells
		Four (4) Duke (or the like) WW-1Waterless Hot Food Well Drop-In Unit, electric, dry operation, with (1) 12" x 20" hot food well, 14-1/2"W x 22-1/2"D x 10.3"H, stainless steel well, removable FDA approved black silicone rubber liner, fully insulated galvanized exterior housing, touch screen control panel, (3) preset temperatures, Wi-Fi enabled, without drain, 72" control wire, UL EPH Classified, cULus
		One (1) HotFrost™ (or the like) Recessed Hot Frost, Hot/Cold switchable standard body drop-in unit, fits (2) 18 x 26" pan per shelf, programmable color touch screen control, stainless steel body and shelves, self-contained refrigeration, 120v/60/1-ph, 5.5 Amps
		One (1) HotFrost™ (or the like) Recessed Hot Frost, Hot/Cold switchable slim orientation Over shelf unit, (2) 18 x 26" pan per shelf, programmable color touch screen control, stainless steel body and shelves, self-contained refrigeration, 120v/60/1-ph, 5.5 Amps
		One (1) SilverKing (or the like) SKFDI123-ELUS Ice Cream Display Freezer, drop-in, (1) hinged glass lid, adjustable temperature control, manual defrost, stainless steel interior, stainless steel & galvanized

		exterior, bottom-mounted self-contained refrigeration, R290, 115v/60/1-ph, 2.1 amps, NEMA 5-15P, cETLus, ETL-Sanitation
		At the beginning of the serving line, provide recessed counter front to accept Traulsen (or the like) RNC-34-D-6 (with 6" casters)
		PROVISION IN COUNTER* Traulsen (or the like) unit is not included in this quote and is to be provided by others. Approved factory cut sheet with electrical requirements with actual unit dimension must be sent to CounterCraft (or the like). - 6" adjustable stainless-steel bullet-feet with stainless steel adjustable kickplates. NOTE: This counter will rest on 6-1/2" ss bullet feet and will clear the existing curb below. CounterCraft (or the like) will provide cut outs at the undershelf to access MEP as required. The curb will not be incorporated into the serving line (Left counter only). - Integral cashier station with cash drawer and plastic till inset. - CounterCraft (or the like) Delivery and Installation services included.
		Full Turnkey Installation – Factory approved/authorized installation of equipment in compliance with local municipal code and guidelines
Serving Line #2	**1**	**Custom Serving Counter; CounterCraft; Model No. SCSL-306 (or the like)**
		Fully enclosed base counter
		Stainless steel top with 2” turn down at all free sides, 4” splash at wall where applicable.
		Provide one (1) full size hotel pan for utensils at the cashier counter. Hotel pan to be custom built into countertop.
		Provide one (1) countertop to ceiling, 1-5/8" round chase tubing for data cable. Location near cashier section, refer to drawings.
		Solid surface tray slide (similar to Corian) without button or rivets.
		Decorative and removable, laminate front panels
		One (1) load center compartments.
		All electrical to be interconnected to load center. Electrical to be located in electrical conduit pipe, flex conduit to be kept to a minimum. Exposed flex conduit will not be accepted. All wiring to be numbered at all junctions, per circuit. Wiring diagram to be provided at each load center door. All receptacles, mounted in the counter, to be recess mounted and labeled.
		One (1) lot CounterCraft (or the like) Food guards with LED lights throughout and heat lamps over hot food wells.
		Four (4) Duke WW-1Waterless Hot Food Well Drop-In Unit, electric, dry operation, with (1) 12" x 20" hot food well, 14-1/2"W x 22-1/2"D x 10.3"H, stainless steel well, removable FDA approved black silicone

		rubber liner, fully insulated galvanized exterior housing, touch screen control panel, (3) preset temperatures, Wi-Fi enabled, without drain, 72" control wire, UL EPH Classified, cULus
		One (1) HotFrost™ (or the like) Recessed Hot Frost, Hot/Cold switchable standard body drop-in unit, fits (2) 18 x 26" pan per shelf, programmable color touch screen control, stainless steel body and shelves, self-contained refrigeration, 120v/60/1-ph, 5.5 Amps
		One (1) HotFrost™ (or the like) Recessed Hot Frost, Hot/Cold switchable slim orientation Over shelf unit, (2) 18 x 26" pan per shelf, programmable color touch screen control, stainless steel body and shelves, self-contained refrigeration, 120v/60/1-ph, 5.5 Amps
		One (1) SilverKing (or the like) SKFDI123-ELUS Ice Cream Display Freezer, drop-in, (1) hinged glass lid, adjustable temperature control, manual defrost, stainless steel interior, stainless steel & galvanized exterior, bottom-mounted self-contained refrigeration, R290, 115v/60/1-ph, 2.1 amps, NEMA 5-15P, cETLus, ETL-Sanitation
		At the beginning of the serving line, provide recessed counter front to accept Traulsen (or the like) RNC-34-D-6 (with 6" casters)
		PROVISION IN COUNTER* Traulsen (or the like) unit is not included in this quote and is to be provided by others. Approved factory cut sheet with electrical requirements with actual unit dimension must be sent to CounterCraft (or the like). - 6 1-2" adjustable stainless-steel bullet-feet with stainless steel adjustable kickplates. - Integral cashier station with cash drawer and plastic till inset. - Delivery and Installation services included.
		Full Turnkey Installation – Factory approved/authorized installation of equipment in compliance with local municipal code and guidelines
Heated Cabinet	**1**	**Reach-in Heated Cabinet; Traulsen; Model No. RFH232W-HHS (or the like)**
		Dimensions: 83.25(h) x 58(w) x 35(d)
		Spec-Line Heated Cabinet, Reach-in, two-section, stainless steel exterior and interior, standard depth cabinet, half-height door or doors with Santoprene® (or the like) EZ-Clean Gaskets, with microprocessor controls, ENERGY STAR®
		1 ea 208/115v/60/1-ph, 15.5 amps, standard
		1 ea 3 year service/labor warranty, standard
		1 ea Left door hinged left/right hinged right, standard
		24 ea Universal tray slide - per pair
		6 ea Credit for standard coated shelf, deduct

		1 st Casters, 6" high (set of 4)
		NOTE: WALL BUMPER PROVIDED BY OTHERS
		Full Turnkey Installation – Factory approved/authorized installation of equipment in compliance with local municipal code and guidelines
Display Refrigerator	**1**	**Reach-in Display Refrigerator; Traulsen; Model No. RHT232WUT-HHG (or the like)**
		Dimensions: 83.25(h) x 58(w) x 35(d)
		Spec-Line Refrigerator, Reach-in Display, two-section, 51.6 cu. ft., self-contained refrigeration, StayClear™ (or the like) Condenser, stainless steel exterior and interior, standard depth, wide half-height glass door or doors with Santoprene® (or the like) EZ-Clean Gaskets, interior lights, (3) adjustable wire shelves per section, microprocessor controls, 6" adjustable stainless steel legs, 1/2 HP, cULus, NSF
		1 ea 115v/60/1-ph, 10.4 amps, with cord & NEMA 5-20P attached, standard
		1 ea 3 year service/labor, 5 year compressor warranty, standard
		1 ea Standard refrigerant, standard
		1 ea Left door hinged left/right hinged right, standard
		2 ea Additional coated shelf on pins (max 8)
		1 st Casters, 6" high (set of 4)
		NOTE: WALL BUMPER PROVIDED BY OTHERS
		Full Turnkey Installation – Factory approved/authorized installation of equipment in compliance with local municipal code and guidelines
Milk Cooler	**1**	**Milk Cooler; Traulsen; Model No. RMC49D6** (or the like)
		Dimensions: 48(h) x 49(w) x 34.25(d)
		Spec-Line Forced-Air Double Access Milk Cooler, sliding door, holds (12) 13"x13" crates or (8) 13"x19" milk crates, stainless steel interior and exterior, reinforced floor, sliding caster rails, (3) heavy-duty stainless-steel dunnage racks, top-mount refrigeration system, digital control, E-Z clean gaskets, floor drain, 6" factory mounted adjustable casters, 1/3 hp, cETLus, NSF
		2 ea 3 year service/labor, 5 year compressor warranty, standard
		2 ea 115v/60/1-ph, 7.2 amps, NEMA 5-15P
		Full Turnkey Installation – Factory approved/authorized installation of equipment in compliance with local municipal code and guidelines