

Capital Project Planning BOARD OF EDUCATION MEETING

January 8, 2025





Capital Planning Goals

- 1. Maintain the District's School buildings in good working order.
- 2. Accommodate the District's existing and projected **enrollment**.
- 3. Ensure Pelham's School Buildings have space to support **instructional programs**.
- 4. Consider **energy efficient and sustainable solutions** to enhance long-term value and resiliency.





Summary of September BOE Presentation

- The Elementary Schools have capacity for the projected enrollments, however Colonial and Siwanoy operate with less support space.
- The projected enrollment for Pelham Memorial High School will exceed "functional capacity".
- The Building Condition Survey identified \$95.9M of work.
- It is time to address ADA requirements at Siwanoy.





September December:

- (3) Facilities Committee Meetings (9/18, 11/14, 12/3)
- Prioritized Infrastructure Work from BCS
- Discussed Air Conditioning + Ground Source Heat Pumps
- Evaluated Building Renovation + Expansion Options, with a focus on Siwanoy and Pelham HS + Annex
- Reviewed Draft Budget Estimates





Roofing

Membrane Roof Near End of Useful Life

Pelham Middle School

Prospect Hill Elementary School







Windows











Insulated Glazing Unit Seal Leaks





Prospect Hill Elementary School


Prospect Hill Elementary School





Exterior Masonry





Pelham Memorial High School


Pelham Memorial High School





Heating Plants





Pelham Memorial High School

Pelham Memorial High School





Project Budget Anatomy

Construction Costs (Referred to as 'hard' or 'direct')

What is paid to the Contractor(s)

Design Contingency (10%)

To cover additional project scope through the design phases

Construction Contingency (10%)

Additional construction costs incurred during construction

Escalation (4-6% per year)

Projected price increases over time

Project Costs (18%)

All non-brick and mortar expenses to include, design professionals, construction mangers, testing services, abatement monitoring, etc.





PELHAM PUBLIC SCHOOLS Prioritize

Prioritized Infrastructure Work

	Desting			Heating Plant		Infrastructure
	Roofing	Windows	Masonry	Replacements	Hydronic Heat	Subtotal
Colonial Elementary	\$165,000	\$1,320,000	\$175,000	\$2,920,000	\$2,500,000	\$7,080,000
Siwanoy Elementary		\$1,905,000	\$345,000	\$2,920,000	\$3,000,000	\$8,170,000
Prospect Hill Elementary	\$2,620,000	\$2,115,000	\$345,000	\$3,175,000	\$3,500,000	\$11,755,000
Hutchinson Elementary	N/A	N/A	N/A	N/A	N/A	N/A
Pelham Middle School	\$2,355,000	N/A	\$390,000	N/A	N/A	\$2,745,000
Pelham High School	\$3,405,000	\$5,725,000	\$605,000	\$4,290,000	\$10,500,000	\$24,525,000
Total	\$8,545,000	\$11,065,000	\$1,860,000	\$13,305,000	\$19,500,000	\$54,275,000





Capacity & Program-Related Items

Colonial – Additional full-size classrooms and a dedicated Cafeteria are recommended to ease marginal functional capacity.


Siwanoy –Additional instructional space and a dedicated Cafeteria are recommended to address instructional space adequacy. <u>ADA Compliance</u>.

Prospect Hill – No major concerns with functional capacity

Middle / High School – Additional classroom space to accommodate increase in enrollment and additional student commons / cafeteria space

District Office – Renovate space in MS/HS for District Office and construct new classrooms to compensate for displaced classroom space.









Colonial Elementary ~\$19,000,000


Additions & Alterations to include 2 ½ story addition & renovation of the existing building.

The Committee, upon weighing capital needs throughout the District, determined no additional study of this concept is warranted.



OPTION A – FIRST FLOOR

Legend:






SIWANOY ADDITION & ALTERATION

Kaeyer, Garment + Davidson Architects, PC 285 Main Street, Mount Kisco, New York 10549 914.666.5900 kgdarchitects.com PELHAM UFSD

FIRST FLOOR PLAN

OPTION A – SECOND FLOOR

Legend:






SIWANOY ADDITION & ALTERATION


PELHAM UFSD

Kaeyer, Garment + Davidson Architects, PC 285 Main Street, Mount Kisco, New York 10549 914,666.5900 kgdarchitects.com

SECOND FLOOR PLAN



285 Main Street, Mount Kisco, New York 10549 914.666.5900 kgdarchitects.com






SIWANOY ADDITION & ALTERATION

PELHAM UFSD

Kaeyer, Garment + Davidson Architects, PC 285 Main Street, Mount Kisco, New York 10549 914.666.5900 kgdarchitects.com FIRST FLOOR PLAN






SIWANOY ADDITION & ALTERATION

PELHAM UFSD

Kaeyer, Garment + Davidson Architects, PC 285 Main Street, Mount Kisco, New York10549 914:666.5900 kgdarchitects.com SECOND FLOOR PLAN




914.666.5900 kgdarchitects.com





SIWANOY ADDITION & ALTERATION PELHAM UFSD **OPTION C - FIRST FLOOR PLAN**

285 Main Street, Mount Kisco, New York 10549 914,666.5900 kgdarchitects.com







914.666.5900 kgdarchitects.com

SIWANOY ADDITION & ALTERATION

Kaeyer, Garment + Davidson Architects, PC 285 Main Street, Mount Kisco, New York 10549 PELHAM UFSD **OPTION C - SECOND FLOOR PLAN**



OPTION D – TEMPORARY ELEMENTARY SCHOOL





Siwanoy Elementary

Option A: Alterations for ADA Accessibility and an Addition. No net change in classrooms.

\$13,500,000

Option B: Alterations for ADA Accessibility, Cafeteria and Classroom Addition, Renovation of Existing Building

Option C: Remove 'New' Wings. New Addition with Classrooms, Cafeteria, and Gym. Renovation of Existing Building.


Option D: Replacement Building, including temporary classrooms at PHS

\$35,500,000

\$28.000,000

~\$90,000,000









出 - 7

CONVERT TO

DISTRICT OFFICES


мŚ

914.666.5900 kgdarchitects.com





PRE BOND CONCEPT DESIGN OPTION A





PRE BOND CONCEPT DESIGN OPTION B





914,666.5900 kgdarchitects.com



Pelham Memorial High School

Option A: Two-Story Addition with Cafeteria and Science Labs. Renovation of the Annex. New, secure main entry.



Option B: Two-Story (partial) Addition with Cafeteria and Science Labs, Renovation of Annex. Renovation of existing space to Student Commons and District Office. Secure main entry. \$34,500,000





Air Conditioning

Add Air Conditioning to All Spaces, to include ventilation upgrades to support air conditioning.

Colonial Elementary\$8,500,000Siwanoy Elementary\$5,500,000Prospect Hill Elementary\$5,000,000Pelham Memorial High School\$23,500,000Total\$42,500,000






Ground Source Heat Pump (Geothermal)

Utilize the earth as a heat sync to generate heating and cooling, reducing dependence on fossil fuels. Must be coupled with air conditioning.

- Closed Loop Well Field
- Circulator Pumps
- Water Source Heat Pump plant for heating & cooling
- Electrical Upgrades







PELHAM PUBLIC SCHOOLS Geothermal - Middletown City Schools



Lawn Restoration Underway



180 Wells Installed Summer 2023



Ground Source Heat Pump (Geothermal)

- Colonial Elementary N/
- Siwanoy Elementary
- Prospect Hill Elementary \$2,00

N/A (Site Constraints)

\$2,000,000

\$2,000,000

Pelham Memorial High School \$6,000,000

Total \$10,000,000





	Scenario 1 Scenario 2		Scenario 3		Scenario 4		Scenario 5		
Infrastructure	\$ 54,275,000	\$	54,275,000	\$	54,275,000	\$	54,275,000	\$	54,275,000
Siwanoy Elementary (Opt C)		\$	35,500,000	\$	35,500,000	\$	35,500,000	\$	35,500,000
High School / Annex (Opt B)				\$	34,500,000	\$	34,500,000	\$	34,500,000
Air Conditioning						\$	42,500,000	\$	42,500,000
Geothermal								\$	10,000,000
Total	\$ 54,275,000	\$	89,775,000	\$	124,275,000	\$	166,775,000	\$	176,775,000



CAPITAL PROJECT PLANNING MILESTONE SCHEDULE

Action	Start	Finish	Comments				
Board of Education Meeting	January	/ 8, 2025					
Capital Project Planning Update			KG+D, BAC Representatives				
Bond Advisory Committee (BAC) Meeting	Jar	า-25					
Review Capital Project Studies - Scope & Budget			KG+D				
Bond Advisory Committee (BAC) Meeting	Jan-25						
Review Capital Project Studies - Scope & Budget			KG+D				
Board of Education Meeting	February	12, 2025					
Capital Project Planning Update			KG+D, BAC Representatives				
SEQRA - BOE declares intent to act as Lead Agency			Commence Required SEQRA Study				
Bond Advisory Committee (BAC) Meeting	Feb-25		Finalize Recommendation to Board of Education				
Board of Education Meeting	March 2	26, 2025					
Capital Project Planning Update			KG+D, BAC Representatives				
SEQRA - BOE Determine Lead Agency Status and SEQRA Determination			30 days minimum after commencement of coordinated review, if required				
Board of Education Meeting	April 2, 2025						
BOE Resolution to conduct bond referendum			45 days, min. prior to date of referendum.				
Public Information Process	Apr-25	May-25					
Referendum	May 20	0, 2025					



