DOCUMENT 00 91 13

ADDENDA

NOTICE TO ALL BIDDERS: THE FOLLOWING MODIFICATIONS, ADDITIONS, DELETIONS, CLARIFICATIONS AND/OR INFORMATION ARE HEREBY MADE PART OF THE CONTRACT DOCUMENTS. ADDENDUM MUST BE ACKNOWLEGDED AS PART OF THE BIF FORM.

1. RFI QUESTIONS

1) We are installing new 5400 Wiremold on this project and installing new data drops. There is no mention of reinstalling electrical outlets in this Wiremold. I'm pretty sure there are outlets in the existing Wiremold so when this is removed I'm assuming the power goes with it.
   (a) Note that bold/darker line indicates New Wiremold and grey line indicates Existing Wiremold. Electrical outlets in Existing Wiremold are to remain.

2) Please reference 27 05 00 2.05B 1 & 2. Use of innerduct and fabric innerduct. s this a requirement given that the required fiber cabling is armored?
   (a) No innerduct is required.

3) Reference T-700 MDF General Note #10. Provide 6" slim line cords. Question: Are these required to be Panduit? Are patch cords required at the WAO? Length??
   (a) Yes, patch cords are required to be Panduit. Contractor is not responsible for patch cords at the Work Area Outlet.

4) Please reference27 00 00 2.02.B & Appendix A 27 10 00. Discrepancy on whether Plenum rated cable is required in all spaces. Question: Is plenum-rated cable required in non-plenum spaces?
   (a) Plenum cable is required throughout due to smaller diameter.

5) Please reference 00 70 00 1.16. Will Sanitary Facilities be required for this project?
   (a) Yes. Contractor is to provide their own sanitary facilities and cannot rely on the site for use.

6) Please reference 00 70 00 13.1.5 & 6. Is SMA and Builders Risk Insurance a requirement for this project?
   (a) SMA insurance is not a requirement and will be waived.

7) Are there DVBE requirements for this project?
   (a) There is DVBE Participation goal, but no requirement. Review of Volume 1 Bid documentation.

8) Our cabling company for that area attended the job walk last week, and they are local. Does that count for this requirement?
   (a) The requirement is waived for the purposes of Section 27 21 00 and 28 20 00. The requirement stands for the purposes of 27 51 23

(Educational Intercom). The Bogen-authorized installer/subcontractor must meet the distance/response time requirement.

9) There is mention of the interior conduits to be factory finished (blue & green), is that correct?
   (a) The interior electrical conduits should be painted to match existing wall colors. This specification will be updated in the conformed set.

10) Did the bid date change?
   (a) The bid date did not change. Bids are due 01/21/2025 at 10am, as noted in the bid documents.

END OF SECTION