



January 20, 2025

Mr. Nick Olson/FMCS Director
Council Bluffs Community School District
300 W. Broadway, Ste 1600
Council Bluffs, IA, 51503
nolson@cb-schools.org

Subject: Radon Measurement Report
Thomas Jefferson High School
2501 West Broadway
Council Bluffs, Iowa
Atlas Project No. P204BS08021B

Dear Mr. Olson:

Atlas Technical Consultants LLC (Atlas) is pleased to provide the Council Bluffs Community School District (Client) with the results of the radon measurement services for the above-referenced property.

PROJECT DESCRIPTION

Atlas Technical Consultants (Atlas) conducted short-term radon measurement for the Council Bluffs Community School District (Client) at Thomas Jefferson High School located at 2501 West Broadway in Council Bluffs, Iowa. The objectives were to collect radon measurements and to compare measured radon concentrations to regulatory evaluation criteria.

Standard Of Care

This measurement event was conducted based on information provided to Atlas by the Client and was conducted in a manner consistent with the level of care and skill ordinarily exercised by members of the profession currently practicing under similar conditions in the same locale. Atlas did not attempt to identify every potential exposure or hazard present in the building. The results, findings, conclusions, and recommendations expressed in this report are based on conditions observed during our measurement activities. The information contained in this report should not be relied upon to represent conditions that existed prior to or after this measurement event. Atlas does not warrant the services of regulatory agencies, laboratories, or other third parties supplying information that may have been used in the preparation of this report.

Reliance

This report is for the exclusive use of the Client. Reliance by any other party on this report is prohibited without written authorization of Atlas and the Client. Reliance on this report by the Client and all authorized parties will be subject to the terms, conditions, and limitations stated in the proposal, this report, and the project contract.



FIELD ACTIVITIES

The Client was informed, prior to the measurement event, that closed-building conditions were to be maintained starting 12 hours prior to the start of measurement and throughout the entire measurement period.

- Closed building conditions include, but are not limited to:
 - Keeping windows closed, including in areas not being tested.
 - Exterior doors being kept closed except for momentary entry and exit.
 - Heating and cooling systems set to normal operation.
 - Fireplaces not being used.

Radon measurements were collected from January 13-15, 2024, by Mr. Stephen Sycuro, an Iowa certified Radon Measurement Specialist (certification number RNTST10107), in accordance with guidelines set forth by the United States Environmental Protection Agency (USEPA) and the Iowa Department of Public Health (IDPH). Mr. Sycuro's certification can be found in [Appendix B](#).

Atlas collected measurements for airborne radon concentrations at 99 first floor, second floor and basement level locations. Ten duplicate and five field blank measurements for quality control purposes were also collected.

METHODS

Radon measurements were collected in general accordance with the American National Standards Institute (ANSI)/American Association of Radon Scientists and Technologists, Inc. (AARST) Protocol for Conducting Measurements of Radon and Radon Decay Products in Multifamily, School, Commercial and Mixed-Use Buildings (MA-MFLB 2023) using State of Iowa-approved activated charcoal devices. The devices were placed between two feet and six feet above the floor surface, in areas of normal air circulation, and away from air vents, doors, and windows. HVAC systems in the areas were set to auto and appeared to be working properly. Atlas assessed each location to ensure that closed-building conditions were met at the time of placement and at the time of collection of the devices. The devices were retrieved 48 hours after placement.

Measurement devices were placed in 100% of the ground-contact units. Analyzed devices included ANSI/AARST Protocol and IDPH required duplicates (10% of devices) and blanks (5% of devices).

Field blanks and duplicate devices were blindly submitted to the laboratory so a distinction could not be made between the devices for internal quality control purposes. A field log identifying measurement locations and summarizing the laboratory analytical results is also attached.

Activated charcoal devices used for sampling were shipped under chain-of-custody to Air Chek, Inc., in Mills River, North Carolina for laboratory analysis to detect gamma rays by scintillation counting using sodium iodide detectors. Air Chek, Inc. is an Iowa-certified radon laboratory.

The laboratory analytical results and field log are included in [Appendix A](#).



EVALUATION CRITERIA

The following has been excerpted from the ANSI/AARST Protocol for Conducting Measurements of Radon and Radon Decay Products In Multifamily, School, Commercial and Mixed-Use Buildings (MA-MFLB 2023) – Section 7.1: Action Level Guidance. The following action level descriptions reflect guidance from the USEPA:

4 pCi/L or greater: Fix the building. The higher the radon concentration, the more quickly action should be taken to reduce the concentrations.

Between 2.0 and 4.0 pCi/L: Consider fixing the building if test results indicate that radon concentrations are greater than half the action level, such as between 2 and 4 pCi/L.

Less than or equal to 2.0 pCi/L: When measurement devices indicate concentrations lower than about 2.0 pCi/L, test data should normally be interpreted as being lower than the test device can accurately measure.

If test results are below the action level, confirm the low results by testing again, at least every five years and whenever significant changes to the building's structure or mechanical systems occur or every two years if there is an active mitigation system installed to ensure continued effectiveness.

FINDINGS

Radon concentrations **were not detected** at or above 4.0 pCi/L in the samples collected at the site.

Radon concentrations **were detected** between 2.0 and 4.0 pCi/L in two of the samples collected at the site.

Two devices placed in rooms C125 in the school and the gym in the activities building were missing at the time of retrieval. Two devices placed in room A101 in the school and D110 in the activities building were damaged and could not be analyzed. Atlas personnel did not see signs that the other devices were tampered with after initial placement.

Results for measurements collected for quality control purposes were found to be within control limits. These results are used to help measure precision and evaluate bias associated with radon concentrations.

RECOMMENDATIONS

Based on the results of the measurements and using guidance from ANSI/AARST, USEPA and IDPH, Atlas recommends the following:

Two of the samples collected at the site have radon concentrations that **do not exceed** the USEPA action level of 4.0 pCi/L but could with daily and seasonal changes.

- Rooms/areas with radon concentrations **between 2.0 and 4.0 pCi/L** should be re-tested by a State of Iowa certified radon measurement specialist with either a long-term or another short-term test. If the average of the two radon concentrations remains at or above 4.0 pCi/L the room should be assessed by a State of Iowa certified radon mitigation company to determine what corrective actions are needed to reduce radon concentrations. The rooms should be re-tested following the corrective actions.



Per section 8.2.5 of the ANSI/AARST Protocol, additional testing should take place when one or more of the following conditions are met:

- A new addition is constructed or alterations for building reconfiguration or rehabilitation occur;
- A ground contact area not previously tested is occupied, or a building is newly occupied;
- Heating or cooling systems are significantly altered, resulting in changes to air pressures or pressure relationships;
- Ventilation is significantly altered by extensive weatherization, changes to mechanical systems or comparable procedures;
- Significant openings to soil occur due to:
 - Groundwater or slab surface water control systems that are altered or added (e.g., sumps, perimeter drain tile, shower/tub retrofits, etc.) or,
 - Natural settlement causing major cracks to develop;
 - Earthquakes or construction blasting, fracking or formation of sink holes nearby;
 - A mitigation system is altered, modified or repaired.
- Significant openings to soil occur due to:
 - HVAC equipment is added, removed, replaced, operated differently or improperly maintained;
 - Significant changes to the slab or foundation, such as major cracks or penetrations from natural settling, or water proofing or groundwater control efforts;
 - An installed mitigation system is altered, modified or repaired;
 - A ground contact area that was not previously tested is occupied; or
 - Every five years.

Should testing indicate concentrations that meet or exceed the action level, conduct evaluations, corrections and further testing until radon concentrations have been mitigated to below the action level.

Please note that there is some uncertainty associated with radon measurement. Factors that affect this uncertainty include statistical variations related to seasonal weather and building operation, as well as operation of building mechanical equipment.

LIMITATIONS

Atlas's radon testing services represent the concentrations only during the time that the testing occurred. There is an uncertainty with any measurement result due to statistical variations and other factors such as daily and seasonal variations in radon concentrations. Variations may be due to changes in the weather, operation of the dwelling, or possible interference with the necessary test conditions.

The results, findings, and conclusions expressed in this report are based only on conditions observed during our survey. Atlas makes no representation or assumptions as to past conditions or future occurrences. The findings of this report represent Atlas's professional judgment; no other warranty is expressed or implied.

Atlas recommends that the Client comply with regulations and response actions in accordance with federal, state, and local regulations. Atlas does not undertake responsibility for the persons in charge of the subject property or the responsibility for reporting to any local, state, or federal public agencies regarding conditions that may present a potential danger to public health or safety.

Our professional services have been performed, our findings obtained, and our conclusions and recommendations prepared in accordance with customary principles and practices in the fields of



environmental science and engineering. This statement is in lieu of other statements either expressed or implied. This report does not warrant against future operations or conditions, nor does it warrant against operations or conditions present of a type or at a location not investigated.

This report is for the exclusive use of the Client as addressed. The scope of services performed in the execution of this evaluation may not be appropriate to satisfy the needs of other users and use or re-use of this document or the findings, conclusions, or recommendations is at the risk of said user.

Atlas appreciates the opportunity to provide you with these services and looks forward to working with you on future assignments. If you have questions regarding the information in this report or if we can be of further assistance, please do not hesitate to contact the Omaha, Nebraska office at (402) 697-9747.

Respectfully submitted,

ATLAS TECHNICAL CONSULTANTS LLC

A handwritten signature in black ink, appearing to read "Stephen Sycuro".

Stephen Sycuro CIE, OHST
Project Manager
Email: Stephen.Sycuro@oneatlas.com
IA Radon Measurement Specialist
#RNTST10107

A handwritten signature in black ink, appearing to read "Phillip Thomas".

Phillip Thomas, OHST, CHMM
Senior Project Manager
Email: Phillip.Thomas@oneatlas.com
IA Radon Measurement Specialist
#RNTST09025

APPENDICES

APPENDIX A – LABORATORY RESULTS & FIELD LOG
APPENDIX B – CERTIFICATIONS

APPENDIX A
LABORATORY RESULTS & FIELD LOG

P9319 / STEPHEN SYCURO

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
11891501	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A111	204BS08021B	1	< 0.3
11891502	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A111	204BS08021B	1	0.8
11891503	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	RECEPTION	204BS08021B	1	< 0.3
11891504	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	RECEPTION	204BS08021B	1	< 0.3
11891505	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A113	204BS08021B	1	< 0.3
11891506	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A113	204BS08021B	1	< 0.3
11891507	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A115	204BS08021B	1	< 0.3
11891508	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A115	204BS08021B	1	0.6
11891509	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A117	204BS08021B	1	< 0.3
11891510	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A117	204BS08021B	1	< 0.3
11891511	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A116	204BS08021B	1	0.5
11891512	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A116	204BS08021B	1	0.7
11891513	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	OFFICE A111	204BS08021B	1	< 0.3
11891514	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	OFFICE A111	204BS08021B	1	< 0.3
11891515	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A121	204BS08021B	1	< 0.3
11891516	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A121	204BS08021B	1	< 0.3
11891517	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A122	204BS08021B	1	< 0.3
11891518	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A122	204BS08021B	1	< 0.3
11891519	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A123	204BS08021B	1	1.7
11891520	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A123	204BS08021B	1	1.7
11891521	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A131	204BS08021B	1	< 0.3
11891522	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A131	204BS08021B	1	< 0.3
11891523	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A131 LECTURE	204BS08021B	1	0.5
11891524	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A131 LECTURE	204BS08021B	1	< 0.3
11891525	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A131 EAST WORKSHOP	204BS08021B	1	< 0.3
11891526	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A131 WEST WORKSHOP	204BS08021B	1	< 0.3
11891527	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A131 OFFICE	204BS08021B	1	0.9
11891528	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A132	204BS08021B	1	< 0.3
11891529	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A133	204BS08021B	1	1.0
11891530	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A124	204BS08021B	1	< 0.3
11891531	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A125	204BS08021B	1	0.9
11891532	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A126	204BS08021B	1	0.6
11891533	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A127	204BS08021B	1	0.9
11891534	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A101	204BS08021B	1	0.5
11891535	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A101	204BS08021B	1	0.9

P9319 / STEPHEN SYCURO


Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
11891536	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A101	204BS08021B	1	0.6
11891537	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A101	204BS08021B	1	???
11891538	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C111	204BS08021B	1	0.8
11891539	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C113	204BS08021B	1	1.3
11891540	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C114	204BS08021B	1	1.0
11891541	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C115	204BS08021B	1	1.1
11891542	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C116	204BS08021B	1	1.9
11891543	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C126	204BS08021B	1	1.3
11891544	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C121	204BS08021B	1	0.9
11891545	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C128	204BS08021B	1	1.3
11891546	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C127	204BS08021B	1	0.9
11891547	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C126	204BS08021B	1	1.4
11891549	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C136	204BS08021B	1	1.3
11891550	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C135	204BS08021B	1	0.7
11891551	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C134	204BS08021B	1	< 0.3
11891552	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C133	204BS08021B	1	0.9
11891553	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C132	204BS08021B	1	1.2
11891554	2025-01-13	4:00 pm	2025-01-15	4:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C131	204BS08021B	1	1.7
11891555	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C219	204BS08021B	2	0.7
11891556	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C218	204BS08021B	2	0.8
11891557	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C212	204BS08021B	2	1.1
11891558	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	C211	204BS08021B	2	0.7
11891559	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B140	204BS08021B	1	1.1
11891560	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B140A	204BS08021B	1	1.4
11891561	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B140B	204BS08021B	1	1.4
11891562	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B140C	204BS08021B	1	1.3
11891563	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B138	204BS08021B	1	< 0.3
11891564	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B132	204BS08021B	1	0.5
11891565	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B133	204BS08021B	1	0.7
11891566	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B134	204BS08021B	1	< 0.3
11891567	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B135	204BS08021B	1	0.5
11891568	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B138 CONFERENCE	204BS08021B	1	< 0.3
11891569	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B136	204BS08021B	1	0.8
11891570	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B137	204BS08021B	1	0.7
11891571	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B116	204BS08021B	1	< 0.3

P9319 / STEPHEN SYCURO

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
11891572	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B117	204BS08021B	1	< 0.3
11891573	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B118	204BS08021B	1	< 0.3
11891574	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B115	204BS08021B	1	< 0.3
11891575	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B114	204BS08021B	1	< 0.3
11891576	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B113	204BS08021B	1	< 0.3
11891577	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B119	204BS08021B	1	< 0.3
11891578	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B119B	204BS08021B	1	< 0.3
11891579	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B119A	204BS08021B	1	0.5
11891580	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B121	204BS08021B	1	< 0.3
11891581	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B112	204BS08021B	1	< 0.3
11891582	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B111	204BS08021B	1	< 0.3
11891583	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B122	204BS08021B	1	0.7
11891584	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B108	204BS08021B	1	0.8
11891585	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B100	204BS08021B	1	0.6
11891586	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B106	204BS08021B	1	0.6
11891587	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B105	204BS08021B	1	0.6
11891588	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B104	204BS08021B	1	0.6
11891589	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B103	204BS08021B	1	< 0.3
11891590	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	B102	204BS08021B	1	< 0.3
11891591	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A01	204BS08021B	0	2.2
11891592	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	SCHOOL	A02	204BS08021B	0	3.2
11891593	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D108	204BS08021B	1	< 0.3
11891594	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D108	204BS08021B	1	< 0.3
11891595	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D107	204BS08021B	1	< 0.3
11891596	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D107	204BS08021B	1	0.7
11891597	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D106	204BS08021B	1	< 0.3
11891598	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D106	204BS08021B	1	< 0.3
11891599	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D105	204BS08021B	1	< 0.3
11891600	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D100	204BS08021B	1	< 0.3
11924801	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D101	204BS08021B	1	< 0.3
11924802	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D102	204BS08021B	1	< 0.3
11924803	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D103	204BS08021B	1	< 0.3
11924804	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D104	204BS08021B	1	< 0.3
11924805	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D109	204BS08021B	1	0.5
11924806	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D110	204BS08021B	1	???

P9319 / STEPHEN SYCURO

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
11924807	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D111	204BS08021B	1	0.7
11924808	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	D113	204BS08021B	1	1.0
11924809	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	WEIGHT ROOM	204BS08021B	1	0.7
11924810	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	WEIGHT ROOM OFFICE	204BS08021B	1	0.6
11924811	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	GYM	204BS08021B	1	< 0.3
11924812	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	GYM	204BS08021B	1	< 0.3
11924813	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	GYM	204BS08021B	1	
11924815	2025-01-13	5:00 pm	2025-01-15	5:00 pm	70	THOMAS JEFFERSON HIGH	ACTIVITIES	GYM	204BS08021B	1	< 0.3

Facility:	Thomas Jefferson High School			# of Residence Devices:	0	
Address:	2501 West Broadway, CB, IA 51501			# of NR Devices:	99	
Contact:	Nicholas Olson			Duplicates:	10	
Set/Type/RS:	1/13/2025	ST	Stephen Sycuro	Blanks:	5	
Retrieve/Type/RS:	1/15/2025	ST	Stephen Sycuro	Total # of Devices:	114	

Serial Number	Start Date	Start Time	Stop Date	Stop Time	Temp.	Facility	Building	Room	Proj. ID	Floor	Result pCi/L
11891501	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A111	204BS08021B	1	< 0.3
11891502	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A111 Dup	204BS08021B	1	0.8
11891503	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	Reception	204BS08021B	1	< 0.3
11891504	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	Reception Blank	204BS08021B	1	< 0.3
11891505	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A113	204BS08021B	1	< 0.3
11891506	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A113 Dup	204BS08021B	1	< 0.3
11891507	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A115	204BS08021B	1	< 0.3
11891508	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A115 Dup	204BS08021B	1	0.6
11891509	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A117	204BS08021B	1	< 0.3
11891510	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A117 Blank	204BS08021B	1	< 0.3
11891511	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A116	204BS08021B	1	0.5
11891512	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A116 Dup	204BS08021B	1	0.7
11891513	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	Office A111	204BS08021B	1	< 0.3
11891514	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	Office A111 Dup	204BS08021B	1	< 0.3
11891515	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A121	204BS08021B	1	< 0.3
11891516	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A121 Blank	204BS08021B	1	< 0.3
11891517	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A122	204BS08021B	1	< 0.3
11891518	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A122 Dup	204BS08021B	1	< 0.3
11891519	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A123	204BS08021B	1	1.7
11891520	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A123 Dup	204BS08021B	1	1.7

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>	<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>	<u>Result</u> pCi/L
11891521	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A131	204BS08021B	1	< 0.3
11891522	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A131 Blank	204BS08021B	1	< 0.3
11891523	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A131 Lecture	204BS08021B	1	0.5
11891524	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A131 Lecture Dup	204BS08021B	1	< 0.3
11891525	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A131 East Workshop	204BS08021B	1	< 0.3
11891526	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A131 West Workshop	204BS08021B	1	< 0.3
11891527	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A131 Office	204BS08021B	1	0.9
11891528	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A132	204BS08021B	1	< 0.3
11891529	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A133	204BS08021B	1	1
11891530	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A124	204BS08021B	1	< 0.3
11891531	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A125	204BS08021B	1	0.9
11891532	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A126	204BS08021B	1	0.6
11891533	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A127	204BS08021B	1	0.9
11891534	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A101	204BS08021B	1	0.5
11891535	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A101	204BS08021B	1	0.9
11891536	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	A101	204BS08021B	1	0.6
11891537	01/13/2025	1600	01/15/2025	Damaged	70	Thomas Jefferson High	School	A101	204BS08021B	1	Damaged
11891538	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C111	204BS08021B	1	0.8
11891539	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C113	204BS08021B	1	1.3
11891540	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C114	204BS08021B	1	1
11891541	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C115	204BS08021B	1	1.1
11891542	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C116	204BS08021B	1	1.9
11891543	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C126	204BS08021B	1	1.3
11891544	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C121	204BS08021B	1	0.9


<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>	<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>	<u>Result</u> <u>pCi/L</u>
11891545	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C128	204BS08021B	1	1.3
11891546	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C127	204BS08021B	1	0.9
11891547	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C126	204BS08021B	1	1.4
11891548	01/13/2025	1600	01/15/2025	Missing	70	Thomas Jefferson High	School	C125	204BS08021B	1	Missing
11891549	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C136	204BS08021B	1	1.3
11891550	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C135	204BS08021B	1	0.7
11891551	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C134	204BS08021B	1	< 0.3
11891552	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C133	204BS08021B	1	0.9
11891553	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C132	204BS08021B	1	1.2
11891554	01/13/2025	1600	01/15/2025	1600	70	Thomas Jefferson High	School	C131	204BS08021B	1	1.7
11891555	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	C219	204BS08021B	2	0.7
11891556	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	C218	204BS08021B	2	0.8
11891557	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	C212	204BS08021B	2	1.1
11891558	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	C211	204BS08021B	2	0.7
11891559	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B140	204BS08021B	1	1.1
11891560	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B140A	204BS08021B	1	1.4
11891561	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B140B	204BS08021B	1	1.4
11891562	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B140C	204BS08021B	1	1.3
11891563	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B138	204BS08021B	1	< 0.3
11891564	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B132	204BS08021B	1	0.5
11891565	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B133	204BS08021B	1	0.7
11891566	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B134	204BS08021B	1	< 0.3
11891567	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B135	204BS08021B	1	0.5
11891568	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B138 Conference	204BS08021B	1	< 0.3

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>	<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>	<u>Result</u> <u>pCi/L</u>
11891569	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B136	204BS08021B	1	0.8
11891570	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B137	204BS08021B	1	0.7
11891571	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B116	204BS08021B	1	< 0.3
11891572	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B117	204BS08021B	1	< 0.3
11891573	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B118	204BS08021B	1	< 0.3
11891574	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B115	204BS08021B	1	< 0.3
11891575	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B114	204BS08021B	1	< 0.3
11891576	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B113	204BS08021B	1	< 0.3
11891577	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B119	204BS08021B	1	< 0.3
11891578	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B119B	204BS08021B	1	< 0.3
11891579	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B119A	204BS08021B	1	0.5
11891580	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B121	204BS08021B	1	< 0.3
11891581	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B112	204BS08021B	1	< 0.3
11891582	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B111	204BS08021B	1	< 0.3
11891583	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B122	204BS08021B	1	0.7
11891584	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B108	204BS08021B	1	0.8
11891585	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B100	204BS08021B	1	0.6
11891586	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B106	204BS08021B	1	0.6
11891587	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B105	204BS08021B	1	0.6
11891588	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B104	204BS08021B	1	0.6
11891589	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B103	204BS08021B	1	< 0.3
11891590	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	B102	204BS08021B	1	< 0.3
11891591	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	A01	204BS08021B	0	2.2
11891592	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	School	A02	204BS08021B	0	3.2

<u>Serial Number</u>	<u>Start Date</u>	<u>Start Time</u>	<u>Stop Date</u>	<u>Stop Time</u>	<u>Temp.</u>	<u>Facility</u>	<u>Building</u>	<u>Room</u>	<u>Proj. ID</u>	<u>Floor</u>	<u>Result</u> pCi/L
11891593	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D108	204BS08021B	1	< 0.3
11891594	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D108 Dup	204BS08021B	1	< 0.3
11891595	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D107	204BS08021B	1	< 0.3
11891596	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D107 Dup	204BS08021B	1	0.7
11891597	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D106	204BS08021B	1	< 0.3
11891598	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D106 Blank	204BS08021B	1	< 0.3
11891599	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D105	204BS08021B	1	< 0.3
11891600	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D100	204BS08021B	1	< 0.3
11924801	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D101	204BS08021B	1	< 0.3
11924802	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D102	204BS08021B	1	< 0.3
11924803	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D103	204BS08021B	1	< 0.3
11924804	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D104	204BS08021B	1	< 0.3
11924805	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D109	204BS08021B	1	0.5
11924806	01/13/2025	1700	01/15/2025	Damaged	70	Thomas Jefferson High	Activities	D110	204BS08021B	1	Damaged
11924807	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D111	204BS08021B	1	0.7
11924808	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	D113	204BS08021B	1	1
11924809	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	Weight Room	204BS08021B	1	0.7
11924810	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	Weight Room Office	204BS08021B	1	0.6
11924811	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	Gym	204BS08021B	1	< 0.3
11924812	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	Gym	204BS08021B	1	< 0.3
11924813	01/13/2025	1700	01/15/2025	Missing	70	Thomas Jefferson High	Activities	Gym	204BS08021B	1	Missing
11924815	01/13/2025	1700	01/15/2025	1700	70	Thomas Jefferson High	Activities	Gym	204BS08021B	1	< 0.3

APPENDIX B
CERTIFICATIONS

National Radon Proficiency Program



Stephen Sycuro
Radon Measurement Professional

ID Number: #108954-RMP Valid 2024-10-03 - 2026-11-30

To confirm validity of this certification call 828-348-0185. Verification of adherence to state and local regulations is advised. See reverse for specific certification designations.

Stephen Sycuro #108954-RMP

This individual is certified for the use of passive measurement devices to be analyzed by NRPP certified Analytical Laboratories and also certified to provide Analytical Services using the following device(s):

AC-8200 Air Chek Foil Bag
AT-8207 RSSI AT-101

The radon office for the state in which this person resides may be contacted for information on radon and local requirements. For additional information contact NRPP at 828-348-0185, or visit the NRPP web-site at nrpp.info
State Radon Program Contact Number: (402) 471-0783

**Bureau of Radiological Health
Radon Measurement Specialist Certification**

Stephen Sycuro

Certification #: RNTST10107

Has complied with the requirements and is hereby authorized to perform radon testing pursuant to Iowa code 136B and 641 Iowa Administrative Code Chapter 43.

Approved Testing Methods:

AT-Alpha-Track Detection

CC-Activated Charcoal Adsorption

LS-Charcoal Liquid Scintillation

Expiration: June 30, 2025



CEU Due Date: June 30, 2025

Radiological Health | Iowa Department of Public Health | Lucas State Office Building | Des Moines, IA 50319

Fold here to mail - Cut here to display

Stephen Sycuro
11117 MOCKINGBIRD DRIVE
OMAHA, NE 68137
UNITED STA

Fold here to mail