



Erate 470 #250010033

Clarifications from Walkthrough

Project Overall

- Project will be completed over summer of 2025
- Must be completed before August 22nd
- Working hours 6am-9pm Monday-Friday
- Tom will be onsite for questions
- District Provides Patch Cables
- Most of the present cable is from the late 90's
- Access panels, if they are needed, will be purchased and installed by the district
 - We do not currently foresee any need for Access Panels
- The District has inventoried teacher drop locations in each room
 - The 2 new drops can follow the location of the existing drops even when not located in the same location as the wall phone

Cabling

- Blue Category 6A
- Shielded where needed
 - Currently we do not see any location where shielded will be needed

Terminations

- 6 drops inside the classrooms
- AP drops(2) need to be at the current location of the AP
- Other above ceiling at Projector
- Surface Mount box with jack(s) in the ceilings
- 2 drops in the hallway locations
- Both end (color) have to be matching jacks
- 3 patch panels per IDF
- 48 port patch panels
- Wall plates for the telephones to be reused.
-

Existing Cable Removal

- Contractor to Demo old networking, Install new and remove existing at each location
- Some of the Science rooms were computer labs, The district will handle the demo for this.



Room Specific

- 3rd Floor “Mezzanine”\Tech Office
 - 2 AP, 4 drops each side of the room by desks
- Room 138 Lab
 - 33 total drops = 26 computers, 2 printers, 1 projector, 1 teacher phone, 2 AP
- For the new IDF (rm 207)
 - The district will handle relocation of the fiber from the current location to the new

Bidder Q&A

No Questions were submitted

Updated Maps

Attached is an updated set of maps reflecting the change in drops for the computer lab (Rm 138) we visited.

