

Dayton's Bluff Elementary School

Inspection Date: 8/13/2024

262 Bates Avenue, Saint Paul, MN 55106

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A	Mudded Pipe Joints on Fiberglass Insulation 1973 Original Building					Total Amount - 441 Joints
	4	BOILER ROOM 1109	NONE DETECTED	207A1A, 509J3, 509J4;		150 Joints
	15	FAN ROOM 1108	NONE DETECTED			50 Joints
	18	TUNNELS THROUGHOUT	NONE DETECTED	100A2A		100 Joints
	43	LOADING DOCK AREA	NONE DETECTED			17 Joints
	45	CUSTODIAL ROOM 1206 OFF LOADING DOCK	NONE DETECTED			8 Joints
	47	STORE ROOM 1208 OFF LOADING DOCK	NONE DETECTED			2 Joints
	51	FAN ROOM 1207 OFF LOADING DOCK	NONE DETECTED			45 Joints
	54	ELEVATOR EQUIPMENT ROOM 1311	NONE DETECTED			8 Joints
	212	CUSTODIAL ROOM 2205	NONE DETECTED	101708ML-2		25 Joints
	213	GYMNASIUM 2101	NONE DETECTED	100A2B, 100A2C		8 Joints
	216	GYMNASIUM STORAGE 2101A	NONE DETECTED			4 Joints
	218	GYMNASIUM STORAGE 2101B	NONE DETECTED			9 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	220	CUSTODIAL ROOM 2102	NONE DETECTED			15 Joints
C1A		Condensate Return Insulation				Total Amount - 30 Sq Ft
	5	BOILER ROOM 1109	NONE DETECTED	ACB450-A001, 2001-1901-DBEW-1A, 2A		30 Sq Ft
C3A		Miscellaneous Tank Insulation Heat Exchanger (1973)				Total Amount - 50 Sq Ft
	6	BOILER ROOM 1109	NONE DETECTED	101708ML-5, 6, 7		50 Sq Ft
D1A		Boiler Gaskets Door Gasket				Total Amount - 2 Sq Ft
	7	BOILER ROOM 1109	75 CH	101708ML-4		2 Sq Ft
D2A		Interior Boiler Insulation Interior Burner Refractory				Total Amount - 40 Sq Ft
	8	BOILER ROOM 1109	ASSUMED			40 Sq Ft
E0A		Stack Insulation 1973 Original Building				Total Amount - 80 Sq Ft
	9	BOILER ROOM 1109	NONE DETECTED	433-2, 3, 4		80 Sq Ft
E1A		Stack Gasket				Total Amount - 2 Sq Ft
	10	BOILER ROOM 1109	75 CH	101708ML-3		2 Sq Ft
I1A		1' x 1' Acoustical Ceiling Tile Smooth				Total Amount - 1130 Sq Ft
	197	KITCHEN AREAS 2202-2204	NONE DETECTED	207-A-4-A		1080 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	201	BACK AREA OFF KITCHEN & STAIRWELL 2202B	NONE DETECTED			50 Sq Ft
I1B	1' x 1' Acoustical Ceiling Tile Rough Texture w/Deep Grooves					Total Amount - 20405 Sq Ft
	19	MEDIA CENTER & WORK ROOMS 1101	NONE DETECTED			2200 Sq Ft
	29	ECFE HALLWAY 1200	NONE DETECTED			150 Sq Ft
	31	THROUGHOUT ECFE AREA	NONE DETECTED			1070 Sq Ft
	48	STORE ROOM 1208 OFF LOADING DOCK	NONE DETECTED			11 Sq Ft
	57	RESTROOMS 1308 & 1309	NONE DETECTED			35 Sq Ft
	59	HALLWAY 1300B CLASSROOMS 1301-1307	NONE DETECTED			105 Sq Ft
	64	CLASSROOMS 1301-1307	NONE DETECTED			2280 Sq Ft
	70	1ST FLOOR MAIN HALLWAY 1100	NONE DETECTED			800 Sq Ft
	73	HALLWAY FOR CLASSROOMS 1401-1415	NONE DETECTED			215 Sq Ft
	77	CLASSROOMS 1401-1415	NONE DETECTED			3200 Sq Ft
	91	CUSTODIAL OFFICE 1414	NONE DETECTED			100 Sq Ft
	97	STORAGE 1412	NONE DETECTED			36 Sq Ft
	101	CUSTODIAL OFFICE 1411	NONE DETECTED			27 Sq Ft
	108	RESTROOMS 1417 & 1418	NONE DETECTED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	111	STAIRWELL 1415 TO ROOM 1513	NONE DETECTED			9 Sq Ft
	113	MUSIC ROOM 1513 & STORAGE	NONE DETECTED			120 Sq Ft
	119	ART ROOM 1516	NONE DETECTED			110 Sq Ft
	125	ART ROOM OFFICE 1514	NONE DETECTED			12 Sq Ft
	150	2ND FLOOR MAIN HALLWAY 2100	NONE DETECTED			1110 Sq Ft
	153	HALLWAYS 2400A & 2400B	NONE DETECTED			750 Sq Ft
	157	CLASSROOMS 2401-2410	NONE DETECTED			3350 Sq Ft
	163	STAIRWELL 2499B	NONE DETECTED			6 Sq Ft
	166	RESTROOM 2413 & 2414	NONE DETECTED			20 Sq Ft
	169	HALLWAY 2300A	NONE DETECTED			450 Sq Ft
	173	CLASSROOMS 2301-2307	NONE DETECTED			2500 Sq Ft
	179	STAIRWELL 2399A BY ROOM 2305	NONE DETECTED			6 Sq Ft
	183	ROOM 2313	NONE DETECTED			95 Sq Ft
	188	RESTROOMS 2311 & 2312	NONE DETECTED			200 Sq Ft
	192	RESTROOMS 2308 & 2309	NONE DETECTED			35 Sq Ft
	205	KITCHEN LOCKER ROOM 2202A	NONE DETECTED			40 Sq Ft
	209	HALLWAY 2200	NONE DETECTED			180 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	221	PHY ED OFFICE 2103	NONE DETECTED			27 Sq Ft
	225	ROOM 2103A	NONE DETECTED			36 Sq Ft
	229	MAIN OFFICE AREA 2001	NONE DETECTED	100-A-3-A	OFFICE AREA.	1100 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Light Texture w/Revealed Edge (1999)					Total Amount - 4761 Sq Ft
	127	ART ROOM OFFICE 1514	NONE DETECTED	101708ML-20		120 Sq Ft
	131	ROOM 1510	NONE DETECTED			400 Sq Ft
	138	HALLWAY 1500 FROM ROOM 1510 TO STAIRS	NONE DETECTED			1000 Sq Ft
	140	ROOM 1504	NONE DETECTED			176 Sq Ft
	231	MAIN OFFICE AREA 2001	NONE DETECTED			1000 Sq Ft
	244	OFFICES & HALLWAY 2000A NORTH OF MAIN OFFICE	NONE DETECTED			2000 Sq Ft
	255	ENTRANCE TO OFFICE & ADULT RESTROOMS	NONE DETECTED			65 Sq Ft
I4A	Acoustical Ceiling Tile Tectum					Total Amount - 10000 Sq Ft
	194	CAFETERIA 2201	NONE DETECTED	207-A-3-A		4000 Sq Ft
	214	GYMNASIUM 2101	NONE DETECTED			6000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K1A	Sheet Vinyl Flooring & Adhesive Gray		Total Amount - 1010 Sq Ft			
	67	CLASSROOMS 1301-1307	NONE DETECTED			170 Sq Ft
	80	CLASSROOMS 1401-1415	NONE DETECTED	072315JP-02	JP-02: ROOM 1401 L/S SINK VANITY.	500 Sq Ft
	160	CLASSROOMS 2401-2410	NONE DETECTED			150 Sq Ft
	176	CLASSROOMS 2301-2307	NONE DETECTED			150 Sq Ft
	186	ROOM 2313	NONE DETECTED			40 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Beige w/Light Brown Streaks		Total Amount - 1630 Sq Ft			
	35	ROOM 1201	4-8 CH (TILE)	433-1	433-1: OLD SCIENCE ROOM (SINCE REMOVED).	400 Sq Ft
	36	ROOM 1204	4-8 CH (TILE)			700 Sq Ft
	38	ROOM 1203	4-8 CH (TILE)			150 Sq Ft
	39	ROOM 1202	4-8 CH (TILE)			380 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic Beige w/Multi-Colored Streaks		Total Amount - 8095 Sq Ft			
	106	STORAGE 1413	3-20 CH (TILE & MASTIC)			25 Sq Ft
	195	CAFETERIA 2201	3-20 CH (TILE & MASTIC)			2350 Sq Ft
	196	CAFETERIA STORAGE 2201A	3-20 CH (TILE & MASTIC)			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	203	BACK AREA OFF KITCHEN & STAIRWELL 2202B	3-20 CH (TILE & MASTIC)			160 Sq Ft
	206	KITCHEN LOCKER ROOM 2202A	3-20 CH (TILE & MASTIC)			20 Sq Ft
	215	GYMNASIUM 2101	3-20 CH (TILE & MASTIC)	2001-1901-DB-2	DB-2: GYMNASIUM.	4800 Sq Ft
	217	GYMNASIUM STORAGE 2101A	3-20 CH (TILE & MASTIC)			270 Sq Ft
	219	GYMNASIUM STORAGE 2101B	3-20 CH (TILE & MASTIC)			270 Sq Ft
K2C	12" x 12" Vinyl Floor Tile & Mastic White w/Black Streaks					Total Amount - 50 Sq Ft
	41	ECFE RESTROOM 1205	ASSUMED			50 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic Beige w/Multi-Colored Smudges (1999)					Total Amount - 1903 Sq Ft
	117	MUSIC STORAGE 1515	NONE DETECTED	101708ML-22		115 Sq Ft
	122	ART ROOM 1516	NONE DETECTED			600 Sq Ft
	128	ART ROOM OFFICE 1514	NONE DETECTED			100 Sq Ft
	133	ROOM 1510	NONE DETECTED			200 Sq Ft
	141	ROOM 1504	NONE DETECTED			176 Sq Ft
	223	PHY ED OFFICE 2103	NONE DETECTED			280 Sq Ft
	227	ROOM 2103A	NONE DETECTED			80 Sq Ft
	235	WORK ROOM 2018	NONE DETECTED			80 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	241	NURSE'S OFFICE 2010	NONE DETECTED			200 Sq Ft
	252	KITCHEN 2002A	NONE DETECTED			72 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Tan w/Gray Smudges					Total Amount - 65 Sq Ft
	256	ENTRANCE TO OFFICE & ADULT RESTROOMS	NONE DETECTED	101708ML-19	BY STAFF RESTROOMS.	65 Sq Ft
K3A	Miscellaneous Flooring Black Flooring Mastic					Total Amount - 870 Sq Ft
	233	MAIN OFFICE AREA 2001	5 CH	101708ML-17	ML-17: BY ROOM 2015.	330 Sq Ft
	237	OFFICE 2019	5 CH			120 Sq Ft
	238	OFFICE 2020	5 CH			120 Sq Ft
	239	OFFICE 2015	5 CH			150 Sq Ft
	240	OFFICE 2014	5 CH			150 Sq Ft
L0A	Flexible Duct Connector Black Vinyl					Total Amount - 50 Sq Ft
	13	BOILER ROOM 1109 & FAN ROOM 1108	NSM			20 Sq Ft
	52	FAN ROOM 1207 OFF LOADING DOCK	NSM			10 Sq Ft
	147	MECHANICAL ROOM 1503	NSM			20 Sq Ft
M0A	Plaster					Total Amount - 1000 Sq Ft
	3	BOILER ROOM 1109	NONE DETECTED	101708ML-8, 9; 509J2;433-6	433-6: OLD BAND AREA (SINCE REMOVED).	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
N0A	Drywall/Joint Compound					Total Amount - 40000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	433-5;509J1	433-5: ROOM 1515.	40000 Sq Ft
P0A	Fire Doors Wood - 1.5 Hr Rating (Warnock Hersey)					Total Amount - 60 Sq Ft
	11	BOILER ROOM 1109	NEW			20 Sq Ft
	146	ELEVATOR ROOM 1504B	NEW			20 Sq Ft
	246	OFFICES & HALLWAY 2000A NORTH OF MAIN OFFICE	NEW			20 Sq Ft
P0B	Fire Doors Laminate -Not Rated (Weldwood)					Total Amount - 340 Sq Ft
	12	BOILER ROOM 1109	45 CH			20 Sq Ft
	14	FAN ROOM 1108	45 CH			20 Sq Ft
	44	LOADING DOCK AREA	45 CH			20 Sq Ft
	46	CUSTODIAL ROOM 1206 OFF LOADING DOCK	45 CH			20 Sq Ft
	53	FAN ROOM 1207 OFF LOADING DOCK	45 CH			20 Sq Ft
	55	ELEVATOR EQUIPMENT ROOM 1311	45 CH			20 Sq Ft
	56	CUSTODIAL CLOSET 1310	45 CH			20 Sq Ft
	63	HALLWAY 1300B CLASSROOMS 1301-1307	45 CH			40 Sq Ft
	83	ROOM 1407	45 CH			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	86	ROOM 1408	45 CH			20 Sq Ft
	110	CUSTODIAL ROOM 1416A	45 CH			20 Sq Ft
	165	STAIRWELL 2499B	45 CH	062923BF-1	BF-1: STAIRWELL 2499B.	20 Sq Ft
	168	CUSTODIAL ROOM 2412	45 CH			20 Sq Ft
	182	STAIRWELL 2399A BY ROOM 2305	45 CH			20 Sq Ft
	191	CUSTODIAL ROOM 2310	45 CH			20 Sq Ft
	208	CUSTODIAL ROOM 2202C BY KITCHEN	45 CH			20 Sq Ft
Q0A	Carpet Adhesive Pink/Blue/Gray Carpet					Total Amount - 61560 Sq Ft
	21	MEDIA CENTER & WORK ROOMS 1101	NONE DETECTED	2001-1901-XX-12-B	XX-12-B: MEDIA CENTER BY 1107.	7200 Sq Ft
	33	THROUGHOUT ECFE AREA	NONE DETECTED			2500 Sq Ft
	61	HALLWAY 1300B CLASSROOMS 1301-1307	NONE DETECTED			350 Sq Ft
	66	CLASSROOMS 1301-1307	NONE DETECTED			7600 Sq Ft
	72	1ST FLOOR MAIN HALLWAY 1100	NONE DETECTED			4000 Sq Ft
	75	HALLWAY FOR CLASSROOMS 1401-1415	NONE DETECTED			720 Sq Ft
	79	CLASSROOMS 1401-1415	NONE DETECTED			10600 Sq Ft
	93	CUSTODIAL OFFICE 1414	NONE DETECTED			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	99	STORAGE 1412	NONE DETECTED			100 Sq Ft
	103	CUSTODIAL OFFICE 1411	NONE DETECTED			120 Sq Ft
	152	2ND FLOOR MAIN HALLWAY 2100	NONE DETECTED			3700 Sq Ft
	155	HALLWAYS 2400A & 2400B	NONE DETECTED			2500 Sq Ft
	159	CLASSROOMS 2401-2410	NONE DETECTED			11200 Sq Ft
	171	HALLWAY 2300A	NONE DETECTED			1500 Sq Ft
	175	CLASSROOMS 2301-2307	NONE DETECTED			8400 Sq Ft
	185	ROOM 2313	NONE DETECTED			270 Sq Ft
	211	HALLWAY 2200	NONE DETECTED			600 Sq Ft
Q0B	Carpet Adhesive 1999 Installation				Total Amount - 5700 Sq Ft	
	132	ROOM 1510	NONE DETECTED			500 Sq Ft
	139	HALLWAY 1500 FROM ROOM 1510 TO STAIRS	NONE DETECTED			1000 Sq Ft
	232	MAIN OFFICE AREA 2001	NONE DETECTED	101708ML-18		2200 Sq Ft
	245	OFFICES & HALLWAY 2000A NORTH OF MAIN OFFICE	NONE DETECTED			2000 Sq Ft
Q0C	Carpet Adhesive Green/Purple/Tan Berber Carpet				Total Amount - 1080 Sq Ft	
	24	MEDIA CENTER WORK ROOM 1105	NEW			180 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	26	MEDIA CENTER WORK ROOM 1104	NEW			180 Sq Ft
	115	MUSIC ROOM 1513	NEW			600 Sq Ft
	121	ART ROOM 1516	NEW			120 Sq Ft
ROA	Baseboard/Mopboard Adhesive Black Baseboard					Total Amount - 4530 Sq Ft
	22	MEDIA CENTER & WORK ROOMS 1101	NONE DETECTED	2001-1901-XX-13B	MEDIA CENTER BY ROOM 1107.	120 Sq Ft
	34	THROUGHOUT ECFE AREA	NONE DETECTED			100 Sq Ft
	62	HALLWAY 1300B CLASSROOMS 1301-1307	NONE DETECTED			100 Sq Ft
	68	CLASSROOMS 1301-1307	NONE DETECTED			925 Sq Ft
	76	HALLWAY FOR CLASSROOMS 1401-1415	NONE DETECTED			120 Sq Ft
	81	CLASSROOMS 1401-1415	NONE DETECTED			1400 Sq Ft
	94	CUSTODIAL OFFICE 1414	NONE DETECTED			10 Sq Ft
	100	STORAGE 1412	NONE DETECTED			10 Sq Ft
	104	CUSTODIAL OFFICE 1411	NONE DETECTED			10 Sq Ft
	156	HALLWAYS 2400A & 2400B	NONE DETECTED			200 Sq Ft
	161	CLASSROOMS 2401-2410	NONE DETECTED			300 Sq Ft
	172	HALLWAY 2300A	NONE DETECTED			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	177	CLASSROOMS 2301-2307	NONE DETECTED			1175 Sq Ft
	204	BACK AREA OFF KITCHEN & STAIRWELL 2202B	NONE DETECTED			10 Sq Ft
ROB	Baseboard/Mopboard Adhesive 4" Tan Baseboard (1999)					Total Amount - 125 Sq Ft
	118	MUSIC STORAGE 1515	NONE DETECTED	101708ML-23		10 Sq Ft
	123	ART ROOM 1516	NONE DETECTED			25 Sq Ft
	129	ART ROOM OFFICE 1514	NONE DETECTED			5 Sq Ft
	134	ROOM 1510	NONE DETECTED			20 Sq Ft
	142	ROOM 1504	NONE DETECTED			10 Sq Ft
	224	PHY ED OFFICE 2103	NONE DETECTED			5 Sq Ft
	228	ROOM 2103A	NONE DETECTED			10 Sq Ft
	236	WORK ROOM 2018	NONE DETECTED			10 Sq Ft
	242	NURSE'S OFFICE 2010	NONE DETECTED			20 Sq Ft
	253	KITCHEN 2002A	NONE DETECTED			5 Sq Ft
	257	ENTRANCE TO OFFICE & ADULT RESTROOMS	NONE DETECTED			5 Sq Ft
ROC	Baseboard/Mopboard Adhesive 4" Green					Total Amount - 120 Sq Ft
	25	MEDIA CENTER WORK ROOM 1105	NONE DETECTED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	27	MEDIA CENTER WORK ROOM 1104	NONE DETECTED			10 Sq Ft
	234	MAIN OFFICE AREA 2001	NONE DETECTED	101708ML-21	ML-21: MUSIC ROOM 1513 (SINCE REMOVED).	100 Sq Ft
R0D	Baseboard/Mopboard Adhesive 4" Green Baseboard					Total Amount - 25 Sq Ft
	116	MUSIC ROOM 1513	NEW			25 Sq Ft
U0A	Light Pad Insulation White Fibrous					Total Amount - 1 Sq Ft
	107	STORAGE 1413	65 CH	101708ML-1		1 Sq Ft
U0B	Light Pad Insulation Square (1973)					Total Amount - 5 Sq Ft
	23	MEDIA CENTER WORK ROOM 1107	ASSUMED			2 Sq Ft
	50	STORE ROOM 1208 OFF LOADING DOCK	ASSUMED			1 Sq Ft
	181	STAIRWELL 2399A BY ROOM 2305	ASSUMED			2 Sq Ft
VOA	Sink Undercoating Pink					Total Amount - 132 Sq Ft
	28	MEDIA CENTER WORK ROOM 1103	10 CH	101708ML-15		4 Sq Ft
	69	CLASSROOMS 1301-1307	10 CH			28 Sq Ft
	82	CLASSROOMS 1401-1415	10 CH			24 Sq Ft
	105	CUSTODIAL OFFICE 1411	10 CH			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	162	CLASSROOMS 2401-2410	10 CH			40 Sq Ft
	178	CLASSROOMS 2301-2307	10 CH			28 Sq Ft
	187	ROOM 2313	10 CH			4 Sq Ft
V0B	Sink Undercoating Gray (1999)					Total Amount - 46 Sq Ft
	37	ROOM 1204	NONE DETECTED	101708ML-13		8 Sq Ft
	124	ART ROOM 1516	NONE DETECTED			8 Sq Ft
	135	ROOM 1510	NONE DETECTED			4 Sq Ft
	143	ROOM 1504	NONE DETECTED			5 Sq Ft
	243	NURSE'S OFFICE 2010	NONE DETECTED			4 Sq Ft
	249	ROOM 2012 (DENTAL OFFICE)	NONE DETECTED			4 Sq Ft
	250	ROOM 2011 (NURSE PRACTITIONER)	NONE DETECTED			4 Sq Ft
	251	ROOM 2008 (STAFF LOUNGE)	NONE DETECTED			4 Sq Ft
	254	KITCHEN 2002A	NONE DETECTED			5 Sq Ft
V0C	Sink Undercoating Black					Total Amount - 16 Sq Ft
	40	ROOM 1202	3 CH			8 Sq Ft
	42	ECFE RESTROOM 1205	3 CH	101708ML-14		8 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A				Total Amount - 210 Sq Ft	
	198	KITCHEN AREAS 2202-2204	NONE DETECTED	101708ML-25		200 Sq Ft
	202	BACK AREA OFF KITCHEN & STAIRWELL 2202B	NONE DETECTED			10 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B				Total Amount - 4732 Sq Ft	
	20	MEDIA CENTER & WORK ROOMS 1101	NONE DETECTED			500 Sq Ft
	30	ECFE HALLWAY 1200	NONE DETECTED			30 Sq Ft
	32	THROUGHOUT ECFE AREA	NONE DETECTED			250 Sq Ft
	49	STORE ROOM 1208 OFF LOADING DOCK	NONE DETECTED			3 Sq Ft
	58	RESTROOMS 1308 & 1309	NONE DETECTED			8 Sq Ft
	60	HALLWAY 1300B CLASSROOMS 1301-1307	NONE DETECTED			20 Sq Ft
	65	CLASSROOMS 1301-1307	NONE DETECTED			600 Sq Ft
	71	1ST FLOOR MAIN HALLWAY 1100	NONE DETECTED			200 Sq Ft
	74	HALLWAY FOR CLASSROOMS 1401-1415	NONE DETECTED			50 Sq Ft
	78	CLASSROOMS 1401-1415	NONE DETECTED			800 Sq Ft
	92	CUSTODIAL OFFICE 1414	NONE DETECTED			20 Sq Ft
	98	STORAGE 1412	NONE DETECTED			8 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	102	CUSTODIAL OFFICE 1411	NONE DETECTED			5 Sq Ft
	109	RESTROOMS 1417 & 1418	NONE DETECTED			5 Sq Ft
	112	STAIRWELL 1415 TO ROOM 1513	NONE DETECTED			3 Sq Ft
	114	MUSIC ROOM 1513 & STORAGE	NONE DETECTED	101708ML-24		40 Sq Ft
	120	ART ROOM 1516	NONE DETECTED			25 Sq Ft
	126	ART ROOM OFFICE 1514	NONE DETECTED			3 Sq Ft
	151	2ND FLOOR MAIN HALLWAY 2100	NONE DETECTED			250 Sq Ft
	154	HALLWAYS 2400A & 2400B	NONE DETECTED			150 Sq Ft
	158	CLASSROOMS 2401-2410	NONE DETECTED			700 Sq Ft
	164	STAIRWELL 2499B	NONE DETECTED			2 Sq Ft
	167	RESTROOM 2413 & 2414	NONE DETECTED			5 Sq Ft
	170	HALLWAY 2300A	NONE DETECTED			120 Sq Ft
	174	CLASSROOMS 2301-2307	NONE DETECTED			600 Sq Ft
	180	STAIRWELL 2399A BY ROOM 2305	NONE DETECTED			2 Sq Ft
	184	ROOM 2313	NONE DETECTED			20 Sq Ft
	193	RESTROOMS 2308 & 2309	NONE DETECTED			8 Sq Ft
	210	HALLWAY 2200	NONE DETECTED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	222	PHY ED OFFICE 2103	NONE DETECTED			6 Sq Ft
	226	ROOM 2103A	NONE DETECTED			9 Sq Ft
	230	MAIN OFFICE AREA 2001	NONE DETECTED	101708ML-16	ML-16: ROOM 2020.	250 Sq Ft
X0A	Miscellaneous Material Interior Side Light Window Glazing Compound					Total Amount - 200 Sq Ft
	2	THROUGHOUT BUILDING	10 CH	101708ML-12	OUTSIDE ROOM 1401.	200 Sq Ft
X0D	Miscellaneous Material AHU Seam Caulk (Gray)					Total Amount - 10 Sq Ft
	16	FAN ROOM 1108	NONE DETECTED	101708ML-10	ROOM 1108.	10 Sq Ft
X0E	Miscellaneous Material AHU Penetration Putty (White)					Total Amount - 5 Sq Ft
	17	FAN ROOM 1108	NONE DETECTED	101708ML-11	ROOM 1108.	5 Sq Ft
X0F	Miscellaneous Material Dark Brown Expansion Caulk					Total Amount - 20 Sq Ft
	149	MAIN STAIRCASES FROM HALLWAY 1100 TO 2100	ASSUMED			20 Sq Ft
X1A	Miscellaneous Material Tan/Black Ceramic Floor Tile System (2015)					Total Amount - 730 Sq Ft
	199	KITCHEN AREAS 2202 & 2204	NEW			580 Sq Ft
	200	KITCHEN OFFICE 2203	NEW			150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1B	Miscellaneous Material 1" Light Gray Ceramic Floor Tile System				Total Amount - 300 Sq Ft	
	84	ROOM 1407 RESTROOM (1407B)	ASSUMED			20 Sq Ft
	87	ROOM 1408 RESTROOM (1408B)	ASSUMED			20 Sq Ft
	89	ROOM 1409 RESTROOM (1409A)	ASSUMED			20 Sq Ft
	95	CUSTODIAL OFFICE RESTROOM 1414A	ASSUMED			20 Sq Ft
	189	RESTROOMS 2311 & 2312	ASSUMED			200 Sq Ft
	207	KITCHEN LOCKER ROOM 2202A	ASSUMED			20 Sq Ft
X1C	Miscellaneous Material 1" X 2" Light Gray Ceramic Wall Tile System				Total Amount - 980 Sq Ft	
	85	ROOM 1407 RESTROOM (1407B)	ASSUMED			100 Sq Ft
	88	ROOM 1408 RESTROOM (1408B)	ASSUMED			100 Sq Ft
	90	ROOM 1409 RESTROOM (1409A)	ASSUMED			100 Sq Ft
	96	CUSTODIAL OFFICE RESTROOM 1414A	ASSUMED			80 Sq Ft
	190	RESTROOMS 2311 & 2312	ASSUMED			600 Sq Ft
X1D	Miscellaneous Material 1' X 1' Green/Gray Stone Floor Tile System (1999)				Total Amount - 604 Sq Ft	
	130	ENTRANCE 1400A	NEW			280 Sq Ft
	258	ADULT RESTROOMS 2014 & 2105	NEW			324 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1E	Miscellaneous Material 4" Ceramic Wall Tile System (1999)					Total Amount - 1000 Sq Ft
	136	ROOM 1510 RESTROOM (1511)	NEW			100 Sq Ft
	144	ROOM 1504 RESTROOM (1504A)	NEW			100 Sq Ft
	247	RESTROOM 2009 NEAR ROOM 2008	NEW			200 Sq Ft
	259	ADULT RESTROOMS 2014 & 2105	NEW			600 Sq Ft
X1F	Miscellaneous Material 2" Ceramic Floor Tile System (1999)					Total Amount - 120 Sq Ft
	137	ROOM 1510 RESTROOM (1511)	NEW			30 Sq Ft
	145	ROOM 1504 RESTROOM (1504A)	NEW			30 Sq Ft
	248	RESTROOM 2009 NEAR ROOM 2008	NEW			60 Sq Ft
X1G	Miscellaneous Material 1' X 2' Beige Stone Floor Tile System (1999)					Total Amount - 400 Sq Ft
	148	STAIRS FROM 1500 HALLWAY TO REC CENTER.	NEW			400 Sq Ft