

437 Edmond Avenue, Saint Paul, MN 55103

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A1A	Mudded Pipe Joints on Air Cell Insulation 1923 Original Building					Total Amount - 20 Joints
	6	THROUGHOUT 1923 ORIGINAL BUILDING	40 CH	207-P-1A	1A: BOILER ROOM.	20 Joints
A4B	Mudded Pipe Joints on Fiberglass Insulation 1971 Addition					Total Amount - 9 Joints
	21	ROOM 1115	3 CH	500-JJT-29	JJT-29: SOUTHEAST SIDE OF ROOM BY 2ND LIGHT FROM EAST WALL.	3 Joints
	30	ROOM 1116	3 CH	500-JJT-25	JJT-25: NORTHEAST CORNER NEXT TO LIGHT.	2 Joints
	198	ROOM 2113	3 CH	500-JJT-20		2 Joints
	203	ROOM 2116	3 CH			2 Joints
B1A	Air Cell Pipe Insulation 1923 Original Building					Total Amount - 100 Lin Ft
	5	THROUGHOUT 1923 ORIGINAL BUILDING	40 CH	207-P-2A	2A: BOILER ROOM.	100 Lin Ft
D1A	Boiler Gaskets Fiberglass					Total Amount - 5 Sq Ft
	11	1923 ORIGINAL BUILDING BOILER ROOM 0100	NONE DETECTED	2001-1504-CC3		5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D2A	Interior Boiler Insulation Back Panel					Total Amount - 10 Sq Ft
	8	1923 ORIGINAL BUILDING BOILER ROOM 0100	NONE DETECTED	100510-ML-25	ML-25: BOILER ROOM 0100.	10 Sq Ft
D2B	Interior Boiler Insulation Front Panel					Total Amount - 10 Sq Ft
	9	1923 ORIGINAL BUILDING BOILER ROOM 0100	NONE DETECTED	100510-ML-19	ML-25: BOILER ROOM 0100.	10 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Pegboard					Total Amount - 1790 Sq Ft
	52	ROOM 1110	NONE DETECTED	207P6A		50 Sq Ft
	61	ROOM 1109	NONE DETECTED			60 Sq Ft
	65	ROOM 1001 (MAIN OFFICE)	NONE DETECTED	500-JJT-12	JJT-12: ABOVE WEST WINDOW.	75 Sq Ft
	68	ROOM 1002	NONE DETECTED			50 Sq Ft
	71	ROOM 1003	NONE DETECTED			25 Sq Ft
	74	ROOM 1004	NONE DETECTED			40 Sq Ft
	82	1923 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1100 OUTSIDE ROOM 1102	NONE DETECTED			350 Sq Ft
	87	ROOM 1102	NONE DETECTED			620 Sq Ft
	93	ROOM 1103	NONE DETECTED			150 Sq Ft
	99	ROOM 1104	NONE DETECTED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	103	ROOM 1105	NONE DETECTED			120 Sq Ft
	107	ROOM 1106	NONE DETECTED			80 Sq Ft
	112	ROOM 1107	NONE DETECTED			70 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Gouges & Pin Holes					Total Amount - 5830 Sq Ft
	54	ROOM 1110	NONE DETECTED			200 Sq Ft
	60	ROOM 1109	NONE DETECTED			300 Sq Ft
	64	ROOM 1001 (MAIN OFFICE)	NONE DETECTED			300 Sq Ft
	67	ROOM 1002	NONE DETECTED			200 Sq Ft
	70	ROOM 1003	NONE DETECTED			60 Sq Ft
	73	ROOM 1004	NONE DETECTED			100 Sq Ft
	109	ROOM 1106	NONE DETECTED			110 Sq Ft
	119	1923 ORIGINAL BUILDING 1ST FLOOR BOYS' RESTROOM 1101	NONE DETECTED			40 Sq Ft
	128	1ST FLOOR NORTH HALLWAY 1200	NONE DETECTED	100510-ML-01	ML-01: OUTSIDE ROOM 1209.	920 Sq Ft
	132	ROOM 1204	NONE DETECTED			1000 Sq Ft
	137	ROOM 1206	NONE DETECTED			1000 Sq Ft
	145	ROOM 1208	NONE DETECTED			800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	150	ROOM 1210	NONE DETECTED			800 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Fissures & Nail Holes					Total Amount - 35 Sq Ft
	46	ROOM 1114 STORAGE	NONE DETECTED	100510-ML-02		35 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Vinyl-Coated Gypsum (2004)					Total Amount - 820 Sq Ft
	155	ROOM 1213 (KITCHEN)	NSM			680 Sq Ft
	157	ROOM 1214 (KITCHEN OFFICE/DRY STORAGE)	NSM			140 Sq Ft
I3A	2' x 4' Ceiling Tile Textured w/Pin Holes					Total Amount - 5225 Sq Ft
	22	ROOM 1115	NONE DETECTED	500-JJT-22	JJT-22: ABOVE MAIN DOOR 2ND TILE EAST.	700 Sq Ft
	31	ROOM 1116	NONE DETECTED			675 Sq Ft
	84	1ST FLOOR HALLWAY 1100 WEST END	NONE DETECTED	500-JJT-18	JJT-18: ABOVE WEST DOOR JAMB TO ROOM 1102.	250 Sq Ft
	199	ROOM 2113	NONE DETECTED			900 Sq Ft
	204	ROOM 2116	NONE DETECTED			900 Sq Ft
	211	ROOM 3111	NONE DETECTED			900 Sq Ft
	216	ROOM 3114	NONE DETECTED			900 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3B	2' x 4' Ceiling Tile Gouges & Pin Holes	Total Amount - 160 Sq Ft				
85	1ST FLOOR HALLWAY 1100 WEST END	NONE DETECTED	091310-ML-07	ML-07: 1ST FLOOR SOUTHWEST HALLWAY.	160 Sq Ft	
I3C	2' x 4' Ceiling Tile Bumpy Texture w/Cuts & Pin Holes	Total Amount - 3300 Sq Ft				
19	1971 ADDITION HALLWAY 1100D	NONE DETECTED	100510-ML-03		300 Sq Ft	
37	1999 ADDITION LIBRARY ROOMS 1117-1120	NONE DETECTED			3000 Sq Ft	
I3D	2' x 4' Ceiling Tile Cracked Mud w/Pin Holes	Total Amount - 2500 Sq Ft				
123	THROUGHOUT 1998 ADDITION 1ST FLOOR	NONE DETECTED	091310-ML-08		900 Sq Ft	
161	THROUGHOUT 1998 ADDITION 2ND FLOOR	NONE DETECTED			800 Sq Ft	
259	THROUGHOUT 1998 ADDITION 3RD FLOOR	NONE DETECTED			800 Sq Ft	
I3E	2' x 4' Ceiling Tile Widthwise Fissures w/Pin Holes	Total Amount - 12 Sq Ft				
248	CLOSET 3103A	NONE DETECTED	100510-ML-04		12 Sq Ft	
K0A	9" x 9" Vinyl Floor Tile & Mastic Gray	Total Amount - 875 Sq Ft				
167	1923 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2100	5 CH (TILE ONLY)	2001-01136-2		450 Sq Ft	
224	1923 ORIGINAL BUILDING 3RD FLOOR HALLWAY 3100	5 CH (TILE ONLY)			425 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K0B	9" x 9" Vinyl Floor Tile & Mastic Black		Total Amount - 875 Sq Ft			
	168	1923 ORIGINAL BUILDING 2ND FLOOR HALLWAY 2100	3 CH (TILE ONLY)			450 Sq Ft
	225	1923 ORIGINAL BUILDING 3RD FLOOR HALLWAY 3100	3 CH (TILE ONLY)	100510-ML-05	ML-05: OUTSIDE ROOM 3102.	425 Sq Ft
K0C	9" x 9" Vinyl Floor Tile & Mastic Light Brown w/Brown & Beige Streaks		Total Amount - 1345 Sq Ft			
	58	ROOM 1110A	5 CH (TILE ONLY)	2001-01136-3		30 Sq Ft
	77	ROOM 1004B	5 CH (TILE ONLY)			25 Sq Ft
	92	ROOM 1102	5 CH (TILE ONLY)	100510-ML-06		620 Sq Ft
	96	ROOM 1103	5 CH (TILE ONLY)			250 Sq Ft
	101	ROOM 1104 STORAGE	5 CH (TILE ONLY)			100 Sq Ft
	105	ROOM 1105	5 CH (TILE ONLY)			120 Sq Ft
	110	ROOM 1106	5 CH (TILE ONLY)			110 Sq Ft
	115	ROOM 1107	5 CH (TILE ONLY)			90 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Beige w/Gray & Pink Smudges		Total Amount - 3890 Sq Ft			
	7	RESTROOM OFF OF BOILER ROOM STAIRS	NONE DETECTED			20 Sq Ft
	18	1923 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1100	NONE DETECTED			660 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	20	1971 ADDITION HALLWAY 1100D	NONE DETECTED			300 Sq Ft
	86	1ST FLOOR HALLWAY 1100 WEST END	NONE DETECTED			410 Sq Ft
	124	THROUGHOUT 1998 ADDITION 1ST FLOOR	NONE DETECTED	100510-ML-08		900 Sq Ft
	162	THROUGHOUT 1998 ADDITION 2ND FLOOR	NONE DETECTED			800 Sq Ft
	260	THROUGHOUT 1998 ADDITION 3RD FLOOR	NONE DETECTED			800 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic Light Brown & Gray Mottle		Total Amount - 2445 Sq Ft			
	172	ROOM 2104	NONE DETECTED	2001-01136-4	01136-4: SOUTHEAST STAIRS (SINCE REMOVED).	875 Sq Ft
	232	ROOM 3107	NONE DETECTED			620 Sq Ft
	253	ROOM 3101	NONE DETECTED	500-JJT-1	JJT-1: BEHIND MIDDLE RADIATOR PIPE.	950 Sq Ft
K2C	12" x 12" Vinyl Floor Tile & Mastic Green w/White Flecks		Total Amount - 2375 Sq Ft			
	177	ROOM 2105	NONE DETECTED			875 Sq Ft
	180	ROOM 2108	NONE DETECTED	2001-1501-V10		620 Sq Ft
	188	ROOM 2109	NONE DETECTED			620 Sq Ft
	235	ROOM 3105	NONE DETECTED	100510-ML-09		260 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2D	12" x 12" Vinyl Floor Tile & Mastic Reddish Brown w/Brown & Beige Flecks		Total Amount - 1960 Sq Ft			
	185	ROOM 2112 (COPY ROOM)	NONE DETECTED			100 Sq Ft
	229	ROOM 3112	NONE DETECTED			620 Sq Ft
	242	ROOM 3106	NONE DETECTED			620 Sq Ft
	258	ROOM 3102	NONE DETECTED	500-JJT-3	JJT-3: BEHIND WEST RADIATOR PIPE.	620 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic White w/Gray Streaks		Total Amount - 250 Sq Ft			
	226	ROOM 4102	NONE DETECTED	100510-ML-07		125 Sq Ft
	252	ROOM 4101	NONE DETECTED			125 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Beige w/Brown & White Streaks		Total Amount - 4830 Sq Ft			
	131	1971 ADDITION GYMNASIUM 1207	3-10 CH (MASTIC ONLY)	100510-ML-10; 2001-01136-1	ML-10: AT DIVIDER.	4800 Sq Ft
	196	HALLWAY OUTSIDE ROOMS 2113 & 2116	3-10 CH (MASTIC ONLY)			15 Sq Ft
	209	HALLWAY OUTSIDE ROOMS 3111 & 3114	3-10 CH (MASTIC ONLY)			15 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle		Total Amount - 610 Sq Ft			
	16	1923 ORIGINAL BUILDING SOUTHEAST STAIRWELL	NONE DETECTED			260 Sq Ft
	78	1923 ORIGINAL BUILDING SOUTHWEST STAIRS	NONE DETECTED	100510-ML-11		350 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2H	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Multi-Colored Streaks					Total Amount - 16 Sq Ft
	217	ROOM 3114	NONE DETECTED	100510-ML-12		16 Sq Ft
K2J	12" x 12" Vinyl Floor Tile & Mastic White w/Multi-Shaded Smudges					Total Amount - 40 Sq Ft
	205	ROOM 2116	NONE DETECTED	100510-ML-13		40 Sq Ft
K2K	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Gray Flecks					Total Amount - 60 Sq Ft
	45	RESTROOM 1114B	NONE DETECTED	100510-ML-14		25 Sq Ft
	76	ROOM 1004A	NONE DETECTED			35 Sq Ft
K2L	12" x 12" Vinyl Floor Tile & Mastic Beige w/Brown Streaks					Total Amount - 900 Sq Ft
	39	ROOM 1114	3 CH (TILE), 7 CH (MASTIC)	091310-ML-06	ML-06: ROOM 1114.	900 Sq Ft
K2M	12" x 12" Vinyl Floor Tile & Mastic Blue Mottle (2004)					Total Amount - 12 Sq Ft
	23	ROOM 1115	NONE DETECTED	100510-ML-15		12 Sq Ft
K2N	12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan Flecks (2004)					Total Amount - 4655 Sq Ft
	120	1923 ORIGINAL BUILDING 1ST FLOOR BOYS' RESTROOM 1101	NONE DETECTED			40 Sq Ft
	129	1ST FLOOR NORTH HALLWAY 1200	NONE DETECTED			1600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	133	ROOM 1204	NONE DETECTED			250 Sq Ft
	138	ROOM 1206	NONE DETECTED			250 Sq Ft
	142	STORAGE 1209	NONE DETECTED			65 Sq Ft
	146	ROOM 1208	NONE DETECTED			200 Sq Ft
	151	ROOM 1210	NONE DETECTED			200 Sq Ft
	158	ROOM 1212 (CAFETERIA)	NONE DETECTED	100510-ML-16	ML-16: SOUTHWEST CORNER.	1650 Sq Ft
	160	ROOM 1212A	NONE DETECTED			400 Sq Ft
K3A	Miscellaneous Flooring Gray Stair Tread					Total Amount - 250 Sq Ft
	17	1923 ORIGINAL BUILDING SOUTHEAST STAIRWELL	NEW			250 Sq Ft
L0A	Flexible Duct Connector Black Vinyl					Total Amount - 5 Sq Ft
	166	1971 ADDITION ROOM 2102 MECHANICAL	NONE DETECTED	500-JJT-8	JJT-8: EAST JOINT MIDDLE TOP.	5 Sq Ft
L0B	Flexible Duct Connector Gray Fabric					Total Amount - 13 Sq Ft
	14	1923 ORIGINAL BUILDING AHU ROOM 0101	NONE DETECTED	500-JJT-19	JJT-19: FRONT OF AHU.	8 Sq Ft
	241	ROOM 3108 CUSTODIAL CLOSET ATTIC	NONE DETECTED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
M0A	Plaster 1923 Original Building	Total Amount - 50000 Sq Ft				
	4	THROUGHOUT 1923 ORIGINAL BUILDING	NONE DETECTED	091310-ML-01, 02, 03, 04, 05; 510-C-4; 500-JJT-15	ML-01: 1ST FLOOR CUSTODIAL CEILING. ML-02: HALLWAY OUTSIDE ROOM 1102 (WALL). ML-03: 2ND FLOOR CUSTODIAL CEILING. ML-04: ROOM 2101 WALL. ML-05: ROOM 3107 STORAGE (CEILING). C-4: (1994 DATA). JJT-15: 1ST FLOOR CUSTODIAL CLOSET.	50000 Sq Ft
N0A	Drywall/Joint Compound Smooth Sheetrock	Total Amount - 1540 Sq Ft				
	29	ROOM 1115	NONE DETECTED	500-JJT-23	JJT-23: NORTHWEST CORNER BY HALLWAY WINDOW.	50 Sq Ft
	80	1923 ORIGINAL BUILDING 1ST FLOOR GIRLS' RESTROOM 1108	NONE DETECTED	500-JJT-16	JJT-16: BENEATH NORTH SINK.	90 Sq Ft
	95	ROOM 1103	NONE DETECTED			400 Sq Ft
	98	ROOM 1104	NONE DETECTED			200 Sq Ft
	102	ROOM 1105	NONE DETECTED			200 Sq Ft
	106	ROOM 1106	NONE DETECTED			200 Sq Ft
	118	1923 ORIGINAL BUILDING 1ST FLOOR BOYS' RESTROOM 1101	NONE DETECTED			150 Sq Ft
	194	1923 ORIGINAL BUILDING 2ND FLOOR BOYS' RESTROOM 2111	NONE DETECTED			100 Sq Ft
	222	1923 ORIGINAL BUILDING 3RD FLOOR BOYS' RESTROOM 3109	NONE DETECTED			150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
N0D	Drywall/Joint Compound 1999 Addition	Total Amount - 1000 Sq Ft				
36	1999 ADDITION LIBRARY ROOMS 1117-1120	NONE DETECTED	100510-ML-17	1000 Sq Ft		
P0A	Fire Doors Pieced Metal w/Wood Core	Total Amount - 100 Sq Ft				
12	1923 ORIGINAL BUILDING BOILER ROOM 0100	NSM	100 Sq Ft			
P0B	Fire Doors Metal - 1 Hr Rating (Curries)	Total Amount - 100 Sq Ft				
122	1203 ELEVATOR EQUIPMENT	NEW	20 Sq Ft			
125	THROUGHOUT 1998 ADDITION 1ST FLOOR	NEW	80 Sq Ft			
P0C	Fire Doors Wood - 1 Hr Rating (Warnock Hersey)	Total Amount - 20 Sq Ft				
126	CORRIDOR 1200B	NEW	20 Sq Ft			
P0D	Fire Doors Wood - 1 Hr Rating (Weyerhaeuser)	Total Amount - 40 Sq Ft				
127	STAIRWELL 1099A	NEW	40 Sq Ft			
P0E	Fire Doors Wood - 1 Hr Rating (Weyerhaeuser)	Total Amount - 20 Sq Ft				
121	1923 ORIGINAL BUILDING 1ST FLOOR BOYS' RESTROOM 1101	NONE DETECTED	080315BV-05	BF-05: BOYS' RESTROOM 1101.	20 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0A	Carpet Adhesive Green Berber Carpet					Total Amount - 275 Sq Ft
	227	ROOM 4102	NONE DETECTED	100510-ML-07		150 Sq Ft
	250	ROOM 4101	NONE DETECTED			125 Sq Ft
Q0E	Carpet Adhesive Blue/Brown Berber Carpet					Total Amount - 90 Sq Ft
	114	ROOM 1107	NONE DETECTED	100510-ML-18	ML-18: AT DOOR FRAME.	90 Sq Ft
Q0H	Carpet Adhesive Purple w/Dark Purple Specks Carpet					Total Amount - 620 Sq Ft
	91	ROOM 1102	NONE DETECTED	100510-ML-6		620 Sq Ft
Q0J	Carpet Adhesive Light Gray w/Dark Gray Specks Carpet					Total Amount - 150 Sq Ft
	237	ROOM 3110	NONE DETECTED	100510-ML-24		150 Sq Ft
Q0K	Carpet Adhesive Multi-Colored Berber Carpet (2004)					Total Amount - 5000 Sq Ft
	1	THROUGHOUT BUILDING	NEW			5000 Sq Ft
Q0L	Carpet Adhesive 2' Green, Purple & Striped Carpet Squares (20XX)					Total Amount - 3000 Sq Ft
	38	1999 ADDITION LIBRARY ROOMS 1117-1120	NEW			3000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROA	Baseboard/Mopboard Adhesive 4" Black Baseboard					Total Amount - 210 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED	500-JJT-11	JJT-11: OLD PRINCIPAL'S OFFICE.	200 Sq Ft
	116	ROOM 1107	NONE DETECTED			10 Sq Ft
ROB	Baseboard/Mopboard Adhesive 4" Dark Brown Baseboard					Total Amount - 200 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	500-JJT-26	JJT-26: ROOM 1116 SOUTHWEST CORNER BENEATH HALLWAY WINDOW.	200 Sq Ft
ROC	Baseboard/Mopboard Adhesive 4" Dark Gray Baseboard (2004)					Total Amount - 5 Sq Ft
	24	ROOM 1115	NEW			5 Sq Ft
SOA	Wood Floor Felt / Vapor Barrier On-Grade (1923)					Total Amount - 185 Sq Ft
	47	ROOM 1114 STORAGE	ASSUMED			35 Sq Ft
	50	ROOM 1112	ASSUMED			150 Sq Ft
SOB	Wood Floor Felt / Vapor Barrier Elevated (1923)					Total Amount - 2630 Sq Ft
	163	ROOM 2101 (LOUNGE)	ASSUMED			220 Sq Ft
	169	ROOM 2103	ASSUMED			620 Sq Ft
	183	ROOM 2107	ASSUMED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	184	ROOM 2107A	ASSUMED			150 Sq Ft
	187	ROOM 2112A	ASSUMED			150 Sq Ft
	191	ROOM 2114	ASSUMED			620 Sq Ft
	238	ROOM 3110	ASSUMED			150 Sq Ft
	245	ROOM 3103	ASSUMED			620 Sq Ft
VOA	Sink Undercoating Black					Total Amount - 60 Sq Ft
	25	ROOM 1115	5-20 CH	2001-1504-CC2		10 Sq Ft
	35	ROOM 1116	5-20 CH			10 Sq Ft
	202	ROOM 2113	5-20 CH			10 Sq Ft
	206	ROOM 2116	5-20 CH			10 Sq Ft
	212	ROOM 3111	5-20 CH			10 Sq Ft
	218	ROOM 3114	5-20 CH	2001-1901-JL-16	JL-16: OLD ROOM 104.	10 Sq Ft
VOB	Sink Undercoating Light Gray					Total Amount - 2 Sq Ft
	236	ROOM 3105 RESTROOM	NONE DETECTED	100510-ML-20		2 Sq Ft
VOC	Sink Undercoating Large Gray					Total Amount - 10 Sq Ft
	44	ROOM 1114	NONE DETECTED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	164	ROOM 2101 (LOUNGE)	NONE DETECTED	100510-ML-21		5 Sq Ft
V0D	Sink Undercoating Gray (2004)					Total Amount - 24 Sq Ft
	134	ROOM 1204	NEW			6 Sq Ft
	139	ROOM 1206	NEW			6 Sq Ft
	147	ROOM 1208	NEW			6 Sq Ft
	152	ROOM 1210	NEW			6 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					Total Amount - 650 Sq Ft
	53	ROOM 1110	NONE DETECTED			50 Sq Ft
	62	ROOM 1109	NONE DETECTED			60 Sq Ft
	66	ROOM 1001 (MAIN OFFICE)	NONE DETECTED			75 Sq Ft
	69	ROOM 1002	NONE DETECTED			50 Sq Ft
	72	ROOM 1003	NONE DETECTED			25 Sq Ft
	75	ROOM 1004	NONE DETECTED			40 Sq Ft
	83	1923 ORIGINAL BUILDING 1ST FLOOR HALLWAY 1100 OUTSIDE ROOM 1102	NONE DETECTED	100510-ML-22		80 Sq Ft
	88	ROOM 1102	NONE DETECTED			150 Sq Ft
	94	ROOM 1103	NONE DETECTED	091310-ML-09		35 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	100	ROOM 1104	NONE DETECTED			25 Sq Ft
	104	ROOM 1105	NONE DETECTED			25 Sq Ft
	108	ROOM 1106	NONE DETECTED			20 Sq Ft
	113	ROOM 1107	NONE DETECTED			15 Sq Ft
X0A	Miscellaneous Material Pipe/Valve Flange Gaskets					Total Amount - 40 Sq Ft
	10	1923 ORIGINAL BUILDING BOILER ROOM 0100	ASSUMED			40 Sq Ft
X0B	Miscellaneous Material Durock Cement Board					Total Amount - 1200 Sq Ft
	13	1923 ORIGINAL BUILDING ELECTRICAL ROOM 0102	NONE DETECTED	080315BV-02	BV-02: ROOM 0102.	1200 Sq Ft
X0C	Miscellaneous Material Corkboard Adhesive (1923)					Total Amount - 1898 Sq Ft
	40	ROOM 1114	ASSUMED			120 Sq Ft
	48	ROOM 1113	ASSUMED			120 Sq Ft
	51	ROOM 1112	ASSUMED			48 Sq Ft
	56	ROOM 1110	ASSUMED			20 Sq Ft
	97	ROOM 1103	ASSUMED			70 Sq Ft
	170	ROOM 2103	ASSUMED			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	173	ROOM 2104	ASSUMED			120 Sq Ft
	178	ROOM 2105	ASSUMED			120 Sq Ft
	181	ROOM 2108	ASSUMED			120 Sq Ft
	189	ROOM 2109	ASSUMED			120 Sq Ft
	192	ROOM 2114	ASSUMED			120 Sq Ft
	228	ROOM 4102	ASSUMED			20 Sq Ft
	230	ROOM 3112	ASSUMED			120 Sq Ft
	234	ROOM 3107	ASSUMED			120 Sq Ft
	239	ROOM 3110	ASSUMED			40 Sq Ft
	243	ROOM 3106	ASSUMED			120 Sq Ft
	246	ROOM 3103	ASSUMED			120 Sq Ft
	251	ROOM 4101	ASSUMED			20 Sq Ft
	254	ROOM 3101	ASSUMED			120 Sq Ft
	256	ROOM 3102	ASSUMED			120 Sq Ft
X0D	Miscellaneous Material Slate Chalkboard Adhesive (1923)					Total Amount - 219 Sq Ft
	41	ROOM 1114	ASSUMED			15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	49	ROOM 1113	ASSUMED			15 Sq Ft
	55	ROOM 1110	ASSUMED			4 Sq Ft
	171	ROOM 2103	ASSUMED			15 Sq Ft
	174	ROOM 2104	ASSUMED			15 Sq Ft
	179	ROOM 2105	ASSUMED			15 Sq Ft
	182	ROOM 2108	ASSUMED			15 Sq Ft
	190	ROOM 2109	ASSUMED			15 Sq Ft
	193	ROOM 2114	ASSUMED			15 Sq Ft
	231	ROOM 3112	ASSUMED			15 Sq Ft
	233	ROOM 3107	ASSUMED			15 Sq Ft
	240	ROOM 3110	ASSUMED			5 Sq Ft
	244	ROOM 3106	ASSUMED			15 Sq Ft
	247	ROOM 3103	ASSUMED			15 Sq Ft
	255	ROOM 3101	ASSUMED			15 Sq Ft
	257	ROOM 3102	ASSUMED			15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0E	Miscellaneous Material Wood Design Countertop (1971)					Total Amount - 40 Sq Ft
	26	ROOM 1115	NONE DETECTED			10 Sq Ft
	32	ROOM 1116	NONE DETECTED	500-JJT-24	JJT-24: NORTHEAST CORNER BENEATH PHONE.	10 Sq Ft
	213	ROOM 3111	NONE DETECTED			10 Sq Ft
	219	ROOM 3114	NONE DETECTED			10 Sq Ft
X0F	Miscellaneous Material Slate Chalkboard Adhesive (1971)					Total Amount - 60 Sq Ft
	27	ROOM 1115	NONE DETECTED	080315BV-03	BV-03: ROOM 1115.	10 Sq Ft
	33	ROOM 1116	NONE DETECTED			10 Sq Ft
	200	ROOM 2113	NONE DETECTED			10 Sq Ft
	207	ROOM 2116	NONE DETECTED			10 Sq Ft
	214	ROOM 3111	NONE DETECTED			10 Sq Ft
	220	ROOM 3114	NONE DETECTED			10 Sq Ft
X0G	Miscellaneous Material Corkboard Adhesive (1971)					Total Amount - 518 Sq Ft
	28	ROOM 1115	ASSUMED			80 Sq Ft
	34	ROOM 1116	ASSUMED			80 Sq Ft
	111	ROOM 1106	ASSUMED			24 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	117	ROOM 1107	ASSUMED			24 Sq Ft
	130	1ST FLOOR NORTH HALLWAY 1200	ASSUMED			150 Sq Ft
	201	ROOM 2113	ASSUMED			40 Sq Ft
	208	ROOM 2116	ASSUMED			40 Sq Ft
	215	ROOM 3111	ASSUMED			40 Sq Ft
	221	ROOM 3114	ASSUMED			40 Sq Ft
X0H	Miscellaneous Material Tan w/Dark Brown Brush Strokes Countertop					Total Amount - 15 Sq Ft
	186	ROOM 2112 (COPY ROOM)	NONE DETECTED	500-JJT-5	JJT-5: WEST SIDE OF ROOM SOUTHWEST CORNER.	15 Sq Ft
X0J	Miscellaneous Material McQuay AHU Tar Gaskets					Total Amount - 10 Sq Ft
	165	1971 ADDITION ROOM 2102 MECHANICAL	12 CH	100510-ML-23		10 Sq Ft
X0K	Miscellaneous Material Slate Chalkboard Adhesive (1971)					Total Amount - 30 Sq Ft
	89	ROOM 1102	NONE DETECTED	500-JJT-17	JJT-17: ROOM 1102 NORTHEAST CORNER BEHIND PIPES.	30 Sq Ft
X0L	Miscellaneous Material Red Laminate Countertop					Total Amount - 5 Sq Ft
	43	ROOM 1114	NONE DETECTED	080315BV-01	BV-01: ROOM 1114.	5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOM	Miscellaneous Material Thin Metal Frame Tackboard Adhesive					Total Amount - 30 Sq Ft
	57	ROOM 1110	ASSUMED			5 Sq Ft
	63	ROOM 1109	ASSUMED			5 Sq Ft
	90	ROOM 1102	ASSUMED			20 Sq Ft
XON	Miscellaneous Material Stone Panel Adhesive					Total Amount - 11 Sq Ft
	81	1923 ORIGINAL BUILDING 1ST FLOOR GIRLS' RESTROOM 1108	NONE DETECTED	080315BV-04	BV-04: RESTROOM 1108.	2 Sq Ft
	175	1923 ORIGINAL BUILDING 2ND FLOOR GIRLS' RESTROOM 2106	NONE DETECTED			2 Sq Ft
	176	RESTROOM 2106A	NONE DETECTED			1 Sq Ft
	195	1923 ORIGINAL BUILDING 2ND FLOOR BOYS' RESTROOM 2111	NONE DETECTED			2 Sq Ft
	223	1923 ORIGINAL BUILDING 3RD FLOOR BOYS' RESTROOM 3109	NONE DETECTED			2 Sq Ft
	249	1923 ORIGINAL BUILDING 3RD FLOOR GIRLS' RESTROOM 3104	NONE DETECTED			2 Sq Ft
XOO	Miscellaneous Material Acoustical Wall Panel Adhesive (2004)					Total Amount - 20 Sq Ft
	159	ROOM 1212 (CAFETERIA)	NEW			20 Sq Ft
XOP	Miscellaneous Material Wired Window Glazing					Total Amount - 4 Sq Ft
	197	HALLWAY OUTSIDE ROOMS 2113 & 2116	4 CH	080315BV-06	BV-06: ROOM 2113.	2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	210	HALLWAY OUTSIDE ROOMS 3111 & 3114	4 CH			2 Sq Ft
X0Q	Miscellaneous Material White Adhesive					Total Amount - 4 Sq Ft
	42	ROOM 1114	NONE DETECTED	021424JA-01, 02	JA-01,02: ROOM 1114.	4 Sq Ft
X1A	Miscellaneous Material 6" Red Quarry Tile					Total Amount - 500 Sq Ft
	15	1923 ORIGINAL BUILDING SOUTHEAST STAIRWELL	ASSUMED			250 Sq Ft
	79	1923 ORIGINAL BUILDING SOUTHWEST STAIRWELL	ASSUMED			250 Sq Ft
X1B	Miscellaneous Material 8" Mauve Ceramic Floor Tile System					Total Amount - 250 Sq Ft
	59	MAIN ENTRANCE 1100A	NEW			250 Sq Ft
X1C	Miscellaneous Material 2" Beige & Purple Ceramic Floor Tile System (2004)					Total Amount - 220 Sq Ft
	135	RESTROOM 1204A	NEW			40 Sq Ft
	140	RESTROOM 1206A	NEW			40 Sq Ft
	143	RESTROOM 1211	NEW			60 Sq Ft
	148	RESTROOM 1208A	NEW			40 Sq Ft
	153	RESTROOM 1210A	NEW			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1D	Miscellaneous Material 4" White Ceramic Wall Tile System (2004)					Total Amount - 440 Sq Ft
	136	RESTROOM 1204A	NEW			80 Sq Ft
	141	RESTROOM 1206A	NEW			80 Sq Ft
	144	RESTROOM 1211	NEW			120 Sq Ft
	149	RESTROOM 1208A	NEW			80 Sq Ft
	154	RESTROOM 1210A	NEW			80 Sq Ft
X1E	Miscellaneous Material 6" Red Quarry Tile (2004)					Total Amount - 950 Sq Ft
	156	ROOM 1213 (KITCHEN)	NEW			950 Sq Ft