

Como Park Senior High School

Inspection Date: 8/12/2024

740 West Rose Avenue, Saint Paul, MN 55117

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2A	Mudded Pipe Joints on Millboard Insulation 1954 Original Building					Total Amount - 10 Joints
	33	KITCHEN OFFICE ROOM 1307B	30 AM, 10 CR	207-Z-5A	Z-5A: BOILER ROOM (SINCE REMOVED).	1 Joints
	101	AUDITORIUM SOUTHWEST EXIT	30 AM, 10 CR			3 Joints
	103	AUDITORIUM NORTHWEST EXIT	30 AM, 10 CR			4 Joints
	140	ROOM 1120A (GYMNASIUM STORAGE)	30 AM, 10 CR			2 Joints
A3A	Mudded Pipe Joints on Pre-formed Insulation 1954 Original Building					Total Amount - 5 Joints
	17	1954 ORIGINAL BUILDING BOILER ROOM EAST WALL	40 AM, 10 CR	207-23A		1 Joints
	138	ROOM 1120A (GYMNASIUM STORAGE)	40 AM, 10 CR			2 Joints
	144	ROOM 1117A (GYMNASIUM STORAGE)	40 AM, 10 CR			2 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4B	Mudded Pipe Joints on Fiberglass Insulation 1978 Addition				Total Amount - 4 Joints	
	133	LOWER POOL MECHANICAL ROOM OFF STAIRWELL 1199A	NONE DETECTED	042619-BF-1, 2, 3, 4, 5, 6, 7; 2001-1501-AN-6, 7, 8	BF-1,2: PENTHOUSE ABOVE WOOD SHOP (SINCE REMOVED). BF-3,4: POOL SOUTH PENTHOUSE (SINCE REMOVED); BF-5,6: POOL NORTH PENTHOUSE (SINCE REMOVED); BF-7: LOWER POOL MECHANICAL (SINCE REMOVED). AN-6: UPPER POOL MECHANICAL ROOM OFF STAIRWELL 1199A (SINCE REMOVED). AN-7: PENTHOUSE ABOVE WOOD SHOP (SINCE REMOVED). AN-8: FAN ROOM EAST OF COMMONS (1313) (SINCE REMOVED).	4 Joints
B2A	Millboard Pipe Insulation 1954 Original Building				Total Amount - 439 Lin Ft	
	19	1954 ORIGINAL BUILDING NORTHEAST TUNNEL OFF BOILER ROOM	55 CH			100 Lin Ft
	22	1954 ORIGINAL BUILDING SOUTHEAST TUNNEL OFF BOILER ROOM	55 CH	061109-BF-5	BF-5: ROOM 1221.	1 Lin Ft
	24	1954 ORIGINAL BUILDING TUNNEL UNDER ROOMS 1212-1224	55 CH			100 Lin Ft
	28	1954 ORIGINAL BUILDING TUNNEL UNDER ROOMS 1424-1433	55 CH			2 Lin Ft
	32	KITCHEN OFFICE ROOM 1307B	55 CH			12 Lin Ft
	49	ELEVATOR EQUIPMENT ROOM IN ROOM 1606	55 CH			10 Lin Ft
	54	STORAGE ROOM 2305B	55 CH			3 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	70	HALLWAY 1300A	55 CH			40 Lin Ft
	100	AUDITORIUM SOUTHWEST EXIT	55 CH			28 Lin Ft
	102	AUDITORIUM NORTHWEST EXIT	55 CH			30 Lin Ft
	107	ROOM 1237 (CHOIR)	55 CH			10 Lin Ft
	126	ROOM 1138	55 CH			16 Lin Ft
	128	MEN'S LOCKER ROOM OFFICE (1118)	55 CH			12 Lin Ft
	135	MAIN GYMNASIUM (1121)	55 CH			50 Lin Ft
	139	ROOM 1120A (GYMNASIUM STORAGE)	55 CH			25 Lin Ft
B3A	Pre-Formed Pipe Insulation 1954 Original Building					Total Amount - 79 Lin Ft
	16	1954 ORIGINAL BUILDING BOILER ROOM EAST WALL	50 AM, 20 CR			20 Lin Ft
	18	1954 ORIGINAL BUILDING NORTHEAST TUNNEL OFF BOILER ROOM	50 AM, 20 CR	207-22A	22A: BOILER ROOM.	1 Lin Ft
	21	1954 ORIGINAL BUILDING SOUTHEAST TUNNEL OFF BOILER ROOM	50 AM, 20 CR			1 Lin Ft
	25	1954 ORIGINAL BUILDING TUNNEL UNDER ROOMS 1212-1224	50 AM, 20 CR			1 Lin Ft
	26	1954 ORIGINAL BUILDING SOUTH TUNNEL UNDER CAFETERIA	50 AM, 20 CR			2 Lin Ft
	27	1954 ORIGINAL BUILDING TUNNEL UNDER ROOMS 1424-1433	50 AM, 20 CR			8 Lin Ft
	48	1954 ORIGINAL BUILDING WEST WING NE STAIRWELL	50 AM, 20 CR			20 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	137	ROOM 1120A (GYMNASIUM STORAGE)	50 AM, 20 CR			13 Lin Ft
	143	ROOM 1117A (GYMNASIUM STORAGE)	50 AM, 20 CR			13 Lin Ft
G1B	Sprayed-On Acoustical Finish White Texture (1994)					Total Amount - 900 Sq Ft
	53	ROOM 2313 (MEDIA CENTER)	NEW			900 Sq Ft
G1C	Sprayed-On Acoustical Finish Coarse, White (2006)					Total Amount - 4000 Sq Ft
	98	AUDITORIUM 1312	NONE DETECTED	052319-BF-3; 122909-ML-17, 18, 19, 20, 21	AUDITORIUM 1312	4000 Sq Ft
H1B	Sprayed-On Structural Fireproofing Gray (1994)					Total Amount - 2500 Sq Ft
	43	CAFETERIA 1302	NONE DETECTED	122909-ML-01, 22, 23, 24, 25	ML-01: AT KITCHEN. ML-22: CAFETERIA SOUTHWEST. ML-23: CAFETERIA NORTHWEST. ML-24: CAFETERIA NORTHEAST. ML-25: CAFETERIA SOUTHEAST.	2500 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Pegboard (1954)					Total Amount - 880 Sq Ft
	29	1954 KITCHEN AREA	NONE DETECTED	212-JJT-2, 45; 301-CT-A, B, C (NOVA); 207-Z7A	JJT-2: ROOM 2418. JJT-45: ROOM 1209.	480 Sq Ft
	108	ROOM 1237 (CHOIR)	NONE DETECTED			400 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Vinyl-Coated Gypsum					Total Amount - 3010 Sq Ft
	37	KITCHEN DISHWASHING ROOM 1307A	NSM			280 Sq Ft
	39	KITCHEN SERVING AREA 1307	NSM			1400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	63	ROOM 1203 AND STORAGE	NSM			1330 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Textured w/Revealed Edge (1994)					Total Amount - 80 Sq Ft
	35	KITCHEN OFFICE ROOM 1307B	NONE DETECTED			80 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Textured w/Revealed Edge (2018)					Total Amount - 101116 Sq Ft
	1	THROUGHOUT BUILDING	NEW			90000 Sq Ft
	44	CAFETERIA 1302	NEW			5500 Sq Ft
	75	ROOM 1218	NEW			1306 Sq Ft
	80	ROOM 1216A	NEW			250 Sq Ft
	83	ROOM 1216	NEW			1100 Sq Ft
	88	ROOM 1214A	NEW			220 Sq Ft
	91	ROOM 1214	NEW			1100 Sq Ft
	129	1978 ADDITION HALLWAY OUTSIDE POOL	NEW			1400 Sq Ft
	146	2004 ADDITION HALLWAY OUTSIDE ROOM 1119 (WEIGHT ROOM)	NEW			240 Sq Ft
I2G	2' x 2' Acoustical Ceiling Tile Textured w/Revealed Edge (2019)					Total Amount - 2660 Sq Ft
	104	THROUGHOUT MUSIC AREAS	NEW			2500 Sq Ft
	110	PRACTICE ROOM 1219	NEW			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	112	PRACTICE ROOM 1217	NEW			40 Sq Ft
	114	PRACTICE ROOM 1215	NEW			40 Sq Ft
	116	PRACTICE ROOM 1235	NEW			40 Sq Ft
I2H	2' x 2' Acoustical Ceiling Tile Vinyl Coated Gypsum (2019)					Total Amount - 420 Sq Ft
	31	1954 KITCHEN AREA	NEW			420 Sq Ft
I2I	2' x 2' Acoustical Ceiling Tile Tectum					Total Amount - 3000 Sq Ft
	124	ROOM 1142/1135 (WRESTLING)	NSM			3000 Sq Ft
I3F	2' x 4' Ceiling Tile Gouges & Pin Holes in Concentric Pattern					Total Amount - 75 Sq Ft
	69	ROOM 1224B	NONE DETECTED			75 Sq Ft
I3H	2' x 4' Ceiling Tile Pockmarks with Pin Holes (2019)					Total Amount - 202 Sq Ft
	55	STORAGE ROOM 2305B	NEW			52 Sq Ft
	118	BACK STAIRWELL OFF ROOM 1207 (BAND)	NEW			150 Sq Ft
I4A	Acoustical Ceiling Tile 4' x 4' & 4' x 8' Baffle Material					Total Amount - 370 Sq Ft
	117	ROOM 1226 (BAND)	NONE DETECTED	212-JJT-71; 207Z9A		370 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J1D	Cementitious Panels Safeaire Fisher-Hamilton Fume Hood (White)					Total Amount - 40 Sq Ft
	60	ROOM 1403	NEW			40 Sq Ft
J2A	Transite Piping/Ducting 4" Electrical Conduit					Total Amount - 6 Sq Ft
	20	1954 ORIGINAL BUILDING NORTHEAST TUNNEL OFF BOILER ROOM	ASSUMED			5 Sq Ft
	148	1978 ADDITION TUNNEL UNDER NURSE'S OFFICE	ASSUMED			1 Sq Ft
J3C	Miscellaneous Cementitious Material Black Epoxy Tabletops					Total Amount - 960 Sq Ft
	79	ROOM 1218	NSM			320 Sq Ft
	87	ROOM 1216	NSM			320 Sq Ft
	95	ROOM 1214	NSM			320 Sq Ft
K0B	9" x 9" Vinyl Floor Tile & Mastic Gray w/Beige Streaks					Total Amount - 405 Sq Ft
	52	ROOM 2313 (MEDIA CENTER) & ASSOCIATED ROOMS	5-7 CH (TILE), NONE DETECTED (MASTIC)	212-JJT-21	JJT-21: 1954 ORIGINAL BUILDING 2ND FLOOR HALLWAY SOUTHEAST OF MEDIA CENTER (SINCE REMOVED).	200 Sq Ft
	68	ROOM 1211A STORAGE	5-7 CH (TILE), NONE DETECTED (MASTIC)	2001-01113-5	5: AUDITORIUM 1312 (SINCE REMOVED).	85 Sq Ft
	111	PRACTICE ROOM 1219	5-7 CH (TILE), NONE DETECTED (MASTIC)			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	113	PRACTICE ROOM 1217	5-7 CH (TILE), NONE DETECTED (MASTIC)			40 Sq Ft
	115	PRACTICE ROOM 1215	5-7 CH (TILE), NONE DETECTED (MASTIC)	050719-BF-1; 122909-ML-36; 2001-01113-4; 212-JJT-9	BF-1: ROOM 1205B (SINCE REMOVED). ML-36: MAIN OFFICE MECHANICAL ROOM 1028 (SINCE REMOVED). 4: ROOM 1418 (SINCE REMOVED). JJT-9: ROOM 2418 (SINCE REMOVED).	40 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Bright Gray Mottle					Total Amount - 782 Sq Ft
	72	ROOM 1222A	NONE DETECTED			312 Sq Ft
	81	ROOM 1216A	NONE DETECTED	122909-ML-44	ML-44: ROOM 1221 PREP ROOM (SINCE REMOVED).	250 Sq Ft
	89	ROOM 1214A	NONE DETECTED			220 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Tan w/Thin Olive & White Streaks (1993)					Total Amount - 400 Sq Ft
	120	1993 ADDITION WEST HALLWAY OUTSIDE FIELD HOUSE	NONE DETECTED	122909-ML-45		400 Sq Ft
K2I	12" x 12" Vinyl Floor Tile & Mastic White w/Tan, Red & Blue Blotches					Total Amount - 180 Sq Ft
	34	KITCHEN OFFICE ROOM 1307B	NONE DETECTED			80 Sq Ft
	42	CUSTODIAL OFFICE (1311)	NONE DETECTED	212-JJT-20	JJT-20: WEST CAFETERIA ENTRY (SINCE REMOVED).	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2N	12" x 12" Vinyl Floor Tile & Mastic Light & Dark Gray Mottle w/White Flecks (2009)					Total Amount - 1750 Sq Ft
	77	ROOM 1218	NONE DETECTED	122909-ML-53	ML-53: ROOM 1218 -WEST (SINCE REMOVED).	650 Sq Ft
	84	ROOM 1216	NONE DETECTED			550 Sq Ft
	92	ROOM 1214	NONE DETECTED			550 Sq Ft
K2O	12" x 12" Vinyl Floor Tile & Mastic Green Mottle (2009)					Total Amount - 2415 Sq Ft
	64	ROOM 1203 AND STORAGE	NONE DETECTED	122909-ML-54	ML-54: STORAGE.	665 Sq Ft
	76	ROOM 1218	NONE DETECTED			650 Sq Ft
	85	ROOM 1216	NONE DETECTED			550 Sq Ft
	93	ROOM 1214	NONE DETECTED			550 Sq Ft
K2P	12" x 12" Vinyl Floor Tile & Mastic Beige Mottle (2009)					Total Amount - 665 Sq Ft
	65	ROOM 1203 AND STORAGE	NONE DETECTED	122909-ML-55	ML-55: STORAGE.	665 Sq Ft
K2R	12" x 12" Vinyl Floor Tile & Mastic Beige w/Black Specks					Total Amount - 240 Sq Ft
	147	2004 ADDITION HALLWAY OUTSIDE ROOM 1119 (WEIGHT ROOM)	NONE DETECTED	122909-ML-48		240 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3D	Miscellaneous Flooring 2' x 2' Gray, Brown and Yellow Rubber Flooring (2018)					Total Amount - 90000 Sq Ft
	2	THROUGHOUT BUILDING	NEW			90000 Sq Ft
K3E	Miscellaneous Flooring Black Flooring Mastic					Total Amount - 70 Sq Ft
	50	ROOM 2607	ASSUMED			40 Sq Ft
	58	ROOM 2307	ASSUMED			30 Sq Ft
K3F	Miscellaneous Flooring Wood-Look Rubber Flooring					Total Amount - 10000 Sq Ft
	123	1993 ADDITION FIELD HOUSE ROOM 1114A	NSM			10000 Sq Ft
L0A	Flexible Duct Connector Green Canvas					Total Amount - 40 Sq Ft
	23	MECHANICAL ROOM OFF SOUTHEAST TUNNEL OFF BOILER ROOM	NONE DETECTED			10 Sq Ft
	141	ROOM 1120A (GYMNASIUM STORAGE)	NONE DETECTED			5 Sq Ft
	142	FAN ROOM ABOVE ROOM 1120A (GYMNASIUM STORAGE)	NONE DETECTED	212-JJT-49; 2001-1501-AN-04	AN-04: FAN ROOM ABOVE GYMNASIUM.	20 Sq Ft
	145	ROOM 1117A (GYMNASIUM STORAGE)	NONE DETECTED			5 Sq Ft
L0B	Flexible Duct Connector Black Vinyl					Total Amount - 9 Sq Ft
	51	ROOM 2722 & 2722A	NSM			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	59	ROOM 2307	NSM			5 Sq Ft
M0A	Plaster 1954 Original Building	Total Amount - 120000 Sq Ft				
	11	THROUGHOUT 1954 ORIGINAL BUILDING	NONE DETECTED	052319-BF-1, 2, 3; 212-JJT-1, 17, 48; 2001-01113-1; 509I-9, 10, 11; 100K-3-A, B, C	BF-1,2,3: AUDITORIUM. JJT-1: ROOM 2421. JJT-17: ROOM 1424. JJT-48: MAIN GYMNASIUM COLUMNS. 01113-1: NURSE'S OFFICE. 3-A,B,C: AUDITORIUM.	120000 Sq Ft
M0B	Plaster 1978 Addition	Total Amount - 900 Sq Ft				
	130	1978 ADDITION GIRLS' POOL LOCKER ROOM SHOWER AREA	NONE DETECTED			450 Sq Ft
	134	1978 ADDITION BOYS' POOL LOCKER ROOM SHOWER AREA	NONE DETECTED	212-JJT-68		450 Sq Ft
M0C	Plaster Plaster Surrounding Recessed Lights	Total Amount - 30 Sq Ft				
	99	AUDITORIUM 1312	NONE DETECTED	042619-BF-8	AUDITORIUM 1312	30 Sq Ft
N0A	Drywall/Joint Compound Remodeled Areas	Total Amount - 20000 Sq Ft				
	12	THROUGHOUT 1954 ORIGINAL BUILDING	NONE DETECTED	101317-BF-1; 212-JJT-15; 509I-6, 7, 8	BF-1: ROOM 1403A. JJT-15 ROOM 1426A.	20000 Sq Ft
N0C	Drywall/Joint Compound 1993 Addition/Renovation	Total Amount - 4400 Sq Ft				
	74	ROOMS 1212-1218	NONE DETECTED			4000 Sq Ft
	119	1993 ADDITION WEST HALLWAY OUTSIDE FIELD HOUSE	NONE DETECTED	122909-ML-14	ML-14: 1993 ADDITION FIELD HOUSE ROOM 1114A (SINCE REMOVED).	400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
N0F	Drywall/Joint Compound 2019 Renovation					Total Amount - 140 Sq Ft
	122	1993 ADDITION FIELD HOUSE ROOM 1114A	NEW			140 Sq Ft
POC	Fire Doors Wood -1 Hr Rating (Weyerhaeuser)					Total Amount - 20 Sq Ft
	56	MECHANICAL ROOM 2312	ASSUMED			20 Sq Ft
POD	Fire Doors Hollow Metal -1.5 Hr Rating					Total Amount - 400 Sq Ft
	10	THROUGHOUT BUILDING HALLWAYS	NSM			400 Sq Ft
Q0B	Carpet Adhesive New Berber Carpet					Total Amount - 10000 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	122909-ML-38	ML-38: ROOM 1208.	10000 Sq Ft
Q0F	Carpet Adhesive 2' X 2' Black Striped Carpet Squares (2019)					Total Amount - 2500 Sq Ft
	105	THROUGHOUT MUSIC AREAS	NEW			2500 Sq Ft
Q0G	Carpet Adhesive Brown/Gray Striped Carpet Squares (2018)					Total Amount - 5000 Sq Ft
	5	THROUGHOUT BUILDING	NEW			5000 Sq Ft
Q0H	Carpet Adhesive Gray Patterned Carpet Squares (2018)					Total Amount - 15000 Sq Ft
	3	THROUGHOUT BUILDING	NEW			15000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
R0D	Baseboard/Mopboard Adhesive Black Baseboard (1993)					Total Amount - 10 Sq Ft
	121	1993 ADDITION WEST HALLWAY OUTSIDE FIELD HOUSE	NONE DETECTED			10 Sq Ft
R0E	Baseboard/Mopboard Adhesive 4" Gray Baseboard					Total Amount - 250 Sq Ft
	73	ROOM 1222A	NONE DETECTED			30 Sq Ft
	78	ROOM 1218	NONE DETECTED			80 Sq Ft
	82	ROOM 1216A	NONE DETECTED			20 Sq Ft
	86	ROOM 1216	NONE DETECTED			50 Sq Ft
	90	ROOM 1214A	NONE DETECTED			20 Sq Ft
	94	ROOM 1214	NONE DETECTED			50 Sq Ft
R0F	Baseboard/Mopboard Adhesive 6" Gray Baseboard (2018)					Total Amount - 1500 Sq Ft
	6	THROUGHOUT BUILDING	NEW			1500 Sq Ft
R0G	Baseboard/Mopboard Adhesive 6" Gray Baseboard (2019)					Total Amount - 150 Sq Ft
	106	THROUGHOUT MUSIC AREAS	NEW			150 Sq Ft
R0H	Baseboard/Mopboard Adhesive 4" Beige Baseboard					Total Amount - 60 Sq Ft
	66	ROOM 1203 AND STORAGE	ASSUMED			60 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
SOA	Wood Floor Felt / Vapor Barrier On Grade (1954)					Total Amount - 3015 Sq Ft
	71	ROOM 1222	10 CH	040109-BF-1, 3	BF-1: ROOM 1217 (SINCE REMOVED). BF-3: ROOM 1221 (SINCE REMOVED).	15 Sq Ft
	125	ROOM 1142/1135 (WRESTLING)	10 CH	122909-ML-16	ML-16: MAIN GYMNASIUM (1121) NORTHEAST CORNER (SINCE REMOVED).	3000 Sq Ft
SOAA	Wood Floor Felt / Vapor Barrier Elevated (1954)					Total Amount - 2000 Sq Ft
	96	AUDITORIUM STAGE	ASSUMED			2000 Sq Ft
SOB	Wood Floor Felt / Vapor Barrier On Grade (2014)					Total Amount - 10000 Sq Ft
	136	MAIN GYMNASIUM (1121)	NEW			10000 Sq Ft
V0D	Sink Undercoating White (2009)					Total Amount - 20 Sq Ft
	61	ROOM 1203	NONE DETECTED	122909-ML-15		20 Sq Ft
V0E	Sink Undercoating Gray (2009)					Total Amount - 10 Sq Ft
	62	ROOM 1203	NONE DETECTED	122909-ML-26		10 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/11A					Total Amount - 225 Sq Ft
	30	1954 KITCHEN AREA	NONE DETECTED	011719BF-1, 2, 3; 072213-BF-1; 301-CTA-1-A, B, C (NOVA)	011719BF-1: ROOM 1220. BF-2: ROOM 1223. ROOM BF-3: ROOM 1214; BF-1: ROOM 1224.	120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	57	MECHANICAL ROOM 2312	NONE DETECTED			5 Sq Ft
	109	ROOM 1237 (CHOIR)	NONE DETECTED			100 Sq Ft
X0C	Miscellaneous Material Tackboard Adhesive (1954)					Total Amount - 41 Sq Ft
	67	ROOM 1211	ASSUMED			25 Sq Ft
	127	ROOM 1120 WOMEN'S LOCKER ROOM	ASSUMED			16 Sq Ft
X0F	Miscellaneous Material Brick Mortar					Total Amount - 5000 Sq Ft
	45	THROUGHOUT 1978 ADDITION EXTERIOR	NONE DETECTED	101317-BF-3	BF-3: 1978 EXTERIOR.	5000 Sq Ft
X0G	Miscellaneous Material Expansion Joint Caulk					Total Amount - 10 Sq Ft
	46	THROUGHOUT 1978 ADDITION EXTERIOR	NONE DETECTED	101317-BF-4	BF-4: 1978 EXTERIOR.	10 Sq Ft
X0H	Miscellaneous Material Exterior Window Caulk					Total Amount - 30 Sq Ft
	47	THROUGHOUT 1978 ADDITION EXTERIOR	NONE DETECTED	101317-BF-5	BF-5: 1978 EXTERIOR.	30 Sq Ft
X0I	Miscellaneous Material Exterior Foundation Damp Proofing (1954)					Total Amount - 8000 Sq Ft
	13	THROUGHOUT 1954 ORIGINAL BUILDING	15 CH	102418CW-01	CW-01: EXTERIOR 1954 ORIGINAL BUILDING BOILER ROOM	8000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0J	Miscellaneous Material Brown Chalkboard Adhesive (1954)					Total Amount - 100 Sq Ft
	14	THROUGHOUT 1954 ORIGINAL BUILDING	NONE DETECTED	021819BF-1; 021419BF-1	021819BF-1: ROOM 1212. 021419BF-1: ROOM 1213.	100 Sq Ft
X0K	Miscellaneous Material Brown Tackboard Adhesive (1954)					Total Amount - 100 Sq Ft
	15	THROUGHOUT 1954 ORIGINAL BUILDING	NONE DETECTED	021419-BF-1	BF-1: ROOM 1213.	100 Sq Ft
X0L	Miscellaneous Material 4' Wood Stained Wall Planks (202x)					Total Amount - 5000 Sq Ft
	9	THROUGHOUT BUILDING HALLWAYS	NEW			5000 Sq Ft
X1A	Miscellaneous Material 8" x 8" Light Red Ceramic Floor Tile System					Total Amount - 300 Sq Ft
	38	KITCHEN DISHWASHING ROOM 1307A	ASSUMED			300 Sq Ft
X1B	Miscellaneous Material 12" x 12" Dark Gray Ceramic Floor Tile System					Total Amount - 1400 Sq Ft
	40	KITCHEN SERVING AREA 1307	NEW			1400 Sq Ft
X1D	Miscellaneous Material 6" x 6" Red Quarry Tile System					Total Amount - 900 Sq Ft
	36	KITCHEN (1304)	ASSUMED			900 Sq Ft
X1E	Miscellaneous Material 4" x 12" Gray Ceramic Tile System (2018)					Total Amount - 15000 Sq Ft
	7	THROUGHOUT BUILDING	NEW			15000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1F		Miscellaneous Material Black Tar Paper at North Wall				Total Amount - 40 Sq Ft
	131	PENTHOUSE ABOVE GIRLS' POOL LOCKER ROOM	ASSUMED			40 Sq Ft
X1G		Miscellaneous Material 1' X 2' Gray Ceramic Tile System (2018)				Total Amount - 10480 Sq Ft
	8	THROUGHOUT BUILDING	NEW			10000 Sq Ft
	41	KITCHEN SERVING AREA 1307 SOUTH AREA	NEW			480 Sq Ft
X1H		Miscellaneous Material White Stage Curtain				Total Amount - 400 Sq Ft
	97	AUDITORIUM STAGE	NONE DETECTED	080621SW-01	SW-01: AUDITORIUM STAGE.	400 Sq Ft
X1I		Miscellaneous Material 1" X 1" Pool Ceramic Tile System				Total Amount - 4000 Sq Ft
	132	POOL AREA	ASSUMED			4000 Sq Ft