

275 Lexington Parkway North, Saint Paul, MN 55104

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A	Mudded Pipe Joints on Fiberglass Insulation 1977 Addition/Installation					Total Amount - 556 Joints
	1	THROUGHOUT BUILDING	NONE DETECTED			250 Joints
	25	BOILER ROOM 0406A	NONE DETECTED	2001-01108-5, 6, 7	A4A JOINTS ALL SAME TIME; BUILDING GUTTED & REDONE AT TIME OF NEW ADDITION.	17 Joints
	41	ROOM 0406C (STORAGE)	NONE DETECTED			4 Joints
	45	MEN'S RESTROOM 0403 PIPE CHASE	NONE DETECTED			10 Joints
	58	MECHANICAL ROOM 0201A (SPRINKLER ROOM)	NONE DETECTED			1 Joints
	84	ROOM 1302	NONE DETECTED			9 Joints
	91	ROOM 1306 (KILN ROOM)	NONE DETECTED			3 Joints
	99	ROOM 1314A	NONE DETECTED			4 Joints
	116	ROOM 1416	NONE DETECTED			2 Joints
	122	ROOM 1501 (GYMNASIUM) STORAGE ROOMS A-E	NONE DETECTED			5 Joints
	127	ROOM 1505 (GYMNASTICS)	NONE DETECTED			2 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	172	ROOM 2303 (FAN ROOM) BY KITCHEN	NONE DETECTED			28 Joints
	216	ROOM 2119	NONE DETECTED			12 Joints
	221	ROOM 2120 (MECHANICAL)	NONE DETECTED	2001-01108-8		27 Joints
	224	MECHANICAL ROOM 2509	NONE DETECTED			7 Joints
	242	ROOM 2512 (MECHANICAL)	NONE DETECTED			86 Joints
	245	3RD FLOOR RESTROOMS 2401 & 2402 PIPE CHASES BY KITCHEN	NONE DETECTED			3 Joints
	272	MECHANICAL ROOM 2308 OFF ROOM 2307	NONE DETECTED			17 Joints
	277	ROOM 2310	NONE DETECTED			2 Joints
	327	ROOM 3411	NONE DETECTED			10 Joints
	348	MECHANICAL ROOM 3111	NONE DETECTED			5 Joints
	357	PENTHOUSE 5101	NONE DETECTED			24 Joints
	391	PENTHOUSE 5401	NONE DETECTED			28 Joints
B3A		Pre-Formed Pipe Insulation				Total Amount - 10 Lin Ft
	21	CRAWLSPACE	ASSUMED			10 Lin Ft
C2B		Water Tank Insulation 199X Installation				Total Amount - 150 Sq Ft
	26	BOILER ROOM 0406A	NONE DETECTED	111708-MA-04, 05, 06		150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D1A	Boiler Gaskets Shiny White Cords		Total Amount - 20 Sq Ft			
	27	BOILER ROOM 0406A	NONE DETECTED	326-FCW-A, B, C		20 Sq Ft
D1B	Boiler Gaskets Shiny White Fabric		Total Amount - 20 Sq Ft			
	28	BOILER ROOM 0406A	NONE DETECTED	326-FFW-A, B, C		20 Sq Ft
D2A	Interior Boiler Insulation Pink Refractory		Total Amount - 200 Sq Ft			
	29	BOILER ROOM 0406A	NONE DETECTED	237-PINK-A, B, C		200 Sq Ft
F2A	Exterior Duct Insulation White Seam Tape		Total Amount - 17 Sq Ft			
	30	BOILER ROOM 0406A	NONE DETECTED	399-WHI-A, B, C		10 Sq Ft
	251	ROOM 2304	NONE DETECTED			7 Sq Ft
H1A	Sprayed-On Structural Fireproofing Tan (Hard)		Total Amount - 143700 Sq Ft			
	20	CRAWL SPACE 0406D & 0101C	NONE DETECTED	2001-1108-13		7500 Sq Ft
	22	BOILER ROOM 0406A	NONE DETECTED	2001-1901-CHS-1A; 509D-5, 6, 7, 8, 9, 10, 11	1A: BOILER ROOM.	3000 Sq Ft
	34	ROOM 0406B (ELECTRICAL)	NONE DETECTED	2001-1901-CHS-2A		1000 Sq Ft
	39	ROOM 0406C (STORAGE)	NONE DETECTED			1200 Sq Ft
	42	THROUGHOUT 1ST FLOOR	NONE DETECTED	2001-1901-CHS-1, 2, 3	CHS-1,2,3: LIBRARY.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	60	THROUGHOUT 2ND FLOOR	NONE DETECTED	2001-1901-CHS-3A	3A: HALLWAY BY ROOM 1203.	50000 Sq Ft
	161	THROUGHOUT 3RD FLOOR	NONE DETECTED			50000 Sq Ft
	309	THROUGHOUT 4TH FLOOR	NONE DETECTED	2001-1901-CHS-4A	4A: HALLWAY BY ELEVATOR.	20000 Sq Ft
	349	THROUGHOUT 5TH FLOOR	NONE DETECTED			10000 Sq Ft
H1B		Sprayed-On Structural Fireproofing Gray (Fluffy)				Total Amount - 2700 Sq Ft
	23	BOILER ROOM 0406A	NONE DETECTED	509D-15, 16, 17, 18, 19, 20, 21		400 Sq Ft
	43	THROUGHOUT 1ST FLOOR	NONE DETECTED			500 Sq Ft
	166	CAFETERIA 2200	NONE DETECTED			1800 Sq Ft
I1A		1' x 1' Acoustical Ceiling Tile 23-Hole Pegboard				Total Amount - 364 Sq Ft
	211	ROOM 2118 (OFF STAIRWELL)	NONE DETECTED	2001-1501-AX4	ROOM 2119.	134 Sq Ft
	217	ROOM 2119	NONE DETECTED			130 Sq Ft
	229	ROOM 2510 (STORAGE/HALLWAY)	NONE DETECTED			100 Sq Ft
I2A		2' x 2' Acoustical Ceiling Tile Gouges & Pin Holes				Total Amount - 96 Sq Ft
	52	STAIRWELL TO OBSERVATION NORTH OFF ROOM 0101	ASSUMED			96 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3A	2' x 4' Ceiling Tile Gouges & Pin Holes in Concentric Pattern					Total Amount - 121972 Sq Ft
	48	OFFICE 0203	NONE DETECTED			168 Sq Ft
	50	OFFICES 0204-0206	NONE DETECTED			364 Sq Ft
	55	VIDEO PRODUCTION 1217	NONE DETECTED			440 Sq Ft
	63	THROUGHOUT 2ND FLOOR	NONE DETECTED			20000 Sq Ft
	164	THROUGHOUT 3RD FLOOR	NONE DETECTED	207S5A		45000 Sq Ft
	313	THROUGHOUT 4TH FLOOR	NONE DETECTED			50000 Sq Ft
	388	MEDIA CENTER 4201	NONE DETECTED			6000 Sq Ft
I3B	2' x 4' Ceiling Tile Tectum					Total Amount - 3360 Sq Ft
	2	THROUGHOUT BUILDING	NSM			3000 Sq Ft
	54	VIDEO PRODUCTION 1218	NSM			360 Sq Ft
I3C	2' x 4' Ceiling Tile Lengthwise Fissures w/Dents & Pin Holes					Total Amount - 300 Sq Ft
	129	ROOM 1214	NONE DETECTED	111708-MA-14		300 Sq Ft
I3D	2' x 4' Ceiling Tile Pin Holes					Total Amount - 150 Sq Ft
	274	ROOM 2309 CHEMICAL STORAGE	NONE DETECTED	111808-MA-11		150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3E	2' x 4' Ceiling Tile Dense Dents, Nail & Pin Holes					Total Amount - 46700 Sq Ft
	143	ROOM 1117 (WEIGHT ROOM)	NONE DETECTED			1700 Sq Ft
	353	THROUGHOUT 5TH FLOOR	NONE DETECTED	111908-MA-02; 207S6A	MA-02: ROOM 4117.	45000 Sq Ft
I3F	2' x 4' Ceiling Tile Vinyl-Coated Gypsum					Total Amount - 1700 Sq Ft
	170	KITCHEN 2204/2302	NONE DETECTED	207S7A		1700 Sq Ft
I3G	2' x 4' Ceiling Tile Fiberglass					Total Amount - 7000 Sq Ft
	167	CAFETERIA 2200	NSM			7000 Sq Ft
J1A	Cementitious Panels Fume Hood - Gray Panels					Total Amount - 40 Sq Ft
	258	ROOM 2304	ASSUMED			40 Sq Ft
J1B	Cementitious Panels Chemical Storage Cabinet Lining					Total Amount - 45 Sq Ft
	275	ROOM 2309 CHEMICAL STORAGE	ASSUMED			45 Sq Ft
J3A	Miscellaneous Cementitious Material Shiny Black Tabletops/Drying Racks					Total Amount - 1852 Sq Ft
	73	ROOM 1202	NONE DETECTED	111708-MA-09	MA-09: DRYING RACK.	220 Sq Ft
	77	ROOM 1203	NONE DETECTED			220 Sq Ft
	254	ROOM 2304	NONE DETECTED			70 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	260	ROOM 2305	NONE DETECTED			30 Sq Ft
	264	ROOM 2306	NONE DETECTED			350 Sq Ft
	269	ROOM 2307	NONE DETECTED			240 Sq Ft
	288	ROOM 2312	NONE DETECTED			75 Sq Ft
	294	ROOM 2404	NONE DETECTED			36 Sq Ft
	296	ROOM 2405	NONE DETECTED			36 Sq Ft
	300	ROOM 2406	NONE DETECTED			360 Sq Ft
	303	ROOM 2408	NONE DETECTED			215 Sq Ft
J3B	Miscellaneous Cementitious Material White Window Sills				Total Amount - 3227 Sq Ft	
	78	ROOM 1203	30 CH			15 Sq Ft
	86	ROOM 1303	30 CH			25 Sq Ft
	88	ROOM 1304	30 CH			25 Sq Ft
	93	ROOM 1308	30 CH			25 Sq Ft
	100	ROOM 1317	30 CH			30 Sq Ft
	107	ROOM 1410	30 CH			42 Sq Ft
	108	ROOM 1412	30 CH			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	111	ROOM 1414	30 CH			30 Sq Ft
	114	ROOM 1415	30 CH			60 Sq Ft
	141	ROOM 1117 (WEIGHT ROOM)	30 CH			30 Sq Ft
	169	CAFETERIA 2200	30 CH			250 Sq Ft
	183	ROOM 2007	30 CH			10 Sq Ft
	186	ROOM 2008	30 CH			10 Sq Ft
	187	ROOM 2009 (PRINCIPAL)	30 CH			20 Sq Ft
	188	OFFICE CONFERENCE ROOMS 2010A & 2010B	30 CH			30 Sq Ft
	190	ROOM 2023	30 CH			16 Sq Ft
	191	ROOM 2022	30 CH			10 Sq Ft
	192	ROOM 2021	30 CH			8 Sq Ft
	193	ROOM 2020	30 CH			8 Sq Ft
	194	ROOM 2019	30 CH			2 Sq Ft
	195	ROOM 2018	30 CH			10 Sq Ft
	196	ROOM 2017	30 CH			2 Sq Ft
	249	ROOM 2403	30 CH			100 Sq Ft
	255	ROOM 2304	30 CH			28 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	265	ROOM 2306	30 CH			30 Sq Ft
	271	ROOM 2307	30 CH			25 Sq Ft
	276	ROOM 2309 CHEMICAL STORAGE	30 CH			10 Sq Ft
	282	ROOM 2311	30 CH			24 Sq Ft
	293	ROOM 2404	30 CH			54 Sq Ft
	297	ROOM 2405	30 CH			54 Sq Ft
	301	ROOM 2406	30 CH			54 Sq Ft
	316	ROOM 3401	30 CH			50 Sq Ft
	317	ROOM 3402	30 CH			50 Sq Ft
	318	ROOM 3403	30 CH			50 Sq Ft
	319	ROOM 3404	30 CH			40 Sq Ft
	321	ROOM 3405	30 CH			50 Sq Ft
	322	ROOM 3406	30 CH			50 Sq Ft
	323	ROOM 3407	30 CH			40 Sq Ft
	325	ROOM 3408	30 CH			50 Sq Ft
	326	ROOM 3409	30 CH			50 Sq Ft
	332	ROOM 3205	30 CH			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	333	ROOM 3206	30 CH			50 Sq Ft
	336	ROOM 3101	30 CH			50 Sq Ft
	338	ROOM 3102	30 CH			50 Sq Ft
	339	ROOM 3103	30 CH			50 Sq Ft
	340	ROOM 3104	30 CH			40 Sq Ft
	341	ROOM 3105	30 CH			50 Sq Ft
	343	ROOM 3106	30 CH			50 Sq Ft
	344	ROOM 3107	30 CH			40 Sq Ft
	346	ROOM 3108	30 CH			50 Sq Ft
	347	ROOM 3109/3110	30 CH			50 Sq Ft
	360	ROOM 4101	30 CH			50 Sq Ft
	361	ROOM 4102	30 CH			50 Sq Ft
	363	ROOM 4103	30 CH			50 Sq Ft
	366	ROOM 4104	30 CH	306-WS-A		50 Sq Ft
	369	ROOM 4105	30 CH			50 Sq Ft
	371	ROOM 4106	30 CH			50 Sq Ft
	372	ROOM 4107	30 CH			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	375	ROOM 4108	30 CH			50 Sq Ft
	377	ROOM 4109	30 CH			50 Sq Ft
	379	ROOM 4110	30 CH			50 Sq Ft
	381	ROOM 4215	30 CH			40 Sq Ft
	382	ROOM 4216	30 CH			10 Sq Ft
	383	ROOM 4217	30 CH			25 Sq Ft
	384	ROOM 4218	30 CH			25 Sq Ft
	385	ROOM 4219	30 CH			25 Sq Ft
	387	ROOM 4222	30 CH			25 Sq Ft
	394	ROOM 4401	30 CH	306-WS-B		50 Sq Ft
	395	ROOM 4402	30 CH			50 Sq Ft
	397	ROOM 4403	30 CH			50 Sq Ft
	398	ROOM 4404	30 CH			50 Sq Ft
	400	ROOM 4405	30 CH			50 Sq Ft
	401	ROOM 4406	30 CH			50 Sq Ft
	403	ROOM 4407	30 CH			50 Sq Ft
	404	ROOM 4408	30 CH			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	405	ROOM 4409	30 CH			50 Sq Ft
	406	ROOM 4410	30 CH			50 Sq Ft
J3C	Miscellaneous Cementitious Material Old Black Countertops					Total Amount - 921 Sq Ft
	94	ROOM 1308	25 CH	399-BLCK-A		50 Sq Ft
	250	ROOM 2403	25 CH	399-BLCK-C		75 Sq Ft
	256	ROOM 2304	25 CH			100 Sq Ft
	266	ROOM 2306	25 CH			36 Sq Ft
	270	ROOM 2307	25 CH			140 Sq Ft
	280	ROOM 2311	25 CH	399-BLCK-B		325 Sq Ft
	289	ROOM 2312	25 CH			195 Sq Ft
J3D	Miscellaneous Cementitious Material Thin, Black Tabletop					Total Amount - 48 Sq Ft
	140	POOL MECHANICAL ROOM	15 CH	111708-MA-17		12 Sq Ft
	259	ROOM 2305	15 CH			12 Sq Ft
	267	ROOM 2306	15 CH			12 Sq Ft
	298	ROOM 2405	15 CH			12 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J3E		Miscellaneous Cementitious Material Black Tabletops - Dark Brown Inside				Total Amount - 236 Sq Ft
	257	ROOM 2304	NONE DETECTED	111808-MA-09		200 Sq Ft
	287	ROOM 2312	NONE DETECTED			36 Sq Ft
J3F		Miscellaneous Cementitious Material Black Sink/Counter w/Lip				Total Amount - 30 Sq Ft
	261	ROOM 2305	15 CH	111808-MA-10		30 Sq Ft
J3G		Miscellaneous Cementitious Material 1" Black Desk Tops				Total Amount - 60 Sq Ft
	286	ROOM 2312	15 CH	111808-MA-13		60 Sq Ft
K0A		9" x 9" Vinyl Floor Tile & Mastic Light Brown				Total Amount - 1110 Sq Ft
	365	ROOM 4104	10 CH (TILE), 5 CH (MASTIC)	111908-MA-03		480 Sq Ft
	368	ROOM 4105	10 CH (TILE), 5 CH (MASTIC)	311-LB-A		300 Sq Ft
	370	ROOM 4106	10 CH (TILE), 5 CH (MASTIC)			330 Sq Ft
K0B		9" x 9" Vinyl Floor Tile & Mastic Dark Brown				Total Amount - 960 Sq Ft
	378	ROOM 4110	10 CH (TILE)	311-DB-A, B, C		960 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K0C	9" x 9" Vinyl Floor Tile & Mastic Gray					Total Amount - 700 Sq Ft
374	ROOM 4108	10 CH (TILE)	311-GRA-A, B, C		700 Sq Ft	
K0D	9" x 9" Vinyl Floor Tile & Mastic Brown					Total Amount - 600 Sq Ft
376	ROOM 4109	10 CH (TILE)	311-BRW-A, B, C		600 Sq Ft	
K1A	Sheet Vinyl Flooring & Adhesive Multi-Colored Pebbles					Total Amount - 190 Sq Ft
105	ROOM 1409	NONE DETECTED	111708-MA-12; 313-PUR-A, B, C		70 Sq Ft	
320	DRINKING FOUNTAIN AREA BY ROOM 3404	NONE DETECTED			8 Sq Ft	
324	DRINKING FOUNTAIN BY ROOM 3407	NONE DETECTED			8 Sq Ft	
335	DRINKING FOUNTAIN BY ROOM 3101	NONE DETECTED			8 Sq Ft	
342	DRINKING FOUNTAIN BY ROOM 3105	NONE DETECTED			8 Sq Ft	
345	DRINKING FOUNTAIN BY ROOM 3107	NONE DETECTED			8 Sq Ft	
367	DRINKING FOUNTAIN OUTSIDE ROOM 4104	NONE DETECTED	313-MC-B		20 Sq Ft	
373	DRINKING FOUNTAIN BY ROOM 4107	NONE DETECTED			20 Sq Ft	
399	DRINKING FOUNTAIN BY ROOM 4404	NONE DETECTED			20 Sq Ft	
402	DRINKING FOUNTAIN BY ROOM 4407	NONE DETECTED	313-MC-A		20 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2A	12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan Flecks					Total Amount - 850 Sq Ft
	231	ROOM 2510 (STORAGE/HALLWAY)	8-10 CH (TILE & MASTIC)	310-TYPE-6-B		560 Sq Ft
	237	ROOM 2511A	8-10 CH (TILE & MASTIC)	310-TYPE-6-C		130 Sq Ft
	241	ROOM 2511C	8-10 CH (TILE & MASTIC)	310-TYPE-6-A		160 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic Beige w/Thin Tan Streaks					Total Amount - 12164 Sq Ft
	18	ROOM 1405 (CUSTODIAL OFFICE)	3 CH (TILE), 5 CH (MASTIC)			250 Sq Ft
	66	ROOM 1106	3 CH (TILE), 5 CH (MASTIC)			70 Sq Ft
	70	ROOM 1201	3 CH (TILE), 5 CH (MASTIC)			210 Sq Ft
	74	ROOM 1202A	3 CH (TILE), 5 CH (MASTIC)			144 Sq Ft
	82	ROOM 1318	3 CH (TILE), 5 CH (MASTIC)			720 Sq Ft
	103	ROOM 1407	3 CH (TILE), 5 CH (MASTIC)			500 Sq Ft
	110	ROOM 1414	3 CH (TILE), 5 CH (MASTIC)			1200 Sq Ft
	124	ROOM 1503 (PHY ED OFFICE)	3 CH (TILE), 5 CH (MASTIC)			290 Sq Ft
	145	ROOM 1116	3 CH (TILE), 5 CH (MASTIC)	111708-MA-19		430 Sq Ft
	146	ROOM 1115	3 CH (TILE), 5 CH (MASTIC)			400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	150	ROOM 1119	3 CH (TILE), 5 CH (MASTIC)			600 Sq Ft
	151	ROOM 1119A	3 CH (TILE), 5 CH (MASTIC)			220 Sq Ft
	154	ROOM 1119C	3 CH (TILE), 5 CH (MASTIC)			250 Sq Ft
	155	ROOM 1120	3 CH (TILE), 5 CH (MASTIC)			600 Sq Ft
	158	ROOM 1215	3 CH (TILE), 5 CH (MASTIC)			400 Sq Ft
	181	ROOM 2102	3 CH (TILE), 5 CH (MASTIC)	2001-01108-11	11: STAIRWELL LANDING WEST OF KITCHEN (SINCE REMOVED).	250 Sq Ft
	185	ROOM 2011 (VAULT)	3 CH (TILE), 5 CH (MASTIC)			60 Sq Ft
	201	OFFICE COPY ROOM 2013	3 CH (TILE), 5 CH (MASTIC)			250 Sq Ft
	248	ROOM 2403	3 CH (TILE), 5 CH (MASTIC)			1000 Sq Ft
	252	ROOM 2304	3 CH (TILE), 5 CH (MASTIC)			1600 Sq Ft
	268	ROOM 2307	3 CH (TILE), 5 CH (MASTIC)			1600 Sq Ft
	285	ROOM 2312	3 CH (TILE), 5 CH (MASTIC)			1120 Sq Ft
K2C		12" x 12" Vinyl Floor Tile & Mastic White w/Tan Flecks				Total Amount - 5050 Sq Ft
	72	ROOM 1202	NONE DETECTED			1140 Sq Ft
	76	ROOM 1203	NONE DETECTED			1140 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	263	ROOM 2306	NONE DETECTED	111808-MA-12		1600 Sq Ft
	299	ROOM 2406	NONE DETECTED			1170 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic White w/Large Brown Smudges					Total Amount - 1514 Sq Ft
	109	HALLWAY/ENTRY OUTSIDE ROOM 1414	NONE DETECTED			60 Sq Ft
	279	ROOM 2311	NONE DETECTED	111808-MA-15		1370 Sq Ft
	330	ROOM 3205	NONE DETECTED			84 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Brown/Pink Mottle					Total Amount - 2415 Sq Ft
	197	OFFICE KITCHEN 2027	NONE DETECTED			215 Sq Ft
	202	THROUGHOUT NURSE'S OFFICE AREA	NONE DETECTED	310-TYPE 5-A, B, C		2200 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle					Total Amount - 700 Sq Ft
	253	ROOM 2304	NONE DETECTED	310-TYPE-3-A, B, C	HALLWAY 2400 OUTSIDE ROOMS 2404-2408 (SINCE REMOVED).	700 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Light Gray Mottle					Total Amount - 1810 Sq Ft
	292	ROOM 2404	NONE DETECTED	310-TYPE 4-B		900 Sq Ft
	295	ROOM 2405	NONE DETECTED	310-TYPE 4-A		910 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2H	12" x 12" Vinyl Floor Tile & Mastic White, Red & Black (2009)					Total Amount - 15700 Sq Ft
	64	HALLWAY TO ROOM 1112	NEW			1350 Sq Ft
	71	2ND FLOOR EAST HALLWAY & STAIRWELL ACROSS FROM ROOM 1202	NEW			1800 Sq Ft
	168	CAFETERIA 2200	NEW			7000 Sq Ft
	175	STAIRWELL OFF CAFETERIA	NEW			320 Sq Ft
	176	STAIRWELL LANDING WEST OF KITCHEN	NEW			480 Sq Ft
	177	CAFETERIA SNACK BAR - 2202A	NEW			220 Sq Ft
	178	HALLWAY OUTSIDE CAFETERIA 2200	NEW			2100 Sq Ft
	179	MAIN ENTRANCE/LOBBY	NEW			450 Sq Ft
	207	3RD FLOOR HALLWAY TA54 WEST OF MAIN ENTRY/LOBBY	NEW			800 Sq Ft
	247	HALLWAY 2300 OUTSIDE SCIENCE ROOMS	NEW			700 Sq Ft
	262	ENTRY FOR ROOMS 2305-2309	NEW			160 Sq Ft
	290	HALLWAY 2400 OUTSIDE ROOMS 2404-2408	NEW			320 Sq Ft
K2I	12" x 12" Vinyl Floor Tile & Mastic Beige/Tan Mottle					Total Amount - 20 Sq Ft
	362	ROOM 4103	NONE DETECTED	111908-MA-04		20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2J		12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan Swirls				Total Amount - 770 Sq Ft
	396	ROOM 4403	10 CH (MASTIC)	310-TYPE 2-A, B, C		770 Sq Ft
K3A		Miscellaneous Flooring Brown Rubber w/Mastic				Total Amount - 1700 Sq Ft
	142	ROOM 1117 (WEIGHT ROOM)	NONE DETECTED	111708-MA-18		1700 Sq Ft
K3B		Miscellaneous Flooring Black Floor Tile Mastic				Total Amount - 7 Sq Ft
	159	STAIRWELL 1199A 2ND FLOOR LANDING	5 CH	312-FL-A, B, C		7 Sq Ft
K3D		Miscellaneous Flooring Old Membrane/Vapor Barrier (1977)				Total Amount - 12000 Sq Ft
	120	ROOM 1501 (GYMNASIUM)	ASSUMED			12000 Sq Ft
K3E		Miscellaneous Flooring 2' X 2' Gray with Beige Flecks Rubber Floor Tile				Total Amount - 1600 Sq Ft
	68	ROOM 1104	NEW			800 Sq Ft
	69	ROOM 1103	NEW			800 Sq Ft
K3F		Miscellaneous Flooring 1' X 2' Brown Marbled Rubber Flooring (201x)				Total Amount - 1500 Sq Ft
	113	ROOM 1415	NEW			1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3G Miscellaneous Flooring White w/Red, Black & Gray Flakes Epoxy Flooring (2021)						Total Amount - 10000 Sq Ft
	4	THROUGHOUT BUILDING	NEW			10000 Sq Ft
LOA Flexible Duct Connector Green Vinyl						Total Amount - 128 Sq Ft
	36	ROOM 0406B (ELECTRICAL)	NSM			4 Sq Ft
	97	ROOM 1314D	NSM			2 Sq Ft
	98	ROOM 1314C	NSM			2 Sq Ft
	173	ROOM 2303 (FAN ROOM) BY KITCHEN	NSM			100 Sq Ft
	273	MECHANICAL ROOM 2308 OFF ROOM 2307	NSM			20 Sq Ft
LOB Flexible Duct Connector Black Vinyl						Total Amount - 444 Sq Ft
	31	BOILER ROOM 0406A	NSM			5 Sq Ft
	37	ROOM 0406B (ELECTRICAL)	NSM			2 Sq Ft
	56	TECHNOLOGY LAB 0101A	NSM			1 Sq Ft
	85	ROOM 1302	NSM			2 Sq Ft
	153	ROOM 1119B	NSM			2 Sq Ft
	174	MAINTENANCE ROOM 2203 BY KITCHEN	NSM			2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	209	ROOM 2117 (MECHANICAL)	NSM			30 Sq Ft
	222	ROOM 2120 (MECHANICAL)	NSM			20 Sq Ft
	243	ROOM 2512 (MECHANICAL)	NSM			150 Sq Ft
	278	ROOM 2310	NSM			2 Sq Ft
	328	ROOM 3411	NSM			8 Sq Ft
	359	PENTHOUSE 5101	NSM			120 Sq Ft
	393	PENTHOUSE 5401	NSM			100 Sq Ft
M0A	Plaster 1912 Original Building					Total Amount - 45300 Sq Ft
	24	BOILER ROOM 0406A	NONE DETECTED	111708-MA-01	SOUTHWEST CORNER.	300 Sq Ft
	35	ROOM 0406B (ELECTRICAL)	NONE DETECTED	111708-MA-07		400 Sq Ft
	40	ROOM 0406C (STORAGE)	NONE DETECTED			400 Sq Ft
	61	THROUGHOUT 2ND FLOOR	NONE DETECTED	111708-MA-02, 11	MA-02: ROOM 1203 CEILING. MA-11: ROOM 1410A - COLUMN.	10000 Sq Ft
	162	THROUGHOUT 3RD FLOOR	NONE DETECTED			10000 Sq Ft
	306	AUDITORIUM STAGE 2201A	NONE DETECTED	111808-MA-16	MA-16: BACK WALL.	3000 Sq Ft
	310	THROUGHOUT 4TH FLOOR	NONE DETECTED	111808-MA-17	ROOM 4409 (WALL).	10000 Sq Ft
	350	THROUGHOUT 5TH FLOOR	NONE DETECTED			10000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	356	PENTHOUSE 5101	NONE DETECTED			600 Sq Ft
	392	PENTHOUSE 5401	NONE DETECTED			600 Sq Ft
MOB	Plaster 1924 Addition					Total Amount - 4540 Sq Ft
	138	ROOM 1512B (POOL STORAGE)	NONE DETECTED	111708-MA-16		40 Sq Ft
	210	ROOM 2118 (OFF STAIRWELL)	NONE DETECTED			1500 Sq Ft
	215	ROOM 2119	NONE DETECTED	111808-MA-06		600 Sq Ft
	227	ROOM 2510 (STORAGE/HALLWAY)	NONE DETECTED	111808-MA-08	MA-08: WALL.	1000 Sq Ft
	233	ROOM 2511	NONE DETECTED			600 Sq Ft
	236	ROOM 2511A	NONE DETECTED			300 Sq Ft
	239	ROOM 2511C	NONE DETECTED			500 Sq Ft
MOC	Plaster 1977 Addition					Total Amount - 17900 Sq Ft
	79	2ND FLOOR RESTROOMS 1204 & 1205	NONE DETECTED	111708-MA-10	MA-10: MEN'S RESTROOM.	400 Sq Ft
	117	2ND FLOOR RESTROOMS 1417 & 1418	NONE DETECTED	509-D-29		500 Sq Ft
	123	WOMEN'S LOCKER ROOM 1502	NONE DETECTED	111708-MA-13		3000 Sq Ft
	126	MEN'S LOCKER ROOM 1504	NONE DETECTED			3000 Sq Ft
	131	ROOMS 1507 & 1508 OFF ROOM 1506	NONE DETECTED			300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	132	ROOM 1509 (MEN'S TEAM LOCKER ROOM)	NONE DETECTED	111708-MA-15	MA-15: WALL NEAR DRINKING FOUNTAIN.	2500 Sq Ft
	134	ROOM 1510 (WOMEN'S TEAM LOCKER ROOM)	NONE DETECTED			2500 Sq Ft
	139	ROOM 1512B (POOL STORAGE)	NONE DETECTED			100 Sq Ft
	156	SOUTH STAIRWELL TO AUDITORIUM	NONE DETECTED			200 Sq Ft
	160	NORTH STAIRWELL TO AUDITORIUM	NONE DETECTED			200 Sq Ft
	223	ROOM 2501	NONE DETECTED			1000 Sq Ft
	225	ROOM 2507 (BAND)	NONE DETECTED			1800 Sq Ft
	244	3RD FLOOR RESTROOMS 2401 & 2402 BY KITCHEN	NONE DETECTED			800 Sq Ft
	329	4TH FLOOR RESTROOMS 3209 & 3210	NONE DETECTED			400 Sq Ft
	334	RESTROOMS 3203 & 3204	NONE DETECTED			200 Sq Ft
	355	STAIRWELL 5199C TO PENTHOUSE 5101	NONE DETECTED			200 Sq Ft
	380	RESTROOMS 4212 & 4212A	NONE DETECTED			300 Sq Ft
	386	RESTROOMS 4220 & 4221	NONE DETECTED			300 Sq Ft
	390	STAIRWELL E (5499D) TO PENTHOUSE 5401	NONE DETECTED			200 Sq Ft
MOD	Plaster Stadium Walls and Ceilings				Total Amount - 5000 Sq Ft	
	407	THROUGHOUT JAMES GRIFFIN STADIUM	NONE DETECTED	120723JA-01, 02, 03	JA-01,02,03: THROUGHOUT JAMES GRIFFIN STADIUM.	5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
NOA	Drywall/Joint Compound Fixed Walls & Ceilings		Total Amount - 30000 Sq Ft			
	62	THROUGHOUT 2ND FLOOR	NONE DETECTED	509D30		10000 Sq Ft
	163	THROUGHOUT 3RD FLOOR	NONE DETECTED			10000 Sq Ft
	311	THROUGHOUT 4TH FLOOR	NONE DETECTED			5000 Sq Ft
	351	THROUGHOUT 5TH FLOOR	NONE DETECTED			5000 Sq Ft
NOB	Drywall/Joint Compound Portable Walls		Total Amount - 10000 Sq Ft			
	312	THROUGHOUT 4TH FLOOR	NONE DETECTED	2001-1501-AX8		5000 Sq Ft
	352	THROUGHOUT 5TH FLOOR	NONE DETECTED			5000 Sq Ft
POA	Fire Doors Metal w/Fiberglass Core (Jamisonic)		Total Amount - 100 Sq Ft			
	47	ROOM 0202	NSM			100 Sq Ft
POB	Fire Doors Metal - .75 Hr Rating		Total Amount - 40 Sq Ft			
	408	JAMES GRIFFIN STADIUM CONFERENCE ROOM	ASSUMED			20 Sq Ft
	410	JAMES GRIFFIN STADIUM NORTHEAST WOMEN'S RESTROOM ENTRYWAY	ASSUMED			20 Sq Ft
POC	Fire Doors Metal - 1.5 Hr Rating		Total Amount - 20 Sq Ft			
	409	JAMES GRIFFIN STADIUM WEST TRAINER OFFICE	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
POD Fire Doors Hollow Metal -1.5 Hr Rating (Underwriters Laboratories)						Total Amount - 1200 Sq Ft
7	THROUGHOUT BUILDING	NSM				1200 Sq Ft
POE Fire Doors Hollow Metal -.75 Hr Rating (Underwriters Laboratories)						Total Amount - 800 Sq Ft
8	THROUGHOUT BUILDING	NSM				800 Sq Ft
P1A Safe Doors Metal						Total Amount - 20 Sq Ft
184	ROOM 2011 (VAULT)	ASSUMED				20 Sq Ft
Q0A Carpet Adhesive Berber Carpet						Total Amount - 200000 Sq Ft
3	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-CESH-2C; 311-LB-A; 309-CM1-A, B, C	OFFICE, SOUTHEAST CORNER.		200000 Sq Ft
Q0B Carpet Adhesive Black & Gray Carpet						Total Amount - 1960 Sq Ft
65	ENTRY 2	NEW				600 Sq Ft
144	ENTRY 17	NEW				160 Sq Ft
180	MAIN ENTRANCE	NEW				1200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0C		Carpet Adhesive Gray & Red Striped Carpet Squares			Total Amount - 1250 Sq Ft	
182	MAIN OFFICE 2001	NEW			800 Sq Ft	
199	OFFICE WORK ROOM 2001A	NEW			450 Sq Ft	
ROA		Baseboard/Mopboard Adhesive Brown Baseboard w/Brown Mastic			Total Amount - 15000 Sq Ft	
5	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-CESH-1C; 308-BC1-A, B, C	1C: OFFICE IN SOUTHEAST CORNER.	15000 Sq Ft	
ROB		Baseboard/Mopboard Adhesive Black 90-Degree Baseboard (2008)			Total Amount - 100 Sq Ft	
121	ROOM 1501 (GYMNSIUM)	NEW			50 Sq Ft	
148	ROOM 1114	NEW			50 Sq Ft	
ROC		Baseboard/Mopboard Adhesive 4" Gray Baseboard (200X)			Total Amount - 300 Sq Ft	
165	THROUGHOUT 3RD FLOOR	NEW			300 Sq Ft	
ROD		Baseboard/Mopboard Adhesive 4" Black (2021)			Total Amount - 1000 Sq Ft	
6	THROUGHOUT BUILDING	NEW			1000 Sq Ft	
ROE		Baseboard/Mopboard Adhesive 4" Cream Baseboard			Total Amount - 10 Sq Ft	
130	ROOM 1214	ASSUMED			10 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
S0B	Wood Floor Felt / Vapor Barrier On Grade (1924)					Total Amount - 8000 Sq Ft
	128	ROOM 1505 (GYMNASTICS)	ASSUMED			8000 Sq Ft
S0C	Wood Floor Felt / Vapor Barrier 1977 Addition (On Grade)					Total Amount - 1550 Sq Ft
	147	ROOM 1114	ASSUMED			1550 Sq Ft
S0D	Wood Floor Felt / Vapor Barrier 1977 Addition (Elevated)					Total Amount - 1700 Sq Ft
	307	AUDITORIUM STAGE 2201A	NSM			1700 Sq Ft
S0E	Wood Floor Felt / Vapor Barrier 1912 Original Building (Elevated)					Total Amount - 7000 Sq Ft
	354	THROUGHOUT 5TH FLOOR CLASSROOMS 4101-4110	ASSUMED			7000 Sq Ft
S0F	Wood Floor Felt / Vapor Barrier 2008 Addition (Floating)					Total Amount - 12000 Sq Ft
	119	ROOM 1501 (GYMNASIUM)	NSM			12000 Sq Ft
TOA	Light Cord Insulation Fuzzy, White					Total Amount - 90 Lin Ft
	46	ROOM 0202	ASSUMED			6 Lin Ft
	49	OFFICES 0204-0206	ASSUMED			24 Lin Ft
	51	ROOM 0101	ASSUMED			36 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	53	STAIRWELL TO OBSERVATION NORTH OFF ROOM 0101	ASSUMED			18 Lin Ft
	157	STORAGE CLOSET 2201C	ASSUMED			6 Lin Ft
VOA	Sink Undercoating Black					Total Amount - 135 Sq Ft
	19	ROOM 1406	3 CH			5 Sq Ft
	67	ROOM 1106	3 CH			10 Sq Ft
	104	ROOM 1407	3 CH			5 Sq Ft
	106	ROOM 1409	3 CH			5 Sq Ft
	112	ROOM 1414	3 CH			45 Sq Ft
	115	ROOM 1415	3 CH			10 Sq Ft
	198	OFFICE KITCHEN 2027	3 CH			5 Sq Ft
	200	OFFICE WORK ROOM 2001A	3 CH			5 Sq Ft
	203	NURSE'S OFFICE - ROOM 2107	3 CH	111808-MA-01		5 Sq Ft
	302	ROOM 2407	3 CH			5 Sq Ft
	304	ROOM 2408	3 CH			5 Sq Ft
	314	ROOM 3420	3 CH			5 Sq Ft
	331	ROOM 3205	3 CH			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	337	ROOM 3118	3 CH			5 Sq Ft
	389	MEDIA CENTER WORK ROOM 4202	3 CH			10 Sq Ft
VOB	Sink Undercoating White					Total Amount - 6 Sq Ft
	87	ROOM 1303	NONE DETECTED	502-YEL-A		6 Sq Ft
VOC	Sink Undercoating Deep Black					Total Amount - 40 Sq Ft
	89	ROOM 1304	5 CH			24 Sq Ft
	95	ROOM 1308	5 CH	111808-MA-02	MA-02: NURSE'S OFFICE -ROOM 2112 (SINCE REMOVED).	16 Sq Ft
VOD	Sink Undercoating Gray					Total Amount - 15 Sq Ft
	90	ROOM 1304	NONE DETECTED			5 Sq Ft
	96	ROOM 1308	NONE DETECTED	502-GRA-A		10 Sq Ft
VOE	Sink Undercoating White					Total Amount - 23 Sq Ft
	75	ROOM 1202A	10 CH			5 Sq Ft
	83	ROOM 1318	10 CH			8 Sq Ft
	364	ROOM 4103	10 CH	502-GRA-B, C		10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1A	1' x 1' Ceiling Tile Adhesive Tan Pucks Associated w/I1A					Total Amount - 325 Sq Ft
	101	VIDEO STORAGE BETWEEN ROOMS 1211 & 1215	NONE DETECTED			200 Sq Ft
	102	ROOM 1211	NONE DETECTED			25 Sq Ft
	212	ROOM 2118 (OFF STAIRWELL)	NONE DETECTED			40 Sq Ft
	218	ROOM 2119	NONE DETECTED	111808-MA-05		40 Sq Ft
	230	ROOM 2510 (STORAGE/HALLWAY)	NONE DETECTED			20 Sq Ft
X0A	Miscellaneous Material Pyrobar Block (1912)					Total Amount - 20000 Sq Ft
	16	THROUGHOUT 1912 ORIGINAL BUILDING	NSM			20000 Sq Ft
X0B	Miscellaneous Material Pyrobar Mortar (1912)					Total Amount - 2000 Sq Ft
	17	THROUGHOUT 1912 ORIGINAL BUILDING	NONE DETECTED	111708-MA-08	MA-08: CRAWL SPACE OFF ROOM 0406C.	2000 Sq Ft
X0C	Miscellaneous Material Foam Acoustical Panel Adhesive (Yellow)					Total Amount - 155 Sq Ft
	57	ROOM 0201B	NONE DETECTED	509-WA-B	WA-B: ROOM 0101 (SINCE REMOVED).	25 Sq Ft
	59	STORAGE ROOM 0102	NONE DETECTED			80 Sq Ft
	149	ROOM 1119	NONE DETECTED	509-WA-C; 509-WA-A	WA-C: ROOM 1113 (SINCE REMOVED). WA-A: ROOM 1120 (SINCE REMOVED).	40 Sq Ft
	152	ROOM 1119B	NONE DETECTED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOD		Miscellaneous Material Green Duct Seam Caulk				Total Amount - 100 Sq Ft
	9	THROUGHOUT BUILDING	5 CH	321-DC1-A		100 Sq Ft
XOE		Miscellaneous Material Dark Gray Duct Seam Caulk				Total Amount - 100 Sq Ft
	10	THROUGHOUT BUILDING	5 CH	321-DC2-A		100 Sq Ft
XOF		Miscellaneous Material Dark Gray Duct Seam Putty				Total Amount - 100 Sq Ft
	11	THROUGHOUT BUILDING	10 CH	321-DC3-A		100 Sq Ft
XOG		Miscellaneous Material White Window Sill Caulk				Total Amount - 200 Sq Ft
	12	THROUGHOUT BUILDING	NONE DETECTED	321-WS1-A		200 Sq Ft
XOH		Miscellaneous Material Dark Brown Window Sill Caulk				Total Amount - 200 Sq Ft
	13	THROUGHOUT BUILDING	3 CH	321-WS2-A		200 Sq Ft
XOJ		Miscellaneous Material Kiln Refractory				Total Amount - 120 Sq Ft
	92	ROOM 1306 (KILN ROOM)	NONE DETECTED	2001-1504-A1		120 Sq Ft
XOK		Miscellaneous Material Streaked Brown Countertops				Total Amount - 22 Sq Ft
	125	ROOM 1503 (PHY ED OFFICE)	NONE DETECTED			6 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	189	OFFICE HALLWAY OUTSIDE CONFERENCE ROOM 2010B	NONE DETECTED	111708-MA-20		10 Sq Ft
	315	ROOM 3415	NONE DETECTED			6 Sq Ft
XOL	Miscellaneous Material White Duct Seam Caulk					Total Amount - 2 Sq Ft
	208	ROOM 2117 (MECHANICAL)	8 CH	111808-MA-03		2 Sq Ft
XOM	Miscellaneous Material Lightweight Concrete Roof Deck Slabs (1924)					Total Amount - 3090 Sq Ft
	213	ROOM 2118 (OFF STAIRWELL)	NONE DETECTED			840 Sq Ft
	219	ROOM 2119	NONE DETECTED	111808-MA-04		860 Sq Ft
	226	ROOM 2510 (STORAGE/HALLWAY)	NONE DETECTED			720 Sq Ft
	234	ROOM 2511	NONE DETECTED			300 Sq Ft
	235	ROOM 2511A	NONE DETECTED			130 Sq Ft
	238	ROOM 2511C	NONE DETECTED			240 Sq Ft
XON	Miscellaneous Material Slate Chalkboard - Nailed (1924)					Total Amount - 48 Sq Ft
	214	ROOM 2119	NSM			48 Sq Ft
XOO	Miscellaneous Material Tackboard Adhesive (1924)					Total Amount - 86 Sq Ft
	220	ROOM 2119	NONE DETECTED	111808-MA-07		36 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	232	ROOM 2510 (STORAGE/HALLWAY)	NONE DETECTED			50 Sq Ft
X0Q	Miscellaneous Material Brown Adhesive Pucks					Total Amount - 2 Sq Ft
	305	ROOM 2409	NONE DETECTED	111808-MA-14		2 Sq Ft
X0R	Miscellaneous Material Coarse White Proscenium Curtain					Total Amount - 600 Sq Ft
	308	AUDITORIUM STAGE 2201A	ASSUMED			600 Sq Ft
X0S	Miscellaneous Material Old Black Roofing					Total Amount - 8 Sq Ft
	358	PENTHOUSE 5101	NONE DETECTED	111908-MA-01		8 Sq Ft
X0T	Miscellaneous Material Black Countertop Adhesive					Total Amount - 5 Sq Ft
	281	ROOM 2311	2 CH	081011-JC-01		5 Sq Ft
X0U	Miscellaneous Material Window Caulk (1912)					Total Amount - 4 Sq Ft
	283	ROOM 2311	3 CH	081011-JC-02		4 Sq Ft
X0V	Miscellaneous Material Window Glaze (1912)					Total Amount - 12 Sq Ft
	284	ROOM 2311	NONE DETECTED	081011-JC-03		12 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0W	Miscellaneous Material Black Dampproofing		Total Amount - 2200 Sq Ft			
	33	BOILER ROOM 0406A	ASSUMED			300 Sq Ft
	38	ROOM 0406B (ELECTRICAL)	ASSUMED			400 Sq Ft
	228	ROOM 2510 (STORAGE/HALLWAY)	ASSUMED			1000 Sq Ft
	240	ROOM 2511C	ASSUMED			500 Sq Ft
X0X	Miscellaneous Material Tackboard Adhesive (1912)		Total Amount - 50 Sq Ft			
	44	ROOM 0404	ASSUMED			50 Sq Ft
X0Y	Miscellaneous Material White Caulking Stadium Sinks		Total Amount - 20 Sq Ft			
	411	JAMES GRIFFIN STADIUM NORTHEAST WOMEN'S RESTROOM ENTRYWAY	NONE DETECTED	120723JA-04, 05	JA-04,05: JAMES GRIFFIN STADIUM NORTHEAST WOMEN'S RESTROOM ENTRYWAY.	20 Sq Ft
X1A	Miscellaneous Material Pipe Flange Gaskets		Total Amount - 30 Sq Ft			
	32	BOILER ROOM 0406A	25 CH	111708-MA-03	"DEAD" LINE SOUTH OF BOILERS.	30 Sq Ft
X1B	Miscellaneous Material 1" x 1" Light Brown Ceramic Floor Tile System		Total Amount - 8050 Sq Ft			
	14	THROUGHOUT BUILDING RESTROOMS	ASSUMED			800 Sq Ft
	118	2ND FLOOR RESTROOMS 1417 & 1418	ASSUMED			1250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	133	ROOM 1509 (MEN'S TEAM LOCKER ROOM)	ASSUMED			3000 Sq Ft
	135	ROOM 1510 (WOMEN'S TEAM LOCKER ROOM)	ASSUMED			3000 Sq Ft
X1C	Miscellaneous Material 6" x 6" Light Brown Quarry Tile System					Total Amount - 1700 Sq Ft
	171	KITCHEN 2204/2302	ASSUMED			1700 Sq Ft
X1D	Miscellaneous Material 2" x 2" Gray Ceramic Wall Tile System					Total Amount - 10 Sq Ft
	81	HALLWAY OUTSIDE ROOM 1205	NEW			3 Sq Ft
	246	HALLWAY OUTSIDE STAIR D ENTRANCE	NEW			4 Sq Ft
	291	HALLWAY OUTSIDE ROOM 2404	NEW			3 Sq Ft
X1E	Miscellaneous Material 4" X 4" White Ceramic Wall Tile System					Total Amount - 100 Sq Ft
	80	HANDWASH AREA OUTSIDE 2ND FLOOR RESTROOMS 1204 & 1205	ASSUMED			100 Sq Ft
X1F	Miscellaneous Material 4" X 4" Beige Ceramic Wall Tile System					Total Amount - 200 Sq Ft
	204	NURSE'S RESTROOM 2107B	ASSUMED			100 Sq Ft
	206	NURSE'S RESTROOM 2113A	ASSUMED			100 Sq Ft
X1G	Miscellaneous Material 8" Gray Quarry Tile System (2020)					Total Amount - 112 Sq Ft
	205	NURSE'S LAB - ROOM 2112	NEW			112 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1H		Miscellaneous Material 4" X 6" Beige Ceramic Baseboard System				Total Amount - 100 Sq Ft
	15	THROUGHOUT BUILDING RESTROOMS	ASSUMED			100 Sq Ft
X1I		Miscellaneous Material 1" X 1" Cream Ceramic Floor Tile System				Total Amount - 3000 Sq Ft
	136	POOL 1512	ASSUMED			3000 Sq Ft
X1J		Miscellaneous Material 1" X 1" White & Black Ceramic Pool Tile System				Total Amount - 4000 Sq Ft
	137	POOL 1512	ASSUMED			4000 Sq Ft