

90 South Western Avenue, Saint Paul, MN 55102

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
B2A		Millboard Pipe Insulation 1922 Original Building				Total Amount - 100 Lin Ft
	7	THROUGHOUT 1922 ORIGINAL BUILDING	NONE DETECTED	071212BF-1, 2, 3	BF-1: ROOM 1116. BF-2: ROOM 2110. BF-3: ROOM 3112.	100 Lin Ft
I1A		1' x 1' Acoustical Ceiling Tile Random Large & Medium Holes				Total Amount - 5740 Sq Ft
	44	ROOM 1101	NONE DETECTED			300 Sq Ft
	48	MAIN OFFICE AREAS	NONE DETECTED			1000 Sq Ft
	62	ROOM 2107	NONE DETECTED			660 Sq Ft
	66	ROOM 2105	NONE DETECTED			660 Sq Ft
	69	ROOM 2104	NONE DETECTED			660 Sq Ft
	72	ROOM 2102	NONE DETECTED	2001-1501-JF3		660 Sq Ft
	75	ROOMS 2101 & 2101A	NONE DETECTED	207K-11A	11A: ROOM 2101A.	1200 Sq Ft
	87	ROOM 3101	NONE DETECTED			600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2A	2' x 2' Acoustical Ceiling Tile Rough (2007)					Total Amount - 1675 Sq Ft
	18	ROOM 1115 (CAFETERIA/AUDITORIUM)	NEW			65 Sq Ft
	54	ROOM 2112 (MEDIA)	NEW			1300 Sq Ft
	56	ROOM 2112A	NEW			160 Sq Ft
	58	ROOM 2112B	NEW			150 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Vinyl-Coated Gypsum					Total Amount - 125 Sq Ft
	24	ROOM 1117 (DISHWASHING)	NONE DETECTED	503-07		125 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Fissures & Pin Holes					Total Amount - 60 Sq Ft
	51	MAIN OFFICE HALLWAY	NONE DETECTED	503-06		60 Sq Ft
I3A	2' x 4' Ceiling Tile Widthwise Fissures w/Pin Holes					Total Amount - 330 Sq Ft
	65	ROOM 2106	NONE DETECTED	510D-3		330 Sq Ft
J3B	Miscellaneous Cementitious Material Shiny Black Table Tops					Total Amount - 200 Sq Ft
	78	ROOM 2101	NONE DETECTED			150 Sq Ft
	90	ROOM 3101 & 3101A	NONE DETECTED	503-02		50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J3C		Miscellaneous Cementitious Material Dull Black Table Tops				Total Amount - 190 Sq Ft
	77	ROOM 2101	NONE DETECTED	503-01	503-01: ROOM 3101 (SINCE REMOVED).	190 Sq Ft
J3D		Miscellaneous Cementitious Material Black Drying Rack				Total Amount - 6 Sq Ft
	89	ROOM 3101	NONE DETECTED	022309-RV-06		6 Sq Ft
K0A		9" x 9" Vinyl Floor Tile & Mastic Tan w/Brown & Beige Streaks				Total Amount - 55 Sq Ft
	43	ROOM 1107	3 CH (TILE), 10 CH (MASTIC)	022309-RV-15	RV-15: ROOM 1109 (SINCE REMOVED).	55 Sq Ft
K1A		Sheet Vinyl Flooring & Adhesive Gray & Blue Marbling (2014)				Total Amount - 570 Sq Ft
	35	ROOM 1111	NEW			570 Sq Ft
K2A		12" x 12" Vinyl Floor Tile & Mastic Light Brown w/White Flecks (1995)				Total Amount - 165 Sq Ft
	27	ROOM 1117B	NONE DETECTED	503-05		125 Sq Ft
	82	2ND FLOOR ELEVATOR LOBBY	NONE DETECTED			20 Sq Ft
	85	3RD FLOOR ELEVATOR LOBBY	NONE DETECTED	022309-RV-08		20 Sq Ft
K3A		Miscellaneous Flooring Blue Marble Design				Total Amount - 3600 Sq Ft
	5	THROUGHOUT BUILDING HALLWAYS	NONE DETECTED	022309-RV-07	RV-07: 3RD FLOOR ELEVATOR LOBBY.	3600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3B Miscellaneous Flooring Orange w/Multi-Colored Spatters						Total Amount - 2500 Sq Ft
	19	ROOM 1115 (CAFETERIA/AUDITORIUM)	NEW			2500 Sq Ft
LOA Flexible Duct Connector Coarse Brown Weave						Total Amount - 32 Sq Ft
	12	FAN ROOM B2 WEST OF BOILER ROOM	NONE DETECTED	022309-RV-01		20 Sq Ft
	16	FAN ROOM B07 NORTH OF BOILER ROOM	NONE DETECTED	2001-1501-JF6		12 Sq Ft
LOB Flexible Duct Connector Black Reinforced Vinyl/Rubber						Total Amount - 30 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	503-09		30 Sq Ft
MOA Plaster 1922 Original Building						Total Amount - 100000 Sq Ft
	6	THROUGHOUT 1922 ORIGINAL BUILDING	NONE DETECTED	022309-RV-05, 10, 11, 12; 510D-4, 5, 6	RV-05: GYMNASIUM STORAGE 3113E (WALL). RV-10: GYMNASIUM STORAGE 3113F (CEILING). RV-11: ROOM 2113A (WALL). RV-12: ROOM 1115B (WALL).	100000 Sq Ft
NOA Drywall/Joint Compound Renovation						Total Amount - 5000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	2001-1501-JF2	JF2: ROOM 2104 NORTH WALL.	5000 Sq Ft
POA Fire Doors Flush-Top Metal - 1.5 Hr Rating (Underwriter's Laboratories)						Total Amount - 40 Sq Ft
	13	FAN ROOM B2 WEST OF BOILER ROOM	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	98	PENTHOUSE MECHANICAL	ASSUMED			20 Sq Ft
POB	Fire Doors Recessed Top, Metal - 1.5 Hr Rating (Underwriter's Laboratories)					Total Amount - 84 Sq Ft
	17	BASEMENT STAIRWELL	ASSUMED			60 Sq Ft
	102	GYMNASIUM STAIRWELL	ASSUMED			24 Sq Ft
POC	Fire Doors Pieced Metal w/Wood Core					Total Amount - 200 Sq Ft
	14	BOILER ROOM	NSM			200 Sq Ft
Q0A	Carpet Adhesive Brown Berber					Total Amount - 290 Sq Ft
	23	ROOM 1116	NONE DETECTED	022309-RV-15; 503-03	RV-15; 503-03: ROOM 1109 (SINCE REMOVED).	200 Sq Ft
	101	ROOM 3113B	NONE DETECTED			90 Sq Ft
Q0B	Carpet Adhesive Tan Carpet Squares (2011)					Total Amount - 4500 Sq Ft
	2	THROUGHOUT BUILDING	NEW			3000 Sq Ft
	93	ROOM 3102	NEW			500 Sq Ft
	94	ROOM 3104	NEW			500 Sq Ft
	95	ROOM 3105	NEW			500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0C		Carpet Adhesive Multi-Colored Berber Carpet (200X)			Total Amount - 1300 Sq Ft	
46	ROOMS 1104 & 1104A	NEW			300 Sq Ft	
50	MAIN OFFICE AREAS	NEW			1000 Sq Ft	
Q0D		Carpet Adhesive Blue Carpet Squares (2014)			Total Amount - 716 Sq Ft	
34	ROOM 1112	NEW			216 Sq Ft	
40	ROOM 1109	NEW			500 Sq Ft	
R0A		Baseboard/Mopboard Adhesive 6" Dark Brown Baseboard (1995)			Total Amount - 4 Sq Ft	
86	3RD FLOOR ELEVATOR LOBBY	NONE DETECTED	022309-RV-08		4 Sq Ft	
R0B		Baseboard/Mopboard Adhesive 4" Brown Baseboard			Total Amount - 2000 Sq Ft	
3	THROUGHOUT BUILDING	NONE DETECTED	503-13	13: KITCHEN STORAGE.	2000 Sq Ft	
R0C		Baseboard/Mopboard Adhesive 4" Gray Baseboard (2014)			Total Amount - 15 Sq Ft	
36	ROOM 1111	NEW			15 Sq Ft	
S0A		Wood Floor Felt / Vapor Barrier 1922 Original Building (Elevated)			Total Amount - 35000 Sq Ft	
8	THROUGHOUT 1922 ORIGINAL BUILDING	NONE DETECTED	022309-RV-14	RV-14: ROOM 1115D	35000 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
TOA	Light Cord Insulation Fuzzy, White					Total Amount - 90 Lin Ft
	20	ROOM 1115 STAGE	ASSUMED			27 Lin Ft
	22	2005 ADDITION OFF OF STAGE (1115E)	ASSUMED			63 Lin Ft
VOA	Sink Undercoating Deep Gray					Total Amount - 198 Sq Ft
	28	ROOM 1118	NONE DETECTED			8 Sq Ft
	52	ROOM 2114	NONE DETECTED			8 Sq Ft
	53	ROOM 2115	NONE DETECTED			8 Sq Ft
	64	ROOM 2107	NONE DETECTED			8 Sq Ft
	68	ROOM 2105	NONE DETECTED	022309-RV-04		8 Sq Ft
	71	ROOM 2104	NONE DETECTED			8 Sq Ft
	74	ROOM 2102	NONE DETECTED			150 Sq Ft
VOB	Sink Undercoating Smooth Gray (2005)					Total Amount - 8 Sq Ft
	21	2005 ADDITION OFF OF STAGE (1115E)	NONE DETECTED	022309-RV-13		8 Sq Ft
VOC	Sink Undercoating Rough Gray w/Ball Faucet					Total Amount - 5 Sq Ft
	39	ROOM 1110	NONE DETECTED	022309-RV-16		5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
V0D	Sink Undercoating Cream					Total Amount - 14 Sq Ft
	29	ROOM 1114	NEW			8 Sq Ft
	47	ROOMS 1104 & 1104A	NEW			6 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/11A					Total Amount - 1750 Sq Ft
	45	ROOM 1101	NONE DETECTED			75 Sq Ft
	49	MAIN OFFICE AREAS	NONE DETECTED			250 Sq Ft
	55	ROOM 2112 (MEDIA)	NONE DETECTED			300 Sq Ft
	57	ROOM 2112A	NONE DETECTED			40 Sq Ft
	59	ROOM 2112B	NONE DETECTED			35 Sq Ft
	63	ROOM 2107	NONE DETECTED			150 Sq Ft
	67	ROOM 2105	NONE DETECTED			150 Sq Ft
	70	ROOM 2104	NONE DETECTED			150 Sq Ft
	73	ROOM 2102	NONE DETECTED	022309-RV-09		150 Sq Ft
	76	ROOMS 2101 & 2101A	NONE DETECTED			300 Sq Ft
	88	ROOM 3101	NONE DETECTED			150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOA	Miscellaneous Material Exterior Window Glaze					Total Amount - 8 Sq Ft
15	BOILER ROOM	NONE DETECTED			2 Sq Ft	
99	PENTHOUSE MECHANICAL	NONE DETECTED	022309-RV-03		4 Sq Ft	
100	GYMNASIUM FAN ROOM	NONE DETECTED			2 Sq Ft	
XOB	Miscellaneous Material Slate Chalkboard Adhesive (1922)					Total Amount - 300 Sq Ft
10	THROUGHOUT 1922 ORIGINAL BUILDING	ASSUMED			300 Sq Ft	
XOC	Miscellaneous Material Tackboard Adhesive (1922)					Total Amount - 650 Sq Ft
83	THROUGHOUT 1922 ORIGINAL BUILDING THIRD FLOOR	NONE DETECTED	062014BF-1	BF-1: 1ST FLOOR HALLWAY.	650 Sq Ft	
XOE	Miscellaneous Material Kiln Block					Total Amount - 60 Sq Ft
79	ROOM 2101A	NONE DETECTED	503-11, 12		60 Sq Ft	
XOG	Miscellaneous Material Thin Metal Frame Corkboard Adhesive					Total Amount - 320 Sq Ft
84	THROUGHOUT 3RD FLOOR HALLWAY	ASSUMED			320 Sq Ft	
XOH	Miscellaneous Material Black Wall Coating					Total Amount - 500 Sq Ft
9	THROUGHOUT 1922 ORIGINAL BUILDING	NONE DETECTED	082312ML-01	ML-01: RESTROOM 1116C.	500 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOI	Miscellaneous Material Wood Frame Window Caulk					Total Amount - 2 Sq Ft
	37	ROOM 1110A	ASSUMED			2 Sq Ft
XOJ	Miscellaneous Material White Window Glazing					Total Amount - 6 Sq Ft
	38	ROOM 1110A	ASSUMED			6 Sq Ft
XOK	Miscellaneous Material Old Gray Interior Window Caulk					Total Amount - 100 Sq Ft
	11	THROUGHOUT 1922 ORIGINAL BUILDING	10 CH	052120-BF-3	BF-3: ROOM 2107.	100 Sq Ft
XOL	Miscellaneous Material White Milkboard Adhesive					Total Amount - 384 Sq Ft
	26	ROOM 1117	ASSUMED			384 Sq Ft
X1A	Miscellaneous Material 8" Red Quarry tile (20XX)					Total Amount - 400 Sq Ft
	25	ROOM 1117	NEW			400 Sq Ft
X1B	Miscellaneous Material 1" Light Brown Ceramic Floor Tile System					Total Amount - 200 Sq Ft
	30	ROOM 1114 RESTROOM	ASSUMED			100 Sq Ft
	41	ROOM 1109 RESTROOM	ASSUMED			50 Sq Ft
	91	RESTROOM ACROSS FROM ROOM 3101	ASSUMED			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1C	Miscellaneous Material 4" Brown Ceramic Wall Tile System					Total Amount - 400 Sq Ft
	31	ROOM 1114 RESTROOM AND SHOWER	ASSUMED			100 Sq Ft
	42	ROOM 1109 RESTROOM	ASSUMED			100 Sq Ft
	81	RESTROOM ACROSS FROM ROOM 2101	ASSUMED			100 Sq Ft
	92	RESTROOM ACROSS FROM ROOM 3101	ASSUMED			100 Sq Ft
X1D	Miscellaneous Material 2" White Ceramic Wall Tile System					Total Amount - 1000 Sq Ft
	32	RESTROOM ACROSS FROM ROOM 1114	ASSUMED			150 Sq Ft
	33	RESTROOM ACROSS FROM ROOM 1112	ASSUMED			150 Sq Ft
	60	BOYS' RESTROOM ACROSS FROM ROOM 2108	ASSUMED			150 Sq Ft
	61	GIRLS' RESTROOM ACROSS FROM ROOM 2108	ASSUMED			150 Sq Ft
	96	GIRLS' RESTROOM ACROSS FROM 3106	ASSUMED			200 Sq Ft
	97	BOYS' RESTROOM ACROSS FROM 3108	ASSUMED			200 Sq Ft
X1E	Miscellaneous Material 1" Beige Ceramic Floor Tile System					Total Amount - 50 Sq Ft
	80	RESTROOM ACROSS FROM ROOM 2101	ASSUMED			50 Sq Ft