

340 Colborne Street, Saint Paul, MN 55102

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A	Mudded Pipe Joints on Fiberglass Insulation 1973 Original Building					Total Amount - 339 Joints
	13	LOBBY/COMMONS (1600)	NONE DETECTED	112310-MV-01	MV-01: HALLWAY 1600.	30 Joints
	22	ROOM 1602	NONE DETECTED			1 Joints
	27	1973 ORIGINAL BUILDING MAIN HALLWAY (1000)	NONE DETECTED	062122CW-03; 112310-MV-03	CW-03: HALLWAY 1000 SOUTH END. MV-03: HALLWAY 1000 BY MAIN OFFICE.	80 Joints
	34	ROOM 1604	NONE DETECTED			3 Joints
	38	ROOM 1605	NONE DETECTED			23 Joints
	43	ROOM 1603	NONE DETECTED			2 Joints
	48	ROOM 1606	NONE DETECTED			10 Joints
	55	GIRLS' RESTROOM (1509)	NONE DETECTED			10 Joints
	59	CUSTODIAL CLOSET (1510)	NONE DETECTED			9 Joints
	62	BOYS' RESTROOM (1511)	NONE DETECTED	112310-MV-02	MV-02: BOYS' RESTROOM 1511.	23 Joints
	65	ROOM 1512	NONE DETECTED			10 Joints
	69	HALLWAY 1500	NONE DETECTED			6 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	75	ROOM 1508	NONE DETECTED			3 Joints
	77	ROOM 1506 (MEDIA CENTER)	NONE DETECTED			30 Joints
	81	ENTRY 1500A (RESOURCE ROOM)	NONE DETECTED			5 Joints
	83	STAFF RESTROOM (1504)	NONE DETECTED			2 Joints
	86	ROOM 1503	NONE DETECTED			24 Joints
	91	ROOM 1502	NONE DETECTED			26 Joints
	97	ROOM 1513 (LOUNGE)	NONE DETECTED			30 Joints
	103	MAIN OFFICE (1001)	NONE DETECTED			2 Joints
	105	ROOM 1002	NONE DETECTED			8 Joints
	121	ROOM 1501	NONE DETECTED			2 Joints
A4B	Mudded Pipe Joints on Fiberglass Insulation PVC-Wrapped Runs				Total Amount - 17 Joints	
	17	ROOM 1601	NONE DETECTED	112310-MV-04	MV-04: ROOM 1601.	4 Joints
	78	ROOM 1506 (MEDIA CENTER)	NONE DETECTED	112310-MV-05	MV-05: ROOM 1506 (IMC).	4 Joints
	87	ROOM 1503	NONE DETECTED			6 Joints
	92	ROOM 1502	NONE DETECTED	112310-MV-06	MV-06: ROOM 1502.	3 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
H1B	Sprayed-On Structural Fireproofing Gray, Fluffy Mineral Wool					Total Amount - 10000 Sq Ft
	5	THROUGHOUT 1973 ORIGINAL BUILDING	NONE DETECTED	112310-MV-07, 121510-MV-04	MV-07: BOYS' RESTROOM 1511. MV-04: HALL 1600 ABOVE EXTERIOR DOOR; 2001-1501- AT-6,7,8,9,10,11,12: BRIDGE VIEW.	10000 Sq Ft
H1C	Sprayed-On Structural Fireproofing Tan w/Vermiculite					Total Amount - 511 Sq Ft
	61	BOYS' RESTROOM (1511)	<1 ACT	121510-MV-01	MV-01: DEBRIS ON LEDGE IN STALL AREA.	1 Sq Ft
	101	WEST ENTRY (1000A)	<1 ACT			50 Sq Ft
	108	ROOM 1003	<1 ACT	112310-MV-08	MV-08: ROOM 1003.	50 Sq Ft
	112	ROOM 1004	<1 ACT			60 Sq Ft
	115	ROOM 1005	<1 ACT			60 Sq Ft
	118	ROOM 1006	<1 ACT	121510-MV-03		140 Sq Ft
	120	ROOM 1501	<1 ACT	121510-MV-02		150 Sq Ft
I2E	2' x 2' Acoustical Ceiling Tile Nail & Pin Holes in Concentric Pattern					Total Amount - 670 Sq Ft
	56	GIRLS' RESTROOM (1509)	NONE DETECTED			280 Sq Ft
	63	BOYS' RESTROOM (1511)	NONE DETECTED	112310-MV-09	MV-09: BOYS' RESTROOM 1511.	280 Sq Ft
	84	STAFF RESTROOM (1504)	NONE DETECTED			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	85	STAFF RESTROOM (1505)	NONE DETECTED			60 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Gouges & Pin Holes w/Revealed Edge					Total Amount - 5330 Sq Ft
	14	LOBBY/COMMONS (1600)	NONE DETECTED	112310-MV-10	MV-10: HALLWAY 1600.	800 Sq Ft
	18	ROOM 1601	NONE DETECTED			290 Sq Ft
	23	ROOM 1602	NONE DETECTED			500 Sq Ft
	28	1973 ORIGINAL BUILDING MAIN HALLWAY (1000)	NONE DETECTED			1700 Sq Ft
	35	ROOM 1604	NONE DETECTED			120 Sq Ft
	39	ROOM 1605	NONE DETECTED			120 Sq Ft
	44	ROOM 1603	NONE DETECTED			500 Sq Ft
	49	ROOM 1606	NONE DETECTED			500 Sq Ft
	60	CUSTODIAL CLOSET (1510)	NONE DETECTED			100 Sq Ft
	98	ROOM 1513 (LOUNGE)	NONE DETECTED			500 Sq Ft
	102	WEST ENTRY (1000A)	NONE DETECTED			200 Sq Ft
I2G	2' x 2' Acoustical Ceiling Tile Light Texture w/Revealed Edge (2011)					Total Amount - 600 Sq Ft
	66	ROOM 1512	NEW			600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3B	2' x 4' Ceiling Tile Gouges & Pin Holes in Concentric Pattern (1998)	Total Amount - 32600 Sq Ft				
	70	HALLWAY 1500	NONE DETECTED	112310-MV-11	MV-11: HALLWAY 1500.	700 Sq Ft
	76	ROOM 1508	NONE DETECTED			600 Sq Ft
	79	ROOM 1506 (MEDIA CENTER)	NONE DETECTED			1500 Sq Ft
	80	ROOM 1507 (MEDIA CENTER OFFICE)	NONE DETECTED			110 Sq Ft
	82	ROOM 1506A (RESOURCE ROOM)	NONE DETECTED			150 Sq Ft
	88	ROOM 1503	NONE DETECTED			1000 Sq Ft
	93	ROOM 1502	NONE DETECTED			1000 Sq Ft
	104	MAIN OFFICE (1001)	NONE DETECTED			1000 Sq Ft
	106	ROOM 1002	NONE DETECTED			100 Sq Ft
	109	ROOM 1003	NONE DETECTED			100 Sq Ft
	113	ROOM 1004	NONE DETECTED			100 Sq Ft
	116	ROOM 1004	NONE DETECTED			100 Sq Ft
	119	ROOM 1006	NONE DETECTED			140 Sq Ft
	122	ROOM 1501	NONE DETECTED			1000 Sq Ft
	124	THROUGHOUT 1998 ADDITION	NONE DETECTED			25000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2D	12" x 12" Vinyl Floor Tile & Mastic Brown w/Tan Streaks					Total Amount - 290 Sq Ft
20	ROOM 1601		NONE DETECTED	112310-MV-13	MV-13: ROOM 1601.	290 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Olive Mottle					Total Amount - 800 Sq Ft
16	LOBBY/COMMONS (1600)		NONE DETECTED			800 Sq Ft
K2J	12" x 12" Vinyl Floor Tile & Mastic Salmon w/Black Specks					Total Amount - 700 Sq Ft
89	ROOM 1503		NONE DETECTED	112310-MV-14	MV-14: ROOM 1503.	300 Sq Ft
94	ROOM 1502		NONE DETECTED			400 Sq Ft
K2L	12" x 12" Vinyl Floor Tile & Mastic Blue w/Black Specks					Total Amount - 100 Sq Ft
107	ROOM 1002		NONE DETECTED	112310-MV-16	MV-16: ROOM 1002.	100 Sq Ft
K2M	12" x 12" Vinyl Floor Tile & Mastic White w/Gray Flecks (2011)					Total Amount - 950 Sq Ft
67	ROOM 1512		NEW			600 Sq Ft
96	ROOM 1513 (LOUNGE)		NEW			350 Sq Ft
K3A	Miscellaneous Flooring Black Mastic					Total Amount - 500 Sq Ft
51	ROOM 1606		8 CH	112310-MV-17	MV-17: ROOM 1606.	500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3B	Miscellaneous Flooring 2' X 2' Light Gray w/Dark Gray and Cream Flecks (202x)					Total Amount - 4300 Sq Ft
	30	1973 ORIGINAL BUILDING MAIN HALLWAY (1000)	NEW			1200 Sq Ft
	71	HALLWAY 1500	NEW			100 Sq Ft
	125	THROUGHOUT 1998 ADDITION	NEW			3000 Sq Ft
K3C	Miscellaneous Flooring 2' X 2' Dark Gray w/Gray and Cream Flecks (202x)					Total Amount - 3850 Sq Ft
	31	1973 ORIGINAL BUILDING MAIN HALLWAY (1000)	NEW			400 Sq Ft
	72	HALLWAY 1500	NEW			450 Sq Ft
	126	THROUGHOUT 1998 ADDITION	NEW			2000 Sq Ft
	127	THROUGHOUT 1998 ADDITION	NEW			1000 Sq Ft
K3D	Miscellaneous Flooring 2' X 2' Blue w/Dark Blue and Cream Flecks (2023)					Total Amount - 450 Sq Ft
	32	1973 ORIGINAL BUILDING MAIN HALLWAY (1000)	NEW			300 Sq Ft
	73	HALLWAY 1500	NEW			150 Sq Ft
M0A	Plaster 1973 Original Building					Total Amount - 10000 Sq Ft
	3	THROUGHOUT 1973 ORIGINAL BUILDING	NONE DETECTED	112310-MV-18	MV-18: ROOM 1513. HOMOGENEOUS TO BRIDGE VIEW SAMPLES 101408ML- 5,6,7,8,9,10,11.	10000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
N0A	Drywall/Joint Compound 1973 Original Building					Total Amount - 10000 Sq Ft
	4	THROUGHOUT 1973 ORIGINAL BUILDING	NONE DETECTED	112310-MV-19	MV-19: ROOM 1513. HOMOGENEOUS TO BRIDGE VIEW SAMPLE 101408ML-4.	10000 Sq Ft
N0B	Drywall/Joint Compound 1998 Addition					Total Amount - 20000 Sq Ft
	123	THROUGHOUT 1998 ADDITION	NONE DETECTED	112310-MV-20	MV-20: HALLWAY 1200 NEAR 1973 ORIGINAL BUILDING.	20000 Sq Ft
P0A	Fire Doors Wood 1 1/2 Hr Rating Warnock Hersey					Total Amount - 100 Sq Ft
	131	THROUGHOUT 1998 ADDITION	ASSUMED			100 Sq Ft
Q0A	Carpet Adhesive					Total Amount - 30000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED			30000 Sq Ft
R0A	Baseboard/Mopboard Adhesive Gray Baseboard					Total Amount - 300 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED			300 Sq Ft
R0B	Baseboard/Mopboard Adhesive Brown Baseboard					Total Amount - 6 Sq Ft
	21	ROOM 1601	NONE DETECTED			6 Sq Ft
R0C	Baseboard/Mopboard Adhesive 4" Dark Gray (202x)					Total Amount - 800 Sq Ft
	74	HALLWAY 1500	NEW			300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	128	THROUGHOUT 1998 ADDITION	NEW			500 Sq Ft
VOA	Sink Undercoating Gray					Total Amount - 58 Sq Ft
	111	ROOM 1003	NONE DETECTED			4 Sq Ft
	114	ROOM 1004	NONE DETECTED			4 Sq Ft
	129	THROUGHOUT 1998 ADDITION	NONE DETECTED	112310-MV-21	MV-21: GATHERING AREA 1200.	50 Sq Ft
VOB	Sink Undercoating Pink					Total Amount - 13 Sq Ft
	52	ROOM 1606	6 CH	112310-MV-22	MV-22: ROOM 1606.	5 Sq Ft
	90	ROOM 1503	6 CH			4 Sq Ft
	95	ROOM 1502	6 CH			4 Sq Ft
VOC	Sink Undercoating Gray (2011)					Total Amount - 22 Sq Ft
	68	ROOM 1512	NEW			17 Sq Ft
	100	ROOM 1513 (LOUNGE)	NEW			5 Sq Ft
XOC	Miscellaneous Material Wired Interior Window Glaze					Total Amount - 25 Sq Ft
	6	THROUGHOUT 1973 ORIGINAL BUILDING	5 CH			25 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0D	Miscellaneous Material Brass-Colored Frame Chalkboard Adhesive					Total Amount - 24 Sq Ft
	25	ROOM 1602	NONE DETECTED	072419-BF-1; 081011MV-01	BF-1: ROOM 1602. MV-01: ROOM 1601 (SINCE REMOVED).	4 Sq Ft
	37	ROOM 1604	NONE DETECTED			4 Sq Ft
	41	ROOM 1605	NONE DETECTED			2 Sq Ft
	47	ROOM 1603	NONE DETECTED			4 Sq Ft
	53	ROOM 1606	NONE DETECTED			10 Sq Ft
X0E	Miscellaneous Material Black Perimeter Ceiling Tile Grid Adhesive					Total Amount - 154 Sq Ft
	15	LOBBY/COMMONS (1600)	10 CH			20 Sq Ft
	19	ROOM 1601	10 CH			6 Sq Ft
	24	ROOM 1602	10 CH			10 Sq Ft
	29	1973 ORIGINAL BUILDING MAIN HALLWAY (1000)	10 CH			50 Sq Ft
	36	ROOM 1604	10 CH			6 Sq Ft
	40	ROOM 1605	10 CH			6 Sq Ft
	45	ROOM 1603	10 CH			10 Sq Ft
	50	ROOM 1606	10 CH			10 Sq Ft
	57	GIRLS' RESTROOM (1509)	10 CH	112310-MV-23	MV-23: GIRLS' RESTROOM (1509).	10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	64	BOYS' RESTROOM (1511)	10 CH			10 Sq Ft
	99	ROOM 1513 (LOUNGE)	10 CH			10 Sq Ft
	110	ROOM 1003	10 CH			2 Sq Ft
	117	ROOM 1006	10 CH			4 Sq Ft
X0H	Miscellaneous Material Red Firestop					Total Amount - 20 Sq Ft
	7	THROUGHOUT 1973 ORIGINAL BUILDING	NONE DETECTED			20 Sq Ft
X0I	Miscellaneous Material Vermiculite					Total Amount - 7504 Sq Ft
	8	THROUGHOUT 1973 ORIGINAL BUILDING	<1 ACT			7500 Sq Ft
	58	GIRLS' RESTROOM (1509)	<1 ACT			4 Sq Ft
X0J	Miscellaneous Material Brass-Colored Frame Tackboard Adhesive					Total Amount - 215 Sq Ft
	26	ROOM 1602	ASSUMED			30 Sq Ft
	33	1973 ORIGINAL BUILDING MAIN HALLWAY (1000)	ASSUMED			110 Sq Ft
	42	ROOM 1605	ASSUMED			15 Sq Ft
	46	ROOM 1603	ASSUMED			30 Sq Ft
	54	ROOM 1606	ASSUMED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0M		Miscellaneous Material Curtain Wall Dampproofing/Vapor Barrier				Total Amount - 7500 Sq Ft
	9	THROUGHOUT 1973 ORIGINAL BUILDING	15 CH	112310-MV-24	MV-24: 1998 ADDITION HALLWAY 1200	7500 Sq Ft
X0N		Miscellaneous Material Brown Interior Door Caulk				Total Amount - 10 Sq Ft
	10	THROUGHOUT 1973 ORIGINAL BUILDING	NONE DETECTED	082212BV-04		10 Sq Ft
X1A		Miscellaneous Material 2" X 2" Gray w/White Specks Ceramic Floor Tile System				Total Amount - 1000 Sq Ft
	130	THROUGHOUT 1998 ADDITION RESTROOMS	ASSUMED			1000 Sq Ft
X1B		Miscellaneous Material 1" X 1" Brown Ceramic Floor Tile System				Total Amount - 750 Sq Ft
	11	THROUGHOUT 1973 ORIGINAL BUILDING RESTROOMS	ASSUMED			750 Sq Ft
X1C		Miscellaneous Material 4" X 4" White Ceramic Wall Tile System				Total Amount - 1500 Sq Ft
	12	THROUGHOUT 1973 ORIGINAL BUILDING RESTROOMS	NEW			1500 Sq Ft