

615 South Chatsworth Street, Saint Paul, MN 55102

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4B	Mudded Pipe Joints on Fiberglass Insulation 1973 Addition/Installation					Total Amount - 11 Joints
	13	1502 CUSTODIAL RECEIVING	NONE DETECTED			1 Joints
	26	SOUTHWEST HALLWAY (1200) FROM ROOMS 1202-1204	NONE DETECTED	041417-BF-31, 32, 33, 34, 35, 36; 410-12, 14; 1379-JL-2-3; 2001-1501-AD-1, 2, 3, 25, 26, 27	BF-31: RECEIVING ROOM (1112) (SINCE REMOVED). BF-32: MAINTENANCE (1110A) (SINCE REMOVED). BF-35: CUSTODIAL/STORAGE 1405 (SINCE REMOVED). BF-36: ROOM 1207 (SINCE REMOVED). 12: ROOM 1112 (SINCE REMOVED). JL-2,3: NORTH HALLWAY FROM COMMONS TO ROOM 1209 (SINCE REMOVED). 1,2: BOILER ROOM (SINCE REMOVED). 3: ELECTRICAL ROOM (SINCE REMOVED). AD-25,26,27: CENTER COMMONS AREA ACROSS FROM ELEVATOR (SINCE REMOVED).	10 Joints
B1A	Air Cell Pipe Insulation 1923 Original Building					Total Amount - 3 Lin Ft
	11	BOILER ROOM (0101)	ASSUMED			3 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
B2A	Millboard Pipe Insulation 1923 Original Building					Total Amount - 6 Lin Ft
	12	BOILER ROOM (0101)	ASSUMED			6 Lin Ft
H1A	Sprayed-On Structural Fireproofing Fluffy w/Green Tint (1999)					Total Amount - 1000 Sq Ft
	23	THROUGHOUT 1999 ADDITION	NONE DETECTED	041417-BF-37, 38; 110408ML-16		1000 Sq Ft
I2H	2' x 2' Acoustical Ceiling Tile Rough Texture w/Revealed Edge (2018)					Total Amount - 20000 Sq Ft
	2	THROUGHOUT BUILDING	NEW			20000 Sq Ft
I2I	2' x 2' Acoustical Ceiling Tile Pock Marks & Pin Holes (2018)					Total Amount - 40000 Sq Ft
	3	THROUGHOUT BUILDING	NEW			40000 Sq Ft
I4A	Acoustical Ceiling Tile 4' X 4' Light Textured w/Revealed Edge (20xx)					Total Amount - 500 Sq Ft
	22	THROUGHOUT MEDIA CENTER AREA	NEW			500 Sq Ft
J2A	Transite Piping/Ducting					Total Amount - 50 Sq Ft
	10	MAIN ENTRY	ASSUMED			50 Sq Ft
K1B	Sheet Vinyl Flooring & Adhesive Sea Green w/White and Gray Flecks (2018)					Total Amount - 1600 Sq Ft
	14	THROUGHOUT OFFICE AREA HALLWAYS	NEW			1600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K1C	Sheet Vinyl Flooring & Adhesive Orange w/White and Gray Flecks (2018)					Total Amount - 400 Sq Ft
	15	MAIN OFFICE RECEPTION AREA	NEW			400 Sq Ft
K3A	Miscellaneous Flooring Rubber Floor w/Blue Border & Brown Interior (2014)					Total Amount - 5000 Sq Ft
	25	GYMNASIUM (1504)	NEW			5000 Sq Ft
K3B	Miscellaneous Flooring 2' X 2' Yellow (2018)					Total Amount - 40000 Sq Ft
	4	THROUGHOUT BUILDING	NEW			40000 Sq Ft
K3C	Miscellaneous Flooring 2' X 2' Gray (2018)					Total Amount - 20000 Sq Ft
	5	THROUGHOUT BUILDING	NEW			20000 Sq Ft
M0A	Plaster 1923 Original Building					Total Amount - 1700 Sq Ft
	8	THROUGHOUT 1923 ORIGINAL BUILDING	NONE DETECTED	051018-BF-5, 6, 7, 8; 112508ML-8, 9, 10, 11, 12, 13; 2001-1501-AD-11	BF-5: HALLWAY NEAR ROOM 1104. BF-6: 3RD FLOOR HALLWAY. BF-7: ROOM 2104. BF-8: ROOM 1108B. AD-11: CONFERENCE ROOM BY CAFETERIA.	1700 Sq Ft
N0A	Drywall/Joint Compound					Total Amount - 3600 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	041417-BF-13, 20, 24; 2001-1501-AD-13, AD-14; 511-F2	BF-13: ROOM 1302. BF-20: 1973 ADDITION STAIRWELL. BF-24: ROOM 1115. AD-13: CONFERENCE ROOM BY CAFETERIA. AD-14: HALLWAY BY GYMNASIUM.	3600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0A	Carpet Adhesive Gold Striped Carpet Squares (2018)					Total Amount - 900 Sq Ft
	16	THROUGHOUT OFFICE AREA	NEW			900 Sq Ft
Q0B	Carpet Adhesive Multi-Color Striped Carpet Squares (2018)					Total Amount - 1000 Sq Ft
	21	THROUGHOUT MEDIA CENTER AREA	NEW			1000 Sq Ft
R0A	Baseboard/Mopboard Adhesive 4" Gray (2018)					Total Amount - 1000 Sq Ft
	6	THROUGHOUT BUILDING	NEW			1000 Sq Ft
X0B	Miscellaneous Material Red Fire Stop					Total Amount - 200 Sq Ft
	7	THROUGHOUT BUILDING	NONE DETECTED	110408ML-04	ROOM 1112.	200 Sq Ft
X0C	Miscellaneous Material Tectum Ceiling & Wall Panels					Total Amount - 8000 Sq Ft
	24	GYMNASIUM (1504)	NONE DETECTED	410-7		8000 Sq Ft
X1A	Miscellaneous Material 1' X 2' Gray Quarry Tile System (2018)					Total Amount - 5075 Sq Ft
	20	NURSE'S RESTROOM	NEW			75 Sq Ft
	28	2018 ADDITION CAFETERIA & RESTROOMS	NEW			5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1B	Miscellaneous Material 4" X 16" White Ceramic Wall Tile System (2018)					Total Amount - 10150 Sq Ft
	19	NURSE'S RESTROOM	NEW			150 Sq Ft
	29	2018 ADDITION CAFETERIA & RESTROOMS	NEW			10000 Sq Ft
X1C	Miscellaneous Material 3" X 6" White Ceramic Wall Tile System (2018)					Total Amount - 150 Sq Ft
	17	THROUGHOUT OFFICE AREA RESTROOMS	NEW			150 Sq Ft
X1D	Miscellaneous Material 4" X 8" Gray Quarry Floor Tile System (2018)					Total Amount - 2500 Sq Ft
	27	KITCHEN AREAS	NEW			2500 Sq Ft
X1E	Miscellaneous Material 6" Red Quarry Floor Tile System					Total Amount - 300 Sq Ft
	9	1923 ORIGINAL BUILDING FIRST FLOOR LANDINGS	ASSUMED			300 Sq Ft
X1G	Miscellaneous Material 2" X 2" Red Brick Pattern Ceramic Floor Tile System					Total Amount - 75 Sq Ft
	18	THROUGHOUT OFFICE AREA RESTROOMS	ASSUMED			75 Sq Ft