

360 Colborne Street, Saint Paul, MN 55102

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4B	Mudded Pipe Joints on Fiberglass Insulation 1973 Addition					Total Amount - 62 Joints
	49	HALLWAY LB1	NONE DETECTED	091912MA-01	HALLWAY LB1 OUTSIDE ROOM 110	6 Joints
	55	ROOM B110	NONE DETECTED			2 Joints
	56	ROOM B111	NONE DETECTED			4 Joints
	57	ROOM B113	NONE DETECTED			10 Joints
	58	ROOM B115	NONE DETECTED	091912MA-02	MA-02: ROOM B115.	10 Joints
	59	PURCHASING B114	NONE DETECTED			8 Joints
	60	ROOM B122	NONE DETECTED			6 Joints
	74	ROOM B206	NONE DETECTED	091912MA-03	MA-03: ROOM B206.	2 Joints
	77	TRAINING ROOM B203	NONE DETECTED			12 Joints
	78	GENERAL COUNSEL OFFICE B124	NONE DETECTED			2 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4C	Mudded Pipe Joints on Fiberglass Insulation Unknown Installation Date					Total Amount - 14 Joints
	16	MECHANICAL ROOM LL01	2-15 CH	22024JA-04, 05; 091912MA-04, 05	JA-04,05: MECHANICAL ROOM L001. MA-04,05: MECHANICAL ROOM L001.	6 Joints
	29	CHILLER ROOM WEST OF MECHANICAL ROOM L001	2-15 CH	22024JA-01, 02, 03; 091912MA-06	JA-01,02,03 & MA-06: CHILLER ROOM.	8 Joints
D1A	Boiler Gaskets White Flat					Total Amount - 10 Sq Ft
	17	MECHANICAL ROOM LL01	NONE DETECTED	091912MA-07	MA-07: MECHANICAL ROOM L001.	10 Sq Ft
D1B	Boiler Gaskets White Round					Total Amount - 4 Sq Ft
	18	MECHANICAL ROOM LL01	NONE DETECTED	091912MA-08	MA-08: MECHANICAL ROOM L001.	4 Sq Ft
D2A	Interior Boiler Insulation Refractory					Total Amount - 200 Sq Ft
	19	MECHANICAL ROOM LL01	ASSUMED			200 Sq Ft
H1A	Sprayed-On Structural Fireproofing Gray w/Vermiculite (1971)					Total Amount - 360 Sq Ft
	14	MECHANICAL ROOM LL01	15 CH	091912MA-09, 10, 11	MA-09: MECHANICAL ROOM L001. MA-10: MECHANICAL ROOM L001 SOUTH WALL. MA-11: MECHANICAL ROOM L001 SOUTH OF TA2.	100 Sq Ft
	28	CHILLER ROOM WEST OF MECHANICAL ROOM L001	15 CH			20 Sq Ft
	71	MAIN ENTRANCE 100A	15 CH			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	123	CAFETERIA 509	15 CH			140 Sq Ft
	126	CONFERENCE ROOM 510	15 CH			60 Sq Ft
H1B	Sprayed-On Structural Fireproofing Gray, Fluffy					Total Amount - 10 Sq Ft
	15	MECHANICAL ROOM LL01	NONE DETECTED	091912MA-12, 13, 14	MA-12,13,14: MECHANICAL ROOM L001.	10 Sq Ft
H1C	Sprayed-On Structural Fireproofing Light Blue					Total Amount - 27500 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED	091912MA-15, 16, 17, 18, 19, 20, 21	MA-15: MECHANICAL ROOM L001. MA-16: LINK HALLWAY. MA-17: ROOM B206. MA-18: ROOM 228. MA-19: ROOM 350. MA-20: ROOM 422. MA-21: ROOM 531.	27500 Sq Ft
H1D	Sprayed-On Structural Fireproofing Gray w/Vermiculite (1973)					Total Amount - 1 Sq Ft
	79	MECHANICAL ROOM B219	40 CH	091912MA-22	MA-22: ROOM B219.	1 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Dents w/Pin Holes					Total Amount - 220 Sq Ft
	39	STORAGE/CLOSET L007	NONE DETECTED	091912MA-31	MA-31: STORAGE L007.	220 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Fissures w/Pin Holes					Total Amount - 40 Sq Ft
	42	COMMUNICATIONS CLOSET L008	NONE DETECTED	091912MA-32	MA-32: CLOSET L008.	40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2C	2' x 2' Acoustical Ceiling Tile Gouges w/Nail & Pin Holes					Total Amount - 20 Sq Ft
	43	COMMUNICATIONS CLOSET L008	NONE DETECTED	091912MA-33	MA-33: CLOSET L008.	20 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Sandpaper Texture w/Revealed Edge					Total Amount - 1650 Sq Ft
	110	ROOM 446	NONE DETECTED			580 Sq Ft
	122	BOARD ROOM 511	NONE DETECTED			870 Sq Ft
	125	HALLWAY 512	NONE DETECTED	091912MA-34	MA-34: HALLWAY 512.	150 Sq Ft
	127	RESTROOM 510A	NONE DETECTED			50 Sq Ft
I3A	2' x 4' Ceiling Tile Dents w/Pin Holes					Total Amount - 140 Sq Ft
	46	AUTOMATION STORAGE	NONE DETECTED	091912MA-35	MA-35: AUTOMATION STORAGE.	140 Sq Ft
I3B	2' x 4' Ceiling Tile 1' x 1'-Look Textured w/Nail & Pin Holes					Total Amount - 7000 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	091912MA-36	MA-36: LINK HALLWAY.	7000 Sq Ft
I3C	2' x 4' Ceiling Tile Grubs w/Nail & Pin Holes					Total Amount - 30000 Sq Ft
	5	THROUGHOUT BUILDING	NONE DETECTED	091912MA-37	MA-37: ROOM B102.	30000 Sq Ft
I3D	2' x 4' Ceiling Tile 1' x 1'-Look Small Slits w/Nail & Pin Holes					Total Amount - 3200 Sq Ft
	48	THROUGHOUT 1973 ADDITION LINK	NONE DETECTED	091912MA-38	MA-38: ROOM B111.	3200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3E	2' x 4' Ceiling Tile Nail & Pin Holes	Total Amount - 80 Sq Ft				
66	COMMUNICATIONS ROOM 126	NONE DETECTED	091912MA-39	MA-39: ROOM 126.	80 Sq Ft	
K1A	Sheet Vinyl Flooring & Adhesive Gray w/Black & White Flecks	Total Amount - 60 Sq Ft				
33	ELEVATORS	NONE DETECTED	091912MA-23	MA-23: ELEVATOR.	60 Sq Ft	
K2A	12" x 12" Vinyl Floor Tile & Mastic Brown w/Tan Marble-Look	Total Amount - 380 Sq Ft				
40	STORAGE/CLOSET L007	3 CH (TILE), 5 CH (MASTIC)			220 Sq Ft	
44	COMMUNICATIONS CLOSET L008	3 CH (TILE), 5 CH (MASTIC)	091912MA-24	MA-24: COMMUNICATION CLOSET L008.	60 Sq Ft	
54	ROOM B102	3 CH (TILE), 5 CH (MASTIC)			100 Sq Ft	
K2C	12" x 12" Vinyl Floor Tile & Mastic Beige w/Pink & Tan Smudges	Total Amount - 565 Sq Ft				
63	CUSTODIAL CLOSET 121A	NONE DETECTED	091912MA-26	MA-26: ROOM 121A.	20 Sq Ft	
67	COMMUNICATIONS ROOM 126	NONE DETECTED			120 Sq Ft	
69	STORAGE CLOSET 123	NONE DETECTED			65 Sq Ft	
83	COMMUNICATIONS ROOM 208	NONE DETECTED			100 Sq Ft	
90	STORAGE ROOM 225A	NONE DETECTED			30 Sq Ft	
96	COMMUNICATIONS ROOM 357	NONE DETECTED			40 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	102	STORAGE ROOM 333A	NONE DETECTED			40 Sq Ft
	107	COMMUNICATIONS ROOM 445	NONE DETECTED			50 Sq Ft
	113	STORAGE ROOM 428A	NONE DETECTED			25 Sq Ft
	121	COMMUNICATIONS CLOSET 506	NONE DETECTED			50 Sq Ft
	131	STORAGE ROOM 519A	NONE DETECTED			25 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic Tan w/Multi-Colored Smudges		Total Amount - 160 Sq Ft			
	72	ROOM 111	NONE DETECTED	091912MA-27	MA-27: ROOM 111.	160 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Purple w/Black Specks		Total Amount - 465 Sq Ft			
	87	COPY ROOM 219	NONE DETECTED	091912MA-28	MA-28: ROOM 219.	100 Sq Ft
	88	STORAGE ROOM 241	NONE DETECTED			120 Sq Ft
	89	STORAGE ROOM 240	NONE DETECTED			45 Sq Ft
	94	STORAGE ROOM 217	NONE DETECTED			200 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Beige Mottle		Total Amount - 240 Sq Ft			
	98	WORK ROOM 353A	NONE DETECTED	091912MA-29	MA-29: WORK ROOM 352.	240 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2G	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle	Total Amount - 12 Sq Ft				
50	HALLWAY LB1	NEW				12 Sq Ft
K3A	Miscellaneous Flooring Brown Stair Tread Adhesive	Total Amount - 90 Sq Ft				
119	STAIRWELL 502	NONE DETECTED	091912MA-30	MA-30: STAIRWELL 502.		90 Sq Ft
K3B	Miscellaneous Flooring Gray w/Gray & White Specks	Total Amount - 580 Sq Ft				
111	ROOM 446	NEW				580 Sq Ft
L0A	Flexible Duct Connector Black Vinyl	Total Amount - 100 Sq Ft				
12	THROUGHOUT BUILDING	NSM				100 Sq Ft
M0A	Plaster Skimcoat Over Sheetrock	Total Amount - 4000 Sq Ft				
1	THROUGHOUT BUILDING	NONE DETECTED	091912MA-40, 41, 42, 43, 44	MA-40: MECHANICAL ROOM L001. MA-41: ROOM L007. MA-42: MECHANICAL ROOM B219. MA-43: ROOM 301. MA-44: ROOM 401.		4000 Sq Ft
N0A	Drywall/Joint Compound	Total Amount - 50000 Sq Ft				
2	THROUGHOUT BUILDING	NONE DETECTED	091912MA-45, 46, 47	MA-45: ROOM B115. MA-46: ROOM 309. MA-47: 5TH FLOOR ELEVATOR LOBBY.		50000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
POA	Fire Doors Metal - 1.5 Hr Rating (Underwriter's Laboratories)					Total Amount - 170 Sq Ft
	25	MECHANICAL ROOM LL01	ASSUMED			20 Sq Ft
	31	STAIRWELL L009	ASSUMED			20 Sq Ft
	34	STAIRWELL LL02	ASSUMED			20 Sq Ft
	35	MECHANICAL ROOM L004	ASSUMED			20 Sq Ft
	36	CUSTODIAL OFFICE L006	ASSUMED			20 Sq Ft
	37	ELECTRICAL ROOM LL03	ASSUMED			20 Sq Ft
	38	STORAGE ROOM L005	ASSUMED			20 Sq Ft
	118	STAIRWELL 502	ASSUMED			20 Sq Ft
	120	PENTHOUSE ELEVATOR MECHANICAL ROOM	ASSUMED			10 Sq Ft
POB	Fire Doors Wood - 1.5 Hr Rating (Algoma)					Total Amount - 380 Sq Ft
	51	HALLWAY LB1	NONE DETECTED	091912MA-48	MA-48: LINK.	20 Sq Ft
	61	STAIRWELL TA6	NONE DETECTED			20 Sq Ft
	62	MAINTENANCE ROOM 128	NONE DETECTED			20 Sq Ft
	73	STAIRWELL 105	NONE DETECTED			20 Sq Ft
	82	STAIRWELL 202	NONE DETECTED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	84	BUSINESS FINANCE 215	NONE DETECTED			20 Sq Ft
	85	HALLWAY 209	NONE DETECTED			20 Sq Ft
	93	STAIRWELL 229	NONE DETECTED			20 Sq Ft
	95	STAIRWELL 302	NONE DETECTED			20 Sq Ft
	97	RECEPTION 310	NONE DETECTED			20 Sq Ft
	99	WORK ROOM 353A	NONE DETECTED			20 Sq Ft
	101	REA 313	NONE DETECTED			20 Sq Ft
	105	STAIRWELL 337	NONE DETECTED			20 Sq Ft
	106	STAIRWELL 402	NONE DETECTED			20 Sq Ft
	108	HALLWAY 449	NONE DETECTED			20 Sq Ft
	112	ELL OFFICE 421	NONE DETECTED			20 Sq Ft
	116	STAIRWELL 432	NONE DETECTED			20 Sq Ft
	117	STAIRWELL 502	NONE DETECTED			20 Sq Ft
	134	STAIRWELL 523	NONE DETECTED			20 Sq Ft
POC	Fire Doors Wood - 1.5 Hr Rating (Algoma)					Total Amount - 20 Sq Ft
	52	HALLWAY LB1	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
P0E	Fire Doors Wood - 1 Hr Rating (Warnock Hersey)	Total Amount - 40 Sq Ft				
	80	MECHANICAL ROOM B219	NEW			20 Sq Ft
	81	STAIRWELL B209A	NEW			20 Sq Ft
P0F	Fire Doors Wood Composite - 1.5 Hr Rating (Eggers)	Total Amount - 40 Sq Ft				
	76	ROOM B206	ASSUMED			40 Sq Ft
Q0A	Carpet Adhesive Green Adhesive	Total Amount - 10000 Sq Ft				
	6	THROUGHOUT BUILDING	NONE DETECTED	091912MA-49	MA-49: ROOM B108.	10000 Sq Ft
Q0B	Carpet Adhesive Tan Adhesive	Total Amount - 30000 Sq Ft				
	7	THROUGHOUT BUILDING	NONE DETECTED	091912MA-50	MA-50: ROOM B108.	30000 Sq Ft
Q0C	Carpet Adhesive Blue Berber Carpet with Yellow Adhesive	Total Amount - 100 Sq Ft				
	53	ROOM B102	ASSUMED			100 Sq Ft
ROA	Baseboard/Mopboard Adhesive 3" Brown Baseboard	Total Amount - 20 Sq Ft				
	41	STORAGE/CLOSET L007	NONE DETECTED			15 Sq Ft
	45	COMMUNICATIONS CLOSET L008	NONE DETECTED	091912MA-51	MA-51: CLOSET L008.	5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROB	Baseboard/Mopboard Adhesive 4" Plum Baseboard					Total Amount - 500 Sq Ft
8	THROUGHOUT BUILDING	NONE DETECTED	091912MA-53	MA-53: ROOM 121A.	500 Sq Ft	
ROC	Baseboard/Mopboard Adhesive 4" Brown Baseboard					Total Amount - 300 Sq Ft
9	THROUGHOUT BUILDING	NONE DETECTED	091912MA-52	MA-52: ROOM 126.	300 Sq Ft	
ROD	Baseboard/Mopboard Adhesive 4" Black Baseboard					Total Amount - 100 Sq Ft
10	THROUGHOUT BUILDING	NONE DETECTED	091912MA-54	MA-54: MAIN ENTRANCE.	100 Sq Ft	
VOA	Sink Undercoating Off-White					Total Amount - 26 Sq Ft
68	HALLWAY 119	NONE DETECTED	091912MA-56	MA-56: HALLWAY 119.	6 Sq Ft	
86	HALLWAY 222	NONE DETECTED			4 Sq Ft	
100	HALLWAY 351	NONE DETECTED			4 Sq Ft	
109	ROOM 446	NONE DETECTED			4 Sq Ft	
130	ADMINISTRATIVE OFFICE 531	NONE DETECTED			8 Sq Ft	
VOB	Sink Undercoating Gray					Total Amount - 12 Sq Ft
75	ROOM B206	NONE DETECTED	091912MA-57	MA-57: ROOM B206.	8 Sq Ft	
124	CAFETERIA 509	NONE DETECTED			4 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0A	Miscellaneous Material Cream Caulk Associated w/AHU					Total Amount - 9 Sq Ft
	20	MECHANICAL ROOM LL01	NONE DETECTED			5 Sq Ft
	26	MECHANICAL ROOM TA1	NONE DETECTED	091912MA-58	MA-58: MECHANICAL ROOM TA2.	2 Sq Ft
	27	MECHANICAL ROOM TA2	NONE DETECTED			2 Sq Ft
X0B	Miscellaneous Material Pipe/Valve Flange Gaskets					Total Amount - 175 Sq Ft
	21	MECHANICAL ROOM LL01	ASSUMED			75 Sq Ft
	30	CHILLER ROOM WEST OF MECHANICAL ROOM L001	ASSUMED			100 Sq Ft
X0C	Miscellaneous Material Black Vapor Barrier					Total Amount - 20 Sq Ft
	22	MECHANICAL ROOM LL01	10 CH			20 Sq Ft
X0D	Miscellaneous Material Black Foam					Total Amount - 200 Sq Ft
	23	MECHANICAL ROOM LL01	NSM			200 Sq Ft
X0E	Miscellaneous Material Gray Fire Stop					Total Amount - 10 Sq Ft
	24	MECHANICAL ROOM LL01	NONE DETECTED	091912MA-60	MA-60: MECHANICAL ROOM L001.	10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0F	Miscellaneous Material Vermiculite (1971)	Total Amount - 25000 Sq Ft				
13	THROUGHOUT 1971 ORIGINAL BUILDING	<1 ACT	091912MA-61, 62, 63	MA-61: MECHANICAL ROOM L001. MA-62: MAIN ENTRANCE. MA-63: ROOM 104.	25000 Sq Ft	
X0G	Miscellaneous Material Red Fire Stop	Total Amount - 100 Sq Ft				
11	THROUGHOUT BUILDING	NONE DETECTED	091912MA-64	MA-64: BASEMENT MAIN ELECTRICAL ROOM.	100 Sq Ft	
X0H	Miscellaneous Material Gray Duct Caulk	Total Amount - 10 Sq Ft				
32	MECHANICAL ROOM LL01	NONE DETECTED	091912MA-65	MA-65: MECHANICAL ROOM L001.	10 Sq Ft	
X0I	Miscellaneous Material Thick White Coating on Metal Ceiling Deck	Total Amount - 15 Sq Ft				
70	ROOM 116	NONE DETECTED	091912MA-66	MA-66: ROOM 117.	15 Sq Ft	
X0J	Miscellaneous Material Vermiculite (1973)	Total Amount - 1000 Sq Ft				
47	THROUGHOUT 1973 ADDITION LINK	ASSUMED			1000 Sq Ft	
X1A	Miscellaneous Material 1" X 1" Multi Shaded Beige Ceramic Floor Tile System	Total Amount - 826 Sq Ft				
64	RESTROOM NEXT TO CUSTODIAL CLOSET 121A	ASSUMED			250 Sq Ft	
91	RESTROOMS NEAR STORAGE ROOM 225	ASSUMED			144 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	103	RESTROOMS NEAR STORAGE ROOM 333A	ASSUMED			144 Sq Ft
	114	RESTROOMS NEAR STORAGE ROOM 428A	ASSUMED			144 Sq Ft
	132	RESTROOMS NEAR STORAGE ROOM 519A	ASSUMED			144 Sq Ft
X1B	Miscellaneous Material 4" X 4" White Ceramic Wall Tile System					Total Amount - 1280 Sq Ft
	65	RESTROOM NEXT TO CUSTODIAL CLOSET 121A	ASSUMED			400 Sq Ft
	92	RESTROOMS NEAR STORAGE ROOM 333A	ASSUMED			220 Sq Ft
	104	RESTROOMS NEAR STORAGE ROOM 333A	ASSUMED			220 Sq Ft
	115	RESTROOMS NEAR STORAGE ROOM 428A	ASSUMED			220 Sq Ft
	133	RESTROOMS NEAR STORAGE ROOM 519A	ASSUMED			220 Sq Ft
X1C	Miscellaneous Material 2" X 2" Light Tan and Brown Colored Ceramic Floor Tile System					Total Amount - 50 Sq Ft
	128	RESTROOM 510A	ASSUMED			50 Sq Ft
X1D	Miscellaneous Material 6" X 6" Tan Marbling Ceramic Wall Tile System					Total Amount - 100 Sq Ft
	129	RESTROOM 510A	ASSUMED			100 Sq Ft