

1075 Third Street East, Saint Paul, MN 55106

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D1A	Boiler Gaskets High Efficiency Boilers (202x)					Total Amount - 10 Sq Ft
	19	1301 BOILER ROOM	NEW			10 Sq Ft
H1A	Sprayed-On Structural Fireproofing Cellulose (1991)					Total Amount - 30000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-23, 24, 25. 020110-MV-02, 03, 04, 05, 06, 15, 16	BF-23,24,25: HALLWAY 1199B. MV-02,03,04,05: BASEMENT STORAGE 0209. MV-06: ROOM 0213. MV-15: ROOM 2309. MV- 16: ROOM 1408.	30000 Sq Ft
I1B	1' x 1' Acoustical Ceiling Tile Pegboard (1930)					Total Amount - 10 Sq Ft
	112	ROOM 2407	NONE DETECTED	020110-MV-27	MV-27: ROOM 2303.	10 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Nail & Pinholes (2021)					Total Amount - 8200 Sq Ft
	80	THROUGHOUT 2ND FLOOR HALLWAY	NEW			4000 Sq Ft
	86	2021 ADDITION 2ND FLOOR STAIRWELL	NEW			200 Sq Ft
	88	2021 ADDITION ROOMS 2201-2210	NEW			4000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2C	2' x 2' Acoustical Ceiling Tile Nails and Pinholes (2022)	Total Amount - 48950 Sq Ft				
	23	THROUGHOUT FIRST FLOOR HALLWAYS	NEW			6000 Sq Ft
	27	FIRST FLOOR ROOMS 1303-1310	NEW			4000 Sq Ft
	35	FIRST FLOOR ROOMS 1401-1410	NEW			1000 Sq Ft
	43	UTILITY ROOMS 1506A, 1507A, 1509, 1505, 1501	NEW			300 Sq Ft
	45	ROOM 1517 OFFICE COMMON AREA	NEW			700 Sq Ft
	49	OFFICES 1518-1522	NEW			500 Sq Ft
	52	ROOM 1502	NEW			100 Sq Ft
	62	GYMNASIUM 1102	NEW			2500 Sq Ft
	65	MEDIA CENTER ROOMS 1103A, 1103B & 1103C	NEW			400 Sq Ft
	67	MAIN OFFICE AREA HALLWAYS	NEW			250 Sq Ft
	72	FIRST FLOOR ROOMS 1201-1206	NEW			1000 Sq Ft
	76	STAIRWELL 1599C	NEW			50 Sq Ft
	78	STAIRWELL 1299A	NEW			50 Sq Ft
	93	SECOND FLOOR ROOMS 2301-2313	NEW			3000 Sq Ft
	102	THROUGHOUT 2ND FLOOR ROOMS 2401-2414	NEW			5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	120	THROUGHOUT 1924 ORIGINAL BUILDING 3RD FLOOR	NEW			3000 Sq Ft
	122	THROUGHOUT 3RD FLOOR ROOMS 3401-3414	NEW			5000 Sq Ft
	130	THIRD FLOOR ROOMS 3301-3313	NEW			3000 Sq Ft
	134	THROUGHOUT 3RD FLOOR ROOMS 3201-3213	NEW			5000 Sq Ft
	144	THROUGHOUT 4TH FLOOR ROOMS 4401-4414	NEW			5000 Sq Ft
	148	FOURTH FLOOR ROOMS 4301-4309	NEW			3000 Sq Ft
	153	ROOM 4202	NEW			100 Sq Ft
I3C	2' x 4' Ceiling Tile Vinyl-Coated Gypsum (1991)					Total Amount - 16 Sq Ft
	58	DRY STORAGE 1706A	NSM			16 Sq Ft
I4A	Acoustical Ceiling Tile Vinyl Coated Gypsum (2022)					Total Amount - 2300 Sq Ft
	55	KITCHEN 1706 AND ASSOCIATED ROOMS	NEW			800 Sq Ft
	60	1101 COMMUNITY ROOM	NEW			300 Sq Ft
	69	THROUGHOUT MAIN OFFICE AREA	NEW			1200 Sq Ft
J3A	Miscellaneous Cementitious Material 1" Black Window Sills (1939)					Total Amount - 95 Sq Ft
	48	ROOM 1517 OFFICE COMMON AREA & OFFICES 1519 & 1520	NONE DETECTED			25 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	115	ROOM 2411	NONE DETECTED			20 Sq Ft
	116	ROOM 2413	NONE DETECTED			40 Sq Ft
	117	ROOM 2414	NONE DETECTED	020110-MV-29	MV-29: ROOM 2306.	10 Sq Ft
J3D	Miscellaneous Cementitious Material 1" Black Window Sills (2022)					Total Amount - 3175 Sq Ft
	59	CAFETERIA 1600	NEW			1000 Sq Ft
	75	FIRST FLOOR ROOMS 1201-1206	NEW			75 Sq Ft
	96	SECOND FLOOR ROOMS 2301-2313	NEW			300 Sq Ft
	105	THROUGHOUT 2ND FLOOR ROOMS 2401-2414	NEW			300 Sq Ft
	125	THROUGHOUT 3RD FLOOR ROOMS 3401-3414	NEW			300 Sq Ft
	132	THIRD FLOOR ROOMS 3301-3313	NEW			300 Sq Ft
	137	THROUGHOUT 3RD FLOOR ROOMS 3201-3213	NEW			300 Sq Ft
	147	THROUGHOUT 4TH FLOOR ROOMS 4401-4414	NEW			300 Sq Ft
	151	FOURTH FLOOR ROOMS 4301-4309	NEW			300 Sq Ft
K2L	12" x 12" Vinyl Floor Tile & Mastic Dark Gray Mottle (2022)					Total Amount - 2700 Sq Ft
	9	THROUGHOUT BUILDING (RESTROOMS)	NEW			2400 Sq Ft
	61	1101 COMMUNITY ROOM	NEW			300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3G	Miscellaneous Flooring 2' X 2' Teal, Light & Dark Gray Rubberized Floor Tile (2021/2022)				Total Amount - 25600 Sq Ft	
	24	THROUGHOUT FIRST FLOOR HALLWAYS	NEW			6000 Sq Ft
	28	FIRST FLOOR ROOMS 1303-1310	NEW			2500 Sq Ft
	36	FIRST FLOOR ROOMS 1401-1410	NEW			750 Sq Ft
	63	GYMNASIUM 1102	NEW			2500 Sq Ft
	66	MEDIA CENTER 1103A	NEW			200 Sq Ft
	71	THROUGHOUT MAIN OFFICE AREA	NEW			400 Sq Ft
	73	FIRST FLOOR ROOMS 1201-1206	NEW			750 Sq Ft
	143	THROUGHOUT 4TH FLOOR HALLWAY	NEW			5000 Sq Ft
	145	THROUGHOUT 4TH FLOOR ROOMS 4401 - 4414	NEW			5000 Sq Ft
	149	FOURTH FLOOR ROOMS 4301-4309	NEW			2500 Sq Ft
K3I	Miscellaneous Flooring Dark Gray Stair Tread				Total Amount - 240 Sq Ft	
	77	STAIRWELL 1599C	NEW			120 Sq Ft
	79	STAIRWELL 1299A	NEW			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3J	Miscellaneous Flooring 2' X 2' Yellow, Light & Dark Gray Rubberized Flooring Tile (202x)				Total Amount - 11500 Sq Ft	
	81	THROUGHOUT 2ND FLOOR HALLWAY	NEW			4000 Sq Ft
	94	SECOND FLOOR ROOMS 2301-2313	NEW			2500 Sq Ft
	103	THROUGHOUT 2ND FLOOR ROOMS 2401-2414	NEW			5000 Sq Ft
K3K	Miscellaneous Flooring 2' X 2' Green, Light & Dark Gray Rubberized Floor Tile (202x)				Total Amount - 12500 Sq Ft	
	123	THROUGHOUT 3RD FLOOR ROOMS 3401-3414	NEW			5000 Sq Ft
	131	THIRD FLOOR ROOMS 3301-3313	NEW			2500 Sq Ft
	135	THROUGHOUT 3RD FLOOR ROOMS 3201-3213	NEW			5000 Sq Ft
L0A	Flexible Duct Connector Black Vinyl				Total Amount - 14 Sq Ft	
	42	ELEVATOR EQUIPMENT ROOM 1410	NSM			2 Sq Ft
	110	MECHANICAL PENTHOUSE 2404	NSM			4 Sq Ft
	111	ELECTRICAL ROOM 2406	NSM			2 Sq Ft
	127	DATA ROOM 3404	NSM			2 Sq Ft
	128	ELECTRICAL ROOM 3406	NSM			2 Sq Ft
	152	MECHANICAL ROOM 4307	NSM			2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
M0A		Plaster 1924 Original Building	Total Amount - 32000 Sq Ft			
	20	THROUGHOUT 1924 ORIGINAL BUILDING BASEMENT	NONE DETECTED	012624-BF-1, 2; 020110-MV-01; 2001-1501-MP-1	BF-1,2: POTATOE ROOM. MV-01: ROOM 0212 (CEILING). MP1: 0212 EAST WALL IN HALL TO CRAWL SPACE	2000 Sq Ft
	22	THROUGHOUT 1924 ORIGINAL BUILDING FIRST FLOOR	NONE DETECTED	020110-MV-11, 12	MV-11: ROOM 1215. MV-12: ROOM 1209.	10000 Sq Ft
	92	THROUGHOUT 1924 ORIGINAL BUILDING 2ND FLOOR	NONE DETECTED	09216-BF-2; 020110-MV-13, 14	BF-2: 2ND FLOOR SOUTH RESTROOM. MV-13: HALLWAY WALL BY ROOM 2205. MV-14: HALLWAY BY BOYS' RESTROOM.	10000 Sq Ft
	157	THROUGHOUT 1924 ORIGINAL BUILDING 4TH FLOOR	NONE DETECTED	020110-MV-22	MV-22: HALLWAY BY ROOM 4204.	10000 Sq Ft
M0B		Plaster 1930 Addition	Total Amount - 13500 Sq Ft			
	33	GYMNASIUM 1304	NONE DETECTED	020110-MV-21, 41	MV-21: ROOM 1107 (SINCE REMOVED). MV-41: GYMNASIUM STORAGE 1105. (SINCE REMOVED)	3000 Sq Ft
	101	THROUGHOUT 1930 ADDITION 2ND FLOOR	NONE DETECTED	020110-MV-31, 34	MV-31: HALLWAY OUTSIDE ELEVATOR. MV-34: ROOM 1302.	5000 Sq Ft
	121	THROUGHOUT 1930 ADDITION 3RD FLOOR	NONE DETECTED	020110-MV-33; 2001-01144-4	MV-33: 3RD FLOOR STAFF RESTROOM.	5000 Sq Ft
	155	THROUGHOUT 1930 ADDITION 4TH FLOOR	NONE DETECTED	020110-MV-35	MV-35: ROOM 4301.	500 Sq Ft
M0C		Plaster 1939 Addition	Total Amount - 11000 Sq Ft			
	44	THROUGHOUT 1939 ADDITION FIRST FLOOR	NONE DETECTED			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	114	THROUGHOUT 1939 ADDITION 2ND FLOOR	NONE DETECTED	020110-MV-27, 32	MV-27: ROOM 2303. MV-32: ROOM 2306 BEAM.	5000 Sq Ft
	140	THROUGHOUT 1939 ADDITION 4TH FLOOR	NONE DETECTED	020110-MV-36	MV-36: HALLWAY OUTSIDE ROOM 4304.	5000 Sq Ft
N0A	Drywall/Joint Compound 1991 Addition/Installation		Total Amount - 70000 Sq Ft			
	3	THROUGHOUT BUILDING	NONE DETECTED	020110-MV-07	MV-07: CUSTODIAL OFFICE 0207.	60000 Sq Ft
	118	THROUGHOUT 1924 ORIGINAL BUILDING 3RD FLOOR	NONE DETECTED			10000 Sq Ft
N0B	Drywall/Joint Compound 1991 Addition		Total Amount - 600 Sq Ft			
	109	MECHANICAL PENTHOUSE 2404	NONE DETECTED	031023BF-7, 8; 020110-MV-42	BF-7,8: ROOM 2308. MV-42: ROOM 2307.	600 Sq Ft
N0C	Drywall/Joint Compound 2022 Installation		Total Amount - 16400 Sq Ft			
	56	KITCHEN 1706 AND ASSOCIATED ROOMS	NEW			400 Sq Ft
	129	THROUGHOUT 1939 ADDITION 3RD FLOOR	NEW			500 Sq Ft
	141	THROUGHOUT 1939 ADDITION 4TH FLOOR	NEW			5000 Sq Ft
	156	THROUGHOUT 1930 ADDITION 4TH FLOOR	NEW			500 Sq Ft
	158	THROUGHOUT 1924 ORIGINAL BUILDING 4TH FLOOR	NEW			10000 Sq Ft
POA	Fire Doors Metal - 1.5 Hr Rating (Underwriters Laboratories)		Total Amount - 100 Sq Ft			
	41	ELEVATOR EQUIPMENT ROOM 1410	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	85	THROUGHOUT 2ND FLOOR HALLWAY	ASSUMED			80 Sq Ft
Q0A	Carpet Adhesive Various Berber Carpet					Total Amount - 70 Sq Ft
	160	OFFICE 4210 UP STAIRWELL ACROSS FROM ROOM 4205	NONE DETECTED	042320-BF-2, 7, 18; 020110-MV-39	BF-2: CONFERENCE ROOM 1009 (SINCE REMOVED). BF-7: MAIN OFFICE 1002 (SINCE REMOVED). BF-18: ROOM 1216. MV-39: OFFICE CLOSET UP STAIRWELL ACROSS FROM ROOM 4201.	70 Sq Ft
Q0D	Carpet Adhesive Gray with Orange Lines Carpet Squares (2022)					Total Amount - 900 Sq Ft
	146	THROUGHOUT 4TH FLOOR ROOMS 4401-4414	NEW			400 Sq Ft
	150	FOURTH FLOOR ROOMS 4301-4309	NEW			400 Sq Ft
	154	ROOM 4202	NEW			100 Sq Ft
Q0E	Carpet Adhesive Green w/Blue Highlights Carpet					Total Amount - 950 Sq Ft
	124	THROUGHOUT 3RD FLOOR ROOMS 3401-3414	NEW			300 Sq Ft
	133	THIRD FLOOR ROOM 3307	NEW			150 Sq Ft
	136	THROUGHOUT 3RD FLOOR ROOMS 3201-3213	NEW			300 Sq Ft
	139	ROOM 3213	NEW			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0F	Carpet Adhesive Dark Gray w/Blue Streaks Carpet (202x)					Total Amount - 4300 Sq Ft
	29	FIRST FLOOR ROOMS 1303-1310	NEW			1500 Sq Ft
	37	FIRST FLOOR ROOMS 1401-1410	NEW			250 Sq Ft
	50	OFFICES 1518-1522	NEW			500 Sq Ft
	53	ROOM 1502	NEW			100 Sq Ft
	70	THROUGHOUT MAIN OFFICE AREA	NEW			1200 Sq Ft
	74	FIRST FLOOR ROOMS 1201-1206	NEW			750 Sq Ft
Q0G	Carpet Adhesive Dark Gray w/Blue Lines Carpet Squares					Total Amount - 2950 Sq Ft
	46	ROOM 1517 OFFICE COMMON AREA	NEW			700 Sq Ft
	64	MEDIA CENTER 1103, ROOM 1103B & ROOM 1103C	NEW			2000 Sq Ft
	68	THROUGHOUT MAIN OFFICE AREA HALLWAYS	NEW			250 Sq Ft
Q0H	Carpet Adhesive Light Gray w/Yellow Carpet (202x)					Total Amount - 600 Sq Ft
	95	SECOND FLOOR ROOMS 2301-2313	NEW			300 Sq Ft
	104	THROUGHOUT 2ND FLOOR ROOMS 2401-2414	NEW			300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
R0D	Baseboard/Mopboard Adhesive Dark Gray Baseboard (2021/2022)					Total Amount - 7400 Sq Ft
	2	THROUGHOUT BUILDING	NEW			2000 Sq Ft
	82	THROUGHOUT 2ND FLOOR HALLWAY	NEW			400 Sq Ft
	142	THROUGHOUT 4TH FLOOR	NEW			5000 Sq Ft
R0E	Baseboard/Mopboard Adhesive 6" Dark Gray Baseboard (202x)					Total Amount - 100 Sq Ft
	34	GYMNASIUM 1304	NEW			100 Sq Ft
S0A	Wood Floor Felt / Vapor Barrier 1924 Original Building					Total Amount - 70 Sq Ft
	159	OFFICE 4210 UP STAIRWELL ACROSS FROM ROOM 4205	NSM			70 Sq Ft
V0C	Sink Undercoating Smooth Black (2021)					Total Amount - 28 Sq Ft
	39	2021 ADDITION ROOM 1203	NEW			5 Sq Ft
	40	2021 ADDITION ROOM 1205	NEW			5 Sq Ft
	87	2021 ADDITION ROOM 2201	NEW			18 Sq Ft
V0D	Sink Undercoating Black Rubber Sheet (202x)					Total Amount - 115 Sq Ft
	30	ROOM 1305	NEW			10 Sq Ft
	31	ROOM 1307	NEW			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	32	ROOM 1309	NEW			10 Sq Ft
	38	ROOM 1403	NEW			10 Sq Ft
	91	ROOM 2201	NEW			5 Sq Ft
	97	ROOM 2305	NEW			5 Sq Ft
	98	ROOM 2311	NEW			10 Sq Ft
	99	ROOM 2315	NEW			10 Sq Ft
	106	ROOM 2403	NEW			5 Sq Ft
	126	ROOM 3407	NEW			5 Sq Ft
	138	3RD FLOOR ROOMS 3201, 3203, 3207	NEW			35 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B					Total Amount - 10 Sq Ft
	113	ROOM 2407	NONE DETECTED	031023BF-13; 020110-MV-27	BF-13, MV-27: ROOM 2303.	10 Sq Ft
X0A	Miscellaneous Material Pipe/Valve Flange Gaskets					Total Amount - 24 Sq Ft
	21	LOWER LEVEL STORAGE ROOM 0302	ASSUMED			24 Sq Ft
X0B	Miscellaneous Material Slate Chalkboard/Tackboard Adhesive (1991)					Total Amount - 400 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	040323BF-9	BF-9: 2203.	400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0C	Miscellaneous Material Slate Chalkboard Adhesive (1930)					Total Amount - 10 Sq Ft
	108	ROOM 2405	NONE DETECTED	040323BF-5, 072910ML-01	BF-05: ROOM 2302.	10 Sq Ft
X0D	Miscellaneous Material Tackboard Adhesive -Brown (1930)					Total Amount - 60 Sq Ft
	107	ROOM 2403	NONE DETECTED	050521-BF-3	BF-3: ROOM 4302 (SINCE REMOVED).	60 Sq Ft
X0L	Miscellaneous Material Black Coating on Clay Block Wall Behind Plaster					Total Amount - 5000 Sq Ft
	17	THROUGHOUT 1924 ORIGINAL BUILDING	NONE DETECTED	073119-BF-1; 092916- BF-2	BF-1: ROOM 2201. 2: 2ND FLOOR BOYS' RESTROOM.	5000 Sq Ft
X0N	Miscellaneous Material Brick Mortar					Total Amount - 1000 Sq Ft
	18	THROUGHOUT 1930 ADDITION	NONE DETECTED	042320-BF-32	BF-32: 1930 ADDITION EXTERIOR.	1000 Sq Ft
X0O	Miscellaneous Material Gray Duct Caulk					Total Amount - 100 Sq Ft
	6	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-8	BF-8: MAIN OFFICE 1002.	100 Sq Ft
X0P	Miscellaneous Material Light Gray Duct Caulk					Total Amount - 100 Sq Ft
	7	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-9	BF-9: MAIN OFFICE 1002.	100 Sq Ft
X0Q	Miscellaneous Material Red Fire Stop					Total Amount - 100 Sq Ft
	8	THROUGHOUT BUILDING	NONE DETECTED	042320-BF-10	BF-10: MAIN OFFICE 1002.	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOR	Miscellaneous Material Whiteboard Adhesive -White					Total Amount - 405 Sq Ft
	5	THROUGHOUT BUILDING	NONE DETECTED	040323BF-4, 6; 050521-BF-4	BF-4: ROOM 2304. BF-6: ROOM 2302. BF-4: ROOM 4205.	100 Sq Ft
	47	ROOM 1517 OFFICE COMMON AREA	NONE DETECTED			25 Sq Ft
	51	OFFICES 1518-1522	NONE DETECTED			200 Sq Ft
	90	2021 ADDITION ROOMS 2201-2210	NONE DETECTED			80 Sq Ft
XOS	Miscellaneous Material Tackboard Adhesive (2021)					Total Amount - 60 Sq Ft
	89	2021 ADDITION ROOM 2201-2210	NEW			60 Sq Ft
XOT	Miscellaneous Material Milkboard Adhesive					Total Amount - 100 Sq Ft
	54	ROOM 1601	NEW			100 Sq Ft
X1F	Miscellaneous Material 6" Red Quarry Tile					Total Amount - 125 Sq Ft
	100	1924 ORIGINAL BUILDING ENTRANCE 2100A	ASSUMED			125 Sq Ft
X1G	Miscellaneous Material Multisized Beige Ceramic Wall Tile System (2021)					Total Amount - 2000 Sq Ft
	25	THROUGHOUT FIRST FLOOR HALLWAYS	NEW			1000 Sq Ft
	83	THROUGHOUT 2ND FLOOR HALLWAY	NEW			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1H	Miscellaneous Material 1" Wood Wall Strips Adhesive (2021)					Total Amount - 1300 Sq Ft
	26	THROUGHOUT FIRST FLOOR HALLWAYS	NEW			500 Sq Ft
	84	THROUGHOUT 2ND FLOOR HALLWAY	NEW			300 Sq Ft
	119	THROUGHOUT 1924 ORIGINAL BUILDING 3RD FLOOR	NEW			500 Sq Ft
X1K	Miscellaneous Material 4" X 12" Blue and White Ceramic Wall Tile System (2022)					Total Amount - 6250 Sq Ft
	10	THROUGHOUT BUILDING (RESTROOMS)	NEW			6250 Sq Ft
X1L	Miscellaneous Material Multi-Size Tan Ceramic Wall Tile System (2022)					Total Amount - 3000 Sq Ft
	11	THROUGHOUT BUILDING (RESTROOMS)	NEW			3000 Sq Ft
X1O	Miscellaneous Material 6" X 6" Tan Quarry Tile System (2023)					Total Amount - 1200 Sq Ft
	57	KITCHEN 1706 AND ASSOCIATED ROOMS	NEW			1200 Sq Ft
Z0A	Miscellaneous Material Roof Membrane					Total Amount - 40000 Sq Ft
	12	THROUGHOUT BUILDING ROOF	NONE DETECTED	042320-BF-35, 40, 46	BF-35: ROOF SECTION 9. BF-40: ROOF SECTION 14. BF-46: ROOF SECTION 13.	40000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Z0B	Miscellaneous Material Roof Perimeter Flashing					Total Amount - 2000 Sq Ft
	13	THROUGHOUT BUILDING ROOF	NONE DETECTED	042320-BF-37, 42, 47	BF-37: ROOF SECTION 9. BF-42: ROOF SECTION 14. BF-47: ROOF SECTION 13.	2000 Sq Ft
Z0C	Miscellaneous Material Roof Penetration Flashing					Total Amount - 300 Sq Ft
	14	THROUGHOUT BUILDING ROOF	NONE DETECTED	042320-BF-36, 41	BF-36: ROOF SECTION 9. BF-41: ROOF SECTION 14.	300 Sq Ft
Z0D	Miscellaneous Material Roof Cement Patch -Gray					Total Amount - 100 Sq Ft
	15	THROUGHOUT BUILDING ROOF	3 - 4 CH	042320-BF-38, 43, 48	BF-38: ROOF SECTION 9. BF-43: ROOF SECTION 14. BF-48: ROOF SECTION 13.	100 Sq Ft
Z0E	Miscellaneous Material Roof Flashing Caulk					Total Amount - 100 Sq Ft
	16	THROUGHOUT BUILDING ROOF	NONE DETECTED	042320-BF-39, 44, 49	BF-39: ROOF SECTION 9. BF-44: ROOF SECTION 14. BF-49: ROOF SECTION 13.	100 Sq Ft