

318 Moore Street, Saint Paul, MN 55104

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A	Mudded Pipe Joints on Fiberglass Insulation Vinyl-Coated Fiberglass					Total Amount - 267 Joints
	10	BOILER ROOM 1212	NONE DETECTED	512-JJT-39; 207T1A; ACB450AC-A002	JJT-39: VALVE ABOVE MAIN DOOR TO CUSTODIAL ROOM.	94 Joints
	36	THEATER STORAGE 1108	NONE DETECTED	512-JJT-22	JJT-22: CAFETERIA 1101 SOUTHWEST CORNER JUST EAST OF SPRAYER (SINCE REMOVED).	8 Joints
	44	ROOM 1106	NONE DETECTED			2 Joints
	59	FAN ROOM 1204 OFF OF BOYS' GYMNASIUM RESTROOM	NONE DETECTED			37 Joints
	66	HALLWAY 1200 BY GYMNASIUM	NONE DETECTED			4 Joints
	70	GYMNASIUM 1201	NONE DETECTED			6 Joints
	85	ROOM 1103	NONE DETECTED	092017-CN-01	CN-01: ROOM 1103.	2 Joints
	136	2ND FLOOR NORTH CUSTODIAL CLOSET 2002	NONE DETECTED	ACB450AC-004		6 Joints
	143	2ND FLOOR HALLWAY 2000 OUTSIDE ROOMS 2004-2011	NONE DETECTED	081319-BF-1	BF-01: HALLWAY OUTSIDE ROOM 2011.	8 Joints
	151	ROOM 2503	NONE DETECTED			2 Joints
	179	ROOM 2301	NONE DETECTED			4 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	190	ROOM 2305	NONE DETECTED			2 Joints
	203	HALLWAY 1000	NONE DETECTED	ACB450AC-A003		4 Joints
	210	1ST FLOOR NORTH CUSTODIAL CLOSET 1003	NONE DETECTED			7 Joints
	295	LIBRARY FAN ROOM	NONE DETECTED			55 Joints
	298	TUNNEL OFF OF FAN ROOM	NONE DETECTED	512-JJT-28	1ST ELBOW ON RIGHT SIDE.	20 Joints
	305	HALLWAY 1400	NONE DETECTED			6 Joints
A4B	Mudded Pipe Joints on Fiberglass Insulation Foil-Wrapped Fiberglass				Total Amount - 392 Joints	
	22	CUSTODIAL OFFICE 1211	NONE DETECTED			3 Joints
	27	KITCHEN STAFF LOCKER/RESTROOM 1209	NONE DETECTED			4 Joints
	30	KITCHEN STORAGE 1208	NONE DETECTED			11 Joints
	32	KITCHEN 1107A	NONE DETECTED	512-JJT-42	JJT-42: KITCHEN ABOVE HAND SINK (SINCE REMOVED).	10 Joints
	39	CAFETERIA 1101	NONE DETECTED	512-JJT-16	JJT-16: SOUTHWEST CORNER ABOVE THERMOSTAT.	16 Joints
	45	ROOM 1106	NONE DETECTED			4 Joints
	48	ROOM 1106A	NONE DETECTED			2 Joints
	57	BOYS' GYMNASIUM RESTROOM 1205	NONE DETECTED			13 Joints
	62	GIRLS' GYMNASIUM RESTROOM 1203	NONE DETECTED			20 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	63	ROOM 1202 OFFICE	NONE DETECTED			7 Joints
	67	HALLWAY 1200 BY GYMNASIUM	NONE DETECTED			3 Joints
	73	HALLWAY 1100 OUTSIDE ROOM 1102/1103	NONE DETECTED			13 Joints
	77	ROOM 1102	NONE DETECTED			7 Joints
	86	ROOM 1103	NONE DETECTED			2 Joints
	101	MAIN ENTRY HALLWAY	NONE DETECTED			13 Joints
	137	2ND FLOOR NORTH CUSTODIAL CLOSET 2002	NONE DETECTED	512-JJT-3	JJT-3: ABOVE DOOR.	6 Joints
	146	2ND FLOOR SOUTHEAST COMMONS AREA 2502	NONE DETECTED			3 Joints
	152	ROOM 2503	NONE DETECTED			2 Joints
	163	ROOM 2501	NONE DETECTED			2 Joints
	170	2ND FLOOR HALLWAY 2300 OUTSIDE SOUTH RESTROOMS	NONE DETECTED	092017CN-02	CN-02: 2ND FLOOR HALLWAY BY ROOM 2402.	4 Joints
	173	2ND FLOOR SOUTHWEST COMMON AREA 2303	NONE DETECTED			3 Joints
	180	ROOM 2301	NONE DETECTED			2 Joints
	196	1ST FLOOR NORTHEAST ENTRANCE 1000A	NONE DETECTED			1 Joints
	204	HALLWAY 1000	NONE DETECTED			52 Joints
	207	GIRLS' 1ST FLOOR NORTH RESTROOM 1001	NONE DETECTED			16 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	211	1ST FLOOR NORTH CUSTODIAL CLOSET 1003	NONE DETECTED			20 Joints
	213	BOYS' 1ST FLOOR NORTH RESTROOM 1005	NONE DETECTED			2 Joints
	221	NURSE'S RESTROOM 1006A	NONE DETECTED			2 Joints
	226	NURSE'S OFFICE 1006	NONE DETECTED			13 Joints
	233	MAIN OFFICE WORK ROOM 1007	NONE DETECTED			12 Joints
	243	1ST FLOOR STAFF RESTROOM 1302	NONE DETECTED			6 Joints
	250	ART ROOM 1304	NONE DETECTED			12 Joints
	258	KILN ROOM 1304A	NONE DETECTED			3 Joints
	263	ART STORAGE 1304B	NONE DETECTED			8 Joints
	271	ROOM 1310	NONE DETECTED			8 Joints
	275	ROOM 1214A	NONE DETECTED			9 Joints
	288	LIBRARY 1402	NONE DETECTED			9 Joints
	299	TUNNEL OFF OF FAN ROOM	NONE DETECTED			30 Joints
	306	HALLWAY 1400	NONE DETECTED			16 Joints
	309	ROOM 1502	NONE DETECTED			2 Joints
	316	ROOM 1504	NONE DETECTED			7 Joints
	322	ROOM 1506	NONE DETECTED			7 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	328	ROOM 1507	NONE DETECTED			7 Joints
D1A	Boiler Gaskets Shiny (2008)					Total Amount - 5 Sq Ft
	11	BOILER ROOM 1212	NONE DETECTED	030509-MV-1		5 Sq Ft
D1B	Boiler Gaskets Gray Burner Gaskets					Total Amount - 2 Sq Ft
	12	BOILER ROOM 1212	45 CH	030509-MV-2		2 Sq Ft
D1C	Boiler Gaskets Rear Stack Box Gasket					Total Amount - 2 Sq Ft
	13	BOILER ROOM 1212	65 CH	030509-MV-3		2 Sq Ft
D1D	Boiler Gaskets Boiler #1					Total Amount - 3 Sq Ft
	15	BOILER ROOM 1212	NONE DETECTED	030509-MV-4		3 Sq Ft
D2A	Interior Boiler Insulation Boiler #2					Total Amount - 100 Sq Ft
	14	BOILER ROOM 1212	ASSUMED			100 Sq Ft
D2B	Interior Boiler Insulation Boiler #1					Total Amount - 5 Sq Ft
	16	BOILER ROOM 1212	ASSUMED			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
EOA	Stack Insulation 1974 Installation	Total Amount - 50 Sq Ft				
	17	BOILER ROOM 1212	NONE DETECTED	512-JJT-33, 34, 35; 202-T2A	JJT-33: LOWER WEST. JJT-34: LOWER MIDDLE. JJT-35: LOWER EAST.	50 Sq Ft
G1A	Sprayed-On Acoustical Finish White Spackle	Total Amount - 5000 Sq Ft				
	287	LIBRARY 1402	<1 CH	512-JJT-7, 8, 9, 13, 14, 15, 26; 207T8A; 510G-9- 12	JJT-7,8,9: SOUTHEAST. JJT- 13,14,15: SOUTHWEST.	5000 Sq Ft
H1A	Sprayed-On Structural Fireproofing Tan, Fluffy	Total Amount - 6130 Sq Ft				
	105	NORTHEAST STAIRWELL 2099A	NONE DETECTED			125 Sq Ft
	110	ROOM 2004	NONE DETECTED			160 Sq Ft
	114	ROOM 2005	NONE DETECTED			160 Sq Ft
	117	ROOM 2006	NONE DETECTED			10 Sq Ft
	121	ROOM 2009	NONE DETECTED			10 Sq Ft
	124	ROOM 2008	NONE DETECTED			10 Sq Ft
	126	ROOM 2010	NONE DETECTED			150 Sq Ft
	128	ROOM 2011	NONE DETECTED	512-JJT-1	JJT-1: ABOVE CEILING BY DOOR.	150 Sq Ft
	131	NORTHWEST STAIRWELL 2099B	NONE DETECTED	030509-MV-6		125 Sq Ft
	133	BOYS' 2ND FLOOR NORTH RESTROOM 2001	NONE DETECTED			75 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	135	2ND FLOOR NORTH CUSTODIAL CLOSET 2002	NONE DETECTED	512-JJT-2	JJT-2: ABOVE DOOR.	50 Sq Ft
	138	GIRLS' 2ND FLOOR NORTH RESTROOM 2003	NONE DETECTED			75 Sq Ft
	142	2ND FLOOR HALLWAY 2000 OUTSIDE ROOMS 2004-2011	NONE DETECTED	510G-13-19		500 Sq Ft
	145	2ND FLOOR SOUTHEAST COMMONS AREA 2502	NONE DETECTED	512-JJT-10	JJT-10: SOUTH HALLWAY.	300 Sq Ft
	150	ROOM 2503	NONE DETECTED	512-JJT-5	JJT-5: BEAM ABOVE THERMOSTAT.	50 Sq Ft
	154	ROOM 2504	NONE DETECTED	512-JJT-6	JJT-6: ABOVE 3RD WINDOW FROM SOUTH WALL.	200 Sq Ft
	158	ROOM 2506	NONE DETECTED			150 Sq Ft
	161	ROOM 2501	NONE DETECTED	030509-MV-7		120 Sq Ft
	169	2ND FLOOR HALLWAY 2300 OUTSIDE SOUTH RESTROOMS	NONE DETECTED			500 Sq Ft
	172	2ND FLOOR SOUTHWEST COMMON AREA 2303	NONE DETECTED	512-JJT-12	JJT-12: BEAM ABOVE NORTHWEST CORNER SOFFIT.	100 Sq Ft
	177	ROOM 2301	NONE DETECTED	512-JJT-11	JJT-11: BEAM ABOVE MAIN DOOR.	75 Sq Ft
	182	ROOM 2302	NONE DETECTED			225 Sq Ft
	186	ROOM 2304	NONE DETECTED			225 Sq Ft
	189	ROOM 2305	NONE DETECTED			100 Sq Ft
	202	HALLWAY 1000	NONE DETECTED			400 Sq Ft
	206	GIRLS' 1ST FLOOR NORTH RESTROOM 1001	NONE DETECTED			80 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	209	1ST FLOOR NORTH CUSTODIAL CLOSET 1003	NONE DETECTED			50 Sq Ft
	212	BOYS' 1ST FLOOR NORTH RESTROOM 1005	NONE DETECTED			80 Sq Ft
	247	ART ROOM 1304	NONE DETECTED	512-JJT-20	JJT-20: BEAM ABOVE SINK AREA ENTRANCE.	160 Sq Ft
	257	KILN ROOM 1304A	NONE DETECTED			80 Sq Ft
	266	HALLWAY 1300	NONE DETECTED	030509-MV-5		50 Sq Ft
	273	ROOM 1214A	NONE DETECTED	512-JJT-24	JJT-24: ABOVE NORTH WINDOW.	300 Sq Ft
	279	ROOM 1311	NONE DETECTED			150 Sq Ft
	303	HALLWAY 1400	NONE DETECTED			500 Sq Ft
	314	ROOM 1504	NONE DETECTED			75 Sq Ft
	318	ROOM 1505	NONE DETECTED			100 Sq Ft
	320	ROOM 1506	NONE DETECTED			100 Sq Ft
	326	ROOM 1507	NONE DETECTED			100 Sq Ft
	331	ROOM 1510	NONE DETECTED			100 Sq Ft
	335	HALLWAY 1500	NONE DETECTED	512-JJT-31	JJT-31: NORTH END OF HALLWAY ABOVE LOUDSPEAKER ON EAST WALL.	160 Sq Ft
H1B	Sprayed-On Structural Fireproofing Tan, Hard				Total Amount - 1660 Sq Ft	
	293	LIBRARY FAN ROOM	NONE DETECTED	030509-MV-8, 9, 10; 510G-1-6		1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	297	TUNNEL OFF OF FAN ROOM	NONE DETECTED	030509-MV-11; 512-JJT-29	JJT-29: 1ST BEAM ON RIGHT SIDE.	500 Sq Ft
	304	HALLWAY 1400	NONE DETECTED	512-JJT-20, 23; 207T7A; 510G-7-8	JJT-20: WEST END. JJT-23: EAST END.	160 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Rough Texture					Total Amount - 25 Sq Ft
	26	CUSTODIAL CLOSET 1210	NONE DETECTED	207-T6A	MAIN ENTRY (SINCE REMOVED).	20 Sq Ft
	216	ISOLATION ROOM CLOSET 1004A	NONE DETECTED			5 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Glacial w/Revealed Edge					Total Amount - 1635 Sq Ft
	75	HALLWAY 1100 OUTSIDE ROOM 1102/1103	NONE DETECTED	030509-MV-12		470 Sq Ft
	94	ROOM 1104	NONE DETECTED			1000 Sq Ft
	98	ROOM 1105	NONE DETECTED			165 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Bumpy Texture w/Revealed Edge					Total Amount - 2390 Sq Ft
	215	ISOLATION ROOM 1004	NONE DETECTED			150 Sq Ft
	218	NURSE'S SICK ROOM 1006	NONE DETECTED			120 Sq Ft
	222	NURSE'S RESTROOM 1006A	NONE DETECTED			40 Sq Ft
	227	NURSE'S OFFICE 1006	NONE DETECTED			150 Sq Ft
	229	MAIN OFFICE 1002	NONE DETECTED	030509-MV-13		400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	231	PRINCIPAL'S OFFICE 1010	NONE DETECTED			140 Sq Ft
	232	MAIN OFFICE ROOM 1009	NONE DETECTED			150 Sq Ft
	234	MAIN OFFICE WORK ROOM 1007	NONE DETECTED			410 Sq Ft
	244	1ST FLOOR STAFF RESTROOM 1302	NONE DETECTED			50 Sq Ft
	245	1ST FLOOR STAFF RESTROOM 1303	NONE DETECTED			70 Sq Ft
	246	ROOM 1305	NONE DETECTED			100 Sq Ft
	289	LIBRARY 1402	NONE DETECTED			170 Sq Ft
	300	ROOM 1306 (SPEECH)	NONE DETECTED			80 Sq Ft
	301	ROOM 1008	NONE DETECTED			180 Sq Ft
	302	ROOM 1403	NONE DETECTED			180 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Small Random Dents & Holes w/Revealed Edge		Total Amount - 3500 Sq Ft			
	342	THROUGHOUT 1999 ADDITION	NONE DETECTED	030509-MV-33		3500 Sq Ft
I3A	2' x 4' Ceiling Tile Glacial		Total Amount - 32180 Sq Ft			
	46	ROOM 1106	NONE DETECTED			900 Sq Ft
	49	ROOM 1106A	NONE DETECTED			90 Sq Ft
	64	ROOM 1202 OFFICE	NONE DETECTED			190 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	68	HALLWAY 1200 BY GYMNASIUM	NONE DETECTED			400 Sq Ft
	74	HALLWAY 1100 OUTSIDE ROOM 1102/1103	NONE DETECTED			150 Sq Ft
	78	ROOM 1102	NONE DETECTED			680 Sq Ft
	87	ROOM 1103	NONE DETECTED			900 Sq Ft
	102	MAIN ENTRY HALLWAY	NONE DETECTED			650 Sq Ft
	106	NORTHEAST STAIRWELL 2099A	NONE DETECTED			240 Sq Ft
	112	ROOM 2004	NONE DETECTED			830 Sq Ft
	116	ROOM 2005	NONE DETECTED			840 Sq Ft
	118	ROOM 2006	NONE DETECTED			430 Sq Ft
	119	ROOM 2007	NONE DETECTED			620 Sq Ft
	122	ROOM 2009	NONE DETECTED			560 Sq Ft
	125	ROOM 2008	NONE DETECTED			430 Sq Ft
	127	ROOM 2010	NONE DETECTED			840 Sq Ft
	130	ROOM 2011	NONE DETECTED			830 Sq Ft
	132	NORTHWEST STAIRWELL 2099B	NONE DETECTED			200 Sq Ft
	144	2ND FLOOR HALLWAY 2000 OUTSIDE ROOMS 2004-2011	NONE DETECTED			2200 Sq Ft
	147	2ND FLOOR SOUTHEAST COMMONS AREA 2502	NONE DETECTED			1200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	153	ROOM 2503	NONE DETECTED			110 Sq Ft
	156	ROOM 2504	NONE DETECTED			830 Sq Ft
	160	ROOM 2506	NONE DETECTED			840 Sq Ft
	164	ROOM 2501	NONE DETECTED			650 Sq Ft
	171	2ND FLOOR HALLWAY 2300 OUTSIDE SOUTH RESTROOMS	NONE DETECTED			800 Sq Ft
	174	2ND FLOOR SOUTHWEST COMMON AREA 2303	NONE DETECTED			1200 Sq Ft
	181	ROOM 2301	NONE DETECTED			110 Sq Ft
	184	ROOM 2302	NONE DETECTED			800 Sq Ft
	188	ROOM 2304	NONE DETECTED			800 Sq Ft
	192	ROOM 2305	NONE DETECTED			700 Sq Ft
	198	ROOM 1501	NONE DETECTED			950 Sq Ft
	205	HALLWAY 1000	NONE DETECTED	ACB450AC-A001	MAIN ENTRY (SINCE REMOVED).	560 Sq Ft
	237	1ST FLOOR NORTHWEST STAIRWELL 1099B	NONE DETECTED			50 Sq Ft
	240	STAFF LOUNGE 1301	NONE DETECTED			380 Sq Ft
	251	ART ROOM 1304	NONE DETECTED			700 Sq Ft
	259	KILN ROOM 1304A	NONE DETECTED			180 Sq Ft
	264	ART STORAGE 1304B	NONE DETECTED			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	268	HALLWAY 1300	NONE DETECTED			480 Sq Ft
	269	ROOM 1308	NONE DETECTED			520 Sq Ft
	272	ROOM 1310	NONE DETECTED			960 Sq Ft
	274	ROOM 1214A	NONE DETECTED			140 Sq Ft
	281	ROOM 1311	NONE DETECTED			960 Sq Ft
	284	ROOM 1309	NONE DETECTED			520 Sq Ft
	285	HALLWAY 1300 OUTSIDE ROOMS 1308 & 1309	NONE DETECTED			300 Sq Ft
	291	LIBRARY 1402A	NONE DETECTED	512-JJT-27	NORTHEAST CORNER.	40 Sq Ft
	307	HALLWAY 1400	NONE DETECTED			700 Sq Ft
	310	ROOM 1502	NONE DETECTED			1500 Sq Ft
	317	ROOM 1504	NONE DETECTED			110 Sq Ft
	319	ROOM 1505	NONE DETECTED			720 Sq Ft
	323	ROOM 1506	NONE DETECTED			720 Sq Ft
	325	ROOM 1508	NONE DETECTED			100 Sq Ft
	329	ROOM 1507	NONE DETECTED			700 Sq Ft
	333	ROOM 1510	NONE DETECTED			400 Sq Ft
	338	HALLWAY 1500	NONE DETECTED			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	339	ROOM 1509	NONE DETECTED			100 Sq Ft
I3C	2' x 4' Ceiling Tile Medium & Small Pin Holes					Total Amount - 228 Sq Ft
	25	HALLWAY 1200 BY CUSTODIAL OFFICE	NONE DETECTED	512-JJT-41; 207-T5A	JJT-41: KITCHEN, JJT-41: ABOVE HAND SINK IN NORTHWEST CORNER (SINCE REMOVED).	228 Sq Ft
I3D	2' x 4' Ceiling Tile Worms & Pin Holes					Total Amount - 100 Sq Ft
	28	KITCHEN STAFF LOCKER/RESTROOM 1209	NONE DETECTED	030509-MV-14		100 Sq Ft
I3E	2' x 4' Ceiling Tile Vinyl-Coated Sheetrock					Total Amount - 1950 Sq Ft
	31	KITCHEN STORAGE 1208	NSM			130 Sq Ft
	33	KITCHEN 1107A	NSM			520 Sq Ft
	41	CAFETERIA 1101	NSM			1300 Sq Ft
I3G	2' x 4' Ceiling Tile Tectum					Total Amount - 980 Sq Ft
	134	BOYS' 2ND FLOOR NORTH RESTROOM 2001	NONE DETECTED	030509-MV-16		150 Sq Ft
	139	GIRLS' 2ND FLOOR NORTH RESTROOM 2003	NONE DETECTED			150 Sq Ft
	167	GIRLS' 2ND FLOOR SOUTH RESTROOM 2402	NONE DETECTED			160 Sq Ft
	168	BOYS' 2ND FLOOR SOUTH RESTROOM 2401	NONE DETECTED			160 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	208	GIRLS' 1ST FLOOR NORTH RESTROOM 1001	NONE DETECTED			180 Sq Ft
	214	BOYS' 1ST FLOOR NORTH RESTROOM 1005	NONE DETECTED			180 Sq Ft
I3H	2' x 4' Ceiling Tile Small Dents & Pin Holes (200X)					Total Amount - 1700 Sq Ft
	40	CAFETERIA 1101	NEW			1200 Sq Ft
	290	LIBRARY 1402	NEW			500 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Reddish/Brown w/Red, Brown & Gray Streaks					Total Amount - 12 Sq Ft
	107	NORTHEAST STAIRWELL 2099A	3 CH	2001-1501-S-5		12 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic White w/Light Green & Gray Streaks					Total Amount - 2655 Sq Ft
	29	KITCHEN STAFF LOCKER/RESTROOM 1209	6 CH (TILE),10 CH (MASTIC)	2001-1501-S02	S02: CAFETERIA 1101 (SINCE REMOVED). SAMPLE WAS SUPPOSEDLY POINT COUNTED.	100 Sq Ft
	50	ROOM 1106A	6 CH (TILE),10 CH (MASTIC)			90 Sq Ft
	52	FAN ROOM/STORAGE 1207	6 CH (TILE),10 CH (MASTIC)			375 Sq Ft
	55	PHY ED STORAGE 1206	6 CH (TILE),10 CH (MASTIC)			150 Sq Ft
	65	ROOM 1202 OFFICE	6 CH (TILE),10 CH (MASTIC)			190 Sq Ft
	235	MAIN OFFICE WORK ROOM 1007	6 CH (TILE),10 CH (MASTIC)			410 Sq Ft
	238	1ST FLOOR NORTHWEST STAIRWELL 1099B	6 CH (TILE),10 CH (MASTIC)			150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	252	ART ROOM 1304	6 CH (TILE),10 CH (MASTIC)	030509-MV-17		700 Sq Ft
	260	KILN ROOM 1304A	6 CH (TILE),10 CH (MASTIC)			190 Sq Ft
	265	ART STORAGE 1304B	6 CH (TILE),10 CH (MASTIC)			120 Sq Ft
	276	ROOM 1214A	6 CH (TILE),10 CH (MASTIC)			140 Sq Ft
	292	LIBRARY 1402A	6 CH (TILE),10 CH (MASTIC)			40 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Gray/Blue & Cream Mottle					Total Amount - 440 Sq Ft
	47	ROOM 1106	NONE DETECTED			280 Sq Ft
	219	NURSE'S SICK ROOM 1006	NONE DETECTED	030509-MV-20		120 Sq Ft
	223	NURSE'S RESTROOM 1006A	NONE DETECTED			40 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Tan w/White & Gray Smudges					Total Amount - 475 Sq Ft
	79	ROOM 1102	NONE DETECTED	030509-MV-21		60 Sq Ft
	88	ROOM 1103	NONE DETECTED			60 Sq Ft
	95	ROOM 1104	NONE DETECTED			190 Sq Ft
	99	ROOM 1105	NONE DETECTED			165 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2G	12" x 12" Vinyl Floor Tile & Mastic Blue	Total Amount - 60 Sq Ft				
340	1974 ADDITION SOUTHEAST ENTRY	NONE DETECTED	030509-MV-34	60 Sq Ft		
K2H	12" x 12" Vinyl Floor Tile & Mastic Green	Total Amount - 60 Sq Ft				
341	1974 ADDITION SOUTHEAST ENTRY	NONE DETECTED	030509-MV-35	60 Sq Ft		
K2I	12" x 12" Vinyl Floor Tile & Mastic Blue, White, Red & Yellow Mottle (2009)	Total Amount - 2805 Sq Ft				
37	THEATER STORAGE 1108	NEW	375 Sq Ft			
42	CAFETERIA 1101	NEW	2400 Sq Ft			
334	ROOM 1510A	NEW	30 Sq Ft			
K2J	12" x 12" Vinyl Floor Tile & Mastic Reddish-Brown w/Light Brown, Brown & Tan	Total Amount - 240 Sq Ft				
108	NORTHEAST STAIRWELL 2099A	6 CH (TILE), 10 CH (MASTIC)	072215BV-03	BV-03: STAIRWELL 2099A.	240 Sq Ft	
K3A	Miscellaneous Flooring Black Mastic	Total Amount - 52 Sq Ft				
220	NURSE'S SICK ROOM 1006	10 CH	030509-MV-20	12 Sq Ft		
224	NURSE'S RESTROOM 1006A	10 CH	40 Sq Ft			

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3B	Miscellaneous Flooring White w/Brown & Gray Pebbles Epoxy Flooring (20xx)					Total Amount - 150 Sq Ft
	228	NURSE'S OFFICE 1006	NEW			150 Sq Ft
K3C	Miscellaneous Flooring Blue Rubber Flooring (2023)					Total Amount - 4500 Sq Ft
	71	GYMNASIUM 1201	NEW			4500 Sq Ft
LOA	Flexible Duct Connector Black Vinyl					Total Amount - 84 Sq Ft
	18	BOILER ROOM 1212	NONE DETECTED	2001-1501-S-03		2 Sq Ft
	53	FAN ROOM/STORAGE 1207	NONE DETECTED			10 Sq Ft
	60	FAN ROOM 1204 OFF OF BOYS' GYMNASIUM RESTROOM	NONE DETECTED			20 Sq Ft
	282	ROOM 1311	NONE DETECTED			2 Sq Ft
	296	LIBRARY FAN ROOM	NONE DETECTED			50 Sq Ft
M0A	Plaster 1974 Installation					Total Amount - 10000 Sq Ft
	9	BOILER ROOM 1212	NONE DETECTED	030509-MV-24		800 Sq Ft
	20	ROOM 1212A MECHANICAL	NONE DETECTED			100 Sq Ft
	21	CUSTODIAL OFFICE 1211	NONE DETECTED	512-JJT-32	JJT-32: EAST CEILING BY CONDUIT.	300 Sq Ft
	24	HALLWAY 1200 BY CUSTODIAL OFFICE	NONE DETECTED			70 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	35	THEATER STORAGE 1108	NONE DETECTED			375 Sq Ft
	51	FAN ROOM/STORAGE 1207	NONE DETECTED			375 Sq Ft
	54	PHY ED STORAGE 1206	NONE DETECTED			150 Sq Ft
	56	BOYS' GYMNASIUM RESTROOM 1205	NONE DETECTED			180 Sq Ft
	58	FAN ROOM 1204 OFF OF BOYS' GYMNASIUM RESTROOM	NONE DETECTED	030509-MV-25		800 Sq Ft
	61	GIRLS' GYMNASIUM RESTROOM 1203	NONE DETECTED			180 Sq Ft
	76	ROOM 1102	NONE DETECTED	512-JJT-43	JJT-43: ABOVE 7 NORTH OF MAIN DOOR.	260 Sq Ft
	84	ROOM 1103	NONE DETECTED			350 Sq Ft
	104	MAIN ENTRY	NONE DETECTED			300 Sq Ft
	111	ROOM 2004	NONE DETECTED			200 Sq Ft
	115	ROOM 2005	NONE DETECTED			100 Sq Ft
	129	ROOM 2011	NONE DETECTED			150 Sq Ft
	155	ROOM 2504	NONE DETECTED			400 Sq Ft
	159	ROOM 2506	NONE DETECTED			150 Sq Ft
	162	ROOM 2501	NONE DETECTED			300 Sq Ft
	166	SOUTHEAST STAIRWELL 2499C	NONE DETECTED			250 Sq Ft
	178	ROOM 2301	NONE DETECTED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	183	ROOM 2302	NONE DETECTED	030509-MV-26		400 Sq Ft
	187	ROOM 2304	NONE DETECTED			400 Sq Ft
	191	ROOM 2305	NONE DETECTED			200 Sq Ft
	194	SOUTHWEST STAIRWELL 2299B	NONE DETECTED			200 Sq Ft
	195	1ST FLOOR NORTHEAST ENTRANCE 1000A	NONE DETECTED			350 Sq Ft
	197	ROOM 1501	NONE DETECTED			350 Sq Ft
	239	STAFF LOUNGE 1301	NONE DETECTED			200 Sq Ft
	248	ART ROOM 1304	NONE DETECTED			150 Sq Ft
	256	KILN ROOM 1304A	NONE DETECTED			100 Sq Ft
	270	ROOM 1310	NONE DETECTED			150 Sq Ft
	280	ROOM 1311	NONE DETECTED			150 Sq Ft
	283	ROOM 1309	NONE DETECTED			120 Sq Ft
	286	SOUTHWEST ENTRY	NONE DETECTED			150 Sq Ft
	294	LIBRARY FAN ROOM	NONE DETECTED	030509-MV-23		100 Sq Ft
	308	ROOM 1502	NONE DETECTED			400 Sq Ft
	315	ROOM 1504	NONE DETECTED			200 Sq Ft
	321	ROOM 1506	NONE DETECTED			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	327	ROOM 1507	NONE DETECTED			120 Sq Ft
	332	ROOM 1510	NONE DETECTED			100 Sq Ft
	336	HALLWAY 1500	NONE DETECTED	2001-1901-LE-2		150 Sq Ft
N0A	Drywall/Joint Compound 1974 Original Building					Total Amount - 15500 Sq Ft
	4	THROUGHOUT 1974 ORIGINAL BUILDING	NONE DETECTED	512-JJT-25; 2001-1901-LE-1	JJT-25: ROOM 1311, EAST WALL UNDER BASEBOARD. 2001-1901-LE-1: LIBRARY.	15500 Sq Ft
N0B	Drywall/Joint Compound Vinyl-Covered Divider Wall					Total Amount - 17800 Sq Ft
	5	THROUGHOUT 1974 ORIGINAL BUILDING	NONE DETECTED	2001-1901-LE-1	2001-1901-LE-1: HALLWAY 1500.	17800 Sq Ft
N0C	Drywall/Joint Compound 2015 Installation					Total Amount - 610 Sq Ft
	249	ART ROOM 1304	NEW			260 Sq Ft
	267	HALLWAY 1300	NEW			175 Sq Ft
	337	HALLWAY 1500	NEW			175 Sq Ft
P0B	Fire Doors Hollow Metal -1.5 Hr Rating (Underwriters Laboratories)					Total Amount - 60 Sq Ft
	19	BOILER ROOM 1212	NSM			20 Sq Ft
	23	CUSTODIAL OFFICE 1211	NSM			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0A	Carpet Adhesive Orange Berber Carpet					Total Amount - 5 Sq Ft
	217	ISOLATION ROOM CLOSET 1004A	NONE DETECTED	2001-1901-XX-24B	24B: NURSE'S OFFICE (SINCE REMOVED).	5 Sq Ft
Q0C	Carpet Adhesive Green Berber Carpet					Total Amount - 50000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	030509-MV-19, 27	19: HALLWAY OUTSIDE ROOM 1102/1103. 27: HALLWAY BY ROOM 1004.	50000 Sq Ft
ROA	Baseboard/Mopboard Adhesive 4' White Baseboard					Total Amount - 2000 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-XX-25B		2000 Sq Ft
ROB	Baseboard/Mopboard Adhesive 4" Brown Baseboard					Total Amount - 1000 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED	030509-MV-28	28: HALLWAY BY ROOM 1206.	1000 Sq Ft
ROC	Baseboard/Mopboard Adhesive 4" Blue Baseboard (2009)					Total Amount - 35 Sq Ft
	38	THEATER STORAGE 1108	NEW			15 Sq Ft
	43	CAFETERIA 1101	NEW			20 Sq Ft
ROD	Baseboard/Mopboard Adhesive 6" White Baseboard					Total Amount - 33 Sq Ft
	89	ROOM 1103	NONE DETECTED			5 Sq Ft
	96	ROOM 1104	NONE DETECTED	072215BV-02	BV-02: ROOM 1105.	20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	100	ROOM 1105	NONE DETECTED			8 Sq Ft
R0E	Baseboard/Mopboard Adhesive 6" Black Baseboard (20xx)					Total Amount - 5 Sq Ft
	103	MAIN ENTRY HALLWAY	NEW			5 Sq Ft
R0F	Baseboard/Mopboard Adhesive 4" Black (2023)					Total Amount - 115 Sq Ft
	69	HALLWAY 1200 BY GYMNASIUM	NEW			15 Sq Ft
	72	GYMNASIUM 1201	NEW			100 Sq Ft
U0A	Light Pad Insulation Round Fixture					Total Amount - 3 Sq Ft
	82	ROOM 1102 RESTROOM	ASSUMED			1 Sq Ft
	92	ROOM 1103 RESTROOM	ASSUMED			1 Sq Ft
	225	NURSE'S RESTROOM 1006A	ASSUMED			1 Sq Ft
V0A	Sink Undercoating Pink (1974)					Total Amount - 20 Sq Ft
	80	ROOM 1102	5 CH	030509-MV-29		5 Sq Ft
	90	ROOM 1103	5 CH			5 Sq Ft
	199	ROOM 1501	5 CH			5 Sq Ft
	241	STAFF LOUNGE 1301	5 CH			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
V0B	Sink Undercoating Black (2003)	Total Amount - 5 Sq Ft				
97	ROOM 1104	NONE DETECTED	030509-MV-30	5 Sq Ft		
V0C	Sink Undercoating Black (1974)	Total Amount - 45 Sq Ft				
140	2ND FLOOR HALLWAY 2000 BY NORTH RESTROOMS	5 CH	030509-MV-31	10 Sq Ft		
148	2ND FLOOR SOUTHEAST COMMONS AREA 2502	5 CH		5 Sq Ft		
175	2ND FLOOR SOUTHWEST COMMON AREA 2303	5 CH		5 Sq Ft		
253	ART ROOM 1304	5 CH		15 Sq Ft		
261	KILN ROOM 1304A	5 CH		5 Sq Ft		
312	HALL BY ROOM 1504	5 CH		5 Sq Ft		
V0D	Sink Undercoating Gray	Total Amount - 5 Sq Ft				
277	ROOM 1214A	ASSUMED		5 Sq Ft		
X0A	Miscellaneous Material Light Red Countertop	Total Amount - 100 Sq Ft				
81	ROOM 1102	NONE DETECTED		10 Sq Ft		
91	ROOM 1103	NONE DETECTED	512-JJT-44	JJT-44: NORTHEAST CORNER OF NORTH SIDE.	40 Sq Ft	
149	2ND FLOOR SOUTHEAST COMMONS AREA 2502	NONE DETECTED		20 Sq Ft		

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	201	ROOM 1501	NONE DETECTED			10 Sq Ft
	254	ART ROOM 1304	NONE DETECTED			10 Sq Ft
	313	HALL BY ROOM 1504	NONE DETECTED			10 Sq Ft
X0B	Miscellaneous Material Chalkboard Adhesive					Total Amount - 160 Sq Ft
	113	ROOM 2004	ASSUMED			20 Sq Ft
	120	ROOM 2007	ASSUMED			20 Sq Ft
	123	ROOM 2009	ASSUMED			20 Sq Ft
	157	ROOM 2504	ASSUMED			10 Sq Ft
	165	ROOM 2501	ASSUMED			10 Sq Ft
	185	ROOM 2302	ASSUMED			20 Sq Ft
	193	ROOM 2305	ASSUMED			20 Sq Ft
	324	ROOM 1506	ASSUMED			20 Sq Ft
	330	ROOM 1507	ASSUMED			20 Sq Ft
X0C	Miscellaneous Material Purple Spotted Countertop					Total Amount - 70 Sq Ft
	141	2ND FLOOR HALLWAY 2000 BY NORTH RESTROOMS	NONE DETECTED	512-JJT-4		50 Sq Ft
	176	2ND FLOOR SOUTHWEST COMMON AREA 2303	NONE DETECTED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0D	Miscellaneous Material Yellow Countertop					Total Amount - 75 Sq Ft
	230	MAIN OFFICE 1002	NONE DETECTED	512-JJT-18	JJT-18: EAST SIDE IN VERTICAL CORNER.	60 Sq Ft
	262	KILN ROOM 1304A	NONE DETECTED			15 Sq Ft
X0E	Miscellaneous Material Butterscotch Countertop					Total Amount - 10 Sq Ft
	242	STAFF LOUNGE 1301	NONE DETECTED	512-JJT-19	JJT-19: WEST SIDE, VERTICAL.	10 Sq Ft
X0F	Miscellaneous Material White w/Tan Countertop					Total Amount - 20 Sq Ft
	255	ART ROOM 1304	NONE DETECTED	512-JJT-21	JJT-21: EAST SIDE SOUTH CORNER VERTICAL.	20 Sq Ft
X0G	Miscellaneous Material Wire Window Glaze					Total Amount - 5 Sq Ft
	109	NORTHEAST STAIRWELL 2099A	NONE DETECTED	030509-MV-32		5 Sq Ft
X0H	Miscellaneous Material Corkboard Adhesive (1974)					Total Amount - 1000 Sq Ft
	6	THROUGHOUT 1974 ORIGINAL BUILDING	ASSUMED			1000 Sq Ft
X0I	Miscellaneous Material Built-Up Gray Rubber Floor					Total Amount - 1500 Sq Ft
	311	ROOM 1502	NSM			1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOK	Miscellaneous Material Stainless Steel Counter Undercoating					Total Amount - 32 Sq Ft
	34	KITCHEN DISHWASHING 1107	ASSUMED			32 Sq Ft
XOL	Miscellaneous Material Dark Gray Countertop					Total Amount - 10 Sq Ft
	236	MAIN OFFICE WORK ROOM 1007	ASSUMED			10 Sq Ft
XOM	Miscellaneous Material Brown Marble-Look Countertop					Total Amount - 10 Sq Ft
	278	ROOM 1214A	ASSUMED			10 Sq Ft
XON	Miscellaneous Material Metal Frame Whiteboard Adhesive					Total Amount - 500 Sq Ft
	7	THROUGHOUT 1974 ORIGINAL BUILDING	NEW			500 Sq Ft
X1A	Miscellaneous Material 6" Brown Quarry Tile					Total Amount - 2200 Sq Ft
	8	THROUGHOUT 1974 ORIGINAL BUILDING	ASSUMED			2200 Sq Ft
X1B	Miscellaneous Material 2" White Ceramic Floor Tile System (20XX)					Total Amount - 52 Sq Ft
	83	ROOM 1102 RESTROOM	NEW			20 Sq Ft
	93	ROOM 1103 RESTROOM	NEW			20 Sq Ft
	200	ROOM 1501	NEW			12 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1C	Miscellaneous Material 2" Gray Ceramic Floor Tile System (1999)					Total Amount - 300 Sq Ft
	343	THROUGHOUT 1999 ADDITION	NEW			300 Sq Ft
X1D	Miscellaneous Material 4" White Ceramic Wall Tile System (1999)					Total Amount - 500 Sq Ft
	344	THROUGHOUT 1999 ADDITION	NEW			500 Sq Ft