

1505 Hoyt Avenue East, St. Paul, MN 55106

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4B	Mudded Pipe Joints on Fiberglass Insulation 1966 Addition					Total Amount - 9 Joints
	52	1966 ADDITION HALLWAY (1300)	8 CH	050509-MV-07, 08	MV-07: OUTSIDE ROOM 1321 W/CANVAS WRAP.	1 Joints
	54	ROOM 1321	8 CH			6 Joints
	63	1966 ADDITION CUSTODIAL ROOM 1359	8 CH			2 Joints
H1A	Sprayed-On Structural Fireproofing Fluffy, Gray Cellulose (2000)					Total Amount - 20050 Sq Ft
	49	ROOM 1317 SPRINKLER ROOM;	NONE DETECTED			50 Sq Ft
	125	THROUGHOUT 2000 ADDITIONS	NONE DETECTED	070920-BF-7, 8, 9, 10, 11, 12; 050509-MV-12	BF-7: ROOM 1302. BF-8: ROOM 1111. BF-9: ROOM 1115. BF-10: ROOM 1105. BF-11: HALL BY 147. BF-12: HALL BY DOOR 5. MV-12: CUSTODIAL ROOM.	20000 Sq Ft
I1B	1' x 1' Acoustical Ceiling Tile Flat Glacial Spline (1966)					Total Amount - 1460 Sq Ft
	55	ROOM 1321	NONE DETECTED	206Z-2A	2A: OUTSIDE ROOM 1351 (SINCE REMOVED).	860 Sq Ft
	62	1966 ADDITION HALLWAY (1351 - 1361)	NONE DETECTED	450Q-A1		600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2D	2' x 2' Acoustical Ceiling Tile Pockmarks with Pin Holes (2016)					Total Amount - 4000 Sq Ft
	105	THROUGHOUT 1990 ADDITION	NONE DETECTED	092221-BF-2	BF-2: THROUGHOUT 1990 ADDITION.	4000 Sq Ft
I2E	2' x 2' Acoustical Ceiling Tile Pockmarks with Pin Holes (2021)					Total Amount - 10000 Sq Ft
	2	THROUGHOUT BUILDING	NEW			10000 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Pockmarks with Pin Holes (2020)					Total Amount - 33250 Sq Ft
	22	ROOM 1301	NEW			900 Sq Ft
	25	ROOM 1303	NEW			900 Sq Ft
	28	ROOM 1307	NEW			400 Sq Ft
	31	ROOM 1309	NEW			900 Sq Ft
	34	ROOM 1310	NEW			900 Sq Ft
	37	ROOM 1311	NEW			900 Sq Ft
	40	ROOM 1313	NEW			900 Sq Ft
	45	ROOM 1315	NEW			900 Sq Ft
	56	ROOM 1321	NEW			400 Sq Ft
	58	ROOM 1324	NEW			900 Sq Ft
	60	ROOM 1323	NEW			900 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	65	ROOM 1352	NEW			250 Sq Ft
	67	ROOM 1355	NEW			250 Sq Ft
	74	ROOM 1227	NEW			900 Sq Ft
	75	ROOM 1224	NEW			900 Sq Ft
	78	ROOM 1225	NEW			900 Sq Ft
	80	ROOM 1222	NEW			900 Sq Ft
	82	ROOM 1221	NEW			900 Sq Ft
	84	ROOM 1220	NEW			450 Sq Ft
	88	ROOM 1215	NEW			900 Sq Ft
	90	ROOM 1213	NEW			900 Sq Ft
	92	ROOM 1210	NEW			900 Sq Ft
	94	ROOM 1211	NEW			900 Sq Ft
	96	ROOM 1209	NEW			900 Sq Ft
	98	ROOM 1207	NEW			900 Sq Ft
	100	ROOM 1205	NEW			450 Sq Ft
	102	ROOM 1201	NEW			450 Sq Ft
	114	ROOM 1123	NEW			450 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	116	ROOM 1121	NEW			450 Sq Ft
	118	ROOM 1121	NEW			700 Sq Ft
	120	ROOM 1114	NEW			250 Sq Ft
	122	ROOM 1104	NEW			300 Sq Ft
	124	ROOM 1102	NEW			250 Sq Ft
	132	2000 ADDITION ROOM 1401	NEW			900 Sq Ft
	134	2000 ADDITION ROOM 1402	NEW			600 Sq Ft
	137	ROOM 1113	NEW			700 Sq Ft
	138	THROUGHOUT 2020 ADDITION CLASSROOMS (1500)	NEW			8000 Sq Ft
I3E	2' x 4' Ceiling Tile Dents & Pin Holes (200X)		Total Amount - 16000 Sq Ft			
	126	THROUGHOUT 2000 ADDITIONS	NONE DETECTED	050509-MV-14	MV-14: HALLWAY BY ROOM 1406.	16000 Sq Ft
J3C	Miscellaneous Cementitious Material Black Window Sills (1990)		Total Amount - 24 Sq Ft			
	106	THROUGHOUT 1990 ADDITION	NONE DETECTED	050509-MV-17	MV-17: ROOM 1121.	24 Sq Ft
J3D	Miscellaneous Cementitious Material Black Window Sills (1966)		Total Amount - 6 Sq Ft			
	72	1966 ADDITION HALLWAY (1200)	NONE DETECTED	050509-MV-18	MV-18: EAST LINK.	6 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3E	Miscellaneous Flooring 2' X 2' Gray Rubberized Floor Tile (2020)					Total Amount - 35790 Sq Ft
	23	ROOM 1301	NEW			900 Sq Ft
	26	ROOM 1303	NEW			900 Sq Ft
	29	ROOM 1307	NEW			400 Sq Ft
	32	ROOM 1309	NEW			900 Sq Ft
	35	ROOM 1310	NEW			900 Sq Ft
	38	ROOM 1311	NEW			900 Sq Ft
	41	ROOM 1313	NEW			900 Sq Ft
	46	ROOM 1315	NEW			900 Sq Ft
	53	ROOM 1322	NEW			440 Sq Ft
	57	ROOM 1321	NEW			400 Sq Ft
	59	ROOM 1324	NEW			900 Sq Ft
	61	ROOM 1323	NEW			900 Sq Ft
	66	ROOM 1352	NEW			250 Sq Ft
	68	ROOM 1355	NEW			250 Sq Ft
	73	ROOM 1227	NEW			900 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	79	ROOM 1225	NEW			900 Sq Ft
	81	ROOM 1222	NEW			900 Sq Ft
	83	ROOM 1221	NEW			900 Sq Ft
	85	ROOM 1220	NEW			450 Sq Ft
	89	ROOM 1215	NEW			900 Sq Ft
	91	ROOM 1213	NEW			900 Sq Ft
	93	ROOM 1210	NEW			900 Sq Ft
	95	ROOM 1211	NEW			900 Sq Ft
	97	ROOM 1209	NEW			900 Sq Ft
	99	ROOM 1207	NEW			900 Sq Ft
	101	ROOM 1205	NEW			450 Sq Ft
	103	ROOM 1201	NEW			450 Sq Ft
	113	ROOM 1123	NEW			450 Sq Ft
	115	ROOM 1121	NEW			450 Sq Ft
	117	ROOM 1121	NEW			700 Sq Ft
	119	ROOM 1114	NEW			250 Sq Ft
	121	ROOM 1104	NEW			300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	123	ROOM 1102	NEW			250 Sq Ft
	133	2000 ADDITION ROOM 1401	NEW			900 Sq Ft
	135	2000 ADDITION ROOM 1402	NEW			600 Sq Ft
	136	ROOM 1113	NEW			700 Sq Ft
	139	THROUGHOUT 2020 ADDITION CLASSROOMS (1500)	NEW			6000 Sq Ft
	144	2020 ADDITION CAFETERIA	NEW			5000 Sq Ft
K3F	Miscellaneous Flooring Rolled Rubberized Floor Adhesive					Total Amount - 5000 Sq Ft
	143	2020 ADDITION GYMNASIUM 0101	NEW			5000 Sq Ft
LOA	Flexible Duct Connector Coarse White					Total Amount - 2 Sq Ft
	71	ROOM 1351	ASSUMED			2 Sq Ft
M0A	Plaster 1964 Original Building					Total Amount - 3000 Sq Ft
	16	THROUGHOUT 1964 ORIGINAL BUILDING	NONE DETECTED	050509-MV-01, 02, 03; 2001-01121-3B; 2001-1501-FL-06	MV-01: ROOM 1203 (FIREBREAK). MV-02: ROOM 1209 (FIREBREAK). MV-03: ROOM 1311 (FIREBREAK). ; 3B: EAST RESTROOM HALLWAY.; FL-06: ROOM 1308	3000 Sq Ft
M0AA	Plaster Plaster Sheets above Windows (1964)					Total Amount - 100 Sq Ft
	17	THROUGHOUT 1964 ORIGINAL BUILDING	NONE DETECTED	062221-BF-1	BF-1: OLD MAIN OFFICE.	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
M0B	Plaster 1966 Addition	Total Amount - 85 Sq Ft				
69	1966 ADDITION STORAGE 1353	NONE DETECTED	050509-MV-04	MV-04: 1966 ADDITION GIRLS' RESTROOM 1357 (SINCE REMOVED).	85 Sq Ft	
M0E	Plaster Exterior Overhangs	Total Amount - 200 Sq Ft				
7	THROUGHOUT BUILDING EXTERIOR	NONE DETECTED	063020-BF-12	BF-12: EXTERIOR BUILDING.	200 Sq Ft	
N0C	Drywall/Joint Compound 1973 Addition	Total Amount - 50 Sq Ft				
48	ROOM 1317 SPRINKLER ROOM	NONE DETECTED	509P4, 2001-1501-FL-01	FL-01: STORAGE ROOM BY HALLWAY TO REC CENTER.	50 Sq Ft	
N0F	Drywall/Joint Compound 2021 Installation	Total Amount - 10000 Sq Ft				
1	THROUGHOUT BUILDING	NEW			10000 Sq Ft	
Q0B	Carpet Adhesive Berber Carpet (2000)	Total Amount - 10000 Sq Ft				
127	THROUGHOUT 2000 ADDITIONS	NONE DETECTED	050509-MV-27	MV-27: ROOM 1401.	10000 Sq Ft	
Q0G	Carpet Adhesive Green w/Light Green Lines (2022)	Total Amount - 1500 Sq Ft				
104	ROOM 1101 (IMC)	NEW			1500 Sq Ft	
Q0H	Carpet Adhesive Black, Blue and Yellow Streaks	Total Amount - 900 Sq Ft				
76	ROOM 1224	NEW			900 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROA	Baseboard/Mopboard Adhesive Brown Baseboard					Total Amount - 500 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED	121021ML-35; 050509-MV-28	ML-35: REC CENTER HALLWAY 1500 (SINCE REMOVED). MV-28: HALLWAY OUTSIDE MAIN OFFICE.	500 Sq Ft
ROB	Baseboard/Mopboard Adhesive Gray Baseboard					Total Amount - 500 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	050509-MV-29	MV-29: ROOM 1213. BOTH TAN & BROWN ADHESIVES ANALYZED.	500 Sq Ft
ROC	Baseboard/Mopboard Adhesive Black Baseboard (2000)					Total Amount - 1000 Sq Ft
	128	THROUGHOUT 2000 ADDITIONS	NONE DETECTED	050509-MV-30	ROOM 1415.	1000 Sq Ft
ROE	Baseboard/Mopboard Adhesive 4" Dark Brown					Total Amount - 500 Sq Ft
	140	THROUGHOUT 2020 ADDITION CLASSROOMS (1500)	NONE DETECTED	121021ML-36	ML-36: CUSTODIAL OFFICE (SINCE REMOVED).	500 Sq Ft
VOC	Sink Undercoating Rough, Gray (2000)					Total Amount - 30 Sq Ft
	129	THROUGHOUT 2000 ADDITIONS	NONE DETECTED	050509-MV-34	MV-34: ROOM 1402.	30 Sq Ft
VOG	Sink Undercoating Black (2020)					Total Amount - 35 Sq Ft
	24	ROOM 1301	NEW			5 Sq Ft
	27	ROOM 1303	NEW			5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	30	ROOM 1307	NEW			5 Sq Ft
	33	ROOM 1309	NEW			5 Sq Ft
	36	ROOM 1310	NEW			5 Sq Ft
	39	ROOM 1311	NEW			5 Sq Ft
	42	ROOM 1313	NEW			5 Sq Ft
X0AA	Miscellaneous Material Vermiculite (1973)					Total Amount - 6500 Sq Ft
	47	THROUGHOUT 1973 ADDITION BUILDING	<1 ACT	121021ML-43, 44, 45	ML-43: ROOM 1508. ML-44: ROOM 1506. ML-45: GYMNASIUM 1504.	6500 Sq Ft
X0F	Miscellaneous Material Chalkboard Adhesive (1966)					Total Amount - 15 Sq Ft
	77	ROOM 1224	ASSUMED			15 Sq Ft
X0G	Miscellaneous Material Tackboard Adhesive (1966)					Total Amount - 140 Sq Ft
	51	THROUGHOUT 1966 ADDITION	ASSUMED			140 Sq Ft
X0I	Miscellaneous Material Metal Frame Chalkboard/Tackboard Adhesive (1990)					Total Amount - 100 Sq Ft
	107	THROUGHOUT 1990 ADDITION	NONE DETECTED	070920-BF-3; 062421-BF-1, 3	BF-3: ROOM 1103. 062421-BF-1: ROOM 1257 (SINCE REMOVED). 062421-BF-3: ROOM 1251 (SINCE REMOVED).	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0J	Miscellaneous Material Whiteboard/Tackboard Adhesive (2000)					Total Amount - 100 Sq Ft
	130	THROUGHOUT 2000 ADDITIONS	NONE DETECTED	070920-BF-2	BF-2: ROOM 1105.	100 Sq Ft
X0K	Miscellaneous Material Gray Cloth Board Adhesive (2000)					Total Amount - 100 Sq Ft
	131	THROUGHOUT 2000 ADDITIONS	NONE DETECTED	070920-BF-1	BF-1: ROOM 1105.	100 Sq Ft
X0L	Miscellaneous Material Interior/Exterior Window Caulk					Total Amount - 100 Sq Ft
	19	THROUGHOUT 1964 ORIGINAL BUILDING	NONE DETECTED	063020-BF-6, 7	BF-6,7: ROOM 1303.	100 Sq Ft
X0M	Miscellaneous Material Interior Window Caulk					Total Amount - 10 Sq Ft
	108	THROUGHOUT 1990 ADDITION	NONE DETECTED	063020-BF-9	BF-9: ROOM 1101.	10 Sq Ft
X0N	Miscellaneous Material Interior Window Sill Caulk					Total Amount - 10 Sq Ft
	109	THROUGHOUT 1990 ADDITION	NONE DETECTED	063020-BF-10	BF-10: ROOM 1101.	10 Sq Ft
X0O	Miscellaneous Material Caulk around Brick and below Windows					Total Amount - 10 Sq Ft
	110	THROUGHOUT EXTERIOR 1990 ADDITION	NONE DETECTED	063020-BF-11	BF-11: ROOM 1101.	10 Sq Ft
X0P	Miscellaneous Material Brick Mortar					Total Amount - 1000 Sq Ft
	6	THROUGHOUT BUILDING EXTERIOR	NONE DETECTED	063020-BF-13	BF-13: EXTERIOR BUILDING	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0Q	Miscellaneous Material Louver Caulk					Total Amount - 10 Sq Ft
8	THROUGHOUT BUILDING EXTERIOR	NONE DETECTED	063020-BF-14	THROUGHOUT BUILDING EXTERIOR	10 Sq Ft	
X0R	Miscellaneous Material Exterior Door Caulk					Total Amount - 10 Sq Ft
9	THROUGHOUT BUILDING EXTERIOR	NONE DETECTED	063020-BF-15	BF-16: DOOR 16.	10 Sq Ft	
X0RR	Miscellaneous Material Damp Proofing (1966)					Total Amount - 2000 Sq Ft
50	THROUGHOUT 1966 ADDITION	8 CH	121021ML-62	ML-62: 1966 TUNNEL.	2000 Sq Ft	
X0S	Miscellaneous Material Expansion Joint Caulk					Total Amount - 20 Sq Ft
10	THROUGHOUT BUILDING EXTERIOR	NONE DETECTED	063020-BF-16	BF-16: EXTERIOR BUILDING.	20 Sq Ft	
X0SS	Miscellaneous Material Black Damp Proofing (1964)					Total Amount - 4000 Sq Ft
20	THROUGHOUT 1964 ORIGINAL BUILDING	ASSUMED			4000 Sq Ft	
X0T	Miscellaneous Material Flange Gasket					Total Amount - 100 Sq Ft
18	THROUGHOUT 1964 ORIGINAL BUILDING	50 CH	052121-BF-5	BF-5: BOILER ROOM.	100 Sq Ft	
X0Z	Miscellaneous Material Red Fire Stop					Total Amount - 100 Sq Ft
5	THROUGHOUT BUILDING	NONE DETECTED	121021ML-42	ML-42: CAFETERIA.	100 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1AA	Miscellaneous Material 6" X 6" White Ceramic Wall Tile System (2020)					Total Amount - 6700 Sq Ft
	44	RESTROOM AREA OUTSIDE ROOM 1311	NEW			1600 Sq Ft
	87	RESTROOM AREA OUTSIDE ROOM 1215	NEW			1600 Sq Ft
	112	RESTROOM AREA OUTSIDE ROOM 1123	NEW			3500 Sq Ft
X1B	Miscellaneous Material 1" X 2" Salmon Exterior Ceramic Tile System					Total Amount - 420 Sq Ft
	21	THROUGHOUT 1964 ORIGINAL BUILDING EXTERIOR	<1 CH (GROUT), NONE DETECTED (TILE & CAULK)	063020-BF-8	BF-8: ROOM 1303.	420 Sq Ft
X1C	Miscellaneous Material 1" X 2" Yellow/Blue Ceramic Wall Tile System					Total Amount - 300 Sq Ft
	70	1966 ADDITION STORAGE 1353	<1 CH (SETTING BED), NONE DETECTED (TILE AND GROUT)	052121-BF-1; 040721-BF-1	052121-BF-1: CUSTODIAL 1304 (SINCE REMOVED). 040721-BF-1: GIRLS RESTROOM NEAR ROOM 1313 (SINCE REMOVED).	300 Sq Ft
X1H	Miscellaneous Material 4" X 4" Beige Ceramic Wall Tile System (2020)					Total Amount - 700 Sq Ft
	141	THROUGHOUT 2020 ADDITION CLASSROOMS RESTROOM (1500)	NEW			700 Sq Ft
X1I	Miscellaneous Material 2" X 2" Beige w/White Specks Ceramic Floor Tile System (2020)					Total Amount - 2520 Sq Ft
	43	RESTROOM AREA OUTSIDE ROOM 1311	NEW			400 Sq Ft
	86	RESTROOM AREA OUTSIDE ROOM 1215	NEW			400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	111	RESTROOM AREA OUTSIDE ROOM 1123	NEW			1000 Sq Ft
	142	THROUGHOUT 2020 ADDITION CLASSROOMS RESTROOM (1500)	NEW			720 Sq Ft
X1J	Miscellaneous Material 1" X 2" Blue Ceramic Wall Tile System (2020)					Total Amount - 400 Sq Ft
	64	1966 ADDITION CUSTODIAL ROOM 1359	NEW			400 Sq Ft
Z0A	Miscellaneous Material Roof Membrane					Total Amount - 20000 Sq Ft
	11	THROUGHOUT BUILDING ROOF	NONE DETECTED	063020-BF-1	BF-1: THROUGHOUT BUILDING ROOF.	20000 Sq Ft
Z0B	Miscellaneous Material Roof Perimeter Flashing					Total Amount - 1000 Sq Ft
	12	THROUGHOUT BUILDING ROOF	NONE DETECTED	063020-BF-2	BF-2: THROUGHOUT BUILDING ROOF.	1000 Sq Ft
Z0C	Miscellaneous Material Bituminous Roof Patch					Total Amount - 50 Sq Ft
	13	THROUGHOUT BUILDING ROOF	NONE DETECTED	063020-BF-3	BF-3: THROUGHOUT BUILDING ROOF.	50 Sq Ft
Z0D	Miscellaneous Material Gray Roof Flashing Caulk					Total Amount - 10 Sq Ft
	14	THROUGHOUT BUILDING ROOF	NONE DETECTED	063020-BF-4	BF-4: THROUGHOUT BUILDING ROOF.	10 Sq Ft
Z0E	Miscellaneous Material Tan Roof Overhang Caulk					Total Amount - 10 Sq Ft
	15	THROUGHOUT BUILDING ROOF	NONE DETECTED	063020-BF-5	BF-5: THROUGHOUT BUILDING ROOF.	10 Sq Ft