

1780 Seventh Street West, Saint Paul, MN 55116

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D1A	Boiler Gaskets Burner Gaskets					Total Amount - 5 Sq Ft
	15	BOILER ROOM 2105	NONE DETECTED	091812MV-01	MV-01: BOILER #2.	5 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Light Texture w/Pin Holes					Total Amount - 20000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	091812MV-07, 16	MV-07: ROOM 1001. MV-16: ROOM 2302.	20000 Sq Ft
I3A	2' x 4' Ceiling Tile Vinyl-Coated Gypsum					Total Amount - 450 Sq Ft
	25	KITCHEN 1107	NSM			450 Sq Ft
I3B	2' x 4' Ceiling Tile Gouges & Pin Holes w/Revealed Edges -2'x2' Look					Total Amount - 900 Sq Ft
	20	ROOM 2310	NONE DETECTED	091812MV-20	MV-20: ROOM 2310.	900 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown & White Smears					Total Amount - 1000 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	091812MV-08	MV-08: ROOM 1005.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2B	12" x 12" Vinyl Floor Tile & Mastic Gray w/Black Smears					Total Amount - 2000 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED	091812MV-10	MV-10: ROOM 2102.	2000 Sq Ft
K2C	12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown and White Streaks					Total Amount - 500 Sq Ft
	23	STAIRWELL B	NEW			150 Sq Ft
	24	FRONT ENTRY AND ELEVATOR LOBBY	NEW			300 Sq Ft
	29	ROOM 1106	NEW			50 Sq Ft
K3A	Miscellaneous Flooring 2' X 2' Tan w/Gray & Brown Specks (2012)					Total Amount - 850 Sq Ft
	31	ROOM 1201	NEW			850 Sq Ft
N0A	Drywall/Joint Compound 1966 Original Building					Total Amount - 20000 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	091812MV-03	MV-03: BOILER ROOM.	20000 Sq Ft
Q0A	Carpet Adhesive Blue/Gray Berber Carpet					Total Amount - 15000 Sq Ft
	5	THROUGHOUT BUILDING	NONE DETECTED	091812MV-12	MV-12: ROOM 2202.	15000 Sq Ft
Q0B	Carpet Adhesive Tan Berber Carpet					Total Amount - 900 Sq Ft
	21	ROOM 2310	NONE DETECTED	091812MV-17	MV-17: ROOM 2310.	900 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROA	Baseboard/Mopboard Adhesive 4" Maroon Baseboard					Total Amount - 450 Sq Ft
	6	THROUGHOUT BUILDING	NONE DETECTED	091812MV-09	MV-09: ROOM 1005.	450 Sq Ft
ROB	Baseboard/Mopboard Adhesive 4" Gray Baseboard					Total Amount - 100 Sq Ft
	7	THROUGHOUT BUILDING	NONE DETECTED	091812MV-11	MV-11: ROOM 2102.	100 Sq Ft
ROC	Baseboard/Mopboard Adhesive 6" Maroon Baseboard					Total Amount - 50 Sq Ft
	12	THROUGHOUT FIRST FLOOR HALLWAY	NEW			50 Sq Ft
VOA	Sink Undercoating Gray					Total Amount - 11 Sq Ft
	17	ROOM 2205	NONE DETECTED	091812MV-14	MV-14: ROOM 2205.	5 Sq Ft
	22	ROOM 2408	NONE DETECTED			6 Sq Ft
VOB	Sink Undercoating Cream					Total Amount - 6 Sq Ft
	28	ROOM 1106	NONE DETECTED			6 Sq Ft
VOC	Sink Undercoating Black (201x)					Total Amount - 20 Sq Ft
	30	ROOM 1201	NEW			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1A	1' x 1' Ceiling Tile Adhesive Green Ceiling Tile Pucks					Total Amount - 110 Sq Ft
	18	ROOMS 2203, 2204 & 2220	NONE DETECTED	091812MV-13	MV-13: ROOM 2204.	110 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Brown Ceiling Tile Pucks					Total Amount - 150 Sq Ft
	19	ROOMS 2301, 2302 & 2310	NONE DETECTED	091812MV-15	MV-15: ROOM 2301.	150 Sq Ft
X0A	Miscellaneous Material Red Seam Caulk on Stack					Total Amount - 5 Sq Ft
	16	BOILER ROOM 2105	NONE DETECTED	091812MV-02	MV-02: BOILER #2 STACK.	5 Sq Ft
X0B	Miscellaneous Material Gray Duct Caulk					Total Amount - 100 Sq Ft
	8	THROUGHOUT BUILDING	NONE DETECTED	091812MV-04	MV-04: BOILER ROOM.	100 Sq Ft
X0C	Miscellaneous Material Red Fire Stop					Total Amount - 50 Sq Ft
	9	THROUGHOUT BUILDING	NONE DETECTED	091812MV-05	MV-05: BOILER ROOM.	50 Sq Ft
X0D	Miscellaneous Material Pink Fire Stop					Total Amount - 50 Sq Ft
	10	THROUGHOUT BUILDING	NONE DETECTED	091812MV-06	MV-06: BOILER ROOM.	50 Sq Ft
X0E	Miscellaneous Material Black Styrofoam Wall Panel Adhesive					Total Amount - 60 Sq Ft
	32	ROOM 1205	5 CH	091812MV-19	MV-19: ROOM 1205.	60 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0F	Miscellaneous Material Vermiculite					Total Amount - 5000 Sq Ft
	11	THROUGHOUT BUILDING	<1 ACT	091613MA-01	MA-01: OFFICE 1105.	5000 Sq Ft
X0G	Miscellaneous Material White Milkboard (2013)					Total Amount - 150 Sq Ft
	27	KITCHEN 1107	NEW			150 Sq Ft
X1A	Miscellaneous Material 2" X 2" Gray with White Specks Ceramic Floor Tile System					Total Amount - 1200 Sq Ft
	13	THROUGHOUT BUILDING RESTROOMS	ASSUMED			1200 Sq Ft
X1B	Miscellaneous Material 4" X 4" White Ceramic Wall Tile System					Total Amount - 2400 Sq Ft
	14	THROUGHOUT BUILDING RESTROOMS	ASSUMED			2400 Sq Ft
X1C	Miscellaneous Material 6" X 6" Red Quarry Tile System					Total Amount - 450 Sq Ft
	26	KITCHEN 1107	ASSUMED			450 Sq Ft