

Hamline Elementary School

Inspection Date: 8/13/2024

1599 Englewood Avenue, Saint Paul, MN 55104

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2A	Mudded Pipe Joints on Millboard Insulation 1953 Original Building					Total Amount - 20 Joints
	199	ROOM 1101 PIPE CHASE	ASSUMED			20 Joints
A4A	Mudded Pipe Joints on Fiberglass Insulation 1974 Addition/Installation					Total Amount - 215 Joints
	9	ROOM 2201	NONE DETECTED	092810MV-1	MV-1: ROOM 2201.	1 Joints
	14	ROOM 2202	NONE DETECTED			1 Joints
	37	HALLWAY 2200	NONE DETECTED			11 Joints
	41	ROOM 2211	NONE DETECTED			1 Joints
	73	ROOM 2221	NONE DETECTED			1 Joints
	78	ROOM 2222	NONE DETECTED			1 Joints
	85	ROOM 1217	NONE DETECTED	482-JJT-2	JJT-2: WEST SIDE ABOVE SPEAKER.	3 Joints
	93	ROOM 1217 RESTROOM	NONE DETECTED			1 Joints
	95	ROOM 1217 STORAGE	NONE DETECTED			6 Joints
	98	ROOM 1216	NONE DETECTED			5 Joints

Hamline Elementary School

Page 1 of 31

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	106	ROOM 1216 RESTROOM	NONE DETECTED			3 Joints
	108	ROOM 1216 STORAGE	NONE DETECTED			5 Joints
	111	ROOM 1214	NONE DETECTED			3 Joints
	118	ROOM 1214A	NONE DETECTED			3 Joints
	124	ROOM 1213	NONE DETECTED			5 Joints
	133	1ST FLOOR HALLWAY 1200	NONE DETECTED	092810MV-2	MV-2: HALLWAY BY ROOM 1214.	38 Joints
	143	ROOM 1205	NONE DETECTED	482-JJT-5	JJT-5: ROOM 1205 ABOVE & SOUTH OF SINK.	4 Joints
	149	ROOM 1206	NONE DETECTED			8 Joints
	155	ROOM 1203	NONE DETECTED			9 Joints
	161	ROOM 1204	NONE DETECTED			11 Joints
	167	ROOM 1201	NONE DETECTED			1 Joints
	173	ROOM 1202	NONE DETECTED			1 Joints
	179	HALLWAY 1220	NONE DETECTED			1 Joints
	319	HALLWAY 1300	NONE DETECTED			2 Joints
	323	FAN ROOM 1302	NONE DETECTED	482-JJT-32	JJT-32: SOUTH SIDE ACROSS FROM STAIRS.	32 Joints
	325	1974 ADDITION LOCKER ROOMS (1304/1305)	NONE DETECTED			10 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	329	1974 ADDITION GYMNASIUM (1307)	NONE DETECTED			3 Joints
	332	1974 ADDITION GYMNASIUM STORAGE 1306	NONE DETECTED			25 Joints
	333	1974 ADDITION GYMNASIUM STORAGE 1308	NONE DETECTED	092810MV-3	MV-3: STORAGE ROOM 1306.	20 Joints
A4B	Mudded Pipe Joints on Fiberglass Insulation 1953 Original Building					Total Amount - 10 Joints
	254	KITCHEN (1123)	NONE DETECTED	092810MV-4	MV-4: KITCHEN 1123.	4 Joints
	257	KITCHEN RECEIVING (1130)	NONE DETECTED	092810MV-5	MV-5: RECEIVING 1130.	2 Joints
	261	HALLWAY 1012C	NONE DETECTED	092810MV-6	MV-6: NORTH ENTRY 1012C.	4 Joints
B2A	Millboard Pipe Insulation 1953 Original Building					Total Amount - 15 Lin Ft
	198	ROOM 1101 PIPE CHASE	10 CH	2001-1501-AF-4, 5, 6		15 Lin Ft
B3A	Pre-Formed Pipe Insulation 1953 Original Building					Total Amount - 4 Lin Ft
	200	ROOM 1101 PIPE CHASE	20 CH, 40 AM	206-U1-A		4 Lin Ft
D1A	Boiler Gaskets					Total Amount - 6 Sq Ft
	265	BOILER ROOM (1110)	40 CH	092810MV-7	MV-7: BOILER ROOM.	6 Sq Ft
D2A	Interior Boiler Insulation Interior Refractory					Total Amount - 100 Sq Ft
	267	BOILER ROOM (1110)	ASSUMED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D2B	Interior Boiler Insulation Burner Refractory					Total Amount - 10 Sq Ft
	268	BOILER ROOM (1110)	ASSUMED			10 Sq Ft
G1A	Sprayed-On Acoustical Finish White					Total Amount - 600 Sq Ft
	340	RECREATION CENTER MEETING ROOM (1506)	NONE DETECTED	482-JJT-36, 37, 38; 509-S9, 10, 11, 12, 13	JJT-36: ABOVE DOOR. JJT-37: ABOVE DRAWING BOARD. JJT-38: ABOVE.	600 Sq Ft
G1B	Sprayed-On Acoustical Finish White Fluffy (2010)					Total Amount - 2500 Sq Ft
	251	CAFETERIA (1120)	NEW			2500 Sq Ft
H1A	Sprayed-On Structural Fireproofing White					Total Amount - 800 Sq Ft
	137	CUSTODIAN'S OFFICE (1208)	NONE DETECTED	482-JJT-9, 10, 11	JJT-9: ABOVE GREEN DOOR TO TUNNELS. JJT-10: ABOVE FIRE DOOR.	600 Sq Ft
	138	1974 ADDITION TUNNELS (1208A)	NONE DETECTED	482-JJT-12, 13	JJT-12: ABOVE GREEN DOOR TO CUSTODIAL OFFICE. JJT-13: ACROSS FROM	200 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Large & Medium Holes					Total Amount - 3990 Sq Ft
	188	ROOM 1101	NONE DETECTED			170 Sq Ft
	207	HALLWAY 1100	NONE DETECTED	092810MV-44	MV-44: HALLWAY BY ROOM 1101.	2300 Sq Ft
	225	GIRLS' RESTROOM 1108	NONE DETECTED			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	228	BOYS' RESTROOM 1112	NONE DETECTED			200 Sq Ft
	245	STAGE (1120A)	NONE DETECTED			450 Sq Ft
	289	ROOM 1001	NONE DETECTED	482-JJT-23	JJT-23: ABOVE NORTH DOOR.	150 Sq Ft
	293	ROOM 1003	NONE DETECTED			150 Sq Ft
	297	ROOM 1005	NONE DETECTED			300 Sq Ft
	306	ROOM 1004 ENTRY	NONE DETECTED			70 Sq Ft
I1B	1' x 1' Acoustical Ceiling Tile Fissures					Total Amount - 680 Sq Ft
	300	PRINCIPAL'S OFFICE 1010	NONE DETECTED			200 Sq Ft
	303	ASSISTANT PRINCIPAL'S OFFICE 1008	NONE DETECTED			100 Sq Ft
	308	ROOM 1004	NONE DETECTED			200 Sq Ft
	315	STORAGE/OFFICE SOUTH OF NURSE'S OFFICE	NONE DETECTED	092810MV-45; 482-JJT-25	MV-45: OFFICE BY ROOM 1004. JJT-25: ABOVE CLOCK.	180 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Chicken Peck Design					Total Amount - 1260 Sq Ft
	362	1996 ADDITION HALLWAYS	NONE DETECTED	482-JJT-31	JJT-31: ABOVE ENTRANCE TO ROOM E-104.	1260 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Grubs w/Pin Holes (2014)					Total Amount - 400 Sq Ft
	54	LIBRARY 2110	NEW			400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3A	2' x 4' Ceiling Tile Chicken Scratch	Total Amount - 17310 Sq Ft				
	10	ROOM 2201	NONE DETECTED			675 Sq Ft
	15	ROOM 2202	NONE DETECTED			675 Sq Ft
	19	ROOM 2203	NONE DETECTED			675 Sq Ft
	23	ROOM 2204	NONE DETECTED			675 Sq Ft
	27	ROOM 2205	NONE DETECTED			675 Sq Ft
	31	ROOM 2206	NONE DETECTED			675 Sq Ft
	45	ROOM 2213	NONE DETECTED	092810MV-8	MV-8: HALLWAY 2200 BY ELEVATOR (SINCE REMOVED).	310 Sq Ft
	57	ROOM 2217	NONE DETECTED			675 Sq Ft
	61	ROOM 2218	NONE DETECTED			675 Sq Ft
	65	ROOM 2219	NONE DETECTED			675 Sq Ft
	69	ROOM 2220	NONE DETECTED			675 Sq Ft
	74	ROOM 2221	NONE DETECTED			675 Sq Ft
	79	ROOM 2222	NONE DETECTED			675 Sq Ft
	86	ROOM 1217	NONE DETECTED			800 Sq Ft
	99	ROOM 1216	NONE DETECTED			800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	112	ROOM 1214	NONE DETECTED	092810MV-9	MV-9: ROOM 1214.	675 Sq Ft
	117	ROOM 1214A	NONE DETECTED			100 Sq Ft
	121	ROOM 1211	NONE DETECTED			150 Sq Ft
	125	ROOM 1213	NONE DETECTED			300 Sq Ft
	130	ROOM 1215	NONE DETECTED			150 Sq Ft
	134	1ST FLOOR HALLWAY 1200	NONE DETECTED			1500 Sq Ft
	144	ROOM 1205	NONE DETECTED			675 Sq Ft
	150	ROOM 1206	NONE DETECTED			675 Sq Ft
	156	ROOM 1203	NONE DETECTED			675 Sq Ft
	162	ROOM 1204	NONE DETECTED			675 Sq Ft
	168	ROOM 1201	NONE DETECTED			675 Sq Ft
	174	ROOM 1202	NONE DETECTED			675 Sq Ft
	180	HALLWAY 1220	NONE DETECTED			200 Sq Ft
	183	ROOM 1223	NONE DETECTED			175 Sq Ft
I3B	2' x 4' Ceiling Tile Vinyl-Coated Sheetrock		Total Amount - 730 Sq Ft			
	255	KITCHEN (1123)	NONE DETECTED	482-JJT-20	JJT-20: ABOVE ENTRANCE TO WOMEN'S RESTROOM.	730 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I3C	2' x 4' Ceiling Tile Chicken Peck Design w/Bumpy Texture					Total Amount - 7665 Sq Ft
	38	HALLWAY 2200	NONE DETECTED			1500 Sq Ft
	42	ROOM 2211	NONE DETECTED			100 Sq Ft
	48	ROOM 2215	NONE DETECTED			100 Sq Ft
	141	1ST FLOOR BOYS' & GIRLS' RESTROOM NEXT TO ROOM 1205 HALLWAY	NONE DETECTED			200 Sq Ft
	187	ROOM 1101	NONE DETECTED	092810MV-10	MV-10: ROOM 1101.	1050 Sq Ft
	211	ROOM 1103	NONE DETECTED			880 Sq Ft
	218	ROOM 1105	NONE DETECTED			880 Sq Ft
	231	ROOM 1107	NONE DETECTED			880 Sq Ft
	238	ROOM 1109	NONE DETECTED	092810MV-11	MV-11: ROOM 1109.	880 Sq Ft
	258	KITCHEN RECEIVING (1130)	NONE DETECTED			120 Sq Ft
	262	HALLWAY 1012C	NONE DETECTED			100 Sq Ft
	279	STAFF LOUNGE (1012)	NONE DETECTED			325 Sq Ft
	286	MAIN OFFICE (1000)	NONE DETECTED	2001-1501-AF-2		650 Sq Ft
I3D	2' x 4' Ceiling Tile Chicken Scratch					Total Amount - 6000 Sq Ft
	320	HALLWAY 1300	NONE DETECTED			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	358	THROUGHOUT 1996 ADDITION CLASSROOMS	NONE DETECTED	482-JJT-26	JJT-26: NORTHWEST CORNER OF TILE ABOVE CLOCK.	5000 Sq Ft
I3E	2' x 4' Ceiling Tile Tectum	Total Amount - 4800 Sq Ft				
	330	1974 ADDITION GYMNASIUM (1307)	NSM			4800 Sq Ft
I4A	Acoustical Ceiling Tile Trapezoid Design w/Rough Texture	Total Amount - 1288 Sq Ft				
	51	STAIRWELL BY LIBRARY	NONE DETECTED			120 Sq Ft
	55	LIBRARY 2110	NONE DETECTED			568 Sq Ft
	203	MAIN ENTRANCE 1100	NONE DETECTED	482-JJT-15; 450L-B6	JJT-15: SOUTHWEST CORNER ABOVE WEST DOOR.	600 Sq Ft
K0A	9" x 9" Vinyl Floor Tile & Mastic Tan w/Brown & White Streaks	Total Amount - 3530 Sq Ft				
	190	ROOM 1101	5 CH (TILE ONLY)			1050 Sq Ft
	213	ROOM 1103	5 CH (TILE ONLY)	2001-01124-1	01124-1: CAFETERIA (SINCE REMOVED).	880 Sq Ft
	220	ROOM 1105	5 CH (TILE ONLY)	092810MV-12	MV-12: ROOM 1105.	800 Sq Ft
	240	ROOM 1109	5 CH (TILE ONLY)	2001-01124-1	01124-1: CAFETERIA (SINCE REMOVED).	800 Sq Ft
K0B	9" x 9" Vinyl Floor Tile & Mastic Maroon w/White & Orange Streaks	Total Amount - 800 Sq Ft				
	233	ROOM 1107	5 CH (TILE ONLY)	2001-01124-3		800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K0C	9" x 9" Vinyl Floor Tile & Mastic Dark Brown w/Cream & Orange Streaks					Total Amount - 70 Sq Ft
	206	ROOM 1102 (COMMUNICATIONS)	5 CH (TILE ONLY)	092810MV-13; 2001-1501-AF-11	MV-13: STORAGE 1102. AF-11: ROOM 1005.	70 Sq Ft
K1A	Sheet Vinyl Flooring & Adhesive Gray Small Pebble Look					Total Amount - 200 Sq Ft
	273	STAFF WOMEN'S RESTROOM (1012B)	NONE DETECTED			100 Sq Ft
	276	STAFF MEN'S RESTROOM (1012A)	NONE DETECTED	092810MV-14	MV-14: RESTROOM 1012A.	100 Sq Ft
K1B	Sheet Vinyl Flooring & Adhesive Tan					Total Amount - 360 Sq Ft
	343	RECREATION CENTER ROOM 1515	NONE DETECTED	092810MV-15	MV-15: RECREATION CENTER ROOM 1515.	360 Sq Ft
K1C	Sheet Vinyl Flooring & Adhesive White/Gray w/Blue & Pink Specks					Total Amount - 50 Sq Ft
	94	ROOM 1217 RESTROOM	NONE DETECTED			25 Sq Ft
	107	ROOM 1216 RESTROOM	NONE DETECTED	092810MV-16	MV-16: 1974 2ND FLOOR RESTROOM.	25 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Yellow					Total Amount - 10 Sq Ft
	126	ROOM 1213	6 CH (MASTIC ONLY)	092810MV-25; 2001-1901-JLC-12; 2001-1501-AF-12	MV-25: ROOM 1213.	10 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic Off-White w/Tan Specks					Total Amount - 700 Sq Ft
	87	ROOM 1217	2 CH (TILE), 6 CH (MASTIC)	092810MV-26	MV-26; ROOM 1217.	200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	96	ROOM 1217 STORAGE	2 CH (TILE), 6 CH (MASTIC)			100 Sq Ft
	100	ROOM 1216	2 CH (TILE), 6 CH (MASTIC)			200 Sq Ft
	109	ROOM 1216 STORAGE	2 CH (TILE), 6 CH (MASTIC)			100 Sq Ft
	119	ROOM 1214A	2 CH (TILE), 6 CH (MASTIC)			100 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic White w/Light Tan & Tan Specks		Total Amount - 725 Sq Ft			
	259	KITCHEN RECEIVING (1130)	NONE DETECTED	2001-1901-JLC-10B		120 Sq Ft
	263	HALLWAY 1012C	NONE DETECTED			280 Sq Ft
	280	STAFF LOUNGE (1012)	NONE DETECTED	092810MV-27	MV-27: STAFF LOUNGE.	325 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/White & Dark Gray Specks		Total Amount - 100 Sq Ft			
	356	THROUGHOUT 1996 ADDITION	NONE DETECTED	482-JJT-28	JJT-28: UNDER SINK WEST SIDE.	100 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic White w/Gray & Brown Streaks		Total Amount - 1650 Sq Ft			
	253	HALLWAY 1500 FROM CAFETERIA TO RECREATION CENTER	NONE DETECTED			600 Sq Ft
	337	RECREATION CENTER KITCHEN	NONE DETECTED			150 Sq Ft
	345	RECREATION CENTER ART ROOM (1504)	NONE DETECTED	2001-1501-AF-13	AF-13: RECREATION CENTER HALLWAY (SINCE REMOVED).	400 Sq Ft
	349	RECREATION CENTER ROOM 1501	NONE DETECTED			500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2G	12" x 12" Vinyl Floor Tile & Mastic White w/Light Gray & Black Smears					Total Amount - 2500 Sq Ft
	252	CAFETERIA (1120)	NONE DETECTED	092810MV-28	MV-28: CAFETERIA 1120.	2500 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Tan w/Beige					Total Amount - 100 Sq Ft
	248	OFFICE 1121A OFF OF CAFETERIA	NONE DETECTED	092810MV-29	MV-29: OFFICE OFF OF CAFETERIA.	100 Sq Ft
K2I	12" x 12" Vinyl Floor Tile & Mastic Beige Mottle					Total Amount - 7507 Sq Ft
	11	ROOM 2201	NONE DETECTED			10 Sq Ft
	16	ROOM 2202	NONE DETECTED	092810MV-31	MV-31: ROOM 2202.	10 Sq Ft
	20	ROOM 2203	NONE DETECTED			10 Sq Ft
	24	ROOM 2204	NONE DETECTED			10 Sq Ft
	28	ROOM 2205	NONE DETECTED			10 Sq Ft
	32	ROOM 2206	NONE DETECTED			10 Sq Ft
	39	HALLWAY 2200	NONE DETECTED			1500 Sq Ft
	58	ROOM 2217	NONE DETECTED			10 Sq Ft
	62	ROOM 2218	NONE DETECTED			10 Sq Ft
	66	ROOM 2219	NONE DETECTED			10 Sq Ft
	70	ROOM 2220	NONE DETECTED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	75	ROOM 2221	NONE DETECTED			10 Sq Ft
	80	ROOM 2222	NONE DETECTED			10 Sq Ft
	113	ROOM 1214	NONE DETECTED			10 Sq Ft
	135	1ST FLOOR HALLWAY 1200	NONE DETECTED	092810MV-30	MV-30: HALLWAY 1200.	1500 Sq Ft
	145	ROOM 1205	NONE DETECTED			10 Sq Ft
	151	ROOM 1206	NONE DETECTED			10 Sq Ft
	157	ROOM 1203	NONE DETECTED			10 Sq Ft
	163	ROOM 1204	NONE DETECTED			10 Sq Ft
	169	ROOM 1201	NONE DETECTED			10 Sq Ft
	175	ROOM 1202	NONE DETECTED			10 Sq Ft
	181	HALLWAY 1220	NONE DETECTED			200 Sq Ft
	191	ROOM 1101	NONE DETECTED			25 Sq Ft
	204	MAIN ENTRANCE 1100	NONE DETECTED			500 Sq Ft
	209	HALLWAY 1100	NONE DETECTED			2300 Sq Ft
	214	ROOM 1103	NONE DETECTED			12 Sq Ft
	222	ROOM 1105	NONE DETECTED			40 Sq Ft
	234	ROOM 1107	NONE DETECTED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	241	ROOM 1109	NONE DETECTED			40 Sq Ft
	321	HALLWAY 1300	NONE DETECTED			1000 Sq Ft
	365	1996 ADDITION ENTRYWAYS	NONE DETECTED			60 Sq Ft
	367	1996 ADDITION INTERVENTION TIME-OUT ROOM	NONE DETECTED			100 Sq Ft
K2J	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle					Total Amount - 200 Sq Ft
	310	ROOM 1004	NONE DETECTED	092810MV-32	MV-32: ROOM 1004.	200 Sq Ft
K2K	12" x 12" Vinyl Floor Tile & Mastic Blue Mottle (1996)					Total Amount - 170 Sq Ft
	366	1996 ADDITION ROOM 1420	NEW			170 Sq Ft
K3A	Miscellaneous Flooring 3' x 3' Red w/Raised Circles					Total Amount - 800 Sq Ft
	326	1974 ADDITION LOCKER ROOMS (1304/1305)	NONE DETECTED	092810MV-33	MV-33: LOCKER ROOM 1304.	400 Sq Ft
	353	RECREATION CENTER RESTROOMS	NONE DETECTED			400 Sq Ft
K3B	Miscellaneous Flooring Black Mastic					Total Amount - 400 Sq Ft
	327	1974 ADDITION LOCKER ROOMS (1304/1305)	7 CH	092810MV-33	MV-33: LOCKER ROOM 1304.	400 Sq Ft
K3C	Miscellaneous Flooring 16" X 16" Light to Dark Shades of Gray (201x)					Total Amount - 3300 Sq Ft
	335	THROUGHOUT RECREATION CENTER	NEW			2000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	341	RECREATION CENTER MEETING ROOM (1506)	NEW			600 Sq Ft
	350	RECREATION CENTER OFFICE 1503	NEW			100 Sq Ft
	351	RECREATION CENTER ROOM 1507	NEW			600 Sq Ft
LOA	Flexible Duct Connector Black Vinyl					Total Amount - 7 Sq Ft
	270	FAN ROOM (1110A)	NONE DETECTED			4 Sq Ft
	336	RECREATION CENTER FAN ROOM	NONE DETECTED	482-JJT-34	JJT-34: BY ISOLATION DUCTS BY ACCESS DOOR.	3 Sq Ft
LOB	Flexible Duct Connector Green Canvas					Total Amount - 1 Sq Ft
	271	FAN ROOM (1110A)	NONE DETECTED	2001-1504-GG1		1 Sq Ft
MOA	Plaster Smooth (1953)					Total Amount - 20000 Sq Ft
	186	THROUGHOUT 1953 ORIGINAL BUILDING	NONE DETECTED	092810MV-17, 18, 19, 20, 21; 509-S-5; 482-JJT-22	MV-17: ROOM 1105. MV-18: ROOM 1107. MV-19: ROOM 1109. MV-20: ROOM 1104. MV-21: ROOM 1103. S-5: ROOM 1101.	20000 Sq Ft
MOB	Plaster Rough (1953)					Total Amount - 1500 Sq Ft
	266	BOILER ROOM (1110)	NONE DETECTED	092810MV-22, 23, 24; 482-JJT-21; 509-S-7	MV-22,23: BOILER ROOM. MV-24: FAN ROOM. JJT-21: ABOVE MAIN ENTRANCE ROOM RESTROOM.	1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
N0A	Drywall/Joint Compound 1974 Addition					Total Amount - 12000 Sq Ft
	2	THROUGHOUT 1974 ADDITION	NONE DETECTED	482-JJT-6	JJT-6: ROOM 1205.	12000 Sq Ft
N0B	Drywall/Joint Compound Vinyl-Covered (1974)					Total Amount - 10000 Sq Ft
	3	THROUGHOUT 1974 ADDITION	NONE DETECTED	482-JJT-7	JJT-7: ROOM 1205.	10000 Sq Ft
N0C	Drywall/Joint Compound 1996 Addition					Total Amount - 2000 Sq Ft
	355	THROUGHOUT 1996 ADDITION	NONE DETECTED	482-JJT-30	JJT-30: ABOVE ENTRANCE.	2000 Sq Ft
N0D	Drywall/Joint Compound Recreation Center Addition					Total Amount - 4500 Sq Ft
	334	THROUGHOUT RECREATION CENTER	NONE DETECTED	482-JJT-40	JJT-40: ABOVE WATER HEATER IN CUSTODIAL CLOSET.	4500 Sq Ft
N0E	Drywall/Joint Compound Office/Lounge Renovation					Total Amount - 1000 Sq Ft
	278	STAFF LOUNGE (1012)	NONE DETECTED			200 Sq Ft
	285	MAIN OFFICE (1000)	NONE DETECTED	2001-1501-A4-10	A4-10: MAIN OFFICE.	800 Sq Ft
P0A	Fire Doors Wood Composite - 1.5 Hr Rating (Eggers)					Total Amount - 260 Sq Ft
	4	THROUGHOUT 1974 ADDITION HALLWAYS	ASSUMED			240 Sq Ft
	324	FAN ROOM 1302	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0E	Carpet Adhesive Gray Berber Carpet		Total Amount - 5000 Sq Ft			
	359	THROUGHOUT 1996 ADDITION CLASSROOMS	NONE DETECTED	2001-101-JLC-9B		5000 Sq Ft
Q0H	Carpet Adhesive Green/Tan Berber Carpet		Total Amount - 19825 Sq Ft			
	12	ROOM 2201	NONE DETECTED			675 Sq Ft
	17	ROOM 2202	NONE DETECTED			675 Sq Ft
	21	ROOM 2203	NONE DETECTED			675 Sq Ft
	25	ROOM 2204	NONE DETECTED	092810MV-34	MV-34: ROOM 2204.	675 Sq Ft
	29	ROOM 2205	NONE DETECTED			675 Sq Ft
	33	ROOM 2206	NONE DETECTED			675 Sq Ft
	43	ROOM 2211	NONE DETECTED			100 Sq Ft
	46	ROOM 2213	NONE DETECTED			310 Sq Ft
	49	ROOM 2215	NONE DETECTED			100 Sq Ft
	52	STAIRWELL BY LIBRARY	NONE DETECTED			500 Sq Ft
	59	ROOM 2217	NONE DETECTED			675 Sq Ft
	63	ROOM 2218	NONE DETECTED			675 Sq Ft
	67	ROOM 2219	NONE DETECTED			675 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	71	ROOM 2220	NONE DETECTED			675 Sq Ft
	76	ROOM 2221	NONE DETECTED			675 Sq Ft
	81	ROOM 2222	NONE DETECTED			675 Sq Ft
	88	ROOM 1217	NONE DETECTED			600 Sq Ft
	101	ROOM 1216	NONE DETECTED	092810MV-35	MV-35: ROOM 1216.	600 Sq Ft
	114	ROOM 1214	NONE DETECTED			675 Sq Ft
	122	ROOM 1211	NONE DETECTED			150 Sq Ft
	127	ROOM 1213	NONE DETECTED			300 Sq Ft
	131	ROOM 1215	NONE DETECTED			150 Sq Ft
	146	ROOM 1205	NONE DETECTED			675 Sq Ft
	152	ROOM 1206	NONE DETECTED			675 Sq Ft
	158	ROOM 1203	NONE DETECTED			675 Sq Ft
	164	ROOM 1204	NONE DETECTED			675 Sq Ft
	170	ROOM 1201	NONE DETECTED			675 Sq Ft
	176	ROOM 1202	NONE DETECTED			675 Sq Ft
	184	ROOM 1223	NONE DETECTED			200 Sq Ft
	192	ROOM 1101	NONE DETECTED			1350 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	219	ROOM 1105	NONE DETECTED			880 Sq Ft
	232	ROOM 1107	NONE DETECTED			880 Sq Ft
	239	ROOM 1109	NONE DETECTED			880 Sq Ft
Q0I	Carpet Adhesive Multi-Colored Berber Carpet					Total Amount - 2605 Sq Ft
	212	ROOM 1103	NONE DETECTED			875 Sq Ft
	287	MAIN OFFICE (1000)	NONE DETECTED	092810MV-38	MV-38: MAIN OFFICE.	650 Sq Ft
	291	ROOM 1001	NONE DETECTED			150 Sq Ft
	295	ROOM 1003	NONE DETECTED			150 Sq Ft
	299	ROOM 1005	NONE DETECTED			300 Sq Ft
	302	PRINCIPAL'S OFFICE 1010	NONE DETECTED			200 Sq Ft
	305	ASSISTANT PRINCIPAL'S OFFICE 1008	NONE DETECTED			100 Sq Ft
	317	STORAGE/OFFICE SOUTH OF NURSE'S OFFICE	NONE DETECTED			180 Sq Ft
Q0J	Carpet Adhesive Dark Blue Carpet					Total Amount - 1260 Sq Ft
	363	1996 ADDITION HALLWAYS	NONE DETECTED	092810MV-47	MV-47: 1996 ADDITION HALLWAY.	1260 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0K	Carpet Adhesive Light to Dark Gray with Blue Accents Carpet Squares (201x)					Total Amount - 1000 Sq Ft
	56	LIBRARY 2110	NEW			1000 Sq Ft
ROA	Baseboard/Mopboard Adhesive 4" Black Baseboard					Total Amount - 834 Sq Ft
	5	1974 ADDITION STAIRWELL 2299B	NONE DETECTED			15 Sq Ft
	13	ROOM 2201	NONE DETECTED			20 Sq Ft
	18	ROOM 2202	NONE DETECTED			15 Sq Ft
	22	ROOM 2203	NONE DETECTED			15 Sq Ft
	26	ROOM 2204	NONE DETECTED			20 Sq Ft
	30	ROOM 2205	NONE DETECTED			15 Sq Ft
	34	ROOM 2206	NONE DETECTED			10 Sq Ft
	40	HALLWAY 2200	NONE DETECTED			80 Sq Ft
	44	ROOM 2211	NONE DETECTED			9 Sq Ft
	47	ROOM 2213	NONE DETECTED			25 Sq Ft
	50	ROOM 2215	NONE DETECTED			15 Sq Ft
	53	STAIRWELL BY LIBRARY	NONE DETECTED			20 Sq Ft
	60	ROOM 2117	NONE DETECTED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	64	ROOM 2218	NONE DETECTED			20 Sq Ft
	68	ROOM 2219	NONE DETECTED			20 Sq Ft
	72	ROOM 2220	NONE DETECTED			20 Sq Ft
	77	ROOM 2221	NONE DETECTED			10 Sq Ft
	82	ROOM 2222	NONE DETECTED			10 Sq Ft
	83	1974 ADDITION STAIRWELL 2299C	NONE DETECTED			15 Sq Ft
	89	ROOM 1217	NONE DETECTED			20 Sq Ft
	97	ROOM 1217 STORAGE	NONE DETECTED			5 Sq Ft
	102	ROOM 1216	NONE DETECTED			20 Sq Ft
	110	ROOM 1216 STORAGE	NONE DETECTED			5 Sq Ft
	115	ROOM 1214	NONE DETECTED			30 Sq Ft
	120	ROOM 1214A	NONE DETECTED			5 Sq Ft
	123	ROOM 1211	NONE DETECTED			5 Sq Ft
	128	ROOM 1213	NONE DETECTED			10 Sq Ft
	132	ROOM 1215	NONE DETECTED			5 Sq Ft
	136	1ST FLOOR HALLWAY 1200	NONE DETECTED			80 Sq Ft
	147	ROOM 1205	NONE DETECTED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	153	ROOM 1206	NONE DETECTED			10 Sq Ft
	159	ROOM 1203	NONE DETECTED			20 Sq Ft
	165	ROOM 1204	NONE DETECTED			20 Sq Ft
	171	ROOM 1201	NONE DETECTED			15 Sq Ft
	177	ROOM 1202	NONE DETECTED			30 Sq Ft
	182	HALLWAY 1220	NONE DETECTED			20 Sq Ft
	185	ROOM 1223	NONE DETECTED			25 Sq Ft
	205	MAIN ENTRANCE 1100	NONE DETECTED			20 Sq Ft
	210	HALLWAY 1100	NONE DETECTED			20 Sq Ft
	215	ROOM 1103	NONE DETECTED			10 Sq Ft
	260	KITCHEN RECEIVING (1130)	NONE DETECTED	2001-1901-JLC-10B		15 Sq Ft
	264	HALLWAY 1012C	NONE DETECTED			15 Sq Ft
	281	STAFF LOUNGE (1012)	NONE DETECTED			10 Sq Ft
	322	HALLWAY 1300	NONE DETECTED			25 Sq Ft
ROE	Baseboard/Mopboard Adhesive 4" Gray Baseboard		Total Amount - 145 Sq Ft			
	282	STAFF LOUNGE (1012)	NONE DETECTED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	288	MAIN OFFICE (1000)	NONE DETECTED			15 Sq Ft
	318	STORAGE/OFFICE SOUTH OF NURSE'S OFFICE	NONE DETECTED			20 Sq Ft
	360	THROUGHOUT 1996 ADDITION CLASSROOMS	NONE DETECTED	482-JJT-29	JJT-29: NORTHWEST CORNER BELOW RADIATOR.	100 Sq Ft
R0F	Baseboard/Mopboard Adhesive 6" Gray Baseboard					Total Amount - 140 Sq Ft
	331	1974 ADDITION GYMNASIUM (1307)	NONE DETECTED	2001-1901-JLC-11B		140 Sq Ft
R0G	Baseboard/Mopboard Adhesive 2" Gray Baseboard					Total Amount - 25 Sq Ft
	344	RECREATION CENTER ROOM 1515	NONE DETECTED			10 Sq Ft
	346	RECREATION CENTER ART ROOM (1504)	NONE DETECTED			15 Sq Ft
R0I	Baseboard/Mopboard Adhesive 6" White Baseboard					Total Amount - 40 Sq Ft
	274	STAFF WOMEN'S RESTROOM (1012B)	NONE DETECTED			20 Sq Ft
	277	STAFF MEN'S RESTROOM (1012A)	NONE DETECTED	092810MV-37	MV-37: MEN'S STAFF RESTROOM.	20 Sq Ft
R0J	Baseboard/Mopboard Adhesive 4" Blue Baseboard					Total Amount - 80 Sq Ft
	364	1996 ADDITION HALLWAYS	NONE DETECTED	092810MV-46	MV-46: 1996 ADDITION HALLWAY.	80 Sq Ft
R0K	Baseboard/Mopboard Adhesive 4" Brown					Total Amount - 45 Sq Ft
	342	RECREATION CENTER MEETING ROOM (1506)	ASSUMED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	352	RECREATION CENTER ROOM 1507	ASSUMED			35 Sq Ft
R0L	Baseboard/Mopboard Adhesive 6" Red Baseboard					Total Amount - 20 Sq Ft
	354	RECREATION CENTER RESTROOMS	NEW			20 Sq Ft
S0A	Wood Floor Felt / Vapor Barrier 1953 Original Building - Elevated					Total Amount - 450 Sq Ft
	247	STAGE (1120A)	ASSUMED			450 Sq Ft
T0A	Light Cord Insulation White Cords					Total Amount - 4 Lin Ft
	249	OFFICE 1121A OFF OF CAFETERIA	ASSUMED			4 Lin Ft
V0A	Sink Undercoating Smooth Black					Total Amount - 20 Sq Ft
	90	ROOM 1217	3 CH			5 Sq Ft
	103	ROOM 1216	3 CH			5 Sq Ft
	129	ROOM 1213	3 CH	092810MV-41	MV-41: ROOM 1203 (SINCE REMOVED).	5 Sq Ft
	283	STAFF LOUNGE (1012)	3 CH	092810MV-40	MV-40: STAFF LOUNGE.	5 Sq Ft
V0B	Sink Undercoating White					Total Amount - 13 Sq Ft
	338	RECREATION CENTER KITCHEN	NONE DETECTED	092810MV-42	MV-42: RECREATION CENTER KITCHEN.	5 Sq Ft
	348	RECREATION CENTER ART ROOM (1504)	NONE DETECTED			8 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
V0C	Sink Undercoating Rough Gray					Total Amount - 5 Sq Ft
	311	ROOM 1004	NONE DETECTED	092810MV-43	MV-43: ROOM 1004.	5 Sq Ft
V0D	Sink Undercoating Gray (1996)					Total Amount - 10 Sq Ft
	357	THROUGHOUT 1996 ADDITION	NONE DETECTED	092810MV-48	MV-48: ROOM 1407.	10 Sq Ft
V0E	Sink Undercoating Gray (2011)					Total Amount - 246 Sq Ft
	1	THROUGHOUT BUILDING	NEW			150 Sq Ft
	7	THROUGHOUT CLASSROOMS 2201-2222	NEW			72 Sq Ft
	142	THROUGHOUT ROOMS 1206 - 1201	NEW			24 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					Total Amount - 965 Sq Ft
	189	ROOM 1101	3 CH			40 Sq Ft
	208	HALLWAY 1100	3 CH	092810MV-44	MV-44: HALLWAY BY ROOM 1101.	550 Sq Ft
	226	GIRLS' RESTROOM 1108	3 CH			50 Sq Ft
	229	BOYS' RESTROOM 1112	3 CH			50 Sq Ft
	246	STAGE (1120A)	3 CH			110 Sq Ft
	290	ROOM 1001	3 CH			35 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	294	ROOM 1003	3 CH			35 Sq Ft
	298	ROOM 1005	3 CH			75 Sq Ft
	307	ROOM 1004 ENTRY	3 CH			20 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B					Total Amount - 165 Sq Ft
	301	PRINCIPAL'S OFFICE 1010	3 CH			50 Sq Ft
	304	ASSISTANT PRINCIPAL'S OFFICE 1008	3 CH			25 Sq Ft
	309	ROOM 1004	3 CH			50 Sq Ft
	316	STORAGE/OFFICE SOUTH OF NURSE'S OFFICE	3 CH	092810MV-45	MV-45: OFFICE BY ROOM 1004.	40 Sq Ft
X0A	Miscellaneous Material Buffalo Board Tar					Total Amount - 2500 Sq Ft
	272	1953 ORIGINAL BUILDING TUNNEL SYSTEM	NONE DETECTED	2001-1501-AF-1		2500 Sq Ft
X0B	Miscellaneous Material Wood Frame Chalkboard Adhesive (1953)					Total Amount - 66 Sq Ft
	193	ROOM 1101	ASSUMED			10 Sq Ft
	216	ROOM 1103	ASSUMED			4 Sq Ft
	223	ROOM 1105	ASSUMED			4 Sq Ft
	235	ROOM 1107	ASSUMED			20 Sq Ft
	242	ROOM 1109	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	292	ROOM 1001	ASSUMED			4 Sq Ft
	296	ROOM 1003	ASSUMED			4 Sq Ft
X0C	Miscellaneous Material Pipe/Valve Flange Gaskets					Total Amount - 30 Sq Ft
	269	BOILER ROOM (1110)	ASSUMED			30 Sq Ft
X1A	Miscellaneous Material Yellow Countertop					Total Amount - 60 Sq Ft
	91	ROOM 1217	NONE DETECTED	482-JJT-1	JJT-1: ROOM 2206 NORTH SIDE (SINCE REMOVED).	30 Sq Ft
	104	ROOM 1216	NONE DETECTED			30 Sq Ft
X1B	Miscellaneous Material Green Countertop					Total Amount - 330 Sq Ft
	6	1974 ADDITION STAIRWELL 2299B	NONE DETECTED			10 Sq Ft
	84	1974 ADDITION STAIRWELL 2299C	NONE DETECTED			10 Sq Ft
	92	ROOM 1217	NONE DETECTED	482-JJT-3	JJT-3: ROOM 1217 NORTHWEST CORNER.	40 Sq Ft
	105	ROOM 1216	NONE DETECTED			40 Sq Ft
	116	ROOM 1214	NONE DETECTED			30 Sq Ft
	148	ROOM 1205	NONE DETECTED			30 Sq Ft
	154	ROOM 1206	NONE DETECTED			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	160	ROOM 1203	NONE DETECTED			30 Sq Ft
	166	ROOM 1204	NONE DETECTED			30 Sq Ft
	172	ROOM 1201	NONE DETECTED			30 Sq Ft
	178	ROOM 1202	NONE DETECTED			30 Sq Ft
	275	STAFF WOMEN'S RESTROOM (1012B)	NONE DETECTED			10 Sq Ft
	284	STAFF LOUNGE (1012)	NONE DETECTED			10 Sq Ft
X1C	Miscellaneous Material Eggshell Countertop		Total Amount - 90 Sq Ft			
	194	ROOM 1101	NONE DETECTED	482-JJT-14	JJT-14: ROOM 1101 NORTHEAST CORNER.	90 Sq Ft
X1D	Miscellaneous Material White & Tan Speckled Countertop		Total Amount - 230 Sq Ft			
	195	ROOM 1101	NONE DETECTED			20 Sq Ft
	221	ROOM 1105	NONE DETECTED			60 Sq Ft
	236	ROOM 1107	NONE DETECTED			60 Sq Ft
	243	ROOM 1109	NONE DETECTED	482-JJT-19	NORTHWEST CORNER.	90 Sq Ft
X1E	Miscellaneous Material Wood Grain Countertop Design		Total Amount - 480 Sq Ft			
	8	THROUGHOUT CLASSROOMS 2201-2222	NONE DETECTED			300 Sq Ft
	196	ROOM 1101	NONE DETECTED			80 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	217	ROOM 1103	NONE DETECTED			25 Sq Ft
	224	ROOM 1105	NONE DETECTED			25 Sq Ft
	237	ROOM 1107	NONE DETECTED	482-JJT-18	JJT-18: ROOM 1107 SOUTHWEST CORNER.	25 Sq Ft
	244	ROOM 1109	NONE DETECTED			25 Sq Ft
X1F	Miscellaneous Material Light Gray Countertop		Total Amount - 10 Sq Ft			
	312	ROOM 1004	NONE DETECTED	482-JJT-24	JJT-24: NORTHWEST CORNER.	10 Sq Ft
X1G	Miscellaneous Material Light Blue Countertops		Total Amount - 200 Sq Ft			
	361	THROUGHOUT 1996 ADDITION CLASSROOMS	NONE DETECTED	482-JJT-27	JJT-27: UPPER INSIDE CORNER OF LARGE WEST CABINET.	200 Sq Ft
X1H	Miscellaneous Material Light Blue Countertop		Total Amount - 80 Sq Ft			
	339	RECREATION CENTER KITCHEN	NONE DETECTED	482-JJT-35	JJT-35: SOUTH FRONT BY SLIDING DOOR.	60 Sq Ft
	347	RECREATION CENTER ART ROOM (1504)	NONE DETECTED			20 Sq Ft
X1I	Miscellaneous Material 2" x 2" Light Brown Ceramic Floor Tile System		Total Amount - 1080 Sq Ft			
	35	2ND FLOOR BOYS' & GIRLS' RESTROOM	ASSUMED			500 Sq Ft
	139	1ST FLOOR BOYS' & GIRLS' RESTROOM NEXT TO ROOM 1205	ASSUMED			500 Sq Ft
	314	ROOM 1004 RESTROOM	ASSUMED			80 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1J	Miscellaneous Material 6" x 6" Red Quarry Tile System					Total Amount - 1330 Sq Ft
	197	ROOM 1101	ASSUMED			200 Sq Ft
	227	GIRLS' RESTROOM 1108	ASSUMED			200 Sq Ft
	230	BOYS' RESTROOM 1112	ASSUMED			200 Sq Ft
	256	KITCHEN (1123)	ASSUMED			730 Sq Ft
X1K	Miscellaneous Material 4" X 4" Blue Ceramic Wall Tile System					Total Amount - 130 Sq Ft
	201	ROOM 1101 RESTROOM	ASSUMED			130 Sq Ft
X1L	Miscellaneous Material 1" X 1" Blue and Tan Ceramic Floor Tile System					Total Amount - 32 Sq Ft
	202	ROOM 1101 RESTROOM	ASSUMED			32 Sq Ft
X1M	Miscellaneous Material 1" X 1" Red and Tan Ceramic Floor Tile System					Total Amount - 26 Sq Ft
	250	1121 STORAGE CLOSET	ASSUMED			26 Sq Ft
X1N	Miscellaneous Material 4" X 4" White Ceramic Wall Tile System					Total Amount - 180 Sq Ft
	313	ROOM 1004 RESTROOM	ASSUMED			180 Sq Ft
X1P	Miscellaneous Material 6" X 6" Cream Ceramic Baseboard System					Total Amount - 100 Sq Ft
	36	2ND FLOOR BOYS' & GIRLS' RESTROOM	ASSUMED			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	140	1ST FLOOR BOYS' & GIRLS' RESTROOM NEXT TO ROOM 1205	ASSUMED			50 Sq Ft
X1Q	Miscellaneous Material 2" X 2" Cream Ceramic Floor Tile System					Total Amount - 200 Sq Ft
	328	1974 ADDITION LOCKER ROOMS (1304/1305)	ASSUMED			200 Sq Ft