Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2A	Mudded Pipe Joints on Millboard Insulation 1956 Original Building					**Total Amount - 158 Joints**
	38	ROOM 1006	15-20 CH	112113MA-01		1 Joints
	66	NURSE 1011	15-20 CH			6 Joints
	100	GIRLS' LOCKER ROOM 1105	15-20 CH			10 Joints
	115	BOYS' LOCKER ROOM 1109	15-20 CH			10 Joints
	126	KITCHEN 1111	15-20 CH			8 Joints
	132	KITCHEN RESTROOM 1111B	15-20 CH			5 Joints
	148	OFFICE 1201	15-20 CH			5 Joints
	156	UNISEX RESTROOM NEAR ROOM 1202	15-20 CH			4 Joints
	171	HALLWAY FROM ROOMS 1205-1321	15-20 CH			50 Joints
	175	MAINTENANCE ROOM 1206	15-20 CH			4 Joints
	194	ROOM 1302	15-20 CH			6 Joints
	209	ROOM 1306	15-20 CH	031909BF-02		3 Joints

© 2024 Institute for Environmental Assessment, Inc. All Rights Reserved.

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	217	ROOM 1308	15-20 CH			3 Joints
	238	ROOM 1310	15-20 CH			2 Joints
	248	ROOM 1312	15-20 CH			3 Joints
	272	ROOM 1314	15-20 CH			4 Joints
	332	ROOM 2322	15-20 CH			2 Joints
	340	ROOM 2321	15-20 CH			2 Joints
	348	ROOM 2319	15-20 CH			4 Joints
	356	ROOM 2320	15-20 CH			4 Joints
	364	ROOM 2318	15-20 CH			2 Joints
	372	ROOM 2317	15-20 CH			2 Joints
	386	ROOM 2314	15-20 CH			2 Joints
	394	ROOM 2315	15-20 CH			2 Joints
	412	ROOM 2313	15-20 CH			2 Joints
	425	ROOM 2311	15-20 CH			2 Joints
	438	ROOM 2309	15-20 CH			2 Joints
	446	ROOM 2307	15-20 CH			2 Joints
	464	ROOM 2305	15-20 CH			2 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	475	ROOM 2303	15-20 CH			4 Joints
A3A	Mudded Pipe Joints on Pre-formed Insulation 1956 Original Building					**Total Amount - 2 Joints**
	36	ROOM 1006	30 CH	207J-3A	3A: MAIN GYMNASIUM FAN ROOM (SINCE REMOVED).	2 Joints
B2A	Millboard Pipe Insulation 1956 Original Building					**Total Amount - 1112 Lin Ft**
	29	HALLWAY FROM MAIN OFFICE TO CAFETERIA	3-60 CH			50 Lin Ft
	37	ROOM 1006	3-60 CH	112113MA-02		4 Lin Ft
	46	COPY ROOM 1007	3-60 CH			12 Lin Ft
	48	OFFICE 1008	3-60 CH			12 Lin Ft
	65	NURSE 1011	3-60 CH			60 Lin Ft
	71	NURSE'S OFFICE 1014	3-60 CH			24 Lin Ft
	76	NURSE'S RESTROOM 1011A	3-60 CH			6 Lin Ft
	99	GIRLS' LOCKER ROOM 1105	3-60 CH			60 Lin Ft
	103	GIRLS' LOCKER ROOM OFFICE 1106	3-60 CH			25 Lin Ft
	111	BOYS' LOCKER ROOM OFFICE 1108	3-60 CH			15 Lin Ft
	114	BOYS' LOCKER ROOM 1109	3-60 CH			20 Lin Ft
	125	KITCHEN 1111	3-60 CH			20 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	131	KITCHEN RESTROOM 1111B	3-60 CH			15 Lin Ft
	147	OFFICE 1201	3-60 CH			40 Lin Ft
	155	UNISEX RESTROOM NEAR ROOM 1202	3-60 CH			20 Lin Ft
	163	STAFF WOMEN'S RESTROOM 1304	3-60 CH			40 Lin Ft
	170	HALLWAY FROM ROOMS 1205-1321	3-60 CH			240 Lin Ft
	174	MAINTENANCE ROOM 1206	3-60 CH			16 Lin Ft
	189	ENTRANCE TO ROOM 1302	3-60 CH	031909BF-01	BF-01: ROOM 1302 (SINCE REMOVED).	2 Lin Ft
	193	ROOM 1302	3-60 CH			40 Lin Ft
	208	ROOM 1306	3-60 CH			90 Lin Ft
	216	ROOM 1308	3-60 CH			50 Lin Ft
	237	ROOM 1310	3-60 CH			60 Lin Ft
	247	ROOM 1312	3-60 CH			40 Lin Ft
	271	ROOM 1314	3-60 CH			30 Lin Ft
	300	STORAGE ROOM 1316B	3-60 CH			2 Lin Ft
	331	ROOM 2322	3-60 CH			4 Lin Ft
	339	ROOM 2321	3-60 CH			4 Lin Ft
	347	ROOM 2319	3-60 CH			25 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	355	ROOM 2320	3-60 CH			25 Lin Ft
	363	ROOM 2318	3-60 CH			4 Lin Ft
	371	ROOM 2317	3-60 CH			4 Lin Ft
	385	ROOM 2314	3-60 CH			4 Lin Ft
	393	ROOM 2315	3-60 CH			4 Lin Ft
	411	ROOM 2313	3-60 CH			4 Lin Ft
	424	ROOM 2311	3-60 CH			4 Lin Ft
	437	ROOM 2309	3-60 CH			4 Lin Ft
	445	ROOM 2307	3-60 CH			4 Lin Ft
	463	ROOM 2305	3-60 CH			4 Lin Ft
	474	ROOM 2303	3-60 CH			25 Lin Ft
B3A	Pre-Formed Pipe Insulation 1956 Original Building					**Total Amount - 30 Lin Ft**
	35	ROOM 1006	15 CH, 15 AM	207I-2A	2A: MAIN GYMNASIUM FAN ROOM (SINCE REMOVED).	10 Lin Ft
	172	HALLWAY FROM ROOMS 1205-1321	15 CH, 15 AM			20 Lin Ft
D1A	Boiler Gaskets Fiberglass					**Total Amount - 4 Sq Ft**
	23	BOILER ROOM 1208	NONE DETECTED	121609ML-2		4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D2A	Interior Boiler Insulation Burner Refractory					**Total Amount - 20 Sq Ft**
	24	BOILER ROOM 1208	ASSUMED			20 Sq Ft
D2B	Interior Boiler Insulation Mineral Wool Access Panel Insulation					**Total Amount - 20 Sq Ft**
	25	BOILER ROOM 1208	ASSUMED			20 Sq Ft
G1A	Sprayed-On Acoustical Finish Light Texture					**Total Amount - 5500 Sq Ft**
	85	AUDITORIUM 1101	NONE DETECTED	ACB450O-A1, A2, A3, A4, A5; 2001-1901-HPJH-1B, 2B		5500 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Rough Crevices					**Total Amount - 18530 Sq Ft**
	33	MAIN OFFICE 1002	NONE DETECTED			1200 Sq Ft
	40	OFFICE 1005	NONE DETECTED			170 Sq Ft
	43	OFFICE 1004	NONE DETECTED			180 Sq Ft
	49	OFFICE 1008	NONE DETECTED			110 Sq Ft
	52	OFFICE 1003	NONE DETECTED			150 Sq Ft
	55	TECHNOLOGY ROOM 1009	NONE DETECTED			100 Sq Ft
	57	OFFICE 1016	NONE DETECTED			80 Sq Ft
	60	OFFICE 1015	NONE DETECTED			180 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	63	COUNSELOR'S WORK ROOM 1010	NONE DETECTED			160 Sq Ft
	67	NURSE 1011	NONE DETECTED			240 Sq Ft
	72	NURSE'S OFFICE 1014	NONE DETECTED			150 Sq Ft
	79	COT ROOM 1013	NONE DETECTED			120 Sq Ft
	82	OFFICE 1012	NONE DETECTED			100 Sq Ft
	86	AUDITORIUM 1101	NONE DETECTED			600 Sq Ft
	93	AUDITORIUM LIGHT BOOTH 2102	NONE DETECTED			200 Sq Ft
	127	KITCHEN 1111	NONE DETECTED			35 Sq Ft
	136	KITCHEN SERVING AREA	NONE DETECTED			400 Sq Ft
	139	CAFETERIA 1114	NONE DETECTED			3200 Sq Ft
	144	CAFETERIA STORAGE ROOMS 1115/1116	NONE DETECTED			360 Sq Ft
	149	OFFICE 1201	NONE DETECTED			280 Sq Ft
	158	OFFICE 1202	NONE DETECTED			250 Sq Ft
	166	OFFICE 1205	NONE DETECTED			240 Sq Ft
	180	STORAGE ROOM 1207	NONE DETECTED	20719A		450 Sq Ft
	184	STAIRWELL NEAR ROOM 1207	NONE DETECTED			100 Sq Ft
	190	ENTRANCE TO ROOM 1302	NONE DETECTED			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	250	ROOM 1312	NONE DETECTED			750 Sq Ft
	256	STAIRWELL NEAR ROOM 1312	NONE DETECTED			50 Sq Ft
	266	ROOM 1312A	NONE DETECTED			750 Sq Ft
	294	ROOM 1316	NONE DETECTED			900 Sq Ft
	302	ROOM 1318	NONE DETECTED			430 Sq Ft
	319	STAIRWELL OUTSIDE ROOM 1320	NONE DETECTED			75 Sq Ft
	323	ROOM 1320	NONE DETECTED			440 Sq Ft
	328	HALLWAY FROM ROOMS 2301-2322	NONE DETECTED			5100 Sq Ft
	380	STORAGE ROOM 2316	NONE DETECTED			150 Sq Ft
	401	HALLWAY TO ROOMS 2310 & 2312	NONE DETECTED			100 Sq Ft
	404	ROOM 2312	NONE DETECTED			350 Sq Ft
	419	STORAGE ROOM 2308A	NONE DETECTED			260 Sq Ft
I1B	1' x 1' Acoustical Ceiling Tile Fissured					**Total Amount - 2000 Sq Ft**
	15	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	121609ML-26; 2001-1901-JB1	ML-26: HALLWAY BY ROOM 1104. JB1: 2ND FLOOR HALLWAY.	2000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2A	2' x 2' Acoustical Ceiling Tile Textured w/Pin Holes					**Total Amount - 33545 Sq Ft**
	30	HALLWAY FROM MAIN OFFICE TO CAFETERIA	NONE DETECTED	121609ML-9		2300 Sq Ft
	201	ROOM 1305	NONE DETECTED			900 Sq Ft
	210	ROOM 1306	NONE DETECTED			620 Sq Ft
	218	ROOM 1308	NONE DETECTED			780 Sq Ft
	224	ROOM 1307	NONE DETECTED			800 Sq Ft
	231	ROOM 1309	NONE DETECTED			860 Sq Ft
	239	ROOM 1310	NONE DETECTED			860 Sq Ft
	249	ROOM 1312	NONE DETECTED			1000 Sq Ft
	259	ROOM 1311	NONE DETECTED			860 Sq Ft
	265	ROOM 1312A	NONE DETECTED			1000 Sq Ft
	274	ROOM 1313	NONE DETECTED			860 Sq Ft
	279	ROOM 1315	NONE DETECTED			860 Sq Ft
	284	ROOM 1314A	NONE DETECTED			1000 Sq Ft
	288	ROOM 1317/1317A	NONE DETECTED			900 Sq Ft
	293	ROOM 1316	NONE DETECTED			1950 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	301	ROOM 1318	NONE DETECTED			860 Sq Ft
	308	ROOM 1319/1319A	NONE DETECTED			900 Sq Ft
	313	ROOM 1321	NONE DETECTED			860 Sq Ft
	322	ROOM 1320	NONE DETECTED			880 Sq Ft
	333	ROOM 2322	NONE DETECTED			980 Sq Ft
	341	ROOM 2321	NONE DETECTED			860 Sq Ft
	349	ROOM 2319	NONE DETECTED			860 Sq Ft
	357	ROOM 2320	NONE DETECTED			980 Sq Ft
	365	ROOM 2318	NONE DETECTED			980 Sq Ft
	373	ROOM 2317	NONE DETECTED			860 Sq Ft
	387	ROOM 2314	NONE DETECTED			980 Sq Ft
	395	ROOM 2315	NONE DETECTED			860 Sq Ft
	408	ROOM 2310	NONE DETECTED			815 Sq Ft
	413	ROOM 2313	NONE DETECTED			860 Sq Ft
	426	ROOM 2311	NONE DETECTED			860 Sq Ft
	439	ROOM 2309	NONE DETECTED			980 Sq Ft
	447	ROOM 2307	NONE DETECTED			900 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	465	ROOM 2305	NONE DETECTED			860 Sq Ft
	476	ROOM 2303	NONE DETECTED			860 Sq Ft
	485	ROOM 2302	NONE DETECTED			1000 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Bumpy Texture w/Nail Holes					**Total Amount - 4500 Sq Ft**
	177	THROUGHOUT MEDIA CENTER	NONE DETECTED			3000 Sq Ft
	187	ROOM 1301	NONE DETECTED	121609ML-19		1500 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Light Texture					**Total Amount - 7740 Sq Ft**
	195	ROOM 1302	NONE DETECTED	121609ML-14		2100 Sq Ft
	200	ENTRANCE HALLWAY BETWEEN ROOMS 1301 & 1305	NONE DETECTED			360 Sq Ft
	432	ROOM 2308	NONE DETECTED			980 Sq Ft
	452	HALLWAY 2306 BETWEEN 2306E AND 2306A	NONE DETECTED			230 Sq Ft
	454	ROOM 2306A	NONE DETECTED			400 Sq Ft
	456	ROOM 2306B	NONE DETECTED			440 Sq Ft
	459	ROOM 2304E	NONE DETECTED			150 Sq Ft
	461	ROOM 2304D	NONE DETECTED			220 Sq Ft
	471	ROOM 2304	NONE DETECTED			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	483	ROOM 2302 AREAS	NONE DETECTED			1000 Sq Ft
	491	ROOM 2301	NONE DETECTED			860 Sq Ft
I2E	2' x 2' Acoustical Ceiling Tile Textured with Nail Holes and Revealed Edge (2021)					**Total Amount - 3700 Sq Ft**
	107	MAIN GYMNASIUM 1107	NEW			2700 Sq Ft
	124	HALLWAY BETWEEN GYMNASIUM AND CAFETERIA	NEW			1000 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Revealed Edge Textured w/Pinholes (2023)					**Total Amount - 11000 Sq Ft**
	1	THROUGHOUT BUILDING	NEW			6000 Sq Ft
	173	HALLWAY FROM ROOMS 1205-1321	NEW			5000 Sq Ft
I2G	2' x 2' Acoustical Ceiling Tile White Tectum					**Total Amount - 2700 Sq Ft**
	108	MAIN GYMNASIUM 1107	NEW			2700 Sq Ft
J3A	Miscellaneous Cementitious Material Black Window Sills (1956)					**Total Amount - 2238 Sq Ft**
	31	HALLWAY FROM MAIN OFFICE TO CAFETERIA	NONE DETECTED			32 Sq Ft
	42	OFFICE 1005	NONE DETECTED			12 Sq Ft
	45	OFFICE 1004	NONE DETECTED			16 Sq Ft
	54	OFFICE 1003	NONE DETECTED			12 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	59	OFFICE 1016	NONE DETECTED			8 Sq Ft
	62	OFFICE 1015	NONE DETECTED			16 Sq Ft
	70	NURSE 1011	NONE DETECTED			12 Sq Ft
	75	NURSE'S OFFICE 1014	NONE DETECTED			12 Sq Ft
	129	KITCHEN 1111	NONE DETECTED			8 Sq Ft
	143	CAFETERIA 1114	NONE DETECTED	121609ML-10	ML-10: CAFETERIA.	64 Sq Ft
	152	OFFICE 1201	NONE DETECTED			12 Sq Ft
	160	OFFICE 1202	NONE DETECTED			12 Sq Ft
	169	OFFICE 1205	NONE DETECTED			12 Sq Ft
	198	ROOM 1302	NONE DETECTED			70 Sq Ft
	205	ROOM 1305	NONE DETECTED			28 Sq Ft
	214	ROOM 1306	NONE DETECTED			28 Sq Ft
	222	ROOM 1308	NONE DETECTED			28 Sq Ft
	228	ROOM 1307	NONE DETECTED			28 Sq Ft
	235	ROOM 1309	NONE DETECTED			28 Sq Ft
	244	ROOM 1310	NONE DETECTED			28 Sq Ft
	255	ROOM 1312	NONE DETECTED			28 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	263	ROOM 1311	NONE DETECTED			28 Sq Ft
	269	ROOM 1312A	NONE DETECTED			28 Sq Ft
	278	ROOM 1313	NONE DETECTED			28 Sq Ft
	283	ROOM 1315	NONE DETECTED			28 Sq Ft
	287	ROOM 1314A	NONE DETECTED			28 Sq Ft
	291	ROOM 1317/1317A	NONE DETECTED			24 Sq Ft
	299	ROOM 1316	NONE DETECTED			56 Sq Ft
	306	ROOM 1318	NONE DETECTED			28 Sq Ft
	312	ROOM 1319/1319A	NONE DETECTED			40 Sq Ft
	317	ROOM 1321	NONE DETECTED			28 Sq Ft
	327	ROOM 1320	NONE DETECTED			24 Sq Ft
	337	ROOM 2322	NONE DETECTED			28 Sq Ft
	345	ROOM 2321	NONE DETECTED			28 Sq Ft
	353	ROOM 2319	NONE DETECTED			28 Sq Ft
	361	ROOM 2320	NONE DETECTED			28 Sq Ft
	369	ROOM 2318	NONE DETECTED			28 Sq Ft
	377	ROOM 2317	NONE DETECTED			28 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	391	ROOM 2314	NONE DETECTED			28 Sq Ft
	399	ROOM 2315	NONE DETECTED			28 Sq Ft
	407	ROOM 2312	NONE DETECTED			12 Sq Ft
	410	ROOM 2310	NONE DETECTED			24 Sq Ft
	417	ROOM 2313	NONE DETECTED			28 Sq Ft
	430	ROOM 2311	NONE DETECTED			28 Sq Ft
	434	ROOM 2308	NONE DETECTED			28 Sq Ft
	443	ROOM 2309	NONE DETECTED			28 Sq Ft
	451	ROOM 2307	NONE DETECTED			28 Sq Ft
	458	ROOM 2306B	NONE DETECTED			24 Sq Ft
	469	ROOM 2305	NONE DETECTED			28 Sq Ft
	472	ROOM 2304	NONE DETECTED			44 Sq Ft
	480	ROOM 2303	NONE DETECTED			20 Sq Ft
	486	ROOM 2302	NONE DETECTED			28 Sq Ft
	493	ROOM 2301	NONE DETECTED			860 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J3B	Miscellaneous Cementitious Material Epoxy Resin Black Science Tabletops (2008)					**Total Amount - 1070 Sq Ft**
	378	ROOM 2317	NSM			180 Sq Ft
	400	ROOM 2315	NSM			180 Sq Ft
	418	ROOM 2313	NSM			250 Sq Ft
	422	STORAGE ROOM 2308A	NSM			30 Sq Ft
	431	ROOM 2311	NSM			250 Sq Ft
	444	ROOM 2309	NSM			180 Sq Ft
J3C	Miscellaneous Cementitious Material Epoxy Fume Food Base (200x)					**Total Amount - 6 Sq Ft**
	423	STORAGE ROOM 2308A	NSM			6 Sq Ft
K0B	9" x 9" Vinyl Floor Tile & Mastic Gray w/White & Black Streaks					**Total Amount - 120 Sq Ft**
	435	ELEVATOR EQUIPMENT ROOM 2306C	3-4 CH (TILE ONLY)	032014MV-01; 121609ML-3; 2001-1501-H2-04	MV-01: AUDITORIUM (SINCE REMOVED). ML-3: GIRLS' LOCKER ROOM 1105 (SINCE REMOVED). HS-04: COPY ROOM 1007 (SINCE REMOVED).	120 Sq Ft
K0E	9" x 9" Vinyl Floor Tile & Mastic Cream w/Brown Streaks					**Total Amount - 475 Sq Ft**
	182	STORAGE ROOM 1207	NONE DETECTED	121609ML-13; 325-1	325-1: MIDDLE OF ROOM 1207.	475 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2A	12" x 12" Vinyl Floor Tile & Mastic White w/Black & White Swirls					**Total Amount - 60 Sq Ft**
	246	STORAGE ROOM 1310A BY ROOM 1310	NONE DETECTED	2001-1504-Q5	Q5: STORAGE ROOM BY ELEVATOR.	60 Sq Ft
K2C	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Gray & White Smudges (2008)					**Total Amount - 4980 Sq Ft**
	264	ENTRANCE TO ROOM 1312A	NEW			100 Sq Ft
	273	ROOM 1314	NEW			200 Sq Ft
	374	ROOM 2317	NEW			860 Sq Ft
	396	ROOM 2315	NEW			860 Sq Ft
	414	ROOM 2313	NEW			860 Sq Ft
	421	STORAGE ROOM 2308A	NEW			260 Sq Ft
	427	ROOM 2311	NEW			860 Sq Ft
	440	ROOM 2309	NEW			980 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic Off-White w/Black Specks (2009)					**Total Amount - 6480 Sq Ft**
	192	ENTRANCE TO ROOM 1302	NEW			120 Sq Ft
	330	HALLWAY FROM ROOMS 2301-2322	NEW			6100 Sq Ft
	379	STORAGE ROOM 2316A	NEW			40 Sq Ft
	382	STORAGE ROOM 2316	NEW			150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	482	HALLWAY OUTSIDE ROOM 2302	NEW			70 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Gray w/Dark Gray & White Specks (2009)					**Total Amount - 11950 Sq Ft**
	151	OFFICE 1201	NEW			280 Sq Ft
	196	ROOM 1302	NEW			2100 Sq Ft
	334	ROOM 2322	NEW			980 Sq Ft
	342	ROOM 2321	NEW			860 Sq Ft
	350	ROOM 2319	NEW			860 Sq Ft
	358	ROOM 2320	NEW			980 Sq Ft
	366	ROOM 2318	NEW			980 Sq Ft
	388	ROOM 2314	NEW			980 Sq Ft
	403	HALLWAY TO ROOMS 2310 & 2312	NEW			100 Sq Ft
	406	ROOM 2312	NEW			350 Sq Ft
	448	ROOM 2307	NEW			900 Sq Ft
	466	ROOM 2305	NEW			860 Sq Ft
	477	ROOM 2303	NEW			860 Sq Ft
	492	ROOM 2301	NEW			860 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2G	12" x 12" Vinyl Floor Tile & Mastic Tan w/Black Specks (2009)					**Total Amount - 600 Sq Ft**
	453	HALLWAY 2306 BETWEEN 2306E AND 2306A	NEW			230 Sq Ft
	460	ROOM 2304E	NEW			150 Sq Ft
	462	ROOM 2304D	NEW			220 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Gray w/Black Specks (2009)					**Total Amount - 840 Sq Ft**
	455	ROOM 2306A	NEW			400 Sq Ft
	457	ROOM 2306B	NEW			440 Sq Ft
K2J	12" x 12" Vinyl Floor Tile & Mastic Beige Mottle (2010)					**Total Amount - 4860 Sq Ft**
	202	ROOM 1305	NEW			900 Sq Ft
	219	ROOM 1308	NEW			400 Sq Ft
	223	STORAGE 1308A	NEW			70 Sq Ft
	225	ROOM 1307	NEW			500 Sq Ft
	229	ROOM 1307 RESTROOM	NEW			30 Sq Ft
	232	ROOM 1309	NEW			500 Sq Ft
	236	ROOM 1309 RESTROOM	NEW			30 Sq Ft
	240	ROOM 1310	NEW			600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	245	ROOM 1310 RESTROOM	NEW			30 Sq Ft
	289	ROOM 1317/1317A	NEW			900 Sq Ft
	309	ROOM 1319/1319A	NEW			900 Sq Ft
K2K	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (2011)					**Total Amount - 50 Sq Ft**
	134	KITCHEN RESTROOM 1111B	NEW			50 Sq Ft
K2L	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle (2012)					**Total Amount - 40 Sq Ft**
	230	ELEVATOR	NEW			40 Sq Ft
K2M	12" x 12" Vinyl Floor Tile & Mastic Gray/Tan Marble-Look (2012)					**Total Amount - 2000 Sq Ft**
	473	ROOM 2304	NEW			1000 Sq Ft
	484	ROOM 2302 AREAS	NEW			1000 Sq Ft
K3A	Miscellaneous Flooring Cork Flooring/Adhesive					**Total Amount - 500 Sq Ft**
	487	ROOM 2302	NONE DETECTED (BROWN MASTIC)	073012-BF-1	BF-1: BAND ROOM.	500 Sq Ft
K3B	Miscellaneous Flooring 2' x 2' Gray w/Gray & White Specks (2014)					**Total Amount - 1710 Sq Ft**
	39	ROOM 1006	NEW			180 Sq Ft
	47	COPY ROOM 1007	NEW			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	69	NURSE 1011	NEW			240 Sq Ft
	74	NURSE'S OFFICE 1014	NEW			150 Sq Ft
	81	COT ROOM 1013	NEW			120 Sq Ft
	84	OFFICE 1012	NEW			120 Sq Ft
	104	GIRLS' LOCKER ROOM OFFICE 1106	NEW			70 Sq Ft
	112	BOYS' LOCKER ROOM OFFICE 1108	NEW			80 Sq Ft
	135	KITCHEN OFFICE 1113	NEW			50 Sq Ft
	146	CAFETERIA STORAGE ROOMS 1115/1116	NEW			360 Sq Ft
	154	ROOM 1202 & ENTRY	NEW			240 Sq Ft
K3C	Miscellaneous Flooring Tan w/Gray & White (2014)					**Total Amount - 100 Sq Ft**
	88	AUDITORIUM 1101	NEW			100 Sq Ft
K3D	Miscellaneous Flooring Blue w/Multi-Colored Specks (2014)					**Total Amount - 4445 Sq Ft**
	207	ENTRANCE TO ROOM 1306	NEW			75 Sq Ft
	211	ROOM 1306	NEW			930 Sq Ft
	260	ROOM 1311	NEW			860 Sq Ft
	275	ROOM 1313	NEW			860 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	280	ROOM 1315	NEW			860 Sq Ft
	314	ROOM 1321	NEW			860 Sq Ft
L0A	Flexible Duct Connector Green Canvas					**Total Amount - 60 Sq Ft**
	26	BOILER ROOM 1208	NONE DETECTED	121609ML-1		6 Sq Ft
	28	MECHANICAL ROOM 1209	NONE DETECTED			6 Sq Ft
	96	AUDITORIUM PENTHOUSE FAN ROOM (2104 STORAGE)	NONE DETECTED			18 Sq Ft
	110	GYMNASIUM FAN ROOM 240	NONE DETECTED			30 Sq Ft
L0B	Flexible Duct Connector Black Vinyl					**Total Amount - 25 Sq Ft**
	97	AUDITORIUM PENTHOUSE FAN ROOM (2104 STORAGE)	NSM			25 Sq Ft
M0A	Plaster 1956 Original Building					**Total Amount - 82000 Sq Ft**
	13	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	042424JA-01, 02; 121609ML-4, 11, 16, 21, 22, 23; 207I-4A	JA-01,02: BOILER ROOM CEILING. ML-4: GIRLS' LOCKER ROOM STORAGE 1105A. ML-11: CAFETERIA. ML-16: ROOM 1006. ML-21: ROOM 1308. ML-22: ROOM 2311. ML-23: ROOM 2304E.	82000 Sq Ft
N0A	Drywall/Joint Compound					**Total Amount - 5000 Sq Ft**
	14	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	121609ML-18; 2001-1504-Q1	ML-18: ROOM 1302. Q1: CUSTODIAL OFFICE IN BOILER ROOM.	5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
N0B	Drywall/Joint Compound Media Center Addition					**Total Amount - 200 Sq Ft**
	176	THROUGHOUT MEDIA CENTER	NEW			200 Sq Ft
P0A	Fire Doors Pieced Metal					**Total Amount - 34 Sq Ft**
	27	BOILER ROOM 1208	NSM			30 Sq Ft
	95	AUDITORIUM LIGHT BOOTH 2102	NSM			4 Sq Ft
P0B	Fire Doors Hollow Metal -1.5 Hr Rating (Ceco)					**Total Amount - 20 Sq Ft**
	436	ELEVATOR EQUIPMENT ROOM 2306C	NSM			20 Sq Ft
Q0A	Carpet Adhesive Blue/Gray Berber Carpet					**Total Amount - 8000 Sq Ft**
	18	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	073012-BF-01; 121609ML-15	BF-01: ROOM 2300. ML-15: ROOM 1005.	8000 Sq Ft
Q0C	Carpet Adhesive Red, Gray & Tan Berber Carpet					**Total Amount - 4175 Sq Ft**
	188	ROOM 1301	NONE DETECTED	121609ML-20	ML-20: ROOM 1301.	1500 Sq Ft
	326	ROOM 1320	NONE DETECTED			880 Sq Ft
	409	ROOM 2310	NONE DETECTED			815 Sq Ft
	433	ROOM 2308	NONE DETECTED			980 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0E	Carpet Adhesive Blue Carpet (2014)					**Total Amount - 110 Sq Ft**
	51	OFFICE 1008	NEW			110 Sq Ft
Q0F	Carpet Adhesive Brown Carpet (2014)					**Total Amount - 400 Sq Ft**
	89	AUDITORIUM 1101	NEW			400 Sq Ft
Q0G	Carpet Adhesive Blue Carpet Squares (2014)					**Total Amount - 3300 Sq Ft**
	32	THROUGHOUT MAIN OFFICE AREA	NEW			2200 Sq Ft
	168	OFFICE 1205	NEW			240 Sq Ft
	304	ROOM 1318	NEW			860 Sq Ft
Q0H	Carpet Adhesive Multi-Colored Berber Carpet (2010)					**Total Amount - 2000 Sq Ft**
	215	ROOMS 1307-1310	NEW			2000 Sq Ft
Q0I	Carpet Adhesive Black and Navy Blue Carpet Squares					**Total Amount - 3000 Sq Ft**
	178	THROUGHOUT MEDIA CENTER	NEW			3000 Sq Ft
R0A	Baseboard/Mopboard Adhesive 4" Gray Baseboard					**Total Amount - 400 Sq Ft**
	19	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	325-2	325-2: 1100B.	400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
R0B	Baseboard/Mopboard Adhesive 4" Brown Baseboard (2009)					**Total Amount - 200 Sq Ft**
	3	THROUGHOUT BUILDING	NEW			200 Sq Ft
R0C	Baseboard/Mopboard Adhesive 4" Black Baseboard (2009)					**Total Amount - 200 Sq Ft**
	4	THROUGHOUT BUILDING	NEW			200 Sq Ft
R0D	Baseboard/Mopboard Adhesive 6" Blue Baseboard					**Total Amount - 200 Sq Ft**
	5	THROUGHOUT BUILDING	NEW			200 Sq Ft
R0E	Baseboard/Mopboard Adhesive 6" Gray Baseboard					**Total Amount - 200 Sq Ft**
	6	THROUGHOUT BUILDING	NEW			200 Sq Ft
S0A	Wood Floor Felt / Vapor Barrier On-Grade (1956)					**Total Amount - 4340 Sq Ft**
	118	EAST AUXILIARY GYMNASIUM 1110	3-8 CH	SN97-77892	77892: MAIN GYMNASIUM (SINCE REMOVED).	1300 Sq Ft
	121	WEST AUXILIARY GYMNASIUM 1104	3-8 CH			1300 Sq Ft
	305	ROOM 1318	3-8 CH	325-5	325-5: MIDDLE OF INNER WALL.	860 Sq Ft
	325	ROOM 1320	3-8 CH			880 Sq Ft
S0C	Wood Floor Felt / Vapor Barrier Elevated (1956)					**Total Amount - 1500 Sq Ft**
	91	AUDITORIUM STAGE 1102	12 CH	121609ML-8	ML-08: STAGE.	1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
S0D	Wood Floor Felt / Vapor Barrier On-Grade (199X)					**Total Amount - 5400 Sq Ft**
	109	MAIN GYMNASIUM 1107	NEW			5400 Sq Ft
T0A	Light Cord Insulation White					**Total Amount - 55 Lin Ft**
	90	AUDITORIUM 1101	50 CH			25 Lin Ft
	92	AUDITORIUM STAGE 1102	50 CH	121609ML-7		30 Lin Ft
U0A	Light Pad Insulation Round					**Total Amount - 2 Sq Ft**
	98	HALLWAY SOUTHEAST OF AUDITORIUM OUTSIDE SPRINKLER SHUT-OFF ROOM	70 CH	121609ML-5		1 Sq Ft
	133	KITCHEN RESTROOM 1111B	70 CH			1 Sq Ft
V0A	Sink Undercoating Gray					**Total Amount - 36 Sq Ft**
	197	ROOM 1302	NONE DETECTED	121609ML-25		24 Sq Ft
	370	ROOM 2318	NONE DETECTED			12 Sq Ft
V0B	Sink Undercoating Black					**Total Amount - 52 Sq Ft**
	243	ROOM 1310	3 CH			6 Sq Ft
	270	ROOM 1312A	3 CH	121609ML-28	ML-28: ROOM 2322; SINCE REMOVED.	6 Sq Ft
	362	ROOM 2320	3 CH			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	392	ROOM 2314	3 CH			20 Sq Ft
V0C	Sink Undercoating Gray (201X)					**Total Amount - 6 Sq Ft**
	338	ROOM 2322	NEW			6 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					**Total Amount - 5014 Sq Ft**
	34	MAIN OFFICE 1002	2 CH			240 Sq Ft
	41	OFFICE 1005	2 CH			40 Sq Ft
	44	OFFICE 1004	2 CH			45 Sq Ft
	50	OFFICE 1008	2 CH			25 Sq Ft
	53	OFFICE 1003	2 CH			35 Sq Ft
	56	TECHNOLOGY ROOM 1009	2 CH			25 Sq Ft
	58	OFFICE 1016	2 CH			20 Sq Ft
	61	OFFICE 1015	2 CH			45 Sq Ft
	64	COUNSELOR'S WORK ROOM 1010	2 CH			160 Sq Ft
	68	NURSE 1011	2 CH	071212MV-01	MV-01: ROOM 1011.	60 Sq Ft
	73	NURSE'S OFFICE 1014	2 CH			35 Sq Ft
	80	COT ROOM 1013	2 CH			30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	83	OFFICE 1012	2 CH			25 Sq Ft
	87	AUDITORIUM 1101	2 CH			200 Sq Ft
	94	AUDITORIUM LIGHT BOOTH 2102	2 CH			50 Sq Ft
	128	KITCHEN 1111	2 CH	121609ML-12	ML-12: HALLWAY WEST OF CAFETERIA (SINCE REMOVED).	9 Sq Ft
	137	KITCHEN SERVING AREA	2 CH			100 Sq Ft
	140	CAFETERIA 1114	2 CH			800 Sq Ft
	145	CAFETERIA STORAGE ROOMS 1115/1116	2 CH			90 Sq Ft
	150	OFFICE 1201	2 CH			70 Sq Ft
	159	OFFICE 1202	2 CH			70 Sq Ft
	167	OFFICE 1205	2 CH	071212MV-02	MV-02: HALLWAY BY ROOM 1307 (SINCE REMOVED).	60 Sq Ft
	181	STORAGE ROOM 1207	2 CH	325-7		110 Sq Ft
	185	STAIRWELL NEAR ROOM 1207	2 CH			100 Sq Ft
	191	ENTRANCE TO ROOM 1302	2 CH			30 Sq Ft
	251	ROOM 1312	2 CH	071212MV-03	MV-03: ROOM 1312.	200 Sq Ft
	257	STAIRWELL NEAR ROOM 1312	2 CH			50 Sq Ft
	267	ROOM 1312A	2 CH			175 Sq Ft
	295	ROOM 1316	2 CH			225 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	303	ROOM 1318	2 CH	071212MV-04	MV-04: ROOM 1318.	215 Sq Ft
	320	STAIRWELL OUTSIDE ROOM 1320	2 CH			75 Sq Ft
	324	ROOM 1320	2 CH			110 Sq Ft
	329	HALLWAY FROM ROOMS 2301-2322	2 CH	071212MV-05	MV-05: HALLWAY BY ROOM 2322.	1275 Sq Ft
	381	STORAGE ROOM 2316	2 CH			35 Sq Ft
	402	HALLWAY TO ROOMS 2310 & 2312	2 CH			25 Sq Ft
	405	ROOM 2312	2 CH	071212MV-06	MV-06: ROOM 2312.	90 Sq Ft
	420	STORAGE ROOM 2308A	2 CH			65 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B (Light Brown)					**Total Amount - 500 Sq Ft**
	16	THROUGHOUT 1956 ORIGINAL BUILDING	NONE DETECTED	100421-BF-5, 6; 092821-BF-2; 071212MV-07, 08; 121609ML-26; 301-MPA	BF-5,6: GYMNASIUM 1107. BF-2: HALLWAY 1100A. MV-07,08: HALLWAY BY CAFETERIA. ML-26: HALLWAY BY ROOM 1104. 301-MPA: STORAGE ROOM 1000A.	500 Sq Ft
W1C	1' x 1' Ceiling Tile Adhesive Associated w/I1C					**Total Amount - 1350 Sq Ft**
	106	MAIN GYMNASIUM 1107	NONE DETECTED	100421BF-1, 2, 3, 4; 071212MV-11	BF-1,2,3,4 & MV-11: GYMNASIUM.	1350 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1D	1' x 1' Ceiling Tile Adhesive Associated w/I1B (Dark Brown Patch)					**Total Amount - 30 Sq Ft**
	17	THROUGHOUT 1956 ORIGINAL BUILDING	2 CH	092821-BF-1; 071212MV-09, 10; 121609ML-27	BF-1: HALLWAY 1100A. MV-09: BY ROOM 1313. MV-10: BY ROOM 2307. ML-27: HALLWAY BY ROOM 1205.	30 Sq Ft
X0A	Miscellaneous Material Tar Coated Fiberglass Inside Perimeter Radiators					**Total Amount - 3000 Sq Ft**
	20	THROUGHOUT 1956 ORIGINAL BUILDING CLASSROOMS	NONE DETECTED	ACB4350-O-A009	A009: ROOM 2300.	3000 Sq Ft
X0B	Miscellaneous Material Wood Frame Chalkboard Adhesive (1956)					**Total Amount - 483 Sq Ft**
	119	EAST AUXILIARY GYMNASIUM 1110	NONE DETECTED			5 Sq Ft
	122	WEST AUXILIARY GYMNASIUM 1104	NONE DETECTED			5 Sq Ft
	141	CAFETERIA 1114	NONE DETECTED			30 Sq Ft
	203	ROOM 1305	NONE DETECTED	073108BF-2	BF-2: ROOM 1301 (SINCE REMOVED).	15 Sq Ft
	212	ROOM 1306	NONE DETECTED			15 Sq Ft
	220	ROOM 1308	NONE DETECTED			10 Sq Ft
	226	ROOM 1307	NONE DETECTED			15 Sq Ft
	233	ROOM 1309	NONE DETECTED			15 Sq Ft
	241	ROOM 1310	NONE DETECTED			15 Sq Ft
	253	ROOM 1312	NONE DETECTED			15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	261	ROOM 1311	NONE DETECTED			15 Sq Ft
	276	ROOM 1313	NONE DETECTED			15 Sq Ft
	281	ROOM 1315	NONE DETECTED			15 Sq Ft
	285	ROOM 1314A	NONE DETECTED			15 Sq Ft
	292	ROOM 1317/1317A	NONE DETECTED			15 Sq Ft
	297	ROOM 1316	NONE DETECTED			10 Sq Ft
	310	ROOM 1319/1319A	NONE DETECTED			23 Sq Ft
	315	ROOM 1321	NONE DETECTED			15 Sq Ft
	335	ROOM 2322	NONE DETECTED			10 Sq Ft
	343	ROOM 2321	NONE DETECTED			15 Sq Ft
	351	ROOM 2319	NONE DETECTED			15 Sq Ft
	359	ROOM 2320	NONE DETECTED			10 Sq Ft
	367	ROOM 2318	NONE DETECTED			10 Sq Ft
	375	ROOM 2317	NONE DETECTED			15 Sq Ft
	383	STORAGE ROOM 2316	NONE DETECTED			10 Sq Ft
	389	ROOM 2314	NONE DETECTED			10 Sq Ft
	397	ROOM 2315	NONE DETECTED			15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	415	ROOM 2313	NONE DETECTED			20 Sq Ft
	428	ROOM 2311	NONE DETECTED			20 Sq Ft
	441	ROOM 2309	NONE DETECTED			15 Sq Ft
	449	ROOM 2307	NONE DETECTED			15 Sq Ft
	467	ROOM 2305	NONE DETECTED			15 Sq Ft
	478	ROOM 2303	NONE DETECTED			15 Sq Ft
	489	ROOM 2302	NONE DETECTED			10 Sq Ft
X0C	Miscellaneous Material Wood Frame Corkboard Adhesive (1956)					**Total Amount - 2364 Sq Ft**
	120	EAST AUXILIARY GYMNASIUM 1110	NONE DETECTED			5 Sq Ft
	123	WEST AUXILIARY GYMNASIUM 1104	NONE DETECTED			5 Sq Ft
	142	CAFETERIA 1114	NONE DETECTED			60 Sq Ft
	204	ROOM 1305	NONE DETECTED			180 Sq Ft
	213	ROOM 1306	NONE DETECTED			100 Sq Ft
	221	ROOM 1308	NONE DETECTED			60 Sq Ft
	227	ROOM 1307	NONE DETECTED			80 Sq Ft
	234	ROOM 1309	NONE DETECTED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	242	ROOM 1310	NONE DETECTED			100 Sq Ft
	254	ROOM 1312	NONE DETECTED			50 Sq Ft
	262	ROOM 1311	NONE DETECTED			100 Sq Ft
	277	ROOM 1313	NONE DETECTED			100 Sq Ft
	282	ROOM 1315	NONE DETECTED			100 Sq Ft
	286	ROOM 1314A	NONE DETECTED			20 Sq Ft
	290	ROOM 1317/1317A	NONE DETECTED			80 Sq Ft
	298	ROOM 1316	NONE DETECTED			30 Sq Ft
	311	ROOM 1319/1319A	NONE DETECTED			28 Sq Ft
	316	ROOM 1321	NONE DETECTED			100 Sq Ft
	336	ROOM 2322	NONE DETECTED			70 Sq Ft
	344	ROOM 2321	NONE DETECTED			100 Sq Ft
	352	ROOM 2319	NONE DETECTED			100 Sq Ft
	360	ROOM 2320	NONE DETECTED			70 Sq Ft
	368	ROOM 2318	NONE DETECTED			70 Sq Ft
	376	ROOM 2317	NONE DETECTED			100 Sq Ft
	384	STORAGE ROOM 2316	NONE DETECTED			16 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	390	ROOM 2314	NONE DETECTED			70 Sq Ft
	398	ROOM 2315	NONE DETECTED			20 Sq Ft
	416	ROOM 2313	NONE DETECTED			20 Sq Ft
	429	ROOM 2311	NONE DETECTED			20 Sq Ft
	442	ROOM 2309	NONE DETECTED			100 Sq Ft
	450	ROOM 2307	NONE DETECTED			100 Sq Ft
	468	ROOM 2305	NONE DETECTED			100 Sq Ft
	479	ROOM 2303	NONE DETECTED	073108BF-1	BF-01: ROOM 2301 (SINCE REMOVED).	100 Sq Ft
	490	ROOM 2302	NONE DETECTED			10 Sq Ft
X0E	Miscellaneous Material Red Fire Stop					**Total Amount - 100 Sq Ft**
	2	THROUGHOUT BUILDING	NONE DETECTED	121609ML-17	ML-17: ROOM 1302.	100 Sq Ft
X0F	Miscellaneous Material Interior Window Caulk					**Total Amount - 200 Sq Ft**
	7	THROUGHOUT BUILDING	NONE DETECTED	060712BF-1		200 Sq Ft
X0G	Miscellaneous Material Interior Window Glaze					**Total Amount - 200 Sq Ft**
	8	THROUGHOUT BUILDING	NONE DETECTED	060712BF-2		200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0H	Miscellaneous Material Exterior Window Caulk					**Total Amount - 200 Sq Ft**
	9	THROUGHOUT BUILDING	NONE DETECTED	060712BF-3		200 Sq Ft
X0I	Miscellaneous Material Exterior Window Glaze					**Total Amount - 200 Sq Ft**
	10	THROUGHOUT BUILDING	NONE DETECTED	060712BF-4		200 Sq Ft
X0J	Miscellaneous Material Exterior Black Dampproofing					**Total Amount - 5000 Sq Ft**
	11	THROUGHOUT BUILDING	12 CH	021712-MA-1	MA-1:	5000 Sq Ft
X0K	Miscellaneous Material Cork Wall Adhesive					**Total Amount - 300 Sq Ft**
	488	ROOM 2302	5 CH	073012-BF-2	BF-2: BAND ROOM.	300 Sq Ft
X0M	Miscellaneous Material Dark Gray Marble Look Vinyl Countertop & Associated Adhesive					**Total Amount - 250 Sq Ft**
	21	THROUGHOUT 1956 ORIGINAL BUILDING CLASSROOMS	NONE DETECTED	082119RR-01; 101717-BF-2	RR-01: ROOM 1307. BF-2: ROOM 1307.	250 Sq Ft
X0N	Miscellaneous Material Yellow w/Brown Streaks					**Total Amount - 250 Sq Ft**
	22	THROUGHOUT 1956 ORIGINAL BUILDING CLASSROOMS	NONE DETECTED	082119RR-02	RR-02: ROOM 1307.	250 Sq Ft
X0O	Miscellaneous Material Thin Metal Frame Tackboard Adhesive					**Total Amount - 8 Sq Ft**
	183	STORAGE ROOM 1207	ASSUMED			8 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0P	Miscellaneous Material White Poured Floor w/Red Black Gray Pebbles					**Total Amount - 3950 Sq Ft**
	252	ROOM 1312	NEW			1000 Sq Ft
	268	ROOM 1312A	NEW			1000 Sq Ft
	296	ROOM 1316	NEW			1950 Sq Ft
X1A	Miscellaneous Material Quarry Tile System (2014)					**Total Amount - 1400 Sq Ft**
	130	KITCHEN 1111	NEW			1000 Sq Ft
	138	KITCHEN SERVING AREA	NEW			400 Sq Ft
X1B	Miscellaneous Material 2" X 2" Gray Ceramic Floor Tile System					**Total Amount - 340 Sq Ft**
	77	NURSE'S RESTROOM 1011A	ASSUMED			40 Sq Ft
	161	STAFF MEN'S RESTROOM 1203	ASSUMED			150 Sq Ft
	164	STAFF WOMEN'S RESTROOM 1304	ASSUMED			150 Sq Ft
X1C	Miscellaneous Material 4" X 4" Gray Ceramic Wall Tile System					**Total Amount - 40 Sq Ft**
	78	NURSE'S RESTROOM 1011A	ASSUMED			40 Sq Ft
X1D	Miscellaneous Material 2" X 2" Blue Ceramic Floor Tile System					**Total Amount - 1770 Sq Ft**
	101	GIRLS' LOCKER ROOM 1105	ASSUMED			150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	105	GIRLS' LOCKER ROOM OFFICE 1106 RESTROOM	ASSUMED			30 Sq Ft
	113	BOYS' LOCKER ROOM OFFICE 1108 RESTROOM	ASSUMED			30 Sq Ft
	116	BOYS' LOCKER ROOM 1109	ASSUMED			300 Sq Ft
	153	OFFICE 1201 RESTROOM	ASSUMED			30 Sq Ft
	157	UNISEX RESTROOM NEAR ROOM 1202	ASSUMED			30 Sq Ft
	199	RESTROOM 1304A	ASSUMED			150 Sq Ft
	206	RESTROOM 1304B	ASSUMED			150 Sq Ft
	307	RESTROOM 1322	ASSUMED			150 Sq Ft
	318	RESTROOM 1324	ASSUMED			150 Sq Ft
	346	RESTROOM 2320B	ASSUMED			150 Sq Ft
	354	RESTROOM 2320A	ASSUMED			150 Sq Ft
	470	RESTROOM 2302D	ASSUMED			150 Sq Ft
	481	RESTROOM 2302C	ASSUMED			150 Sq Ft
X1E	Miscellaneous Material 2" X 2" Light Yellow Ceramic Floor Tile System					**Total Amount - 200 Sq Ft**
	102	GIRLS' LOCKER ROOM 1105	ASSUMED			100 Sq Ft
	117	BOYS' LOCKER ROOM 1109	ASSUMED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1F	Miscellaneous Material 4" X 4" Yellow Ceramic Wall Tile System					**Total Amount - 450 Sq Ft**
	162	STAFF MEN'S RESTROOM 1203	ASSUMED			450 Sq Ft
X1G	Miscellaneous Material 4" X 4" Pink Ceramic Wall Tile System					**Total Amount - 450 Sq Ft**
	165	STAFF WOMEN'S RESTROOM 1304	ASSUMED			450 Sq Ft
X1H	Miscellaneous Material 1' X 1' Beige Quarry Floor Tile System					**Total Amount - 225 Sq Ft**
	179	MEDIA CENTER EAST ENTRY	NEW			225 Sq Ft
X1I	Miscellaneous Material 6" X 6" Brown Quarry Floor Tile System					**Total Amount - 643 Sq Ft**
	12	THROUGHOUT BUILDING STAIRWELLS	ASSUMED			500 Sq Ft
	186	STAIRWELL NEAR ROOM 1207	ASSUMED			50 Sq Ft
	258	STAIRWELL NEAR ROOM 1312	ASSUMED			28 Sq Ft
	321	STAIRWELL OUTSIDE ROOM 1320	ASSUMED			65 Sq Ft

EMSL Analytical, Inc.
3410 Winnetka Avenue North New Hope, MN 55427
Tel/Fax: (763) 449-4922 / (763) 449-4924
http://www.EMSL.com / minneapolislab@emsl.com

EMSL Order: 352403751
Customer ID: IFEA50
Customer PO:
Project ID:

Attention: Emma Squires-Sperling
Inst. For Environmental Assessment
9201 West Broadway
Suite 600
Brooklyn Park, MN 55445
Project: 202410449 Hazel Park Prep

Phone: (763) 315-7927
Fax: (763) 315-7920
Received Date: 04/24/2024 4:20 PM
Analysis Date: 04/29/2024
Collected Date:

Test Report: Asbestos Analysis of Bulk Materials via AHERA Method 40CFR 763 Subpart E Appendix E supplemented with EPA 600/R-93/116 using Polarized Light Microscopy

			Non-Asbestos		Asbestos
Sample	**Description**	**Appearance**	**% Fibrous**	**% Non-Fibrous**	**% Type**
042424JA-01 *352403751-0001*	Boiler Room - Plaster ceiling	Gray/Beige Non-Fibrous Homogeneous		100.0% Non-fibrous (Other)	**None Detected**
042424JA-02 *352403751-0002*	Boiler Room - Plaster ceiling	Gray/Beige Non-Fibrous Homogeneous		100.0% Non-fibrous (Other)	**None Detected**

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations . The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. New Hope, MN NVLAP Lab Code 200019-0; Colorado AL-24478

Initial report from: 04/29/2024 13:55:49

EMSL Analytical, Inc.
3410 Winnetka Avenue North New Hope, MN 55427
Tel/Fax: (763) 449-4922 / (763) 449-4924
http://www.EMSL.com / minneapolislab@emsl.com

EMSL Order: 352403751
Customer ID: IFEA50
Customer PO:
Project ID:

Attention: Emma Squires-Sperling
Inst. For Environmental Assessment
9201 West Broadway
Suite 600
Brooklyn Park, MN 55445
Project: 202410449 Hazel Park Prep

Phone: (763) 315-7927
Fax: (763) 315-7920
Received Date: 04/24/2024 4:20 PM
Analysis Date: 04/29/2024
Collected Date:

The samples in this report were submitted to EMSL for analysis by Asbestos Analysis of Bulk materials via EPA/600 (0513) Method using Polarized Light Microscopy. The reference number for these samples is the EMSL Order ID above. Please use this reference number when calling about these samples.

Report Comments:

Sample Receipt Date:	04/24/2024	Sample Receipt Time:	4:20 PM
Analysis Completed Date:	04/29/2024	Analysis Completed Time:	1:55 PM

Analyst(s):

Amanda Picha PLM (2)

Samples Reviewed and approved by:

Rachel Travis, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. New Hope, MN NVLAP Lab Code 200019-0; Colorado AL-24478

Initial report from: 04/29/2024 13:55:49

9201 West Broadway North, Suite 600
Brooklyn Park, MN 55445
(763) 315-7900
1-800-233-9513

352403751

CHAIN OF CUSTODY

OrderID: 352403751

Client # _____ Project # 20241044g

Client St. Paul Public Schools

Address _____

Building Name Hazel Park Prep

Project Name _____

Contact Person _____

IEA Project Manager Brenda F.

Other Information _____

Shaded Areas are for Laboratory Use Only!

Verbal results to | Phone, Fax No. or E-Mail | TAT (circle) 6 hr 24 hr 48 hr 72 hr 96 hr Specify

Verbal results relayed to | Verbal results relayed by | Date | Time

Analysis location: ○ On Site ○ Lab ○ Regional Office ○ Other _____

Sample #	Work Area or Phase #	Sample Description/Location	Sample type or Material code	Volume	Matrix type: Air	Bulk	Dust	Analysis requested: PCM	PLM	TEM	Other	Filter type: MCE	.8 um	.45 um
042424JA-01		Plaster ceiling – Boiler Room	MOA		○	●	○	○	●	○		○	○	○
-02		" " " "	MOA		○	●	○	○	●	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○
					○	○	○	○	○	○		○	○	○

The MN Department of Health Alternative Indoor Air Standard for this project is: _____ F/CC. | Batch Number: | Samples Acceptable? ○ Yes ○ No

Sampled by	Date	Time	Delivered by	Date	Time	Received by lab	Date	Time	Entered by	Date	Time
Jeff Anderson	4-24-24		Emma	4-24-24	PM	Andrew Eggold	4/24/24	4:20pm			
Received by	**Date**	**Time**	**Delivered by**	**Date**	**Time**	**Analysis by**	**Date**	**Time**	**Delivered by**	**Date**	**Time**
Emma	4-24-24	AM									

WL

© IEA, Inc. 2010